



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.


About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

KF


20046


William Cameron Forbes



N. Canum Forbes

1904





WORKS OF
AUSTIN T. BYRNE, C. E.,

PUBLISHED BY
JOHN WILEY & SONS.

**Inspection of the Materials and Workmanship
Employed in Construction.**

A reference book for the use of inspectors, superintendents, and others engaged in the construction of public and private works. 12mo, cloth, 555 pp., \$3.00.

A Treatise on Highway Construction.

Designed as a text-book and work of reference for all who may be engaged in the location, construction, or maintenance of roads, streets, and pavements. 8vo, cloth, 936 pp., \$5.00.

A TREATISE
ON
HIGHWAY CONSTRUCTION.

DESIGNED AS
A TEXT-BOOK AND WORK OF REFERENCE
FOR ALL WHO MAY BE ENGAGED IN THE
LOCATION, CONSTRUCTION, OR MAINTENANCE
OF
ROADS, STREETS, AND PAVEMENTS.

BY
AUSTIN T. BYRNE, C.E.

FOURTH REVISED AND ENLARGED EDITION.
FIRST THOUSAND.

NEW YORK:
JOHN WILEY & SONS.
LONDON: CHAPMAN & HALL, LIMITED.
1902.

KF20046



**COPYRIGHT, 1892, 1900,
BY
AUSTIN T. BYRNE.**

ROBERT DRUMMOND, PRINTER, NEW YORK.

PREFACE TO THE FOURTH EDITION.

PURSUANT to the purpose of the author and the publishers to keep this work abreast of the times, a thorough revision of the Third Edition has been made,—minor errors being corrected, obsolete matter expunged, and considerable new matter (some one hundred and twenty-five pages) added. Among the chapters expanded are those on Stone Pavements, Brick Pavements, Broken-stone Pavements, and Asphaltum and Coal-tar Pavements. Included in the new matter will be found some important tables on asphalt production and manufacture, the comparative cost of laying and maintenance of pavements in various cities of this country and Europe, with other valuable data, and a number of specification forms.

NEW YORK, November, 1900.

PREFACE TO THE THIRD EDITION.

THE favorable reception of the previous editions and the advance made in every branch of highway construction and maintenance have induced the author to revise and enlarge the work, and thus keep up with the progressive spirit of the age and render it more worthy of approbation.

A large amount of new matter has been added and many important alterations have been made. Defective illustrations have been replaced with new and better ones.

Among the principal additions to the subject matter in this edition may be mentioned the articles on bitumen, asphaltum, and asphalt, the varieties and nomenclature of asphalt, fluxes for asphaltum, causes of failure of asphalt pavements, tests of paving-brick, blast-furnace slag, chert, Florida clay, artificial stone, statistics of roads in the United States, etc.

The selection of tools, machinery, and other articles of manufacture for reference and illustration has been guided solely by their merits and fitness for the intended purpose.

The writer takes this opportunity to gratefully acknowledge the kindness of those who have assisted in furnishing data, etc.

NEW YORK, *February*, 1896.

A. T. B.

PREFACE.

ALTHOUGH volumes have been written on the subject of highway construction, still the matter is widely scattered through the pages of the standard works on engineering, technical journals and periodicals, in pamphlets and reports of city engineers, and is therefore not always easily accessible when wanted.

The author, having found the need of a comprehensive and practical work of reference upon the many subjects connected with highways, has in the following pages endeavored to collate the varied mass of information. In doing so he has derived valuable assistance from the works of the authors mentioned below (which works may be profitably studied by those desiring further information upon the subjects treated of), and takes this method of acknowledging his indebtedness and thanks, instead of inclosing every extract in quotation-marks.

AUTHORS AND PUBLICATIONS REFERRED TO.

Allnutt.—Wood Pavements; Prize Essays on Road-making and Maintenance.

A Move for Better Roads.

Baker.—Masonry Construction; Cost of Bad Roads, in Report of the Illinois Society of Engineers and Surveyors.

Baumeister.—The Cleaning and Sewerage of Cities.

Boulnois.—Dirty Dust-bins and Sloppy Streets; The Municipal and Sanitary Engineer's Handbook.

Burgoyne.—On Rolling New-made Roads.

Burnell.—Selection, Inspection, and Use of Cement and Mortar (a paper read before the Engineers' Club of St. Louis).

Brande.—Encyclopædia of Science, Literature, and Art.

- Callanan*.—Roads and Road-making.
- Clark*.—Recent Practice in the Construction of Roads and Streets (London).
- Cluss*.—Mortars and Concretes of Antiquity and Modern Times (a paper read before the American Institute of Architects).
- Codrington*.—Maintenance of Macadamized Roads.
- Dobson*.—Pioneer Engineering.
- Encyclopædia Britannica.
- Engineering and Building Record.
- Engineering Magazine.
- Engineering News and American Railway Journal.
- Gillespie*.—The Principles and Practice of Road-making.
- Gillmore*.—Roads, Streets, and Pavements; Limes, Hydraulic Cements, and Mortars; Strength of the Building Stones in the United States.
- Good Roads.
- Greene*.—The Construction and Care of Streets (a paper read before the Commonwealth Club of New York); Asphalt and its Uses (a paper read before the American Institute of Mining Engineers); Roads and Road-making (in Harper's Weekly).
- Harper's Weekly.
- Haupt*.—Common Roads, in Reports of the Pennsylvania Board of Agriculture; The Best Arrangement of City Streets, in Franklin Institute Journal; Importance of Good Wagon-roads, in Engineering Magazine; Engineering; Specifications and Contracts.
- Haywood*.—Reports Addressed to the Commissioners of Sewers of the City of London.
- Henck*.—Field-book for Railroad Engineers.
- Herschel*.—The Science of Road-making.
- Hughes*.—The Roads and Walks of Central Park, New York.
- Hurst*.—Architectural Surveyor's Handbook.
- Jenks*.—Road Legislation for the American State.
- Journal of the Association of Engineering Societies.
- Journal of the Franklin Institute.
- Journal of the Society of Arts.
- Knight*.—American Mechanical Dictionary.
- Kuichling*.—Cement Mortars for Use in Public Works (Report to the Executive Board of the City of Rochester, New York).
- Law*.—The Art of Constructing Common Roads.
- Lippincott's Magazine.
- Love*.—Pavements and Roads.
- McClanahan*.—Roads and Road-drainage, in Report of the Illinois Society of Engineers and Surveyors.
- Mahan*.—Civil Engineering.

Manuel de l'Ingénieur des Ponts et Chaussées.

Mathewson.—City Streets: How to Build them and Why (a paper read before the Ohio Society of Surveyors and Civil Engineers).

Molesworth.—Pocketbook of Formulæ and Memorandum.

Morin.—Aide Memoir; Expérience sur le Tirage des Voitures.

Moseley.—Mechanics of Engineering.

Nelson.—Making and Mending of Country Roads, in Harper's Weekly.

Newberry.—The Street Pavements of New York, in School of Mines Quarterly.

North.—Construction and Maintenance of Roads; Highways and National Prosperity, in Engineering Magazine.

Nystrom.—Pocketbook of Mechanics.

Paget.—Report on the Economy of Road Maintenance and Horse-draft through Steam Road-rolling.

Parnell.—Treatise on Roads.

Paving and Municipal Engineering.

Pennell.—What I Know about European Roads, in Harper's Weekly.

Pope.—Improvement of City Streets.

Potter.—The Common Roads of Europe and America, in the Engineering Magazine; Our Common Roads, in the Century Magazine; The Gospel of Good Roads.

Proceedings of the Association of Municipal and Sanitary Engineers and Surveyors.

Proceedings of the Institution of Civil Engineers.

Rankine.—Civil Engineering.

Reports of the Engineer Department of the District of Columbia.

Reports of the Pennsylvania Board of Agriculture.

Reports of the Tenth and Eleventh United States Census.

Reports of the United States Geological Survey.

Reports of Various City Civil Engineers.

Rhawn.—A Plea for Better Roads.

Ripley.—Improved Roads (an address before the New Jersey State Board of Agriculture).

School of Mines Quarterly.

Scribner's Magazine.

Searles.—Field Engineering.

Shaler.—The Common Roads, in Scribner's Magazine.

Shunk.—Treatise on Railway Construction and Location for Young Engineers.

Smith.—Parks and Pleasure Grounds.

Speed.—The Common Roads of Europe, in Lippincott's Magazine.

Spon.—Dictionary of Engineering.

Stone.

The Century Magazine.

The Clay Worker.

The Manufacturer.

The Sanitarian.

The Technologist.

The Transit.

Torrey.—Pavement Construction and Economies (an address at the Street-paving Exposition, Indianapolis).

Transactions of the American Society of Civil Engineers.

Transactions of the Canadian Society of Civil Engineers.

Trautwine.—Engineer's Pocketbook.

United States Consular Reports on the Streets and Highways of Foreign Countries.

Vose.—Manual for Railroad Engineers.

Waddell.—General Specifications for Highway Bridges.

Wellington.—The Economic Theory of Railway Location.

Wheeler.—Repair and Maintenance of Roads.

Wilkins.—Mountain Roads, etc.

Wright.—Mechanical Dictionary.

Whipple.—Microscopy of Drinking-water.

Wilkins.—Mountain Roads, etc.

Wright.—Mechanical Dictionary.

TABLE OF CONTENTS.

CHAPTER I.

PAVEMENTS.

	PAGE
Object of pavements—The qualities essential to a good pavement—The interests affected in the selection of pavements—Selection of suitable pavements—Cost of wagon transportation—Cost of railroad transportation—Effect of reducing the cost of wagon transportation—Problem involved in the selection of the most suitable pavement—Adaptability—Desirability—Economic desirability of pavements—Tractive force required on different pavements—Number of horses required to move a given load on different pavements—Economy of smoothness—Serviceability—Comparative safety—Observations of Capt. Greene—Observations of Col. Haywood—Deductions from the observations—Condition of the weather and slipperiness—Cause of the difference in the observations of Capt. Greene and Col. Haywood—Slipperiness, cure for—Durability—Causes affecting durability—Durability of different pavements—Cost of pavements—Cheapest pavement—What a good pavement should cost—Economy and public bodies—First cost—Relative economies—Maintenance—Prevailing opinion regarding pavements—Cleansing—Comparison of pavements with regard to facility for cleaning—Annual cost for service—Consequential damages—Disadvantages of dirty and noisy pavements—Gross cost—Traffic census—Traffic census in the United States—Weights of vehicles—Form of traffic census—Tonnage—Guaranteeing pavements—Deferred payments—Justification of contracts for maintenance—Destruction of pavements—Amount of money wasted in continually opening streets—European methods	1

CHAPTER II.

MATERIALS EMPLOYED IN THE CONSTRUCTION OF PAVEMENTS.

Materials employed for paving—Physical and chemical qualities—Breaking and crushing tests—Methods of testing durability—Method of testing	ix
---	----

the comparative value of paving-stones—Absorptive power—Description of materials—Granite—Syenite—Amount and value of granite used for street purposes in the United States—Price of paving-blocks—Various uses of granite—Specific gravity, weight, and resistance to crushing of various granites—Manufacture of granite blocks—Sandstone—"Bluestone"—Commercial names of sandstone—Analyses of sandstone—Specific gravity, weight, and resistance to crushing—Amount and value of sandstone used for street purposes in the United States—Amount and value of bluestone used in 1889—Limestone—Uses of limestone—Experience with limestone—Specific gravity, weight, and resistance to crushing—Amount and value of limestone used in 1880—Trap-rock—Specific gravity, weight, and resistance to crushing—Bitumen—Asphaltum—Asphalt—Origin—Occurrence—Distribution—Nomenclature—Composition—Refined asphaltum—Refining asphaltum—Asphaltic cement—Flux for asphaltum—Liquid asphalt—Petroleum residuum—Examination of—Specifications for—Asphaltic paving materials—Bituminous limestone—Manner of using bituminous limestone—Analysis of European bituminous rocks—Bituminous sandstones—Manner of using the sandstone—Trinidad Asphaltum—Characteristics of crude Trinidad—Composition of Trinidad asphaltum—Refined Trinidad asphaltum—Refining Trinidad asphaltum—Characteristics of refined Trinidad asphaltum—Bermudez asphalt—California asphaltum—Buena Vista asphalt—Asphalt mastic—analysis and tests of asphaltum—Penetration tests—Analysis of California asphaltum—Prices of asphaltum in 1897-98—Production and varieties of, in the United States—Imports of, to the United States—Percentage of the uses of asphaltum—Paving-pitch—Gas-tar—Brick—Clay—Composition of clay—Quality of clay required for paving-brick—Manufacture of paving-brick—Repressed brick—Analyses of clay—Characteristics of good paving-brick—Tests of paving-brick—Standard tests adopted by the National Brick Manufacturers' Association—Specific gravity, weight, and resistance to crushing—Absorptive power of brick—Tests of Ohio paving-brick—Wood—Quality of wood—Creosoting—Specific gravity, weight, and resistance to crushing—Absorptive power of wood—Sand—Use, price, and weight of—Gravel—Shingle—Chert—Specific gravity, weight, and resistance to crushing of various substances

CHAPTER III.

STONE PAVEMENTS.

Early stone pavements—Cobblestone pavement—Specifications for—Belgian-block pavement—Specifications for—Granite-block pavement—Advantages and defects of granite-block pavements—Quality of stone for pavements—Size and shape of the blocks—Dressing the blocks—

Manner of laying the blocks—Gauging the size of the blocks—Foundation for the blocks—Cushion-coat—Joint-filling—Bituminous cement—Sandstone-block pavements—Limestone-block pavements—Pavements on steep grades—Durability of granite blocks—Wear of granite block—Cost of maintaining granite-block pavements—Method of paying for granite-block pavements—Number of blocks to the square yard—Cost of construction of granite-block pavements—Cost of Belgian-block pavements—Cost of sandstone-block pavements—Cost of cobblestone pavements—Heads of specifications for granite-block pavements.	99
--	----

CHAPTER IV.

WOOD PAVEMENTS.

Success of, in Europe—Failure of, in America—Advantages of—Objections to—Wood pavements and death-rate—Systems of wood pavements—Size and form of the blocks—Number of blocks per square yard—Essentials necessary to successful construction—Foundation for wood pavements—Chief causes of failure—Quality of the wood—Chemical treatment of the wood—Dimensions of the blocks—Expansion of wood blocks—Width of joints—Filling for joints—Durability of wood pavements—Duration and life of wood pavements in European and American cities—Wear of wood pavements—Cost of wood pavements—Cost of maintaining wood pavements—Description of various systems of wood paving—Heads of specifications for wood-block paving—Maintenance of wood pavements by contract—Specifications for cedar-block pavements—Microbes in wood pavements—Cedar-block pavements—Karri (Australian) block pavement—Creosoted pine blocks—Cottonwood and gum blocks—Redwood block pavement—Jetley's patent	124
--	-----

CHAPTER V.

ASPHALTUM AND COAL-TAR PAVEMENTS.

Introduction of asphalt—Difference between European and American asphalt—Advantages of asphalt—Defects of asphalt—Asphalt pavement injured by illuminating-gas—Durability of asphalt—Wear—Cost of construction—Extent of asphalt pavements in 1897-99—Cost of maintenance—Foundation—Asphalt cement pavements—Composition of—Failure of—Trinidad-asphalt pavements—Composition of, preparation of—Memoranda—Extracts from reports of city civil engineers—Experiments with asphalt pavements in various cities—Heads of specifications for standard Trinidad-asphaltum pavement—Specification for asphaltum pavements on bituminous base—On hy-

	PAGE
draulic base—On surface of old pavements—Specifications for asphalt pavement, Washington, D. C., 1899—Maintenance of asphalt pavements under contract—Bermudez asphalt—European asphalt pavements—Bituminous-limestone pavements in America—Coal-tar pavements—Coal-tar and asphaltum—Vulcanite pavement—Advantages and defects of coal-tar or distillate pavements—Specifications for coal-tar distillate pavements—Asphalt-block pavements—Advantages and defects—Cost of asphalt-block pavements—American bituminous-rock pavements—Specifications for—Expansion of asphalt—Repairs to asphalt pavements—Specifications for the repairs of asphalt pavements—For the condition of asphalt pavements at end of guarantee period	157

CHAPTER VI.

BRICK PAVEMENTS.

Advantages and defects of brick pavements—Durability of—Size and shape of the bricks—Quality of the bricks—Foundation for—Sand cushion—Manner of laying—Joint-filling—Cost of brick pavements—Variety of systems—Heads of specifications for brick pavement—Extract from paving-brick specifications—Rumbling in brick pavements—Number of brick and block required per square yard—Brick paving for country roads—Average price of paving-brick per thousand in 1898 219

CHAPTER VII.

BROKEN-STONE PAVEMENTS.

Introduction of broken-stone pavements—Methods of Tresaguet, Telford, and Macadam—Modern Telford and Macadam pavements—Defects of Telford system—Defects of Macadam system—Advantages of broken-stone pavements—Defects common to all broken-stone pavements—Essentials requisite to successful construction—Erroneous methods of construction—Quality of the stone—Abrasion and cementation tests of stone—Size of the stones—Shape of the stones—Breaking of the stone—Hand-breaking—Cost of breaking by hand—Amount broken by hand—Stone-crushers—Cost of operating crushers—Amount of stone broken by crushers—Dimensions, capacity, etc., of stone-crushers—Cost of quarrying and crushing stone—Voids in broken stone—Weight of broken stone—Area covered by a cubic yard of broken stone—Thickness of the broken stone—The New Jersey and Bridgeport roads—Number of cubic yards of broken stone required per mile—Spreading the stone—Thickness of the layers—Binding, necessity of, qualities of—Injurious effects of large amounts—Practice of the French engineers—Watering—Compacting the broken stone, by traffic, by horse-

	PAGE
rollers, by steam-rollers—Defects of traffic consolidation—Advantages of rolling—Defects of horse-rollers—Introduction of steam-rollers—Advantages of steam-rolling—Pressure exerted by rollers and by loaded vehicles—Defects of wide rollers—Objections to picks on steam-rollers—Steepest grade on which a steam-roller can be operated—Cost of maintaining steam-rollers—Amount of rolling—Manner of applying the roller—Cost of rolling—Cost of broken-stone pavements—Cost of broken stone roads in Massachusetts—Difference in cost of broken-stone pavements in Europe and America—Wear of broken-stone pavements—Effect of climate on broken-stone roads—Cost of maintaining broken-stone pavements—Specifications of modern broken-stone roads in England—Methods of construction adopted in Chicago, in Bridgeport, in St. Louis—Heads of specifications for broken-stone pavements	246

CHAPTER VIII.

MISCELLANEOUS PAVEMENTS.

Gravel, quality of—Preparing and laying the gravel—Repairing gravel roads—Cost of construction—Weight of gravel—Bituminous macadam—Preparing and laying—Concrete macadam—Stone trackways, advantages of—Trackways in Italy—Cost of stone trackways—Jasperite—Artificial-granite blocks—Plank roads—Method of construction—Life and cost of plank roads—Log roads—Charcoal—Iron—Blast-furnace slag—Chert—Florida clay—Tar-macadam—Artificial stone—Hydraulic cement—Clinkers—Glass—Novaculite—Destructor concrete—Cork—Copper slag—Steel trackways—India rubber—Artificial paving-stones—Asphaltina—Asphalt-granite pavement	299
---	-----

CHAPTER IX.

FOUNDATIONS.

Necessity of foundations—Essentials necessary to the forming of stable foundations—Influence of the character of the soil—Defects of sand and plank foundations—Blast-furnace slag as a foundation-material—Concrete, advantages of—Thickness of the concrete—Quality of the concrete—Strength of the concrete—Specific gravity of concrete—Proportions—Determination of voids in the broken stone—Voids in sand—Quantity of water, some of the usual proportions—Mixing, laying, and ramming the concrete—Transverse strength of concrete—Compressive strength of concrete—Cost of concrete—Proportions for Portland-cement concrete—Limes, characteristics of—Cements, natural and artificial—Tests of cement—Characteristics of Portland cement—Testing cement—Composition of mortar—Quality and quan-

tity of sand—Quantity of water—Strength of mortar—Effect of frost on mortar—Weight of cement—Specifications for concrete—Specifications for the preparation of the roadbed—Foundation employed in Liverpool	319
---	-----

CHAPTER X.

RESISTANCE TO TRACTION.

Conditions causing resistance to traction—Want of uniformity of the surface—Resistance of penetration—Rolling resistance of wheels—Experiments of M. Dupuit—Friction—Resistance to traction on different road-surfaces—Experiments of MM. Dupuit and Morin—Gravity—Tractive power of horses and gradients—Work done by a horse—Loss of tractive power on inclines—Effect of inclines on the load a horse can draw—Steep grades objectionable—Equivalent length of inclined and level roads—Character of vehicles—Width of tires—Size of wheels—Effect of wheels—Wheel diameters	366
---	-----

CHAPTER XI.

LOCATION OF COUNTRY ROADS.

Considerations governing location—Principles governing location—Economy of motive power—Selection of best route—Reconnaissance, object of—Points to be attended to in making reconnaissance—Configuration of the country—Ridges and passes—Watercourses and valleys—Streams give the direction of the high ground—Preliminary survey—Data to be obtained on preliminary surveys—Topography—Map—Memoir—Levels—Cross-levels—Profile—Bridge sites—Principles to be observed in making final selection—Examples of cases to be treated—Intermediate towns—Mountain roads—Method of surveying mountain roads—Loss of height—Water on mountain roads—Halting-places—Alignment—Curves, kind of—Reduction of grade on curves—Increasing wheelway on curves—Excessive crookedness to be avoided—Curving roads, advantages of—Zigzags, objections to—Final location—Construction profile—Gradient, definition of—Determination of gradients—Angle of repose, to ascertain—Tractive power required in descending inclines—Men and animals ascending steep slopes—Maximum grade and traffic—Maximum grade to be adopted—Maximum suitable for various pavements—Maximum adopted by Telford—Maximum adopted by the French engineers—Smooth and rough surfaced inclines—Determination of maximum grade—To determine the most advantageous grade—Cost of grades—Grade of mountain roads—Minimum grade—Minimum grade adopted by the French engineers—Undulating grades—Level stretches, objections to—Vertical curves, application of—Different methods of designing the same grades	389
---	-----

CHAPTER XII.

WIDTH AND TRANSVERSE CONTOUR.

PAGE

Width of roadways—Minimum width—Advantage of wide roads—Width of land appropriated for road purposes in various localities—Width of mountain roads—Number of acres required per mile for different widths—Transverse contour, object of—Amount of rise required for different pavements—Form of transverse contour—Form for streets—Form for country roads—Excessive rise, evils of—Straight sides objectionable—Concave form not desirable—Contour on hillside roads . 416

CHAPTER XIII.

EARTH-WORK.

Earth-work, definition of—Equalizing earth-work—Transverse balancing—Borrow-pits—Spoil-banks—Staking out of borrow-pits—Shrinkage of earth—Increase of rock—Settlement of embankments—Failure of earth-work—Stability of earth-work—Angle of repose of earths—Angle of slopes—Effect of moisture on earth—Angle of slopes in rock excavation—Form of side slopes—Protection of side slopes—Slips—Catch-water ditches—Drainage of side slopes—Embankments, best materials for—Manner of forming embankments—Slopes of embankments—Drainage of embankments—Embankments over plains—Embankments across marshes—Description of an embankment formed by Mr. G. Waite, C.E.—Embankments across bogs—Embankments on hillsides—Roadways on rock-slopes—Rock excavation—Blasting—Quantity of rock loosened—Line of least resistance—Quantity of powder required—Cost of excavating rock—Haul—Cost of earth-work—Loosening earth—Transport of earth—Limits to which shovels, wheelbarrows, carts, scrapers, and dump-wagons may be employed—Loosening and transporting by machinery—Calculating amount of earth-work—Calculation of half-widths and areas—Examples of cross-sections of earth-work—Calculation of sectional areas—Formulae for the calculation of areas—Table of cubic contents 421

CHAPTER XIV.

DRAINAGE AND CULVERTS.

Drainage, object and necessity of—Methods employed for securing drainage—Division of natural soils—Mitre-drains—Tile-drains—Silt-basins—Protection of drain-outlets—Cost of drains—Fall of drains—Side ditches—Springs, treatment of—Drainage of the surface—Protection of gutters—Water-breaks objectionable—Catch-water ditches—Culverts—Area of water-way—Rainfall—Determination of area of water-way—Catch-pools—Materials for culverts—Cement and earthenware

	PAGE
pipes, dimensions and cost of—Iron pipe-culverts, dimensions and cost of—Box-culverts—Arch-culverts—Thickness of arch—Thickness of abutments—Dimensions and cost of drain-tile—Discharging capacity of circular pipes	455

CHAPTER XV.

BRIDGES, RETAINING-WALLS, PROTECTION WORKS, TUNNELS, FENCING.

Bridges, importance of—Care in their construction—The loads for which bridges should be proportioned—Materials for bridges—Wood—Types of timber bridges—Diagrams and dimensions of timber bridges—Sub-structure of bridges—Retaining-walls—Proportions of retaining-walls—Form of retaining-walls—Dry-stone retaining-walls—Foundation of retaining-walls—How retaining-walls fail—Coping for retaining-walls—Weep-holes—Formulae for calculating the thickness of retaining-walls—Surcharged walls—Least thickness of retaining-walls—Where retaining-walls should be built—Protection of roads—Parapets, dimensions of—Earth mounds—Wooden railings afford no protection—Guard-stones—Roads along the seashore, margin of rivers and lakes—Bulkheads and masonry walls—Tunnels—Fences—Cost of fencing	480
---	-----

CHAPTER XVI.

CITY STREETS.

Laying out of streets—Best arrangement of streets—Width of streets—Street grades—Grade at street-intersections—Accommodation summits—Transverse grade—Transverse contour—Sub-foundation drainage of streets—Surface drainage of streets—Gutters—Catch-basins—Street lines and monuments—Street profiles—Increasing the width of the carriageway at street corners	500
---	-----

CHAPTER XVII.

FOOTPATHS, CURBS, GUTTERS.

Footpaths, definition of—Qualities required—Width—Cross-slope—Foundation—Surface requirements—Materials employed for footpaths—Stone, manner of dressing—Specifications for flagstones—Wood—Asphalt—Proportions and materials employed in Paris—Number of square yards that a ton of prepared asphalt will lay—Life of asphalt footways—Specifications for asphalt footway pavements—Brick—Specifications for brick walls—Artificial stone, varieties of—Formation of artificial stone—Wear of artificial stone—Specifications for concrete	
---	--

	PAGE
footwalks—Specifications for artificial-stone footwalks—Tar concrete—Specifications for tar-concrete footpaths—Gravel, manner of constructing—The Central Park walks—Drainage of gravel walks—General directions for the construction of gravel walks—Curbstones—Setting curb—Specifications for granite curb—Specifications for blue-stone curb—Specifications for setting curb—Specifications for artificial-stone curb and gutter—Specifications for dressing old curb—Specifications for resetting curb—Hollow curbs—Gutters—Specifications for cobble gutters—Specifications for brick gutters—Specifications for gutter-stones—Crossing or bridge-stones—Specifications for bridge-stones—Specifications for relaying bridge-stones—Prices	527

CHAPTER XVIII.

RECONSTRUCTION AND IMPROVEMENT OF COUNTRY ROADS.

Rectification of alignment and grades—Drainage—Improvement of the surface—Improving clay roads—Improving sand roads—Scraping or road machines, manner of using—Cost of constructing earth roads—Cost of maintaining earth roads—Value of improvements, how to ascertain—Data required—Defects of existing roads—Profit of eliminating unnecessary grades—Profit of eliminating unnecessary length—Profit of improving the surface—Annual loss occasioned by bad roads	577
---	-----

CHAPTER XIX.

MAINTENANCE.—REPAIRING; CLEANSING; AND WATERING.

Maintenance, definition of—Necessity of—What good maintenance comprises—System of maintenance—Maintenance of country roads—Directions for maintaining macadamized highways—Errors commonly committed in the maintenance of broken-stone roads—Amount of water required—Cost of maintenance—Repair—Organization of road force—Instructions to roadmen—System of highway maintenance adopted in France—Street cleansing—Intervals at which it is performed—Objections to dusty streets—Dirt-producing causes—Composition of street dust—Amount of refuse collected from city streets—Amount of dirt produced by different pavements—Methods employed for cleansing—Systems of executing the work—Cost of cleansing—Methods of cleansing employed in Berlin, Paris, London, Baltimore, Boston, and other American cities—Street orderly system—Cost of street sweeping—Amount of surface swept by one man—Amount of surface swept by a machine broom—Cost of operating mechanical sweepers—Brooms—Carts and wagons—Disposal of street dirt—Removal of snow—Methods employed—System adopted in Milan—Disposal of snow—Weight of snow—Street washing—Street sprinkling—Systems employed—Quantity of water required—Cost of sprinkling—Sea-water for street sprinkling—sanding pavements	585
--	-----

CHAPTER XX.

TREES.

PAGE

Opinions regarding the planting of trees on roads and streets—Trees on the French and Belgian roads—Financial value of trees—Fruit-trees in Saxony—Selection of trees—Qualities necessary to good road-trees—Distance apart to plant trees—Trees at street-intersections—Protection of trees	647
--	-----

CHAPTER XXI.

STAKING OUT THE WORK.

Object of—Distance apart of stakes—Straight lines and curves—Side slopes—Setting out culverts—Length of culverts—Setting out bridges—Drains, setting out—Setting out vertical curves—Staking out transverse contour of street pavements—Setting stakes for curb—Setting stakes for any structure—Fixing lines upon water—Bench marks	653
--	-----

CHAPTER XXII.

SPECIFICATIONS AND CONTRACTS.

Specifications, contents of—Tests of materials—Contracts—General specifications for clearing—Close-cutting—Grubbing—Grading—Formation of embankments—Earth-work, measurement and classification—Drains—Catch-water ditches—Off-take ditches—Rip-rap—Retaining, breast, slope, and parapet walls—Culverts—Masonry, classification of—Arch-culvert masonry—Centring—Laying masonry in freezing weather—Pointing—Grouting—Brick masonry—Dry walls—Dry box-culverts—Pipe culverts—Cement—Cement tests—Sand—Mortar—Concrete—Foundation excavation—Artificial foundations—Timber—Piles—Cofferdams—Wrought-iron—Cast iron—General stipulations applicable to all contracts—Interpretation of specifications—Omissions in specifications—Engineer defined—Contractor defined—Notice to contractor, how served—Preservation of engineer's marks and stakes—Dismissal of incompetent persons—Spirituous liquors—Quality of materials—Samples—Deviations from plans and specifications—Right reserved to alter details—Inspectors—Defective work—Measurement of work—Excavation—Overhaul—Masonry—Timber—Piles—Culverts and drain-pipe—Stone, brick, and pole drains—Concrete—Curbing—Gutters—Crossing or bridge-stones—Catch-basins—Bridges—Pavements—Partial payments—Commencement of work—Time of completion—Progress of work—Forfeiture of contract—Damages for non-completion—Evidence of payment of claims—Protection of persons and property—Bond for faithful performance of work—Power to suspend work—Loss and damage—Miscellaneous work—Cleaning up—

	PAGE
Personal attention of contractor—Contract not to be assigned—Payment of workmen—Prices—Payments, when made—Heads of specifications for a highway—Specifications for a bulkhead—Heads of specifications for grading, macadamizing, curbing, and flagging—Specifications for the supply of broken stone—Indemnification for patent claims—Indemnity bond—Right to construct sewers—Old materials, disposal of—Security retained for repairs—Alteration of manhole covers, stopcock boxes, etc.—Heads of specifications for repaving—Specifications for street cleansing—Instructions to bidders—Form of proposal—Form of agreement—Form of bond—Specifications for team labor—Specifications for sprinkling—Form of monthly certificate—Affidavit of contractor—Certificate of final acceptance	650

CHAPTER XXIII.

IMPLEMENTS AND PRICES.

Description and prices—Tools for clearing—Tools for grading—Mechanical graders—Tools for draining—Tools for rock excavation—Hand-drills—Steam-drills—Tools for macadamizing—Stone-crushers—Sprinkling-carts—Horse rollers—Steam rollers—Tools employed in the maintenance of macadam roads—Tools employed for block pavements—Concrete-mixing machines—Tools employed for asphalt pavements—Tools used for cleansing pavements—Mechanical sweepers—Street patrol hand-cart—Sprinkling-carts—Snow-shovels and ploughs—Tools employed for artificial stone pavements—Catch-basins—Sewer-inlets and gutter-crossings—Street name-plates—Direction indicators—The viagraph	710
--	-----

CHAPTER XXIV.

MISCELLANEOUS NOTES.

Comparison of European and American Methods and Prices—Statistics of Roads in the United States—Average Weight of Load for Horses—Average Cost of Haulage per Ton per Mile—Average Length of Haul from Farms to Market—Average Total Cost per Ton for the Whole Length of Haul—Pavements and Horseshoes—Annual Cost of Structures—Interest and Sinking-fund Tables—Sprinkling Oil on Roads—Sinking Funds—Annual Cost of Pavements—Relative Economy of Materials	798
APPENDIX I.—Naming and Numbering Country Roads and Houses	808
APPENDIX II.—Methods of Assessing the Cost of Street Paving	818
APPENDIX III.—Ordinance Regulating the Width of Wagon-tires	821
APPENDIX IV.—Cycle-paths	828
INDEX	825

LIST OF TABLES.

NUMBER	PAGE
1. Cost of wagon transportation on different road-surfaces.....	3
2. Tractive force required upon level roads of different materials.....	6
3. Comparison of gross cost of pavements.....	18
4. Comparative rank of pavements.....	21
5. Absorptive power of stone.....	27
6. Specific gravity, weight, and resistance to crushing of granites.....	29
7. Production and value of granite in the United States in 1889 for street uses	30
8. Analyses of sandstones.....	33
9. Specific gravity, weight, and resistance to crushing of sandstones	34
10. Production and value of sandstone in the United States in 1889 for street uses.....	35
11. Production and value of bluestone used for street purposes in the United States in 1889.....	35
12. Specific gravity, weight, and resistance to crushing of limestones.....	37
13. Production and value of limestone used for street purposes in the United States in 1880.....	37
14. Specific gravity, weight, and resistance to crushing of trap-rocks.....	38
14a. Composition of asphaltum.....	48
15. Analyses of European bituminous rocks.....	53
16. Composition of Trinidad asphaltum.....	55
17. Prices of asphaltum in 1897-98	74
18. Production of asphaltum in the United States.....	74
18a. Varieties of asphaltum, etc., produced in the United States.....	75
19. Imports of asphaltum in 1897-98.....	75
20. Analyses of clay.....	83
21. Tests of paving-brick.....	87
21a. Tests of Ohio paving-brick.....	88-91
22. Specific gravity, weight, and resistance to crushing of wood.....	92
23. Absorptive power of wood.....	98
24. Specific gravity, weight, and resistance to crushing of various sub- stances	97
25. Wear and duration of granite pavements in London....	114

NUMBER	PAGE
26. Number of granite blocks to the square yard.....	117
27. Cost of granite-block in various cities in the United States in 1890....	118
28. Extent and cost of Belgian-block in the United States in 1890.....	119
29. Extent and cost of sandstone-block in the United States in 1890.....	119
30. Extent of cobblestone pavement in the United States in 1900.....	120
31. Duration and cost of wood pavements in London.....	136
32. Wear of wood pavements.....	138
33. Extent and cost of wood pavements in various localities.....	139
34. First cost and cost of maintaining wood pavements in London.....	140
35. Extent and cost of asphalt pavements in various cities.....	169-173
35a. Cost of maintaining asphalt pavements.....	173
36. Cost of asphalt-block pavements in various cities.....	210
37. Cost of brick pavements.....	228-230
38. Coefficients of quality of stones.....	260
39. Cost of quarrying and crushing stone.....	268
40. Number of cubic yards of broken stone required per mile of road....	271
41. Cost of broken-stone roads.....	281
42. Cost of broken-stone pavements in various cities.....	283
43. Cost of gravel pavements.....	301
44. Amount of water absorbed by Portland cement.....	336
45. Adhesive strength of mortars.....	345
46. Shearing strength of mortars.....	346
47. Tensile strength of mortars.....	347
48. Effect of size of grain of sand on tensile strength of mortar.....	350
49. Character of sieves for sifting sand....	350
50. Resistance to traction on different road-surfaces.....	373
51. Tractive force on a level.....	375
52. Resistance of gravity on different grades.....	375
53. Tractive power of horses at different velocities.....	378
54. Duration of a horse's daily labor and maximum velocity unloaded....	378
55. Increase in tractive power.....	378
56. Maximum amount of labor a horse is capable of performing at different velocities.....	379
57. Gross load which a horse can draw on different grades.....	380
58. Effect of grades upon the loads a horse can draw on different pavements.....	381
59. Force required to draw loaded vehicles on inclines and equivalent level roads.....	383
60. Best width of wheel-tires.....	384
61. Coefficient of resistance for different pavements.....	408
62. Methods of designating grades.....	414
63. Number of acres required per mile for different widths of roadways....	417
64. Amount of transverse rise for different pavements.....	418
65. Natural slopes of earth.....	425
66. Lengths and angles of slopes.....	425

NUMBER	PAGE
67. Amount of powder required.....	443
68. Capacity of drill-holes	443
69. Coefficient for different earth-slopes.....	451
70. Earth-work table.....	458
71. Cost and weight of vitrified culvert-pipe.....	471
72. Cost and weight of Portland-cement pipe.....	471
73. Dimensions, weight, and prices of iron pipe.....	472
74. Dimensions of box-culverts.....	474
75. Thickness of arches	476
76. Thickness of abutments.....	478
77. Dimensions, weight, and prices of drain-tile.....	479
78. Discharging capacity of circular pipes.....	479
79. Span and dimensions of bridges.....	484
80. " " " " " ".....	485
81. Coefficients for thickness of retaining-walls.....	492
82. Width, maximum grade, and average width of sidewalks in several cities	508
83. Street statistics of various cities	526
84. Number of square yards that one ton of prepared rock asphalt will lay.....	530
85. Composition of dirt from paved streets.....	623
86. Amount of refuse collected from city streets	623
87. Average cost per head of population for street maintenance in various cities	627
88. Wages in European countries.....	793
89. The amount of one dollar at compound interest for a term of years. 800-802	
90. The annual sinking fund that with compound interest will amount to one dollar at the end of a term of years.....	803-805

LIST OF ILLUSTRATIONS.

FIGURE	PAGE
1. Roman pavements.....	100
2. Cobblestone pavements.....	100
3. Belgium block pavement	100
4. Early granite-block pavements.....	100
5-7. Improved granite-block pavement.....	108
7a, 7b. Street-intersection paved with granite blocks.....	106, 107
8. Cobblestones on steep grades	112
9, 10. Granite block on steep grades.....	112
12. Section showing joint-filling.....	128
13. Plan of street paved with wood blocks.....	128
13a. Pavement of round blocks.....	129
14, 15, 15a, 15b. Sections of asphalt pavements.....	158, 159
15c, 15d. Asphalt with brick gutter.....	168
16, 17. Hale brick pavement.....	220
18. Section of brick pavement on concrete.....	220
19. Plan showing arrangement at junction.....	220
19a. Plan of brick paving at street intersections.....	224
19b. The Hayden paving-block.....	281
19c. Cross-section macadam road with brick trackway.....	244
19d. Cross-section brick trackway underdrained.....	244
20. Broken-stone pavements in France previous to 1775.....	247
21. Tresaguet's system.....	247
22. Telford's system.....	247
23. Macadam's system.....	247
24. Shape of stone for broken-stone pavements.....	265
25-28. Type sections of broken-stone pavements.....	296
29-32. Stone trackways.....	304, 305
32a. Cross-section of steel trackway.....	317
33. Form of briquette for testing tensile strength of cement.....	841
34. Clamps for holding briquette.....	841
35. Cement-testing machine.....	841
36. Diagram, resolution of forces in overcoming obstacles on roads.....	866

FIGURE	PAGE
37-39. Diagrams illustrating resistance of penetration.....	368, 369
40. Resolution of the force of gravity on inclined planes.....	376
41. Mechanical advantage of wheels.....	387
42. Contour map.....	393
43. Map of preliminary surveys.....	394
44. Preliminary profile.....	395
45. Diagram road between two distant towns.....	399
46. Simple curve.....	402
47. Compound curve.....	402
48. Reverse curve.....	402
49. Double reverse curve.....	402
50. Construction profile.....	405
51-53. Application of vertical curves.....	415
54. Transverse contour of streets.....	419
55. Transverse contour for country roads.....	419
56. Hillside road showing stepping of slopes and retaining-walls.....	428
57. Formation of embankments by end dumping.....	430
58. " " " " layers.....	431
59. Usual method of forming embankments.....	432
60. Embankments over plains.....	433
61, 62. Embankments on hillsides, manner of stepping the slope.....	437
63-65. Embankments of rock-slopes.....	438, 439, 440
66-68. Formation of a road in the face of a cliff.....	440
69. Profile of cut and fill illustrating calculation of overhaul.....	446
70-76. Examples of earthwork cross-sections.....	449
77. Examples of profile and cross-sections of earthwork.....	452
78. Cross-section of blind drain.....	458
79. " " pole drain.....	458
80. " " stone drain.....	458
81. " " tile drain.....	458
82. Protection of drain-outlet.....	458
83, 84. Silt-basins.....	458
85-89. Examples of the drainage of country highways.....	461
90. Section of country highway.....	463
91. Drainage of road in embankment.....	463
92. " " suburban streets.....	463
93-96. Head-walls for pipe-culverts.....	463
96a. Wing abutment for single pipe-culvert.....	469
96b. Head-wall for double pipe-culvert.....	469
96c. Head-wall for triple pipe-culvert.....	470
96d. Section of pipe-culvert.....	470
97-101. Examples of box-culverts.....	473
102-108. Examples of arch-culverts.....	475, 477
109-124. Types of timber bridges.....	483
125-133. Simple timber bridge.....	484, 485, 486


FIGURE	PAGE
133a. Iron swing-bridge.....	487
133b, 132c. Types of iron bridges.....	488
133-136. Examples of retaining-walls.....	489
137-139. " " road construction along the seashore or margin of rivers.....	494, 495
140. Examples of mound and ditch fence.....	496
141, 142. Arrangement of city streets....	502, 508, 505
143, 144. " " street-intersections.....	509, 510
145. Crowns in street gutters.....	512
146-148. Arrangement of streets with opposite sides at different levels.	512, 518
140. Sub-foundation drainage of streets.....	514
150-153. Examples of catch-basins.....	515, 516
153a. Examples of sewer inlet.....	519
153b. Sewer inlet without basin.....	520
154, 155. Surface-drainage at street-intersection	521
156. Objectionable form of water-way at street crossings.....	521
157. Street monument.....	522
158, 159. Example of widening carriageway at street-intersections.....	524
160. Improper method of dressing flag- and bridge-stones.....	529
161. Drainage of park walks.....	554
162-166. Fire-clay curb.....	566
167. Iron curb.....	566
168. Granite curb, Washington, D. C.....	568
169. Bluestone curb.....	568
170, 171. Hollow curb.....	570
172. Arrangement of gutter-stones.....	571
173-176. Examples of crossings and gutters.....	574, 575
177. Tree-protection.....	651
178. Setting slope-stakes.....	652
179. " out culverts on horizontal ground.....	653
180, 181. Setting out culverts on sloping ground.....	654
182. Setting out vertical curves.....	656
183. " stakes for street contours.....	657
184. " " " curb.....	657
185. " " " any structure.....	658
186. Bush-hooks.....	710
187. Axe mattock.....	710
188. Pick mattock.....	710
189. Grading-pick.....	711
190. Clay-pick.....	711
191. Shovels.....	711
192. Grading-plough.....	712
193. Hardpan-plough.....	712
194, 195. Drag-scraper.....	718
196. Pole-scraper.....	714

FIGURE	PAGE
197-199. Wheeled scraper.....	715
200-202. Wheelbarrows.....	716
203. Earth-cart.....	717
204, 205. Dump-cars.....	718, 719
206, 207. Dump-wagon.....	721
208-210. Mechanical graders or road machines.....	722, 723
211, 212. New Era grader.....	724
213. Surface-grader.....	726
214. Road-leveller.....	726
215. Draining-tools.....	727
216. Hand-drilling tools.....	729
217. Steam-drill.....	731
218. Portable boiler.....	733
219. Straight-edge.....	734
220. Roadbed-roller.....	735
221. Sprinkling-cart.....	735
232-233. Stone-crushers.....	740-745
234. Stone-screen.....	746
235, 236. Engines and boilers.....	747, 748
237-241. Stone-crushing plants.....	749-751
242. Stone-distributing cart.....	252
243-246. Horse-rollers.....	252-254
247-251. Steam-rollers.....	757-760
252-254. Paving-hammers.....	761
255-259. Paving-rammers.....	762
260. Asphalt rammers.....	762
261. Asphalt smoothing-iron.....	762
262. Fire-pot roller.....	763
263. Portable fire-box.....	763
264, 265. Steam-rollers for asphalt.....	764
266. Asphalt-mixing machine.....	765
267. Surface-heater for asphalt.....	766
268, 269. Concrete-mixing machines.....	767, 768
270. Sand-dryer.....	769
271. Portable heater for asphalt.....	769
272-276. Sweeping-machines.....	770-772
277. Scraping-machine.....	775
278-280. Patrol-cart.....	774, 775
281. Hand-scoop.....	775
282. Hand-sweeper.....	776
283. Dump-cart.....	776
284-286. Combined sweeping-and collecting-machines.....	777-779
287, 288b. Street-sprinklers.....	780, 782
289, 290. Snow-ploughs.....	783
291-297. Tools for artificial stone pavements.....	784

LIST OF ILLUSTRATIONS.

xxvii

FIGURE	PAGE
298. Iron catch-basin.....	785
299-300. Gutter-gratings.....	786
301. Sewer inlet-trap.....	787
302, 303. Inlet for broken-stone roads.....	787
304, 305. Gutter crossing.....	788
306. Gutter boxes.....	789



INTRODUCTION.

HISTORICAL SKETCH.

ROADS are pathways formed through a country to facilitate the movement of persons and exchange of commodities. They are of various kinds, according to the state of civilization and wealth of the country traversed; thus, they range from rude paths, passable only by pedestrians, to the comparatively perfect modern road, passable alike by persons and vehicles.

The motive for the formation of roads is found (1) in the inquisitive spirit of man, and his desire for intercourse with his fellows; (2) in the necessity of obtaining provisions for his sustenance in times of scarcity; and (3) in the desire to gratify his fancies with the products of other localities.

With the progress of civilization and the congregation of men in cities and towns their wants multiply, and the products of the earth have to be collected and transported to supply them. This collecting, transporting, and exchanging of products is trade or commerce, and its importance and expansion are directly proportional to the facilities afforded.

Countries inhabited by the least civilized people whose wants are supplied by nature in the immediate vicinity of their dwellings are almost destitute of roads; hence it has come to be said that roads are the physical symbol by which to measure the progress of any age or people. "If the community is stagnant, the condition of the roads will indicate the fact; if they have no roads, they are savages."

Although roads are the offspring of civilization, they have be-

come the chief factors, if not indeed the means, for its advancement. Without them the invention of printing and other arts so beneficial to the welfare of men would separately be ineffectual, or productive of advantages of a very limited extent. Without roads, the interchange of advantages, moral, intellectual, and physical, which now takes place in all highly civilized countries between the rural and urban population, could not be maintained; without them, indeed, large towns or cities could not continue to exist. The supply of the population collected in such places, with the various products of agriculture necessary to their physical existence, could not be sustained. Nor, on the other hand, would the rural population affording that supply be benefited by a return in exchange of the refinements of the town, and the various articles of luxury and necessity obtained by commerce from every part of the globe.

It is frequently asserted that, since the introduction and development of railroads, the latter have assumed to a greater and greater degree the functions of the common road, and that highways are no longer an indication of progress. This is true to only a limited extent. Railroads have changed the character of the traffic on the common roads, and personal travel for business or pleasure is no longer dependent upon the condition of the highways; but commercial intercourse as represented in the exchange of products is as much dependent upon the condition of the public road to-day as it ever was, for the reason that it is impossible to construct a railroad to the door of each producer and consumer. Hence railroads never can supersede the common road, and every ton of freight carried by them must be conveyed over a highway at either or both terminals, and the cost of this highway transportation has a marked influence not alone upon the price paid by the consumer, but also on the profit realized by the producer.

If railroads may be compared to the arteries of a living body, then the common roads are the veins, and each is equally necessary in quickening and communicating life to the parts to which they lead. But the true relation between railroads and wagon-roads frequently seems to be lost sight of; the functions of each are quite different and in no sense rivals. The highway serves the very important purpose of effecting local intercourse and of connecting the local freight and passenger traffic with the railroad service. Roads running parallel to the railroad and connecting towns al-

ready joined by the railroad are of but little importance. It is the roads running at an angle with the railroad and connecting it with the country to the right and left, thus acting as feeders, that require attention in modern times. In Baden, Germany, this relation of the roads to the railroads was early recognized by striking from the list of state roads all those that ran parallel to the railroad or had lost their importance by its construction, in order to save funds for the support of the others; while most of those running across the railroad, if they crossed at a station so that they served as feeders, were raised to the grade of state roads.

The word "road" is derived from the Anglo-Saxon *rad*, a riding, and *ridan*, to ride, and as generally used it means a public highway, although, as a generic term, it is applied to any kind of a path open to travel.

The word "highway" is probably the more correct term when applied to a traveled thoroughfare, but custom has established the propriety of using the word "road."

The word "highway" is used several times in the Old Testament, while the word "road" is used but once.

As to when paved roads were first introduced little is known; we find here and there in the works of the ancient historians occasional mention of road construction. Herodotus speaks of a great Egyptian road, constructed under King Cheops, upon which 100,000 men were employed for ten years. Strabo informs us that the city of Babylon was paved about the year 2000 B.C., and that three great highways ran from there to Suza, Ecbatana, and Sardes. The highway leading from Babylon to Memphis was paved at an early date, and along it arose the cities of Nineveh, Palmyra, Damascus, Tyre, Antioch, and other great commercial cities.

The importance of roads to the welfare of nations was not unknown to the ancients. The senate of Athens, the governments of Lacedæmon, Thebes, and other states of Greece, bestowed much care upon them. The Carthaginians were systematic and scientific road-makers; they built up and consolidated an empire so prominent in military and naval achievements and in the arts and industries of civilized life that for four hundred years it was able to hold its own against the preponderance of Greece and Rome.

The Romans learned the art of making paved roads from the Carthaginians, and the highways constructed by them are great monuments in this department of art.

The first Roman road was constructed under the direction of the censor Appius Claudius (312 B.C.). This road, named after him the Appian Way, was frequently, on account of its excellence, called the "queen of roads." Under Augustus and Julius Cæsar the Roman capital was made to communicate with all the chief towns by paved roadways, and during the last African war a road of this kind was constructed from Spain through Gaul to the Alps. Later these great lines of communication were extended through Savoy, Dauphiné, and Provence; through Germany, every part of Spain, through Gaul, and even to Constantinople; through Hungary, Macedonia, and to the mouths of the Danube. Neither did the interposition of seas obstruct the labor or daunt the enterprise of this great people. The lines of communication thus constructed to the shores of the continent of Europe were continued at corresponding points of the neighboring islands and continents. Sicily, Corsica, Sardinia, England, Africa, and Asia were accordingly penetrated and intersected by roads, forming the continuation of the great European lines. These gigantic works were the most solid structures of their kind which have been formed in any age, and many of them still remain, often forming the foundation of modern roads and in some instances constituting the road-surface now used. From these remains and the accounts of ancient writers we are enabled to follow the methods employed in their construction. The engineering appears to have been very simple. A prominent landmark was selected in the direction desired, and the road located on an absolute straight line without reference to intervening obstacles.

The roads were divided into two classes: (1) Private roads, the use of which was free, while the soil remained private property; and (2) public roads, of which the use, the management, and the soil itself were alike vested in the state. The public roads were divided into three classes. The military roads were called "prætorian roads," being under the immediate government of prætors, or military superiors. The high roads were called "consular roads," because they were made and maintained by the authority of the consuls; and the local roads leading from the consular roads to small places were called "vicinal roads." The width of the

roads varied from 8 to 20 feet, and the method of construction was as follows: Two shallow trenches, called *sulci*, were first dug parallel to each other, marking the width of the road. The space between them was excavated to solid ground; in this excavation the road materials were placed, arranged in four layers having a total thickness of about three feet: (1) The *statumen*, or foundation, consisting of two courses of large flat stones laid in lime-mortar, or of stones not smaller than the hand could grasp; (2) The *rudus*, composed of broken stones mixed with one third their quantity of lime-mortar, and forming a layer about 9 inches in thickness; (3) The *nucleus*, composed of fragments of brick, stones, and pottery, set in lime-mortar, and about 6 inches thick; (4) The *summa crusta*, or *pavimentum*, composed of large irregularly shaped stones about 6 inches thick, closely jointed and fitted with the utmost nicety. These roads bore uninjured the weight of columns, obelisks, and other immense blocks of stone weighing hundreds of tons; notwithstanding this, the utmost weight which each class of vehicle was permitted to carry was regulated by law, and those laws were strictly enforced. Although these roads were eminently durable, they were deficient in the other qualities requisite for a good road, and Horace states that they were "less fatiguing to people who travel slowly."

Streets were paved with large polygonal blocks, laid as described above, and footways with rectangular slabs. Specimens are still to be seen in Rome and Pompeii.

The curator viarum of the Romans was an official of distinction, wielding great authority, and Plutarch tells us of Caius Gracchus that when he was appointed supreme director for making roads, the people were charmed to see him go forth on his tours of road-making followed by such numbers of ambassadors, magistrates, architects, and artificers.

When the Romans conquered Gaul they found many roads or trails from three to six feet wide, and the French archæologists tell us that nearly 13,000 miles of these trails were improved by the invaders.

In Peru the Incas built great roads, the remains of which attest their magnificence. Humboldt in his "Aspects of Nature" speaks of the mountain road from Quito to Cuzco as "a marvellous work, not inferior to the most imposing Roman roadways." It was from

1500 to 2000 miles in length, and most of it was at an elevation of over 12,000 feet above the level of the sea; it was 20 feet wide and paved with stones 10 feet square, and had a running stream and a row of shade-trees on each side. Prescott in his "History of Peru," in speaking of this road, says that "it was conducted over sierras covered with snow; galleries were cut through the living rock; rivers were crossed by means of bridges swung suspended in the air; precipices were scaled by stairways hewn out of the native bed, and ravines of hideous depth were filled up with solid masonry."

In the breaking-up of society which followed the decline of the Roman Empire, the roads fell out of repair and finally into ruin. During the Dark Ages they were regarded with terror as aids to plunder, and such intercourse as was maintained took place almost exclusively by rude paths capable of being passed on foot, or at best by horses. With the reconstruction of society in Europe the roads gradually became practicable for pack-animals and the rude vehicles of the time; but no serious attempt was made to restore or replace the public highways until the middle of the eighteenth century. About this time the revival of road construction was almost simultaneous in England and France, and shortly afterwards the other chief countries of Europe took up the matter.

Among the first laws passed in England on the subject of roads is one in the year 1285, directing that all bushes and trees along the roads leading from one market to another should be cut down for 200 feet on either side, to prevent robbers lurking therein, and providing "that when any highway is worn deep and inconvenient that another shall be laid out alongside." Henry VIII. also made provision under this head by enacting "that two justices of the peace and twelve other men of wisdom and discretion shall choose fresh routes when the old ones are worn out." In 1346 Edward III. authorized the first toll to be levied for the repair of the roads. In 1523 the English Parliament passed the first act relative to the improvement of the public roads.

Regarding the condition of the English highways a hundred and fifty years ago, Lord Macaulay tells us that it was no uncommon thing for the fruits of the earth to rot in one place when a score of miles away the people were suffering from a scarcity of the very food which was spoiling and almost within their reach. The roads

were so wretched that the food could not be transported. At this time each parish was obliged to build and maintain the roads within its confines, and it not infrequently happened that a poor and impoverished agricultural community was expected to maintain a highway between two rich and prosperous towns.

Mr. Arthur Young in his "Six Months' Tour in the North of England" gives us the following account of the state of the roads at that time (1770): "I know not in the whole range of language terms sufficiently expressive to describe this infernal road. Let me most seriously caution all travellers who may accidentally propose to travel this terrible country to avoid it as they would the devil; for a thousand to one they break their necks or their limbs, by overthrows or breaking-downs. They will here meet with ruts, which I measured, actually four-feet deep, and floating with mud only from a wet summer. What, therefore, must it be after a winter? The only mending it receives is tumbling in some loose stones, which serve no other purpose than jolting a carriage in the most intolerable manner. These are not merely opinions, but facts; for I actually passed three carts broken down in these eighteen miles of execrable memory."

England sought to improve the ill-condition of her highways by the establishment of a comprehensive system of turnpikes, and before the beginning of this century thirty thousand miles of these roads had been built; but they were constructed in such an imperfect manner that they were but little improvement on the old roads. Even as late as 1809 the roads answered the description of Mr. Young, and little improvement was effected till the advent of MacAdam and Telford. Contemporaries and in some respects advocates of rival systems, to these two men England owes her present admirable system of roads; and Charles Dickens wrote: "Our shops, our horses' legs, our boots, our hearts, have all been benefited by the introduction of MacAdam."

The French and the Swiss probably have the best highways of any of the European countries. Until the time of Louis XIV. the roads of France received no more attention than did those of England. This monarch had several fine roads made in the environs of Paris for his personal use and pleasure. They were very wide and paved only in the centre. Shortly after the construction of these royal roads the nation began to appreciate the advantage of good

roads, but it was not until the advent of the first Napoleon that the modern system of magnificent highways was inaugurated, solely for military purposes, and this object has never been lost sight of ; so that, although in modern times their use as a means of communication for the people accounts for their great and increasing number, it is largely owing to their military character that the French government expends the enormous sums it does annually on the national roads.

The material and financial prosperity, thriftiness, and contentment of the French people has long excited the admiration of the world; neither internal revolution nor defeat from abroad appears to have entailed upon them burdens too heavy for them to bear. Students of economic problems ascribe this marvellous condition to the far-reaching and splendidly maintained system of highways, on which the obstacles to economical transportation have been reduced to the minimum.

In the United States the highways have not improved as rapidly as other institutions; in fact, they are very inferior to those of Europe. The reason for this may be attributed to several causes, among which may be mentioned (1) the excellence of the railroad systems and waterways; (2) the indifference of those in charge of highway maintenance; (3) the want of appreciation of the benefits of good roads and the fear of increased taxation on the part of the rural population; (4) the dispersion of the people over large areas in their search for desirable localities for residence; and (5) the ill-effects of the system requiring the personal service of the rural population on the highways.

The experience of Europe in road improvement shows that the highways should be taken as much as possible out of the hands of local authorities, and administered by either national or state governments in accordance with the needs of the people who use the roads; and that as the whole public is benefited by good roads, therefore all should pay for their improvement and maintenance. This view of the subject is not new in the United States, for Washington recommended in a letter to Patrick Henry that the roads of Virginia be taken away from the control of the county courts and be given to the State authorities. One of Hamilton's pet schemes was that of road improvement, and he recognized thoroughly that roads left to local authority would never be satisfac-

torily built. During the past ninety years there has been more or less national legislation in regard to common roads. Several very comprehensive measures have passed one or another of the Houses of the National Congress, but the only road of any consequence constructed by the government was the national road (650½ miles in length, 80 feet in width, and macadamized for a width of 30 feet), which it originally was intended should go from the tide-water of the Atlantic Ocean to the Ohio River. It was built from Cumberland in Maryland to a point in Ohio several hundred miles from the Ohio River, and there it was allowed to stop, being finally donated to the States through which it passes. In this way ended the first great effort of the Federal Government to build and establish, as the Constitution of the United States contemplated, a system of post-roads all over the country.

The date of the first introduction of street pavements cannot be determined with certainty. Livy informs us that in the year 584 (about 170 B.C.) the censors caused the streets of Rome to be paved from the ox market to the temple of Venus. Streets paved with lava, having deep ruts worn by the wheels of chariots, and raised banks on each side for foot-passengers, are found at Pompeii and Herculaneum.

Abderahman, the caliph of Cordova, Spain, caused the streets of that city to be solidly paved, A.H. 236 (A.D. 950), and a man might walk after sunset ten miles in a straight line by the light of the public lamps.

The earliest reference to street pavements in the British Isles is found in the records of the city of Glasgow. In the year 1577 the council resolved to spend £200, "to big the calsayis," or, to modernize it somewhat, to build the causeways.

The date of the first introduction of pavements into London is unknown, but the streets of that city were not paved at the end of the eleventh century. It is related that in the year 1190 the church of St. Mary-le-Bow in Cheapside was unroofed by a violent wind, and that four pillars, 26 feet in length, sunk so deep into the ground that scarcely 4 feet of them appeared above the surface of the soft earth forming the street. Holborn was first paved in 1417, and Smithfield in 1614. The first act for paving and improving the City of London was passed in 1532. The streets were described in the simply-worded statute as "very

foul, and full of pits and sloughs, so as to be mighty perilous and noxious, as well for all the king's subjects on horseback as on foot with carriages" (litters).

The capital of France was not paved in the twelfth century, for Rigord, the physician and historian of Philip II., relates that, the king standing one day at a window of his palace near the Seine and observing that the carriages which passed threw up the dirt in such a manner that it produced a most offensive stench, his majesty resolved to remedy this intolerable nuisance by causing the streets to be paved, which was accordingly done. The orders for this purpose were issued by the government in the year 1184, and upon that occasion, it is said, the name of the city, which was then called Lutetia, on account of its dirtiness, was changed to that of Paris.

Dijon, France, had paved streets as early as 1391, and it is remarked by historians that after this was done dangerous diseases, such as dysentery, spotted fever, and others, became less frequent in that city.

In the United States, Boston, Mass., appears to have been the first city to pave its streets, for when Josselyn visited that city in 1663 he found many streets paved with pebbles; and Ward said in 1699: "The buildings, like their women, being neat and handsome, and their streets, like the hearts of the male inhabitants, are paved with pebble." Drake says that the paving of the public streets began very early and was made of importance after 1700; the sidewalks were also early paved with cobblestones and flags.

We learn that the first regular paving of a Philadelphia street was due to an accident. A man on horseback being mired and thrown from his horse, breaking his leg, a subscription was raised and the street paved with pebbles from the river-bank. In 1719 many sidewalks were being paved with brick and the cartway with cobblestone.

In 1750 the grand jury represented the great need of paved streets, "so as to remedy the extreme dirtiness and miry state of the streets;" but the first general effort worthy of mention to pave the streets was made in 1761-62, and then the only means applied to the purpose was that produced by lotteries.

In New York City the first stone pavement appears to have

been laid in about the year 1657 on Brower Street, between Broad and Whitehall, and known to-day as Stone Street.

The division of streets into carriageways and footways appears to have been first practised in 1614, in which year the citizens of London began to pave the margins of the streets before their doors, but the middle of the streets was paved with large pebbles very unevenly. In 1761 raised footways of square granite blocks were used in Westminster and for London generally in 1766.

In 1704 the Common Council of Albany, N. Y., ordered "that ye streets be paved before each inhabitant's door within this city, eight foot breadth from their houses and lotts, before ye 25th of October next ensuing, upon penalty of forfeiting the summe of 15 shillings for ye Behooffe of ye sheriffe, who is to sue for ye same."

In New York the first footwalks were laid in 1790, on the west side of Broadway, from Vesey to Murray Street, and opposite for the same distance along the Bridewell fence. They were narrow pavements of brick and stone, scarcely wide enough to permit two persons to walk abreast.

In 1696 the first contract for cleaning the streets of New York was made. Prior to this the work had been done by the citizens, every man being required to keep the street clean before his door.

In 1697 the first attempt at lighting the streets of New York was made. This was done by hanging out a lantern with a candle in it upon the end of a pole from the window of every seventh house on the nights when there was no moon, the expense being divided equally among the several houses.

Authority to construct toll-roads was first granted in England, in 1346, but their construction did not become general until 1676, and they were entirely abolished in 1878.

In the United States the first toll-road company was incorporated in Pennsylvania in 1792, to construct and maintain an artificial road from Philadelphia to Lancaster, a distance of about 70 miles. The framers of the act authorizing the construction of this road recognized the importance of the relation between the load and the width of the wheel-tire. The rate of toll was graded according to the width of the tire, and the maximum load to be carried by the different widths of tire was distinctly stated. Vehicles with tires of less breadth than four inches were not

allowed to carry more than two and a half tons between the first day of December and the first day of May, and not more than three tons during the rest of the year.

The act also provided for the placing of milestones and the erection of guide-posts at all intersecting roads, with the name of the place to which they led and its approximate distance in miles.

Though considerable advance in processes and machines have been made during the past hundred years, the two chief factors in the preservation of roads so ably regulated in the above mentioned act are still the same, and in many cases are the cause of the evils we suffer from in the shape of bad highways.

A TREATISE ON HIGHWAY CONSTRUCTION.

CHAPTER I.

PAVEMENTS.

1. General Considerations.—The object of a pavement is (1) to secure a water-tight covering that will preserve the natural soil from the effects of moisture, and not, as commonly supposed, to support the vehicles, the weight of which and that of the covering material must be actually borne by the natural soil. (2) To furnish a smooth surface on which the force of traction will be reduced to the least possible amount, and over which vehicles may pass with safety and expedition at all seasons of the year.

2. The Qualities essential to a good pavement may be stated as follows:

- (1) It should be impervious.
- (2) It should afford good foothold for horses.
- (3) It should be hard and durable, so as to resist wear and disintegration.
- (4) It should be adapted to every grade.
- (5) It should suit every class of traffic.
- (6) It should offer the minimum resistance to traction.
- (7) It should be noiseless.
- (8) It should yield neither dust nor mud.
- (9) It should be easily cleaned.
- (10) It should be cheap.

3. Interests affected in the Selection.—Of the above requirements, numbers 2, 4, 5, and 6 affect the traffic and determine the cost of haulage by the limitations of loads, speed, wear and tear of horses and vehicles. If the surface is rough or the foothold bad, the weight of the load a horse can draw is decreased, thus necessitating the making of more trips or the employment of more horses and vehicles to move a given weight. A defective surface necessitates a reduction in the speed of movement and consequent loss of time; it increases the wear of horses, thus decreasing their life-service, and lessens the value of their current services; it also increases the cost of maintaining vehicles and harness.

Numbers 7, 8, and 9 affect the occupiers of the adjacent premises, who suffer from the effect of dust and noise; and second, the owners of said premises, whose income from rents is diminished where these disadvantages exist.

Numbers 3 and 10 affect the taxpayers alone, first as to the length of time during which the covering remains serviceable, and second as to the amount of the annual repairs. Number 1 affects the adjacent occupiers principally on hygienic grounds. Numbers 7 and 8 affect both traffic and occupiers.

4. Selection of Pavements.—In the selecting of the most suitable pavement, whether for a street or a country road, all classes of citizens are alike interested; for of all the systems of intercommunication none is brought into more direct contact with the people than the public highway, and its effect upon the price of commodities is felt by all. Not a ton of agricultural or mechanical produce can reach its destination without first and last paying toll to the condition of the highway over which it has to be hauled; in the form of time, wear and tear of horses, harness, and vehicles thus enhancing its cost to the consumer without any increased benefit to the producer, who must be compensated for the cost of all unnecessary expenses of transportation due to the ill condition of the highway.

5. Cost of Wagon Transportation.—It is apparent that but few people comprehend the cost of transportation by horses and wagons, or realize the amount of money annually wasted by the ill condition of the roadways.

Table I shows from actual observation the cost of moving a load of one ton a distance of one mile on level roadways with

different pavements in the usual condition in which they are maintained. The excessive amount of these charges is seen when it is remembered that the same goods using the roadways are now carried by the railroads at an average cost of $\frac{1}{10}$ of a cent per ton-mile.

TABLE I.

COST OF TRANSPORTATION BY HORSES AND WAGONS PER TON-MILE ON DIFFERENT ROAD-COVERINGS.

Iron rails.....	1.28	cents per ton-mile	
Asphalt.....	2.70	"	"
Stone, paving, dry and in good order.....	5.88	"	"
" " ordinary condition.....	12.00	"	"
" " covered with mud	21.80	"	"
Broken stone, dry and in good order.....	8.00	"	"
" " moist " " "	10.80	"	"
" " ordinary condition.....	11.80	"	"
" " covered with mud.....	14.80	"	"
" " ruts and mud.....	26.00	"	"
Earth, dry and hard	18.00	"	"
" ruts and mud.....	39.00	"	"
Gravel, loose.....	51.60	"	"
" compacted.....	12.80	"	"
Plank, good condition.....	8.80	"	"
Sand, wet.....	32.60	"	"
" dry.....	64.00	"	"

6. In 1890 the railroads of the United States carried over 600,000,000 tons of freight. Most if not all of this had to be handled at one or both terminals in wagons. If the distance hauled was but one mile and the rate per ton-mile $22\frac{1}{4}$ cents, which is the average rate of haulage, the cost would be \$133,500,000. The low rate of railroad transportation has been achieved by careful and scientific study, and by daily attention to every portion of the road-bed and rolling stock. Defective parts are instantly removed and new ones substituted so that the road is always in good order. But pavements once laid are left to batter the vehicles, and the vehicles, in return, to pound the pavements: little or no attention being paid to them until they finally become unendurable and are entirely renewed. Moreover, on every well-managed railroad the statistics of cost of transportation are the subject of the most scientific study, and at the end of each year it is exactly ascertained

just how much it has cost to haul a ton of freight one mile, and what proportion of this is for train service, what for maintenance of rolling stock, what for maintenance of way, and so on; whereas very few engineers in charge of highways have attempted to find out accurately what is the relative damage done to vehicles and horses by different kinds of pavements, what is the relative amount of force required to draw a unit of weight on different surfaces, what is the relative cost of maintaining different pavements during a term of years under a unit of traffic, or what is the exact proportion of horses falling on different surfaces.

7. Effect of Reducing the Cost of Wagon Transportation.—If the cost of wagon transportation could be reduced by the improvement of the highways to, say, five cents per ton-mile, what would be the result? It would create an annual saving of many millions of dollars and it would put in motion a large tonnage of various kinds of merchandise that cannot now be handled with profit; it would give a large margin of profit on many products which are now moved with little profit, and would directly benefit both the producer and the consumer.

The cost of wagon transportation over the roads of France does not exceed one third the like expense in America, it being common in rural districts to haul three tons and in the cities from three to five tons net freight with one horse.

8. Problem involved in the Selection of Pavements.—The problem involved in the selection of the most suitable pavement is composed of the following factors: first, adaptability; second, desirability; third, serviceability; fourth, durability; fifth, cost.

9. Adaptability.—The best pavement for any given roadway will depend altogether on local circumstances. Pavements must be adapted to the class of traffic that will use them. The pavement suitable for a road through an agricultural district will not be suitable for the streets of a manufacturing centre, nor will the covering suitable for heavy traffic be suitable for a pleasure-drive or a residential district.

General experience indicates the relative fitness of the several materials as follows:

For country roads, suburban streets, and pleasure-drives, broken stone. For streets having heavy and constant traffic, rectangular blocks of stone laid on a concrete foundation with the joints filled

with bituminous or Portland cement grout. For streets devoted to retail trade and where comparative noiselessness is essential, asphalt, wood, or brick.

10. Desirability.—The desirability of a pavement is its possession of qualities which make it satisfactory to the people using and seeing it. Between two pavements alike in cost and durability, people will have preferences arising from the condition of their health, personal prejudices, and various other intangible influences, causing them to select one rather than the other in their respective streets. Such selections are often made against the demonstrated economies of the case, and usually in ignorance of them. Whenever one kind of pavement is more economical and satisfactory to use than is any other, there should not be any difference of opinion about securing it, either as a new pavement or in the replacement of an old one.

Popular prejudices about pavements affect the prices of real estate upon paved streets, and so help to determine their desirability. A stranger's impression of a city or town depends largely upon the ease with which he can go from place to place in the transaction of business or in the pursuit of pleasure, and he is pleased or displeased exactly in proportion to the smoothness of his journey or the ruggedness of his way. Massive business blocks, pretentious private residences, stately public buildings, beautiful parks and lawns, possess no attraction for one who is compelled to pick a way for his feet and keep his eyes on the ground for fear of stumbling over jagged stones or falling in the mud. To man and beast alike, the roadway that offers a few or no obstacles to easy travel is a delight which shortens the journey by mitigating the pangs of fatigue.

To persons who ride for pleasure or for health, rough pavements cause great annoyance. The pleasure of fast driving in the parkways or roadways devoted to that purpose is defeated by the necessity of jolting over rough pavements until the driveway is reached, and in the case of invalids the rough roadways prevent the taking of air altogether in many cases.

11. The economic desirability of pavements is governed by the ease of movement over them, and is measured by the number of horses or pounds of tractive force required to move a given weight, usually one ton, over them. The following table shows the relative

tractive force required upon level roads formed of different materials, asphalt being taken as the standard of excellence in this respect:

TABLE II.

NUMBER OF HORSES REQUIRED TO MOVE ONE TON ON DIFFERENT PAVEMENTS.

Asphalt.....	1.00
Stone blocks, dry and in good order.....	1.50 to 2.00
“ “ in fair order.....	2.00 “ 2.50
“ “ covered with mud	2.00 “ 2.70
Macadam, dry and in good order.....	2.50 “ 3.00
“ in a wet state.....	3.30
“ in fair order.....	4.50
“ covered with mud.....	5.50
“ with the stones loose.....	5.00 “ 8.20

See also Tables L and LI, pages 372 and 375.

12. From Table II it is seen that to move the same load at the same speed and for the same length of time, with the same fatigue to each horse, requires from $1\frac{1}{2}$ to 3 horses on stone block pavements, and $2\frac{1}{2}$ to $8\frac{1}{2}$ on macadam, while for asphalt but 1 is required.

If iron rails be taken as the standard of excellence, the number of horses required will be as follows:

Iron rails.....	1
Asphalt.....	$1\frac{1}{2}$
Stone block, best condition.....	$3\frac{1}{2}$
“ “ ordinary condition.....	5
“ “ bad “	8
Macadam	5.7 to 8
Cobblestones, good.....	6.6 “ 13.8
“ ordinary.....	25
Earth, dry.....	20
Sand.....	40

13. **Economy of Smoothness.**—From the above table the great economy of smoothness becomes at once apparent. But it is evident that, as in all lines of transportation, the greatest resistance regulates the load over the rest of the route, unless there be auxiliary power; so the continuity of the surface should remain unbroken by any other grade of material which would increase the resistance.

The advantages of smooth pavements to owners and users of horses and vehicles are enormous. With them one third greater loads could be moved; there would be no stuck teams, fewer worried, beaten horses, fewer angry, overworked drivers, and thus fewer delays and interruptions to business.

14. Serviceability.—The serviceability of a pavement is its quality of fitness for use. This quality is measured by the expense caused to the traffic using it, viz., the wear and tear of horses and vehicles, loss of time, etc. No statistics are available from which to deduce the actual cost of wear and tear. It has been estimated as follows:

On cobblestones.....	5	cents	per	mile	travelled
“ belgian block.....	4	“	“		
“ granite block.....	3	“	“		
“ wood.....	2.5	“	“		
“ broken stone in first-class condition...	1.2	“	“		
“ asphalt... ..	1	“	“		

The serviceability of any pavement depends in a great measure upon the amount of foothold afforded by it to the horses, provided, however, that its surface be not so rough as to absorb too large a percentage of the tractive energy required to move a given load over it. Cobblestones afford excellent foothold, and for this reason are largely employed by horse-car companies for paving between the rails; but the resistance of their surface to motion requires the expenditure of about 280 pounds of tractive energy to move a load of 1 ton. Asphalt affords the least foothold, but the tractive force required to overcome the resistance it offers to motion is only about 30 pounds per ton.

15. Comparative Safety.—The comparison of pavements in this respect is the distance travelled before a horse falls. The materials affording the best foothold for horses are as follows, stated in the order of their merit:

- (1) Earth dry and compact.
- (2) Gravel.
- (3) Broken stone (macadam).
- (4) Wood.
- (5) Sandstone and brick.
- (6) Asphalt.
- (7) Granite blocks.

16. The most complete observations made in the United States to ascertain the prevalence of accidents on the different pavements were made under the direction of Capt. F. V. Greene, the results of which show that a horse may travel before falling on

Asphalt (Trinidad).....	588 miles
Granite	413 "
Wood.....	272 "

17. Observations for the same purpose were made in London under the direction of Col. Haywood. The results were as follows. The three classes of pavements, wood, asphalt, and stone, were observed as nearly as was possible under the same conditions of space, weather, gradients, and soundness. The result of fifty days' observation showed that before meeting with an accident a horse would travel a far greater distance on wood than he could either on asphalt or stone. The following table shows the distance travelled by a horse before meeting with an accident:

DRY-WEATHER DISTANCES.

Wood.....	646 miles
Asphalt.....	223 "
Granite.....	78 "

DAMP-WEATHER DISTANCE.

Wood.....	193 miles
Asphalt.....	125 "
Granite.....	168 "

THOROUGHLY-WET-WEATHER DISTANCES.

Wood.....	432 miles
Asphalt.....	192 "
Granite.....	537 "

Another mode of observation gave the distance travelled as follows:

Wood.....	446 miles
Asphalt.....	191 "
Granite.....	132 "

18. The foregoing figures appear to show that

- (1) Asphalt was most slippery when merely damp, and safest when perfectly dry.
- (2) That granite was most slippery when dry and safest when wet.

(3) That wood was most slippery when damp and safest when dry. It will be noticed that only under a single condition, and that the least persistent, is granite safer than wood or asphalt, and that wood is safer than asphalt under all circumstances.

Granite was least safe and wood and asphalt most safe when clean.

19. Slight rain makes asphalt and wood more slippery than they are at other times. On asphalt the slipperiness begins almost immediately the rain commences. Wood requires more rain before its worst condition ensues. The slipperiness lasts longer upon wood, on account of its absorbent nature, than it does upon the asphalt. When dry weather comes after the rain, then asphalt is in its most slippery condition and horses fall upon it very suddenly. On wood their efforts to save themselves are more effectual. Wood is also frequently in that peculiar condition of surface in which horses slip or slide along it without falling. A small quantity of dirt on asphalt makes it very slippery. In damp weather granite blocks become very greasy and slippery; in dry weather, if of a hard variety, the surface polishes and becomes rounded and the only foothold is by the joints between the blocks.

In winter, during frost, asphalt is usually dry and safe; wood, retaining moisture, is very slippery. Under snow there is very little if any difference between the safety of asphalt and wood.

20. The difference in the results obtained by Capt. Greene and Col. Haywood may be due in the case of the wood and stone pavements to climatic causes. London is more damp and foggy than any one of the American cities in which the traffic was observed, and therefore its pavements would be more slippery. The difference in the asphalt returns may be accounted for by the difference in the character of the material. The asphalt pavements in London are made from natural bituminous rock, which makes a very smooth, hard surface, while the American pavements are made from natural bitumen mixed with sand, which forms a rough, granular surface. Moreover, these observations were made some eighteen years ago, at a time when asphalt was a new thing and its proper treatment very insufficiently understood. It was not then recognized that asphalt requires to be constantly and thoroughly cleansed in order to do justice to itself. That the number of falls on asphalt is decreasing as its use is becoming more extended is shown by the following:

In Berlin in 1885, 4403 horses fell on an area of 398,000 square yards of asphalt pavement, in 1887 the number was reduced to 2456, while the area had increased to 485,000 square yards.

That asphalt is but slightly more dangerous than some kinds of stone is shown by observations made at Paris some years ago in two streets, one paved with the hard sandstone much used in that capital, and the other with asphalt. In the street paved with stone one out of every 1308 horses fell, and in that paved with asphalt one out of every 1409 fell.

21. Slipperiness can be cured on both wood and asphalt: on the asphalt by sprinkling it with sand, on the wood by sprinkling it with gravel. The result in both cases is dirt. The sand thrown on the asphalt tends to wear it out; the gravel thrown on the wood tends to preserve it.

22. Kinds of Falls and their Causes.—The commonest falls on wood are falls on the knees, which are less likely to injure the horses and are less inconvenient to the traffic than other falls. Falls on haunches are more numerous on asphalt than on wood. Of complete falls there are fewest on wood and most on granite. The falls on asphalt are generally due to sudden pulling up and sharp turning; those on granite, to the excessive width of the blocks, which fail to afford proper foothold.

23. Durability.—The durability of a pavement is its quality, which relates to the length of time during which it is serviceable and not to the length of time it has been down. The only measure of the durability of a pavement *is the amount of traffic tonnage it will bear before it becomes so worn that the cost of replacing it is less than the expense incurred by its use.*

24. As a pavement is a construction, it necessarily follows that there is a vast difference between the durability of the pavement and the durability of the materials of which it is made. Iron is eminently durable, but as a paving material it is a failure.

25. Durability and Dirt.—The durability of a paving material will vary considerably with the condition of cleanliness observed. One inch of overlying dirt will most effectually protect the pavement from abrasion and indefinitely prolong its life. But the dirt is expensive, it injures apparel and merchandise, and is the cause of sickness and discomfort. In the comparison of different pavements no traffic should be credited to the dirty one.

26. A pavement so rough and insecure that the traffic is kept off the road might be a most durable one, but it certainly would be lacking in serviceability. In a general way of speaking, the value of city property depends upon the volume of the traffic in the street upon which it is located. Ordinarily a pavement is not wanted by the owners of property on the street, however durable it may be, if it lacks serviceability; and they may not want it, even when it is serviceable, if it is not popular.

27. **Life of Pavements.**—The life or durability of the different pavements under like conditions of traffic and maintenance may be taken as follows:

Granite block.....	12 to 30 years
Sandstone.....	6 " 12 "
Asphalt	10 " 14 "
Wood.....	3 " 7 "
Limestone.....	1 " 3 "
Brick.....	5 " ? "
Macadam.....	?

28. **Cost.**—The question of cost is the one which usually interests the taxpayers, and is probably the greatest stumbling-block in the attainment of good roadways. The first cost is usually charged against the property abutting on the highway to be improved. The result is that the average property-owner is always anxious for a pavement that costs little, because he must pay for it, not caring for the fact that cheap pavements soon wear out and become a source of endless annoyance and expense. Thus false ideas of economy always have stood and undoubtedly to some extent always will stand in the way of realizing that the best is the cheapest.

29. The pavement which has cost the most is not always the best, nor is that which has cost the least the cheapest; *the one which is truly the cheapest is the one which makes the most profitable returns in proportion to the amount which has been expended upon it.* No doubt there is a limit of cost to go beyond which would produce no practical benefit, but it will always be found more economical to spend enough to secure the best results, and it will always cost less in the long-run. One dollar well spent is many times more effective than one half the amount injudiciously expended in the hopeless effort to reach sufficiently good results which may look as

well for the time, no matter how soon it may have to be done over again.

30. A good roadway should cost more to build than a poor one, but it is often the case that the poor road costs as much as a good one would. But even when a good one is more expensive, it will be easier and cheaper to keep in repair, and will last many years longer, while its advantages and the saving to those who daily use it will much more than compensate for the extra expense they may have been put to in building it.

31. Economy and Public Bodies.—The true economy for public bodies which never die is to secure the best, in the best possible manner; for the best, every essential point being considered, is the cheapest. If a cheap pavement is adopted, the cost to maintain it will be so excessive as to more than make the difference between its first cost and that of a first-class one. As an instance of the profitable results of this policy the experience of the city of Liverpool, England, may be cited.

After many years of experiment and the expenditure of vast sums of money in pavements, the corporation of Liverpool now points with justifiable pride to its 250 miles of the best paved streets in the world.

The policy adopted by this corporation in the execution of public works in the best possible manner, and generally by their own workmen, has proved successful in every way; and, by a judicious primary expenditure, the cost of maintenance of the roads, sewers, and other public works is reduced to a minimum, and the greatest economy is thereby attained.

The laying of the impervious pavement which was adopted in 1872 for the carriage-ways of the city has been continued up to date without intermission, and is still in progress, resulting in nearly 1,750,000 yards, superficial, of impervious carriage-way pavements, and a saving by the execution of this class of work unprecedented in municipal experience.

The financial result can best be shown by the following: "Dealing with the year 1879, under the present city engineer (Mr. Clement Dunscombe, M.A., M. Inst. C. E.), the estimated expenditure for the general repairs to the roads in this city was £28,000 (\$136,080), the mileage of adopted roads at that time being 226 miles. Concurrently with the extension of the impervious carriage-way

pavements, the expenditure under this head has been reduced year by year till the estimated cost for the current year (1889) is only £8400 (\$40,824), with a street mileage under repair of 254 miles. This reduction has not been effected, as might at first sight be supposed, by an increased rate under this head, due to an augmented expenditure of capital requiring the provision of additional interest and sinking fund to redeem the original debt for paving and like works within 23 years (from 1870, when the loan was effected, to 1893, when it will be paid), as the amount raised on paving-rate account in the year 1879 was, approximately, £17,000 (\$82,620) more than in the year 1889, although the interest and sinking fund on the debt had increased from about £13,000 (\$63,180) per annum in the year 1879 to about £47,000 (\$228,420) per annum in the year 1889."

Permission is never given to private companies or persons to cut through the pavement in any street for any purpose. When such work is necessary, the corporation will do it in its own thorough way, and the interested parties must pay the entire cost—a regulation worth noting.

With the introduction of the improved pavements, it was found absolutely necessary, in order to attain the best results, to purchase the street-railroad tracks and reconstruct them in connection with the new pavements. Accordingly the city purchased some fifty miles of street-railroad tracks, and reconstructed them in a most substantial manner, and then rented them to the several original car companies at a fixed annual rental of 10 per cent on their cost. The city keeps the tracks in good condition. The success of these lines is conclusive proof that when street-car tracks are well designed and properly constructed they do not form the slightest impediment even to the narrowest-wheeled vehicles.

32. Economic Benefit.—The economic benefit of a good roadway is comprised in its cheaper maintenance, greater and easier facility for travelling, thus reducing the cost of transportation, less cost of repairs to vehicles, less wear of horses (thus increasing the life and time of serviceability and enhancing the value of their present service), saving of time, ease and comfort to those using it.

33. First Cost.—The cost of construction is largely controlled by the locality of the place, its proximity to the particular material used, and the character of the foundation. Tables XXVII, XXVIII,

XXIX, XXX, XXXV, XXXVI, XXXVII, XLI, XLII, and XLIII show the cost of different pavements in several of the principal cities of America.

34. The Relative Economies of Pavements—whether of the same kind in different condition or different kinds in like good condition—are sufficiently determined by summing their cost under the following headings of account:

- (1) Annual interest upon first cost.
- (2) Annual expense for maintenance.
- (3) Annual cost for cleaning and sprinkling.
- (4) Annual cost for service and use.
- (5) Annual cost for consequential damages.

35. First.—The first cost of a pavement is like any other permanent investment, measurable for purposes of comparison by the amount of annual interest on the sum expended. Thus, assuming the worth of money to be 4%, a pavement costing \$4 per square yard entails an annual interest loss or tax of \$0.16 per square yard.

36. Second. Maintenance.—Under this head must be included all outlays for repairs and renewals which are made from the time when the pavement is new and at its best to a time subsequent when, by any treatment, it is again put in equally good condition. The gross sum so derived divided by the number of years which elapse between the two dates gives an average annual cost for maintenance.

37. Maintenance means the keeping of the pavement in a condition practically as good as when first laid. The cost will vary considerably, depending not only upon the material and manner in which it is constructed, but upon the condition of cleanliness observed, and the quantity and quality of the traffic using it.

38. The prevailing opinion that no pavement is a good one unless when once laid it will take care of itself is erroneous; *there is no such pavement*. All pavements are being constantly worn by traffic and the action of the atmosphere, and if any defects which appear are not quickly repaired they soon become unsatisfactory and are destroyed. To keep them in good repair incessant attention is necessary and is consistent with economy. Yet claims are made that particular pavements cost little or nothing for repairs, simply because repairs are not made, while any one can see the need of them.

39. Third.—Any pavement, to be considered as properly cared

for, must be kept dustless and clean. While circumstances legitimately determine in many cases that streets must be cleaned at daily, weekly, or semi-weekly intervals, the only admissible condition for the purpose of analysis of street expenses must be that of like requirements in both or all cases subjected to comparison.

40. The cleansing of pavements both as regards its efficiency and cost depends (1) upon the character of the surface; (2) upon the nature of the material of which they are composed. Block pavements present the greatest difficulty; the joints can never be perfectly cleansed. The order of merit for facility of cleansing is (1) asphalt, (2) brick, (3) stone, (4) wood, (5) macadam.

41. *Fourth.*—The annual cost for service is made up by combining several items of cost incidental to the use of the pavement for traffic; for instance, the limitation of the speed of movement, as in cases where a bad pavement causes slow driving and the consequent loss of time; or cases where the condition of a pavement limits the weight of the load which the horse can haul, and so compels the making of more trips or the employment of more horses and vehicles; or cases where it causes greater wear and tear of vehicles, of equipage, and of horses. If a vehicle is run 1500 miles in a year and its maintenance costs \$30 a year, then the cost of its maintenance per mile travelled is two cents. If the value of a team's time is, say, \$1 for the legitimate time taken in going one mile with a load, and in consequence of bad roads it takes double that time, then the cost to traffic from having to use that one mile of bad roadway is \$1 for each load. The same reasoning applies to circumstances where the weight of the load has to be reduced so as to necessitate the making of more than one trip. Again, bad pavements lessen not only the life-service of horses, but also the value of their current service. The unit of these accounts is obtained by first finding the cost per mile of distance travelled, which cost divided by 5.280 and multiplied by the unit of area gives the desired result.

42. *Fifth. Consequential Damages.*—The determination of consequential damages arising from the use of defective or unsuitable pavements involves the consideration of a wide array of diverse circumstances. Rough-surfaced pavements, when in their best condition, afford a lodgment for organic matter composed largely of the urine and excrement of the animals employed upon the road-

way. In warm and damp weather these matters undergo putrefactive fermentation and become the most efficient agency for generating and disseminating noxious vapors and disease-germs, now recognized as the cause of a large part of the ills afflicting mankind. Pavements formed of porous materials are objectionable on the same if not even stronger grounds.

43. Pavements productive of dust and mud are objectionable, and especially so on streets devoted to retail trade. If this particular disadvantage be appraised at so small a sum per lineal foot of frontage as \$1.50 per month, or six cents per day, it exceeds the cost of the best quality of pavement free from these disadvantages. Rough-surfaced pavements are noisy under traffic and insufferable to nervous invalids, and much nervous sickness is attributable to them. To all persons interested in nervous invalids this damage from noisy pavements is rated as being far greater than would be the cost of substituting the best quality of noiseless pavement; but there are, under many circumstances, specific financial losses, measurable in dollars and cents, dependent upon the use of rough, noisy pavements. They reduce the rental value of buildings and offices situated upon streets so paved, offices devoted to pursuits wherein exhausting brain-work is required. In such locations quietness is almost indispensable, and no question about the cost of a noiseless pavement weighs against its possession. When an investigator has done the best he can to determine such a summary of costs of a pavement, he may divide the amount of annual tonnage of the street traffic by the amount of annual costs and know what number of tons of traffic are borne for each cent of the average annual cost, which is the crucial test for any comparison, as follows:

(1) Annual interest upon the first cost.....	\$
(2) Average annual expense for maintenance and renewal.....	
(3) Annual cost for custody (sprinkling and cleaning).....	
(4) Annual cost of service and use	
(5) Annual cost of consequential damages.	
Amount of average annual cost.....	
Annual tonnage of traffic.	
Tons of traffic for each cent of cost.	

44. Gross Cost of Pavements.—Since the cost of a pavement depends upon the material of which it is formed, the width of the roadway, the extent and nature of the traffic, the condition of

repair and cleanliness in which it is maintained, it follows that in no two streets is the endurance or the cost the same, and the difference between the highest and lowest periods of endurance and amount of cost is very considerable.

The comparative cost of various street pavements in Liverpool, including interest on first cost, sinking fund, maintenance, and cleaning, when reduced to a uniform standard traffic of 100,000 tons per annum for each yard in width of the carriage-way, is given by Mr. Deacon as follows:

	Per Square Yard per Annum.
Block pavements of hard granites.....	\$0.23
" " " softer "	0.28
Bituminous concrete.....	0.35
Wood pavement.....	0.58
Macadam, on pitch foundation.....	0.71

Taking the standard of traffic at 40,000 tons per annum, for each yard in width the cost for the last three pavements is:

Bituminous concrete.....	0.27
Wood.....	0.41
Macadam.....	0.47

Asphalt may be placed between wood and bituminous concrete, in the above order. These comparisons show the high cost of a macadamized surface in a street where traffic is great; and however well it may be maintained, it is much dirtier and dustier than any other pavement, though it is superior to them all in safety, and to block pavements in the matter of noise.

Table III shows the approximate comparative gross cost of various pavements in the United States for a period of fifty years, the pavement at the end of that period to be in as good condition as when first laid.

45. Traffic Census.—Comparison of pavements in respect to their gross cost can be effected only by comparing the gross traffic tonnage which each will bear for a unit of cost. As this can be ascertained only by direct observation, it is desirable that engineers in charge of roads and streets find out accurately the traffic tonnage, the amount of force required to draw a unit of weight over different surfaces in like condition, the cost of maintaining different coverings during a given period under a unit of traffic tonnage, the

TABLE III.
COMPARISON OF THE GROSS COST OF PAVEMENTS FOR A PERIOD OF 50 YEARS.

	Cost per Square Yard.			
	Granite Block.	Asphalt.	Wood.	Brick.
Foundation, 6 in. concrete.....	\$1.00	\$1.00	\$1.00	\$1.00
Materials, labor, etc	3.25	2.50	1.40	1.80
Total first cost.....	4.25	3.50	2.40	2.80
Interest on materials and sinking fund, 50 yrs. @ 4 %.....	26.00	20.00	11.20	14.40
Interest on foundation @ 4 %.....	2.00	2.00	2.00	2.00
Maintenance, 50 years	2.50	4.50	7.50	2.50
Cleaning, etc., 50 years	5.00	1.00	6.00	2.50
3 renewals of surface @ \$3.25	9.75
5 " " " @ 2.50.....	12.50
12 " " " @ 1.40.....	16.80
8 " " " @ 1.80.....	14.40
Cost of service	30.00	10.00	20.00	15.00
" " consequential damages (" ")	10.00	1.00	1.50	2.00
Total.....	89.50	54.50	67.40	55.60
Less value of foundation.....	1.00	1.00	1.00	1.00
Less value of old material....	88.50	53.50	66.40	54.60
	1.00	.1025
+ 50)	87.50	53.40	66.40	54.35
Annual gross cost.....	1.75	1.068	1.33	1.087

relative safety of different surfaces, and the damage done to vehicles and horses by different pavements. These items should be carefully observed and recorded. As the amount of travel is variable, the observations should be made for a certain period on consecutive days, and should be repeated at different seasons of the year.

46. The most extensive observations on this subject in the United States were made under the direction of Capt. F. V. Greene, member of the American Society of Civil Engineers. The method of observing and recording was as follows: "The observations were made on six consecutive days (Sundays omitted) at the same place, and were continuous from 7 A.M. to 7 P.M., except when darkness prevented. No addition was made for this omission, nor for night traffic."

The printed instructions issued to each observer contained the following rules as a guide in estimating weights:

Less than 1 ton.

- 1-horse carriages, empty or loaded.
- 1-horse wagons, empty or light loaded.
- 1-horse carts, empty.

Between 1 and 3 tons.

- 1-horse wagons, heavy loaded.
- 1-horse carts, loaded.
- 2-horse wagons, empty or light loaded.

Over 3 tons.

Wagons and trucks drawn by two or more horses and heavy loaded.

"Special note will be made, in the column of Remarks, of any unusually heavy loads, such as 6-horse trucks loaded with stone or iron, and an estimate given of their weight."

The weight and number of the horses was disregarded, because Capt. Greene wished to make comparison with English reports in which their weight was disregarded. *Their weight should be included in all observations, as the action of their feet is an important factor in the wear of pavements.*

47. Capt. Greene assigned the following weights to each class of vehicles:

Light-weight vehicles one-half ton each, including their load; medium weight two tons, and the heavy weight four tons.

The weight to be assigned to each class of vehicles had better be ascertained by occasionally weighing a typical vehicle and its load. The weight of horses may be taken at one-half ton each.

48. Form of Traffic Census.

TRAFFIC CENSUS

of.....	Street.
Class of pavement.....
Condition.....
Width between curbs.....
Date of observation.....
State of the weather.....
Temperature.....
Name of observer.....

Classification of Vehicles.	Hours of Observation.						
	6 to 7.	7 to 8.	8 to 9.	9 to 10.	10 to 11.	11 to 12.	12 to 1.
1-horse light.....							
1- " loaded.....							
2- " light.....							
2- " loaded.....							
3- " light.....							
3- " loaded.....							
4- " light.....							
4- " loaded.....							
Led horses, No. of....							
Totals.....							
Number of falls.....							
Remarks.....							

49. To obtain tonnage, multiply the total number of vehicles in each class by the weights assigned to that class, and adding together the products the total vehicular tonnage is ascertained, which divided by the width between curbs and the number of days of observation gives the average daily tonnage per foot of width.

Under Condition note the state of repair and cleanliness; whether the surface is dry, damp, or greasy. Under Falls note the kind, whether on knees, haunches, or complete, and if possible the cause.

" The average tonnage per vehicle is an almost infallible indicator of the character of the street, i.e., whether devoted to residential or business purposes. It ranges from 0.68 tons on Fifth Avenue, New York City, to 2.08 tons on a portion of Wabash Avenue, Chicago. The same character is indicated by the proportions of light and heavy vehicles in the street. On Fifth Avenue, New York, for instance, 91% of all the vehicles weigh less than one ton, while on Wabash Avenue only 25% of them have so little weight. The general average for all cities is as follows: Less than 1 ton, 67%; between 1 and 3, 26%; more than 3 tons, 7%. The average tonnage per foot of width in each city, so far as here observed, varies from 151 in New York to 30 in Buffalo, and the general average is 77. For all the cities observed the average daily tonnage per foot of width is 77, and varies from 273 tons on Broadway, New York, to 7 tons on a granite street in St. Louis. The average weight per vehicle is, for all cities, 1.15 tons. The average width of the streets between curbs is 44 feet."

In London the traffic on some of the asphalt- and wood-paved streets exceeds 400 tons per foot of width per day.

In Liverpool granite-block pavements sustain a daily traffic tonnage per foot of width of from 400 to 500 tons.

The comparative rank of pavements in the order of their merit is shown in Table IV.

TABLE IV.

COMPARATIVE RANK OF PAVEMENTS, NAMED IN THE ORDER OF THEIR MERIT.

Order of Merit.	Durability.	Serviceability.	Hygienic Fitness.	Service on Grades.	Gross Annual Cost.	Facility for Cleansing.
1	Granite	Asphalt	Asphalt	Granite	Asphalt	Asphalt
2	Asphalt	Brick	Brick	Brick	Brick	Brick
3	Brick	Wood	Granite	Wood	Wood	Granite
4	Wood	Granite	Wood	Asphalt	Granite	Wood

50. **Guaranteeing Pavements.**—To secure pavements that shall be durable and serviceable, the municipal authorities often require the contractors to guarantee their pavements for a term, usually, of five years, under provisions calling for maintenance in good condition during that period of time and for final delivery in good order. Such contracts involve two kinds of service, that of construction, and of maintenance for a limited period. In the latter the conditions are exacted indiscriminately alike on streets with heavy traffic and on those with very light traffic, and thereby become sometimes burdensome, unless the same contractor paves so many streets of all kinds as to correct the inequality by securing of fair average traffic condition. The correct policy to pursue in contracting for maintenance would be to measure the service of the pavement by the tonnage rather than by the years. To do so equitably the city needs information about the traffic, which it can obtain only by having a traffic census taken as described in Art. 45.

51. Many contracts for street pavements in some European cities have provided for the construction and the maintenance of the pavements for long terms, say of twenty years, payments to be made in equal annual instalments throughout the term. Such arrangements appeared at first to be very favorable, owing to the first payments being so much less than they otherwise would be for the whole cost of construction. The pro-rata annual payments

provided for the interest and risks of various kinds, with contractors' profits thereon, in addition to the direct outlays for construction and repairs, so that the final outcome was unsatisfactory to both parties to the contract. The prevailing custom in this country is to pay the cost of construction of a pavement as soon as completed. Two methods of meeting the expense of maintenance are followed. In one the municipality meets the annual requirements as they occur, and in the other, under contract for a term, say, of ten or twenty years, the contractor, for equal annual payments, is required to keep the pavement and turn it over to his successor in good condition at the expiration of the contract.

In the city of New York the guarantee period for asphalt pavements is fifteen years, during which payments are made as follows: on completion of the work seventy per cent of the cost; at the expiration of five years three per cent is paid yearly for the period of ten years.

52. This annual payment has to cover the contingency of the contractor's being at the expense of completely renewing the pavement. The equal annual amounts paid on contracts for maintenance, as just explained, include two funds, one of repair accounts and the other a sinking fund, intended to meet the cost of renewing the pavement, which must be done if the contract is for a long term of years.

53. If an attempt is made to separate, for each year, the proportion of the annual payment which should provide for each of the two purposes, it would be found that the earlier years would be contributing little or nothing for repairs, as, the pavement being new, they would not be required, but the proportion so applied would increase gradually, and at last consume nearly all the annual payment.

54. The justification of contracts for the continuous maintenance of pavements is in the advantage gained from having some one admittedly responsible for their condition and more amenable to discipline than are city officials for neglect. With this consideration in mind each community can determine whether it is to its advantage or not to contract for such maintenance.

55. Destruction of Pavements.—The most serious cause of the destruction of street pavements is the frequency with which they are torn up for the introduction and repairing of underground pipes, and no pavement can be designed which will withstand such frequent disturbance. The only radical remedy for this evil is a

very costly one in its first inauguration, but it is one that would be economical in the end, and that is a subway or series of subways under our roadways.

56. The amount of money wasted in continually opening up the streets, digging, bracing, and refilling, is a considerable item, not counting the interference with travel and business, and would be sufficient to cover the interest on the cost of the subways. The waste, being distributed through many companies, is not sufficiently felt to cause a reconstruction. The streets of New York were opened 27,088 times in 1890 by the gas, steam-supply, and other companies, and during 1894 17,475 openings were made, in connection with which there were relaid 27,500 square yards of asphalt pavement, and 166,000 square yards of granite pavement.

In Washington, D. C., during 1893, the total surface of pavement removed and restored in connection with openings in the streets was 19,652 square yards, at a cost of \$47,594.83.

57. Under the best municipal administrations of Europe neither corporations nor individuals are permitted to disturb the pavements. All removals and restorations are done by the city's own employes, upon the deposit, by the parties who require the streets to be opened, of a sufficient sum to cover the expense for each piece of paving done, at a fixed price per yard according to the kind of pavement.

Moreover, interference with the pavements is of rare occurrence, for the companies having pipes underground are required to thoroughly examine and reinstate their mains and services concurrently with the paving of a street, of the execution of which due notice is given them by the city. Such regulations are quite practical, and there can be no hardship in requiring American companies to pay for like work.

In New York the Department of Public Works has an organized system of supervision to insure the proper restoration of the pavements torn up by private corporations. The companies or individuals making the openings are required to pay the cost of inspection as well as the cost of restoring the pavement.

It is stated that in Victoria Street, one of London's busiest thoroughfares, not a single stone has been disturbed from the carriage-way in twenty-five years. This street, as well as many others, has a subway in which are contained the gas and water pipes and upwards of six conduits for telegraph and electric wires.

CHAPTER II.

MATERIALS EMPLOYED IN THE CONSTRUCTION OF PAVEMENTS.

58. Selection of Paving Material.—The materials most commonly used for pavements are stone in the form of blocks and broken fragments: wood in the form of blocks and plank, asphalt in two forms,—sheet and block,—and clay in the form of brick.

59. In considering the relative fitness of the various materials, the following physical and chemical qualities must be sought for:

(1) Hardness, or that disposition of a solid which renders it difficult to displace its parts among themselves.

(2) Toughness, or that quality by which it will endure light but rapid blows without breaking.

(3) Ability to withstand the destructive action of the weather, and probably some organic acids produced by the decomposition of excretal matters, always present upon roadways in use.

(4) The porosity, or water-absorbing capacity, is of considerable importance. There is perhaps no more potent disintegrator in nature than frost, and it may be accepted as fact that of two rocks which are to be exposed to frost, the one most absorbent of water will be the least durable.

60. Breaking and Crushing Tests possess no definite value in determining upon the fitness of a material for paving purposes. It is an elementary fact in mechanics that a body may bear an enormous crushing strain gradually applied and yet be readily broken by a smart blow from a light hammer. Taking the ascertained breaking and crushing strains as lying between $3\frac{1}{2}$ and 7 tons per square inch, it may be safely said that no such strains are ever brought to bear upon any single inch of roadway in practice, not

even during the passage of a ten-ton roller. The direct pressure or strain as applied in a testing-machine has no resemblance to the quick blows of horses' hoofs, much less to the abrading action of wheels.

61. Methods of Testing Durability.*—The only true test of the fitness of any material for paving is by an experimental trial upon a certain length of roadway under a unit of traffic. The "Rattler" tests now much employed to test the quality of bricks for paving do not fairly represent the condition of the materials in the pavement; in the latter the material is supported on all sides but one, and is subjected to pressure and percussion on this side, while in the "Rattler" tests the materials are thrown into violent collision with large pieces of iron weighing anywhere from five to fifteen pounds. It is evident that under this treatment the corners of the material will readily succumb, and the wear in consequence will be much greater and of a different nature than it would be under actual conditions. The methods adopted for testing any material should represent as nearly as possible the requirements of practical use.

The laboratory returns should state:

1. The technical and common names of the material;
2. Its geological occurrence;
3. Present use of the material;
4. Specific gravity;
5. Weathering properties;
6. Resistance to crushing in the three conditions: (a) dry; (b) water-soaked; (c) dried after being subjected to a freezing and thawing process.
7. Absorptive properties;
8. Resistance to abrasion;
9. Character and cementing qualities of the detritus.

62. The following plan of testing the comparative value of paving-stones is adopted at the Paris Laboratory for Testing Materials. While it may be questioned whether this method is superior to the "Rattler" test, it indicates foreign appreciation of the fact that the "Rattler" test is not what it should be. The stone or other

* See also Arts. 355, 118a.

samples are clamped to a horizontal plate revolving round a vertical spindle and brought to bear with equal pressure against a similarly disposed revolving plate of cast-iron. Along with the samples to be tested is placed a specimen of the standard material, which is Yvette sandstone. The coefficient of wear is the proportion between the volumes worn, which is ascertained by weighing the specimens and determining the volume from this weight. The coefficient for first-class materials is from 1 to 1.40, and for second-class materials from 1.40 to 2.40. If the wear is greater than that represented by the coefficients, the material is rejected.

63. At St. Louis, Mo., some years ago, strips of different pavements 22 inches wide and 8 feet long were laid down as a test, and a two-wheeled cart with tires $2\frac{1}{4}$ inches wide, and loaded to two tons, or 800 pounds per inch width of tire, was rolled back and forth by machinery. The heaviest traffic at that time in St. Louis was 75 tons per day per foot of width, and the average for business streets was 35 tons. Estimating the effect of horses' shoes at one third of this amount, 50 tons per foot were taken as a standard. The samples were weighed before and after testing, and were subjected to an amount of travel by the above cart equivalent to eight and one half years on the street.

The total abrasion of the fire-brick pavement was 9%, or a depth of $\frac{3}{4}$ of an inch, but about one half of the bricks were broken. Asphaltum blocks under the same test wore 14%, and but one was broken. Broken stone lost 1% under a traffic of 12.7 tons per foot of width. Broken stone and sand lost 1% under 16 tons per foot. Limestone blocks lost 1% under 4400 tons per foot of width. Wood blocks lost 1% under 12,900 tons per foot, and the granite blocks lost 1% under 70,000 tons.

The action of the elements was not taken into consideration; it would undoubtedly increase the wear of the several materials.

64. **Absorptive Power of Stones, etc.**—All materials absorb water to a greater or less extent, and their durability is much affected by their absorbing capacity. This capacity depends largely on the density, a dense stone absorbing less than a light and more porous one. The absorbing capacity is a matter of much importance, especially in cold climates. The water absorbed, on freezing, tends by its expansion to disintegrate the stone. It has been said that the act of freezing is equivalent to the blow of a ten-ton hammer.

on every square inch of surface. Whether this be so or not, the continued expansion and contraction of a porous stone is quite sufficient to disintegrate it, and this disintegration will be the greater the more water the stone contains.

TABLE V.
ABSORPTIVE POWER OF STONES, ETC.

	Percentage of water absorbed.
Granites.....	0.066 to 0.155
Marbles.....	0.08 " 0.16
Limestones.....	0.20 " 5.00
Sandstones.....	0.41 " 5.48
Brick, common.....	2.00 " 25.00
" paving.....	0.15 " 8.00
Mortars.....	10.00 " 50.00
Wood.....	0.16 " 9.00
Asphalt....	Impervious

Stones that have already begun to decompose absorb a much larger quantity of water than those fresh from the quarry, and decay will be more rapid. Other things being equal, the less the absorption the better the stone or brick.

65. Description of Materials.—Granite is an unstratified or igneous rock, composed of silica or quartz, feldspar, and mica. In addition to these essential constituents, one or more accessory minerals may be present; the more commonly occurring are hornblende, pyroxene, epidote, garnet, tourmaline, magnetite, pyrite, and graphite. And the character of the rock is often determined by the presence of these accessory constituents in quantity.

Granite varies in texture from very fine and homogeneous to coarse porphyritic rocks in which the individual grains are an inch or more in length. The color is also dependent upon the minerals present: if the feldspar is the orthoclase (potash-spar), it communicates a red color; the soda-spar produces gray. The mica also plays an important part in the modification of color: if it is the white muscovite, it produces no change; but if the black biotite mica be present, it modifies the color accordingly. Hornblende gives a dark mottled appearance; pyroxene as augite also gives a darker appearance; epidote communicates a green color.

The durability of the granites is closely related to their mineralogical composition. The presence or absence of certain species

influences the hardness and homogeneous nature of the stone. Although popularly regarded as the most durable stone, there are some notable exceptions.

The quartzose, feldspathic, and micaceous granites are unsuitable for paving purposes. The quartzose are too brittle, the feldspathic are too easily decomposed. When the feldspar is in excess the granite rapidly decays and disintegrates in consequence of the action of air and water on the feldspar, the potash of which seems to be removed, and the residue falls into a white powder composed chiefly of silica and alumina. The micaceous are too easily laminated.

The term "granite" as popularly used is not restricted to rock species of this name in geological nomenclature, but includes what are known as gneisses (foliated and bedded granites, syenite, gabbro, and other crystalline rocks whose uses are the same); in fact, the similar adaptability and use have brought these latter species into the class of granites. The term is often improperly applied to the diabases or trap-rocks.

66. Syenite differs from granite in having more hornblende, with some plagioclase, feldspar, and mica, and little or no quartz. (It is called syenite because it was first found in the island of Syene in Egypt.) It is massive and its occurrence is like that of granite. It furnishes the best material for paving-blocks, and is better in proportion to the darkness of color and the predominance of hornblende.

67. The Sioux Falls stone, much used for paving in the West, is a quartzite, close-grained, non-absorbent, and frost-proof. It does not break evenly as granite and sandstone.

68. The gneiss, quartz, and silicious rocks, though hard, are too brittle and deficient in toughness for paving purposes.

69. Table VI. shows the specific gravity, weight, and resistance to crushing of various granites.

TABLE VI.

SPECIFIC GRAVITY, WEIGHT, AND RESISTANCE TO CRUSHING OF VARIOUS GRANITES.

Localities.	Specific Gravity.	Average Weight, pounds per cubic foot.	Resistance to Crushing, pounds per square inch.
Kirtland Rocks, Conn.....	2.66	166	35,000
Lord's Island, Conn.....			24,000
Chaumont Bay, N. Y.....	2.65	162.2	22,700
Mystic River, Conn.....	2.63	164.4	22,250
Sharkey's Quarry, Me.....	2.72		22,125
Richmond, Va.....			21,250
Haron Island, Mich.....			20,650
Rockport, Mass.....	2.61	163.2	19,750
Port Deposit, Md.....			19,750
Quincy, Mass.....	2.66	166.2	19,500
Duluth, Minn.....			19,000
Hurricane Island, Me....	2.67	166.9	15,000
Mount Sorrel, England....	2.67	167	12,800
Bay of Fundy, Canada.....			11,916
Aberdeen, Scotland (gray)....	2.62	163	10,900
" " (red).....	2.62	165	
Dublin, Ireland.....			10,450
New Haven, Conn.....			9,750
Cornish, Wales.....	2.66	166	6,800
Patapsco, Md.....	2.64	163	5,340

70. Table VII shows the amount of production and value of granite for street purposes throughout the United States for the year 1889. From this table it appears that the number of blocks used for paving amounted to nearly 62,000,000; that the value per thousand varies from \$32.22 in Wisconsin to \$78.67 in Delaware.

TABLE VII.

PRODUCTION AND VALUE OF GRANITE FOR STREET USES IN 1889.*

States.	Cubic feet, including Paving- blocks.	Value, including Paving- blocks.	Value per cubic foot.	Number of Paving- blocks.	Value of Paving- blocks.	Value per thou- sand.
California.....	8,284,232	\$551,613	\$0.17	7,303,821	\$297,286	\$40.70
Colorado.....	1,100	280	0.21
Connecticut.....	567,860	109,261	0.19	761,100	40,683	53.45
Delaware.....	155,500	67,202	0.43	104,333	8,208	78.67
Georgia.....	658,603	250,684	0.38	1,599,952	84,951	53.10
Maine.....	3,786,541	927,949	0.25	17,704,915	824,113	46.55
Maryland.....	1,051,010	125,958	0.12	286,950	10,310	35.93
Massachusetts...	1,475,093	466,147	0.32	6,106,016	378,627	62.01
Minnesota.....	338,640	141,554	0.42	1,239,000	68,045	54.92
Missouri.....	871,209	216,986	0.25	4,323,130	216,986	50.19
New Hampshire...	1,157,992	252,256	0.22	2,043,739	87,569	42.85
New Jersey.....	2,089,796	236,310	0.11	3,999,912	168,555	42.14
New York.....	247,902	51,062	0.21	587,120	26,962	45.92
North Carolina..	221,820	42,605	0.19	775,000	34,200	44.13
Oregon.....	117,400	30,200	0.26	587,000	30,200	51.45
Pennsylvania....	1,996,486	368,323	0.18	3,836,127	241,793	63.03
Rhode Island....	213,477	65,817	0.31	781,765	45,817	58.61
South Carolina...	94,489	34,016	0.36
South Dakota....	601,000	170,695	0.28	3,017,500	170,694	56.57
Vermont.....	231,128	48,323	0.21	883,096	45,643	51.69
Virginia.....	286,946	75,925	0.26	342,895	18,505	53.97
Wisconsin.....	1,285,000	223,825	0.17	5,540,000	179,075	32.32
Total.....	20,683,244	\$4,456,891	\$0.23	61,822,871	\$2,978,172	\$48.17

* 11th U. S. Census.

71. Value of Granite Blocks.—In the most important States which produce paving blocks, namely, California, Maine, Massachusetts, Missouri, New Jersey, and Pennsylvania, the value varies from \$40 to something over \$60 per thousand. The variation in the price for these States, in all of which the production of paving-blocks has been going on for some time, is due to the quality of the stone used for these purposes, and also to the special care observed in trimming blocks to certain definite sizes. In some localities surface rock of inferior quality is broken up into paving-blocks, which are sold at low prices. In a number of cities considerable

care is taken by the municipal authorities in the selection of the granite for paving material. This care is exercised both with reference to the quality of the stone and to invariability of size, and consequently the price paid is in some cases markedly higher than that paid in other cities more indifferent in regard to the material employed.

72. The following list is presented for the purpose of showing the various uses of granite for street and road construction:

Paving-blocks.	Basin-heads.
Curbing.	Crossing-stones.
Flagging.	Gutter-stones.

Crushed for artificial stone; broken for concrete.

73. **Manufacture of Granite Paving-blocks.**—The manufacture of paving-blocks varies in many of its details from the ordinary methods of granite-cutting. The high skill and fine workmanship of the stone-cutter are not needed, but a quickness in seeing and taking advantage of the directions of cleavage, as well as a deftness in handling the necessary tools, is requisite.

The tools used for making blocks are knapping-hammers, opening-hammers, reels, chisels, and for initial splits drills, wedges, and half-rounds. When the block-maker quarries his own stock it is called "motion work," and the same process is used as in quarrying stone for other purposes, except that, as large blocks are not required, most of it can be done with plug and feather.

Slabs, having been split out in the usual manner to sizes that may be easily turned over and handled by one man, are subdivided into pieces corresponding approximately to the dimensions of the required blocks. This is done by striking repeated blows upon the rock along the line of the desired break with heavy knapping and opening hammers. When a break is to be made crosswise the grain, it is frequently necessary to chisel a light groove across one face, and commonly across the adjacent sides, to guide the fracture produced by striking on the opposite surface with the opening-hammer. Good splits can, however, be made along either the rift or grain by the skilful use of the opening-hammer alone. Blocks broken out in the manner described are trimmed and finished with the reel, which is a hand-hammer having a long, flat steel head attached to a short handle. Block-makers become very expert in the use of this tool, and without making any measurements turn

out in a surprisingly short time a large number of blocks. In Maine, which is far ahead of any other State in the number of blocks made, the entire product of many quarries is used for this purpose exclusively. This is also the case in California, which comes second, though the blocks are manufactured chiefly from the surface "boulders" or detached masses of basalt so common in Sonoma County. Other quarries, however, in various parts of the country utilize only the "grout," small or irregular-shaped pieces, for making paving-blocks, and haul the stock to the breakers, who work in sheds; but the greatest number of blocks are made on the spot where the rock is quarried, the workmen being protected during the hottest months by a temporarily spread canvas fly.

Blocks are counted as they are thrown into the cart which is usually needed to haul them to the shipping point. Several paving-block quarries in Maine are situated on steep mountain-slopes so near water communication that blocks may be slid in long board chutes from the quarry directly into the hold of the vessel used for their transportation.

Paving breakers seldom work by the day, but are paid a certain sum per thousand for making the blocks; the price paid in 1889 ranging from \$22 to \$30 according to the size of block made, kind of stone used, locality, and whether the tools were furnished and the blocks quarried by their employers. Workmen using their own tools are commonly paid one dollar more per thousand for the blocks made; and when they quarry the stock they use, from \$2 to \$5 per thousand is allowed in addition.

74. **Sandstones** are rocks made up of grains of sand which are cemented together by silicious, ferruginous, calcareous, or argillaceous material. From the nature of the cementing material the rocks are variously designated as ferruginous, calcareous, etc. In most cases the cementing material determines the color. The various shades of red and yellow depend upon the iron oxides. The purple tints are said to be due to oxide of manganese. The gray and blue tints are produced by iron in the form of ferrous oxide or carbonate.

75. The hardness, strength, and durability depend upon the nature of the cementing material. If the cementing material be one which decomposes readily, as in the argillaceous and calcareous varieties, the whole mass is soon reduced to sand.

76. Sandstones are widely distributed, and they represent all of the geological periods, from the oldest to the most recent formations.

77. The sandstones obtained from the Upper Silurian and the Lower Carboniferous formations are much used in the form of blocks for street paving in the Lake and Western cities. They are durable and do not become smooth or slippery when wet, but in the form of fragments for broken stone roads they are useless.

78. **Hudson River Bluestone.**—The term "Hudson River bluestone" is used to designate the blue, fine-grained, compact, and even-bedded sandstone which is so largely employed for flagging and curbing in the cities and towns of New York and neighboring States.

The color is predominantly dark gray and hence (more by contrast with the red sandstone) a "bluestone."

In texture the range is from the fine shaly or argillaceous to the highly silicious and even conglomerate rock.

The best bluestone is rather fine-grained and not very plainly laminated, and its mass is nearly all silica or quartz which is cemented together by a silicious paste and contains very little argillaceous matter.

It is so compact as not to absorb moisture to any extent, and hence soon dries after rain or ice; it has the hardness to resist abrasion and wears well; it is even-bedded and thus presents a good

TABLE VIII.
ANALYSES OF SANDSTONE.

Kind of Stone.	Locality.	Silica.	Alumina.	Iron Oxides.	Manganese Oxide.	Lime.	Magnesia.	Potash.	Soda.	Carbonic Acid, Water, and Loss.
		p. ct.	p. ct.	p. ct.	p. ct.	p. ct.	p. ct.	p. ct.	p. ct.	p. ct.
Manyard.....	{ E. Long- meadow, Mass. }	79.88	8.76	2.43	2.57	4.08	2.79
Worcester.....		88.89	8.96	1.79	0.41	0.37	0.86	1.83
Kibble.....		81.38	9.44	3.54	0.11	0.76	0.88	4.49
Brownstone ..	Portland, Conn.	69.94	13.15	2.48	0.70	3.09	Trace	3.30	5.43	1.01
Sandstone ..	Stony Pt., Mich.	84.57	8.90	6.48	0.68	Under'd	1.98
Quartzite.....	Pipestone, Minn.	84.53	12.83	2.12	0.81	Trace	0.11	0.84	2.31
Buff.....	Amherst, Ohio.	97.00	1.00	1.15	0.64	0.21
Berea.....	Berea, Ohio.	96.90	1.68	0.55	0.55	0.32
Euclid Bluest.	Euclid Co., Ohio.	95.00	2.50	1.00	1.50
Columbia.....	Columbia, Ohio.	96.50	1.00	0.50	2.00
Red.....	Laurel Run, Pa.	94.00	Trace	1.90	1.10	1.00	1.98
Elyria.....	Grafton, Ohio.	87.66	1.72	3.52	0.17	0.20	2.06
Sandstone.....	Fond du Lac, Mn.	78.24	10.88	3.33	0.95	1.60	1.67	0.06

smooth natural surface, and it has a grain which prevents it from becoming slippery; it is not materially affected by freezing and thawing; it is strong and not apt to get broken if well laid.

79. Commercial Names of Sandstone.—The commercial names of sandstone are usually obtained from places where it is quarried, as, Berea, Grit, Medina, etc.

80. Table VIII on the opposite page, giving analyses of sandstone from a number of localities, will serve to indicate its general composition.

81. The specific gravity, weight, and resistance to crushing of various sandstones is given in Table IX. The amount of production and value of sandstone for street purposes in the United States in 1889 is given in Tables X and XI.

TABLE IX.

SPECIFIC GRAVITY, WEIGHT, AND RESISTANCE TO CRUSHING OF VARIOUS SANDSTONES.

Localities.	Specific Gravity.	Average Weight, pounds per cubic foot.	Resistance to Crushing, pounds per square inch.
Potadam (red), N. Y.....	2.60	162.28	42,804
Medina, N. Y.....			17,725
Malden (bluestone), N. Y.....	2.75	171.47	
Warsaw (bluestone), N. Y.....	2.68	167.10	
Albion, N. Y.....			18,500
Craigleith, Scotland.....	2.45	158	5,287
Belleville, N. J.....	2.56	159.67	11,700
Kasota, Minn.....			11,675
Seneca, Ohio.....			10,500
Berea, Ohio.....	2.57	160.06	10,250
Little Falls, N. Y.....			9,850
Dorchester, New Brunswick....			9,412
Vermillion, Ohio.....			8,850
Massillon, Ohio.....			8,750
Cleveland, Ohio.....			7,910
Abroath (pavement), England..	2.47	155	7,884
Marquette, Mich.....	2.53	158.17	7,450
Middletown (Portland), Conn....	2.62	163.48	6,950
North Amherst, Ohio.....			6,850
Oxford (bluestone), N. Y.....	2.71	168.9	18,472
Fond du Lac, Wis.....			6,250
Bristow, Va.....	2.61	163	
Yorkshire, England.....	2.51	157	5,714
Warrensburg, Ohio.....			5,000
Haverstraw, N. Y.....			4,350
Derby Grit, England.....	2.4	150	3,100
Cheshire (red), England.....	2.15	133	2,185
Nova Scotia.....	2.62	168.50	

TABLE X.

PRODUCTION AND VALUE OF SANDSTONE FOR STREET USES IN 1889, BY STATES AND TERRITORIES.*

States and Territories.	Cubic Feet.	Value.	Value per cubic foot.
Arkansas.....	27,160	8,215	0.30
California.....	100	200	2.00
Colorado.....	1,926,464	509,955	0.26
Connecticut.....	40,500	2,250	0.06
Idaho.....
Illinois.....	8,300	50	0.02
Iowa.....	8,840	880	0.10
Kansas.....	452,015	182,188	0.29
Kentucky.....	13,900	1,600	0.12
Maryland.....	40,320	2,045	0.05
Massachusetts.....	501,221	40,471	0.08
Michigan.....	2,496	550	0.22
Minnesota.....	51,930	88,300	0.74
Missouri.....	6,533	2,512	0.88
New Mexico.....	10,000	3,000	0.80
New York.....	2,864,366	459,158	0.16
Ohio.....	1,603,614	430,552	0.27
Pennsylvania.....	354,907	175,062	0.20
West Virginia.....	42,075	28,274	0.55
Florida, Georgia, Nevada, Rhode Island, Vermont.....	13,865	2,660	0.19
Total.....	8,463,506	\$1,882,823	\$0.22

* 11th U. S. Census.

TABLE XI.

PRODUCTION AND VALUE OF "BLUESTONE" FOR STREET USES IN 1889.

States.	Cubic Feet.	Value.	Value per cubic foot.
New Jersey.....	15,649	8,550	0.55
New York.....	2,357,724	475,403	0.20
Pennsylvania.....	786,513	265,959	0.34
Total.....	3,159,886	\$749,912	\$0.24

82. Limestone.—Limestone is essentially carbonate of lime, but it always contains some additional constituent; the more commonly occurring impurities or accessory matters are silica in the form of

quartz, clay, iron, magnesia, etc. And limestones are said to be silicious, argillaceous, ferruginous, magnesian, dolomitic, bituminous, etc., according as they contain one or another of these constituents. Other foreign mineral matter may be found in them, and in such quantity as to give character to the mass.

In color there is a wide variation, depending upon the impurities; it ranges from the white of the more nearly pure carbonate of lime through gray, blue, yellow, red, brown, and to black.

The texture also varies greatly; it may be coarse or fine. The terms *coarse-grained* and *fine-grained* are applied when the mass resembles sandstone in its granular aggregations. Other terms, as *saccharoidal* (like sugar), *oolitic*, *crinoidal*, etc., are also used to describe the texture. The state of aggregation of the constituent particles varies greatly, and the stone may be hard and compact, almost vitreous, or loosely cemented and crumbling with slight pressure, like sugar, or, again, like chalk, dull and earthy.

From this general statement of the range in composition and texture, it follows that there is an equally wide variation in hardness, strength, and durability of limestones. Some are hard and strong, surpassing in their resistance to crushing force many granites, and nearly as durable as the best sandstone; others are friable and fall to pieces under slight pressure, or they are disintegrated rapidly by atmospheric agents.

83. The limestones are used for flagging and curbing, being selected for these purposes on account of accessibility or cheapness. For broken-stone roads with light traffic the limestones are eminently suitable; they possess the quality of forming a mortar-like detritus which binds the stones together and enables them to wear better than a harder material that does not bind. For this purpose the most suitable ones are the silicious, magnesian, dolomitic, and bituminous.

84. The experience of all cities using paving-blocks of limestone is that it wears unevenly, and in a year or two the blocks are shivered and split by the action of frost.

Table XII shows the specific gravity, weight, and resistance to crushing of various limestones. Table XIII shows the production and value of limestone for street uses in 1889, by States and Territories.

TABLE XII.

SPECIFIC GRAVITY, WEIGHT, AND RESISTANCE TO CRUSHING OF VARIOUS LIMESTONES.

Localities.	Specific Gravity.	Average Weight, pounds per cubic foot.	Resistance to Crushing, pounds per square inch.
Joliet, Ill.	16,900
Bardstown, Ky.	2.69	168	16,250
North River, N. Y.	2.71	169	18,425
Marblehead, Ohio.	12,600
Glens Falls, N. Y.	2.70	169	11,475
Marquette, Mich.	8,050
Billingsville, Mo.	7,250
Caen, France.	8,650
Purbeck, England.	2.6	162	9,160
Anglesea, "	7,579
Blue Lias "	2.467	154

TABLE XIII.

PRODUCTION AND VALUE OF LIMESTONE FOR STREET USES IN 1890, BY STATES AND TERRITORIES.*

	Cubic Feet.	Value.	Value per cubic foot.
Alabama.	96,000	9,800	0.10
Arkansas.	2,000	500	0.25
California.	35,000	1,390	0.04
Illinois.	10,221,892	505,576	0.05
Indiana.	2,614,862	316,722	0.12
Iowa.	1,707,931	53,641	0.03
Kansas.	771,041	97,502	0.13
Kentucky.	1,762,711	86,054	0.05
Maryland.	145,670	6,750	0.05
Michigan.	485,377	18,156	0.04
Minnesota.	68,788	11,778	0.17
Missouri.	11,542,723	670,351	0.06
Nebraska.	1,926,469	86,643	0.04
New York.	5,241,262	197,091	0.04
Ohio.	7,236,981	183,285	0.03
Pennsylvania.	2,042,804	72,512	0.04
Tennessee.	14,500	3,400	0.23
Texas.	67,750	32,278	0.48
Vermont.	9,990	2,088	0.21
Virginia.	7,560	190	0.03
Wisconsin.	488,811	27,789	0.06
Total.	46,491,622	\$2,383,456	\$0.05

* 11th U. S. Census.

85. The material called Ligonier "Granite," which is extensively used for paving, etc., is a silicious limestone from localities

near Pittsburg, and is said to have a crushing strength of 23,000 pounds per square inch.

86. **Trap-rock** is the common name given to a large group of unstratified eruptive or igneous rocks. They are composed of feldspar (usually labradorite), augite, hornblende, and some magnetite and titanite iron.

The term *trap* is derived from *trappa*, a Swedish word for stair, because the rocks of this class frequently occur in large tabular masses rising one above the other like steps, as seen on the west shore of the Hudson River from Jersey City to Haverstraw. The various proportions and states of aggregation of the simple minerals, and their differences in external forms, give rise to many varieties—such as *dolorite*, which depends for its hardness upon silica and feldspar, and may be either light or dark colored. *Basalt* is one of the most common varieties; it is of a dark green, gray, or black color, is composed of augite and feldspar, very compact in texture and of considerable hardness, it often contains iron, whence the name *basalt*, an Ethiopian word for iron. *Greenstone*, another variety, is composed of hornblende and feldspar and is of a dark green color.

The trap-rocks are hard and tough, have no true cleavage, and break irregularly; they are difficult to work. But there is much variation in the stones of different localities. The rock of the Palisades in New Jersey splits easily into blocks, and has been extensively used for paving in New York, Brooklyn, and Jersey City, under the name of "Belgian block;" but since the introduction of granite for this purpose their use has considerably decreased.

The trap-rocks are exceedingly durable and eminently suitable for broken-stone roads, but for paving-blocks they are a failure.

87. Table XIV shows the crushing resistances, specific gravity, and weight of trap-rocks.

TABLE XIV.

CRUSHING RESISTANCE, SPECIFIC GRAVITY, AND WEIGHT OF TRAP-ROCKS.

Locality.	Resistance to Crushing, pounds per square inch.	Specific Gravity.	Weight of one cubic foot, pounds.
Staten Island, N. Y.	22,250	2.86	178 8
Jersey City Heights, N. J.	20,750 to 22,250	8.03	189.5
Palisades, N. J.	19,700		

88. Bitumen, Asphaltum, Asphalt.—*Bitumen* is the name used to denote a group of mineral substances, composed of different hydrocarbons, found widely diffused throughout the world in a variety of forms which grade from thin volatile liquids to thick semi-fluids and solids, sometimes in a free or pure state, but more frequently intermixed with or saturating different kinds of inorganic or organic matter.

88a. To designate the condition under which bitumen is found different names are employed; thus the liquid varieties are known as *naphtha* and *petroleum*, the semi-fluid or viscous as *maltha* or *mineral tar*, and the solid or compact as *asphaltum* or *asphalt*.

89. Three distinct varieties of asphaltum are recognized, namely, the *earthy*, the *elastic*, and the *hard* or *compact*.

89a. The *earthy* variety, represented by the *chapopota* of Mexico, Colombia, and other parts of South America, has a brownish-black dull color, an earthy uneven fracture, when freshly excavated a strong though not unpleasant earthy odor, is soft enough to take an impression of the nail, hardens slightly on exposure to the atmosphere, and burns with a clear brisk flame, emitting a powerful odor, and depositing much soot.

89b. *Elastic asphaltum* is of various shades of brown; is soft, flexible, and elastic; it has an odor strongly bituminous, and is of about the density of water; it burns with a clear flame and much smoke. Like caoutchouc, it takes up pencil marks, and on this account is called *mineral caoutchouc*; it has been found only at three places: in the fissures of a slaty clay at Castleton, England; at Montrelais, France; and in Massachusetts.

89c. *Hard or compact asphaltum* is the most useful variety; it forms large deposits in many parts of the world, and is of various degrees of quality, according to its age and the impurities mixed with it; when nearly pure its ordinary characteristics are as follows: Color brownish black and black; lustre resinous or coal-like; opaque. At temperatures below 100° F. it is brittle and breaks with a conchoidal fracture. Melts ordinarily at 190° F. to 195° F., and is liquid at about 212° F. At 212° F. it has a peculiar but agreeable aromatic odor, somewhat resembling, but still very different from, that of coal tar; at ordinary temperatures the odor is scarcely perceptible, but when rubbed it is quite strong. It kindles

readily and burns brightly with a thick smoke. Distilled by itself it yields a bituminous oil of a yellow color (consisting of hydrocarbons mixed with oxidized matter), water, some combustible gases, and sometimes traces of ammonia.

After combustion it leaves about one third of its weight of charcoal and ashes containing silica, alumina, oxide of iron, sometimes oxide of manganese, lime, and other inorganic and organic matter. Its composition and hardness are variable.

Specific Gravity.—Pure bitumen has a density less than water; but in consequence of the impurities mixed with it the specific gravity of asphaltum varies from 1.0 to 1.7. *Solubility:* It is insoluble in water, partly or wholly soluble in chloroform and disulphide of carbon, partly or wholly in oil of turpentine and petroleum ether, and commonly partly in alcohol.

90. By different solvents asphaltum may be decomposed into three distinct though complex substances which have been named by Boussingault and other chemists who have investigated it *petrolene*, *asphaltene*, and *retine*. Nothing definite is known concerning these compounds or how their variable proportions and composition affect the quality of an asphaltum. In the past they have received but little attention from chemists, due probably to the limited use of asphaltum; but now, in view of its large and increasing employment for paving and other industrial purposes, their investigation offers a wide and undoubtedly profitable field for chemical research.

90a. The characteristics of these compounds, so far as known, are generally as follows:

Petrolene is the compound which is considered to give the viscous or adhesive quality. It may be described as that portion of the bitumen which is soluble in petroleum ether. It is lighter than water, very combustible, and has a high boiling-point, pale yellow color, and peculiar odor. On evaporating off the ether it remains as a resin with a brownish-black color, which dissolves readily in the volatile oils. Its composition is carbon, hydrogen, and sulphur. The amount present in an asphaltum is variable, ranging from 3 to 70 per cent of the weight of the asphaltum.*

* It has been found that a bitumen suitable for paving purposes should contain at least 70 per cent of petrolene.

Asphaltene is the compound which gives the hardness to asphaltum. It contains the elements of petroleine, together with a quantity of oxygen, and probably arises from the oxidation of that compound. It is that portion of the bitumen which is insoluble in ether. It is dissolved out by carbon disulphide, chloroform, benzene, etc. Its color is a brilliant black; density greater than water. It burns like resins in general, leaving a very abundant coke. Like petroleine, it is composed of carbon, hydrogen, and oxygen, and the amount present in an asphaltum is as variable—ranging from 1 to about 60 per cent.

Retine is dissolved out by alcohol (anhydrous) from that portion of the asphaltum which is unaffected by the solvents above mentioned. It is a yellow resin composed of carbon, hydrogen, and sulphur. What effect this compound has upon asphaltum is unknown. Some authorities claim that its presence is injurious.

91. Origin of Bitumen.—The origin of bitumen is unknown. It is supposed to be the ultimate product resulting from the destruction under certain conditions of the organized remains of animals and vegetables, producing (1) naphtha, (2) petroleum, (3) maltha or mineral tar, (4) asphaltum. The whole of these substances merge into each other by insensible degrees, so that it is impossible to say at what point maltha ends and asphaltum begins. *Naphtha*, the first of the series, is in some localities found flowing out of the earth as a clear, limpid, and colorless liquid; as such it is a mixture of hydrocarbons, some of which are very volatile and evaporate on exposure. It takes up oxygen from the air, becomes brown and thick, and in this condition it is called *petroleum*.

91a. The hardening of the bituminous fluids which have oozed out or been exposed by other causes upon the surface of the earth seems, in most cases at least, to have resulted from the loss of the vaporizable portions, and also from a process of oxidation which consists, first, in a loss of hydrogen, and finally in the oxygenation or evaporation of the more volatile portions, which gradually transforms them into mineral tar or maltha, and, still later, into solid glossy asphaltum, of which *gilsonite*, *wurtzilite*, *uintahite*, etc., are examples.

92. Occurrence and Distribution of Asphaltum.—Deposits of asphaltum are found widely diffused throughout the world, and at

various altitudes ranging from below sea-level to thousands of feet above. It is, however, seldom found among the primitive or older rock formations, but seems to belong exclusively to the secondary and tertiary formations. Intermixed with the argillaceous stratas, it forms extensive beds or lakelike deposits on both continents, the most remarkable of which are those situated in the West Indies and South America. The most notable of these are the so-called pitch lakes on the island of Trinidad, and at Bermudez, Venezuela.

92a. Saturating the calcareous and sandstone formations, it forms large subterraneous deposits in Europe and the United States. The calcareous varieties occur more extensively in Europe than in America, and are the source of the material employed there for street-paving under the name of *asphalte*. The sandstone class is found extensively in the Western and Southwestern States, especially in California, Texas, Kentucky, and the Indian Territory.

92b. In a free or nearly pure state it is found in veins and seams in the primitive rock and volcanic formations. This class of deposit is rare and the amount of asphaltum is generally insignificant. A notable exception, however, are the deposits of Utah, etc. The mines from which gilsonite, wurtzilite, uintahite are produced are said to be very extensive, and the material is very nearly pure. Similar deposits are found in Mexico, Cuba, and various parts of South America.

92c. In many localities beds of shale, sand, and cretaceous limestone are found saturated with maltha, from which the bitumen is extracted by boiling or macerating with water.

92d. From the variety of the deposits and their manner of occurrence it seems that asphaltum belongs to no particular era or age. Moreover, the asphaltum obtained from these different sources is not uniform either in character, appearance, hardness, or chemical composition. The ultimate composition of specimens from several localities is given in Table XIVa.

93. Nomenclature.—As indicated above, the varieties of bitumen and asphaltum are as numerous as the localities producing them; hence there is a great variety of names used to designate the same substance which is oftentimes misleading, if not confusing. As an illustration of this variety the following may be mentioned:

native pitch, mineral pitch, glance pitch, grahamite, albertite, pianzite, elaterite, gilsonite, wurtzilite, uintahite, turrellite.

TABLE XIVa.

COMPOSITION OF THE BITUMEN OF VARIOUS ASPHALTS.

Locality.	Consistency.	In Extracted Bitumen.			
		Sulphur.	Carbon.	Hydrogen.	Nitrogen.
Trinidad (Lake).....	Hard	6.16	82.38	10.69	0.81
California (Waldorf).....	"	6.48	82.77	10.62	0.85
" (La Patera).....	"	6.23	83.80	9.88	0.70
Texas (Uvalde).....	"	9.60	80.32	10.09	0.28
Cuba (Bejucal).....	"	8.52	80.87	10.42	0.19
Utah (Gilsonite).....	"	1.79	89.28	8.66	0.79
Kentucky.....	Medium	3.89	84.16	11.52	1.68
Indian Ter. (Chickasaw)...	Soft	1.98	85.65	12.87
" (Ardmore).....	"	1.47	87.40	11.05	0.65
California (Alcatraz).....	"	1.32	85.72	11.88	1.21
Bermudez (Venezuela).	"	5.87	82.88	10.70	0.75

93a. Sometimes the name of the locality where it is found is used as a prefix and is thus useful to indicate the source. Such names are Dead Sea bitumen, Egyptian asphalt, Cuban, Trinidad, Bermuda, Californian, Kentucky, etc.

93b. The name *asphalte* has been adopted by the French to designate the material obtained from their bituminous limestone deposits, and is now generally employed throughout Europe to denote both the carbonate of lime impregnated with asphaltum and the pavement made from that material.

93c. The name *lithocarbon* has been recently adopted to designate a cretaceous limestone saturated with bitumen found in Texas.

93d. Some authorities apply the terms asphaltum, asphalt, and liquid asphalt to the semi-fluid and viscous bituminous substance or *maltha*, which by heat may be transformed into asphaltum. This application seems to be erroneous, because asphaltum technically means bitumen in the solid form. Others use the same terms to designate the entire mixture of bitumen, mineral and organic matter, while others apply them to denote the purified material.

94. The names which seem to be the most used in the United

States and which are at the same time descriptive of the various classes are as follows :

Crude asphaltum or *crude asphalt* is applied to all mixtures of bitumen, clay, sand, etc.; e.g., crude Trinidad asphalt.

Refined asphaltum or *asphalt* is used to denote the asphaltum after it has been wholly or partly freed from the combined organic and inorganic matters.

The limestone rocks impregnated with bitumen are called *bituminous* or *asphaltic limestones*. The term *rock asphalt* is also applied to the same material, the name of the source being also used, as "Italian rock asphalt," "Val de Travers rock asphalt," etc.

The sandstones containing bitumen are known as *bituminous* or *asphaltic sandstones*, the name of the source being also mentioned.

The semi-fluid bitumen is designated by the names *maltha* and *mineral tar*.

The term *asphalt* is also frequently but erroneously applied to various preparations in which the cementing material is coal tar or the residue of oil-refineries, etc.—substances which are entirely dissimilar to asphaltum, though apparently possessing some of its characteristics.

The term *bitumen* is employed to designate the truly bituminous portion of the asphaltum and its compounds.*

95. Refined Asphaltum is asphaltum freed from the combined water and accompanying inorganic and organic matter. By comparatively simple operations the several varieties of asphaltum may be reduced to an equal state of purity.

95a. The argillaceous varieties, such as Trinidad, Bermudez, etc., are purified in iron vessels by the application of heat either directly from fire or indirectly by steam, the temperature em-

* *Manjak* is the name given to the asphaltum found in the Island of Barbadoes. Its composition is :

Volatile organic matter	70.85
Non-volatile organic matter	26.97
Mineral matter... ..	0.18
Molsture.....	2.00
	<hr/>
	100.00

ployed ranges from 212° F. to 350° F. During the application of the heat, the asphaltum is liquefied, the combined water is evaporated, the organic matters rise to the surface and are skimmed off, and the inorganic settle to the bottom of the vessel; when the liberation of the impurities is completed, the liquid asphaltum is drawn off into barrels and constitutes the refined asphaltum of commerce.

95b. The calcareous and silicious varieties are purified by boiling or macerating them with hot water, according to the freedom with which they part with the intermixed impurities. During the action of the water the sand and other ingredients fall to the bottom of the vessel, and the bitumen rises to the surface or forms clots on the sides of the boiler, whence it is skimmed off and thrown into another boiler, where it is boiled for some time, during which the water and more volatile oils are evaporated, and the mineral matters still retained fall to the bottom, leaving the bitumen in the form of a thick viscid substance, in which state it is used in several of the arts. By continuing the boiling for a considerable time or by increasing the temperature to about 250° F. the volatile portions are driven off and the viscid bitumen is brought to a condition which upon cooling causes it to become solid.

95c. The operation of refining or purifying, while exceedingly simple, requires to be performed with much care, for the reason that if the asphaltum is melted at too high a temperature it will be burned or coked, or if the heating is prolonged at a low temperature the result will be practically the same. In either case the petroleum is converted into asphaltene.

96. **Asphaltic Cement.**—Asphaltum in a refined or pure state is valueless as a cementing medium, owing to its hardness, brittleness, and lack of cementitious properties; therefore it is necessary to add some substance which will impart to it the required plastic, adhesive, and tenacious qualities. This substance must be one that will partially dissolve the asphaltene and form a chemical union by solution instead of a mechanical mixture. The duty which it has to perform is an important and peculiar one: if it is a perfect solvent of the constituents of the bitumen, the adhesive qualities will be destroyed; if it is an imperfect one, the asphaltum will retain its brittleness.

96a. The requirements of a suitable flux are that it shall be a fluid containing no substances volatile under 300° F., and shall possess the power to dissolve the asphaltum without destroying or lessening its adhesive properties.

96b. The materials employed to give the required qualities to the hard asphaltum are called the "flux," and those in general use are crude or specially prepared residuum oil obtained from the distillation of petroleum, and crude or refined maltha.

The process of adding the flux is called "oiling" or "tempering," and is conducted as follows: The refined asphaltum is melted and the temperature raised to about 300° F.; the oil previously heated is then pumped or in other ways added to the asphaltum, in the proportion of 10 to 20 pounds of oil to 100 pounds of refined asphaltum—the proportion of the oil is varied between the limits stated according to its quality, the hardness of the asphaltum, and the purpose for which the cement is to be employed. The mixture of residuum oil and asphaltum is agitated either by mechanical means or by a blast of air for several hours or until the material has acquired the desired properties. The agitation must be performed with great thoroughness to secure a uniform mixture, and must be continued whenever the material is in a melted condition, as a certain amount of separation takes place when the melted cement stands at rest. It is therefore customary to agitate it constantly when in use as well as during its preparation.

96c. The process of "tempering" when *maltha* is used as the flux is practically the same as outlined above, with the exception that the mixing is performed at a lower temperature and entirely by mechanical means, and a separation of the ingredients seldom occurs when the cement is standing at rest.

96d. The maltha from many localities is to be had in the market; it is sold for fluxing purposes under various trade names, among which may be named "Alcatraz" liquid asphaltum, "Standard" liquid asphalt, "Utah" liquid asphalt, etc.; also artificial fluxing materials which are offered as substitutes for oil and maltha, such as the "Pittsburg asphaltic flux," etc. The analyses of some of these fluxing agents are as follows:

"ALCATRAZ" LIQUID ASPHALT.

Specific gravity	1.05
Bitumen soluble in carbon disulphide.....	98.70 per cent.
Bitumen soluble in petroleum naphtha.....	89.17 " "
Mineral matter.....	1.30 " "
Organic non-bituminous matter.....	trace.

"UTAH" LIQUID ASPHALT (CRUDE.)

Specific gravity.....	0.9068
Bitumen soluble in carbon disulphide.....	76.15 per cent.
Bitumen soluble in ether.....	64.90 " "
Mineral matter	3.40 " "
Organic non-bituminous matter...	20.45 " "
Loss at 100°C.....	24.72 " "

"PITTSBURG" ASPHALTIC FLUX.

Moisture.....	0.05 per cent.
Volatile oil 212° F. to 312° F.....	1.60 " "
Volatile oil about 312° F.....	89.19 " "
Fixed carbon.....	8.48 " "
Ash.....	0.68 " "
Bitumen soluble in carbon disulphide.....	99.82 " "
Bitumen soluble in ether.....	65.00 " "

97. The enduring qualities of an asphaltic cement depend upon (1) the character of the fluxing agent, (2) the temperature at which the asphaltum has been refined and the temperature at which the flux is added, (3) the degree of incorporation of the flux with the asphaltum, that is whether the union is a chemical or mechanical one.

97a. The diversity found in the durability of pavements made from cement in which the flux is residuum of petroleum is considered by many authorities to be due primarily to the variable character of the residuum. This material is a thick heavy oil varying considerably in composition, according to the source of the petroleum and method of distillation; its base is *paraffine*—a substance so different from asphaltum that when the two are brought together the result is a mixture partly mechanical and partly chemical, and, being of different specific gravities, they partly separate when allowed to stand for any considerable period without stirring.

Regarding the use of petroleum residuum as a flux for asphaltum, Mr. A. W. Dow, Inspector of Asphalts and Cements, District of

Columbia, in his report for 1897 says: "I have made a careful study of this, and am thoroughly convinced that the use of all petroleum residuum is injurious, some much more so than others. That it is not adaptable, either chemically or physically, to this use, can be readily seen by looking into its properties. With a change of but a few degrees of temperature, it passes from a liquid to a solid state. On standing a month or two a hardening sets in, due either to polymerization or slow crystallization, which makes it even more susceptible to change in temperature. I am also led to believe, from various experiments, that many asphalts are not entirely soluble in petroleum residuum, and for that reason asphalt cement in which it is used is not a chemical, but merely a mechanical mixture or emulsion of the asphalt and the oil. From this it can readily be seen that the undesirable properties of the petroleum residuum are imparted to the asphalt cement to a degree proportional to the quantity of residuum used."

97b. During the early days of the manufacture of asphaltic cement, for paving purposes, from Trinidad asphaltum and residuum oil, the oil as it came from the refineries was poured directly into the liquid asphaltum without any investigation as to its quality. The results produced by this method in cements nominally prepared in exactly the same way were very variable and oftentimes unsatisfactory. With the increased demand for asphaltic cement many improvements both in the method of adding the oil and in its quality have been made. The oil is now subjected to careful examination to ascertain :

1. Specific gravity.
2. Flash-point.
3. Percentage volatile in a given time at 400° F.
4. Susceptibility to changes in temperature as revealed by changes in viscosity.
5. Presence of crystals of paraffine.

97c. The demand for heavy petroleum oil or residuum for use in the manufacture of cement for paving purposes has become so extensive that the oil-refining companies find it profitable to produce an oil that shall be nearly uniform in character. In preparing this oil the object aimed at is (1) the removal of the hard paraffines, which are very susceptible to changes of temperature, becoming soft under the summer sun and brittle at or below the

freezing-point; their presence imparts similar properties to the asphalt cement; (2) to remove the lighter and more volatile oils; care in their removal must be exercised: if too large a percentage is removed, the oil becomes heavy and thick, and too large a proportion is required to make a cement of suitable consistency—therefore there is a limit to the amount that can be removed.

97d. Specifications for Petroleum Residuum.—The petroleum residuum used in the manufacture of asphalt cement shall be a petroleum from which the lighter oils have been removed by distillation, without cracking, until the oil has the following characteristics:

Specific gravity ranging between 20° and 23° Baumé.

Flash-point (as taken in a New York State Board of Health oil-tester), between 300° and 425° F.

Distillate at 400° F. for thirty hours, less than 10 per cent. The distillate shall be made with about 50 grams of oil in a small glass retort provided with a thermometer and packed entirely in asbestos. The residue in the retort after distillation must be fluid at 75° F., and not coarsely crystalline on cooling.

The quantity of residuum necessary to soften the asphalt into a cement containing bitumen whose penetration is 80° on Bowen's scale shall not be over 33 per cent of the total quantity of bitumen in the asphalt.

The flowing-point shall be determined by cooling 100 cc. of oil in a small bottle and noting the temperature at which it flows readily from one end of the bottle to the other.

98. Authorities differ as to the relative merits of residuum oil and maltha as fluxes for asphaltum. Some claim that they are unsuitable on account of the volatile oils they contain, which on evaporating leave the cement in a porous or spongelike condition, which readily absorbs water, and is thus subject to the destroying action of frost. Others hold that if the oil or maltha is heated sufficiently to drive off the volatile oils they are deprived of their solvent power and are converted into substances so similar to asphaltum that their addition renders it more brittle.

98a. The writer, from his observations, considers that a more enduring cement can be obtained by adding asphaltum to maltha and allowing it to dissolve therein at a temperature of 212° to 220° F., or by submitting maltha to a process of distillation in which

the temperature is carefully regulated. Under such a process bitumen of any consistency from plastic to hard can be produced. Either of these methods would be more satisfactory and more under control than the present one of transforming a comparatively hard and brittle substance into a soft and plastic one.

98b. An examination of the bituminous limestones and sandstones shows them to be cemented together, not by hard bitumen, but by the softer varieties; and where these formations have been exposed to the destroying action of the elements they show no sign of disintegration, but are solid and impervious.

98c. Some of the most enduring constructions of antiquity, which have withstood the ravages of time for upwards of 3000 years, are cemented with bitumen. The bitumen which the ancients used was not the hard brittle variety we employ, but the soft plastic maltha, used in its natural condition as it oozed out of the springs.

99. Asphaltic Paving Materials.—All asphaltic or bituminous pavements are composed of two essential parts, namely, the cementing material (matrix) and the resisting material (aggregate). Each has a distinct function to perform: the first furnishes and preserves the coherency of the mass; the second resists the wear of the traffic.

99a. Two classes of asphaltic paving compounds are in use, namely, *natural* and *artificial*. The natural variety is composed of either limestone or sandstone naturally cemented by bitumen. To this class belong the bituminous limestones of Europe, Texas, Utah, etc., and the bituminous sandstones of California, Kentucky, Texas, Indian Territory, etc. The artificial consists of mixtures of asphaltic cement manufactured, as described in Art. 96, with sand and stone-dust. To this class belong the pavements made from Trinidad, Bermudez, Cuban, and similar asphaltums. For the artificial variety most of the hard bitumens are, when properly prepared, equally suitable. For the aggregate the most suitable materials are stone-dust from the harder rocks, such as granite, trap, etc., and sharp angular sand. These materials should be entirely free from loam and vegetable impurities. The strength and enduring qualities of the mixture will depend upon the

quality, strength, and proportion of each ingredient, as well as upon the cohesion of the matrix and its adhesion to the aggregate.

99b. Bituminous Limestone consists of carbonate of lime naturally cemented with bitumen in proportions varying from 80 to 93 per cent of carbonate of lime and from 7 to 20 per cent of bitumen. Its color when freshly broken is a dark (almost black) chocolate-brown, the darker color being due to a larger percentage of bitumen. At a temperature of from 55° to 70° F. the material is hard and sonorous and breaks easily with an irregular fracture; at temperatures between 70° and 140° F. it softens, passing with the rise in temperature through various degrees of plasticity, until, at between 140° and 160° F., it begins to crumble, at 212° F. it commences to melt, and at 280° F. it is completely disintegrated. Its specific gravity is about 2.235.

99c. Bituminous limestone is the material employed for paving purposes throughout Europe. It is obtained principally from deposits at Val-de-Travers, canton of Neuchâtel, Switzerland; at Seyssel, in the department of Ain, France; at Ragusa, Sicily; at Limmer, near Hanover; and at Vorwohle, Germany.

99d. The constituents of the more important of these deposits are given in Table XV.

99e. Bituminous limestone is found in several parts of the United States. Two of these deposits are at present being worked, one in Texas, the material from which is called "lithocarbon," and one on the Wasatch Indian Reservation. These deposits contain from 10 to 30 per cent of bitumen.

99f. The bituminous limestones which contain about 10 per cent of bitumen are used for paving in their natural condition, being simply reduced to powder, heated until thoroughly softened, then spread while hot upon the foundation and tamped and rammed until compacted.

TABLE XV.
ANALYSIS OF EUROPEAN BITUMINOUS ROCKS.*

Constituents.	Val de Travers.	Seyssel.	Lobsan.	Sicil- ian.	Mae- stu.	Forens.
	Per cent.	Per cent.	Per cent.	Per cent.	Per cent.	Per cent.
Water and matter vol. at 212° F.†	0.50	1.90	3.40	0.80	0.40	0.25
Bitumen.....	10.10	8.00	11.90‡	8.85	8.80	2.25
Carbonate of lime.....	87.95	89.55	69.00	87.50	9.15	97.00
Silicious sand.....	3.05	0.60	57.40
Aluminum and peroxide of iron	0.25	0.15	5.70§	0.90	4.85	0.15
Sulphur.....	5.00
Carbonate of magnesia.....	0.30	0.10	0.30	0.95	8.10	0.20
Different materials insol. in acids	0.45	0.10	11.85	0.05
Loss.....	0.45	0.20	1.65	0.40	0.45	0.10
	100.00	100.00	100.00	100.00	100.00	100.00

* Laboratoire de l'École des Ponts et Chaussées. M. Léon Malo.

† The water given above depends on the dryness of the sample at the time of analysis, the figures not being of importance in the result.

‡ This quantity appeared to contain a certain proportion of oil, which was mixed with the bitumen and was not exactly determined.

§ This comprises 4.45 per cent of iron combined with sulphur.

ANALYSIS OF LITHOCARBON, UVALDE COUNTY, TEXAS.

Water	00.27
Asphalt.....	13.68
Sulphur.....	trace.
Iron pyrites.....	trace.
Alumina.....	0.60
Magnesia.....	0.31
Carbonate of lime.....	82.06
Silica.....	3.08
	100.00

99g. Bituminous Sandstones are composed of sandstone rock impregnated with bitumen in amounts varying from a trace to 70 per cent. They are found both in Europe and America. In Europe they are chiefly used for the production of pure bitumen, which is extracted by boiling or macerating them with water. In the United States extensive deposits are found in the Western States,

and since 1880 they have been gradually coming into use as a paving material, and now upwards of a hundred and fifty miles of streets in Western cities are paved with them. They are prepared for use as a paving material by crushing to powder, which is heated to about 250° F., or until it becomes plastic, then spread upon the street and compressed by rolling; sometimes sand or gravel is added, and it is stated that a mixture of about 80 per cent of gravel makes a durable pavement. Good results have been obtained by mixing from 10 to 50 per cent of bituminous limestone, such as that from Vorwhole, Germany. This rock contains from 7 to 10 per cent of hard asphaltum without any oils, and imparts to the more friable sandstones, having the asphaltum in a different condition, the tenacity and hardness which they lack in the natural condition.

Kentucky Bituminous Sandstone.—The bituminous sandstone found in Breckinridge County, Ky., has been used in several cities, including Louisville, Brooklyn, Buffalo, etc. It is composed of fine white sand and from 8 to 12 per cent of bitumen. An analysis of the sandstone showed that it contains 96.88 per cent of silica, 0.81 of sesquioxide of iron, 0.46 of alumina, 0.34 of lime, 0.2 of magnesia, 0.81 of soda, 0.2 of potash, and 0.25 of combined water and loss.

Recent specifications for the preparation of this material require that the wearing surface of the pavement is to be composed of 80 to 70 per cent of the Kentucky rock and 20 to 30 per cent of Vorwhole (German) bituminous limestone. These rocks to be pulverized and the powder of each mixed in the mills and then screened. The mixture to be heated to a temperature of from 150° to 250° F., and to reach the street at not less than the former temperature, spread in one layer, compressed with hot rollers and tampers to a thickness of two inches.

Utah Bituminous Calcareous Sandstone.—This sandstone has been used for paving with varying results. It contains about 11 per cent of bitumen and 89 per cent mineral matter, which consists of

Silica and insoluble silicates.....	68.00
Ferric oxide.....	1.16
Aluminum oxide.....	2.80
Calcium carbonate.....	26.68
Magnesium carbonate, alkali, and undetermined matter.....	1.91
	<hr/> 100.00

100. Trinidad Asphaltum.—The deposits of asphaltum in the island of Trinidad, W. I., have been the main source of supply for the asphaltum used in street-paving in the United States. Three kinds are found there, which have been named, according to the source, *lake pitch*, *land* or *overflow pitch*, and *iron pitch*. The first and most valuable kind is obtained from the so-called Pitch-lake; this lake or deposit is situated about 2 miles from the seashore of the island at an elevation of 138 feet, and has an area of about 115 acres and is of unknown depth. It is quite circular in shape, and is supposed to occupy the crater of an extinct mud volcano. The surface is not flat and even, but is formed of irregular oval-shaped domes, resembling large mushrooms, separated by narrow and shallow channels and pools of water; with the exception of a small space in the centre the surface is sufficiently hard to support the weight of animals and loaded carts. The small space in the centre is called the "boiling spring." Here soft pitch still wells up, but soon becomes hard. The asphaltum is easily excavated with picks, and in the early days of the industry was loaded into two-wheeled carts, hauled by mules to the shore, and there dumped into piles, from which it was carried in baskets by coolies wading through the surf to lighters and from the lighters loaded into sailing vessels. Recently the concessionaires of the lake have built a tramway and pier by which the material is easily conveyed and quickly loaded into the vessels lying at the pier.

100a. The term *land* or *overflow pitch* is applied to the deposits of asphaltum found outside of the lake. These deposits form extensive beds of variable thickness, and are covered with from a few to several feet of earth; they are considered by some authorities to be formed from pitch which has overflowed from the lake, by others to be of entirely different origin. The name *cheese pitch* is given to such portions of the land pitch as more nearly resemble that obtained from the lake.

100b. The term *iron pitch* is used to designate large and isolated masses of extremely hard asphaltum found both within and without the borders of the lake. It is supposed to have been formed by the action of heat caused by forest fires which, sweeping over the softer pitch, removed its more volatile constituents.

100c. The name *épurée* is given to asphaltum refined on the

island of Trinidad. The process is conducted in a very crude manner in large, open, cast iron sugar boilers.

100d. The Characteristics of Crude Trinidad Asphaltum, both *lake* and *land* are as follows: It is composed of bitumen mixed with fine sand, clay, and vegetable matter. Its specific gravity varies according to the impurities present, but is usually about 1.28. Its color when freshly excavated is a brown, which changes to black on exposure to the atmosphere. When freshly broken, it emits the usual bituminous odor. It is porous, containing gas-cavities, and in consistency it resembles cheese. If left long enough in the sun, the surface will soften and melt and will finally flow into a more or less compact mass. The average composition of both the land and lake varieties is shown by the following analyses:

TABLE XVI.

AVERAGE COMPOSITION OF TRINIDAD ASPHALTUM.

Constituents.	Lake.		Land.
	Hard.	Soft.	
	Per cent.	Per cent.	Per cent.
Water.....	27.85	34.10	26.62
Inorganic matter.....	26.88	25.05	27.57
Organic non-bituminous matter...	7.68	6.85	8.05
Bitumen.....	38.14	34.50	37.76
	100.00	100.00	100.00
When the analyses are calculated to a basis of dry substances, the composition is inorganic matter.....	36.56	33.00	37.74
Organic matter not bitumen.....	10.57	9.64	10.68
Bitumen.....	52.87	52.36	51.58
	100.00	100.00	100.00
The substances volatilize in 10 hours at 400° F.	3.66	12.24	0.86 to 1.37
" " soften at.....	190° F.	170° F.	200° to 250° F.
" " flow at.....	200° F.	185° F.	210° to 328° F.

100e. Refined Trinidad Asphaltum.—The crude asphaltum is refined or purified by melting it in iron kettles or stills by the ap-

plication of indirect heat. In the earlier refineries upright cylindrical kettles holding about ten tons were used; the heat was obtained from a coal fire, the kettles being protected from its direct action by a brick arch. In this form of still the refining process occupied from one hundred and twenty to one hundred and forty hours, and, as the plant became deteriorated, much longer; sediment collected on the bottom, causing much waste of fuel, coking of the asphaltum, and the burning out of the still itself. In consequence of these defects their use is practically abandoned and in their place horizontal boilers have been adopted. In their most approved form these boilers or stills consist of a boiler about twenty feet long and ten feet in diameter furnished with two longitudinal flues eighteen inches in diameter placed four feet from the bottom and four feet between centres. These stills are placed in brickwork surrounded with loam to prevent radiation, and are provided with flues so arranged that the direct heat from the fire passes first along one side, then back along the other, repeating this at a higher level, then through one flue in the still and back through the other, and finally under the bottom. In this way overheating on the bottom is prevented and better results are obtained in evaporating the water from the upper layers of crude material. These stills hold about thirty tons of crude material, and the time of refining is much reduced. After some years practice with the above-described method agitation of the asphaltum with a current of air during the refining process was introduced, with the object of further reducing the time required and the possibility of injury to the asphaltum.

Recently a departure has been made from this last-described method; it consists in the use of steam-heat in place of coal-fire heat. The objects aimed at are a reduction in time and prevention of the injury by coking or burning of the asphaltum, which frequently occurred when refining with direct heat. In this later process instead of large cylindrical boilers or stills smaller rectangular kettles are used, holding about twenty-five tons; these are furnished with gangs of pipe for the circulation of steam at a pressure of about 100 pounds per square inch; agitation is produced by jets of dry steam or air. By this method a charge is refined in about twelve hours and the product is very uniform in quality.

100f. Irrespective of the method adopted for heating, the process of refining proceeds as follows: During the heating the water and lighter oils are evaporated, the asphaltum is liquefied, the vegetable matter rises to the surface and is skimmed off, the earthy and silicious matters settle to the bottom, and the liquid asphaltum is drawn off into old cement- or flour-barrels.

100g. When the asphaltum is refined without agitation, the residue remaining in the still forms a considerable percentage of the crude material, frequently amounting to 12 per cent, and it was at one time considered that the greater the amount of this residue the better the quality of the refined asphaltum; but since agitation has been adopted the greater part of the earthy and silicious matters are retained in suspension and it has come to be considered just as desirable for a part of the surface mixture as the sand which is subsequently added. The refined asphaltum, if for local use, is generally converted into cement in the same still in which it was refined.

100h. In the earlier part of the refining process the water contained in the crude material is liberated and forms in pools on the surface; this water is of a distinct saline and thermal character, containing a large amount of salts in solution, which probably explains the efflorescence seen upon the crude asphaltum and which is frequently attributed to sea salt.

100i. The principal salts in solution are, in the order of their amount, sodic chloride and sulphate, ammoniac, potassic, and ferrous sulphates, borates, iodides, etc.

100j. The distillate from the stills is strongly acid, and free hydrochloric, sulphuric, and hydrosulphuric acids and other sulphur compounds have been determined in it.

100k. The steam which is formed in the refining of the crude asphaltum at first contains much hydrogen sulphide, which blackens all the white-lead paint in the vicinity of the refinery. This, under favorable conditions of heat and evaporation, at times changes to sulphurous anhydride, which again bleaches out the white paint. The condensed steam shows a strongly acid reaction. In the presence of one another the hydrocarbons and the thermal water at high temperature evidently produce complicated reactions.

100l. The residue from the bottom of the still consists of some clay mixed with silica in the form of minute fragments of quartz

and some of the salts contained in the water, An analysis showed it to consist of:

Clay, silica, and silicates insoluble in acid.....	87.67 p.c.
Soluble salts, alumina, iron, lime, etc.....	12.33 p.c.
	100.00 P. C.

Of the insoluble portion about 95 per cent is silica, and frequently the lime is absent.

100m. The organic matter not bituminous possesses no distinctive characteristics; it occurs as an impalpable powder without any signs of organization.

100n. The Characteristics of Refined Trinidad Asphaltum are as follows:

AVERAGE COMPOSITION OF REFINED TRINIDAD ASPHALTUM.

	Lake.	Land.
Specific gravity at 77° F.....	1.38	1.43
	Per cent.	Per cent.
Bitumen.....	56.29	53.75
Organic matter not bituminous	8.05	8.01
Inorganic matter.....	35.66	38.24
	100.00	100.00
Bitumen soluble in petroleum naphtha.....	41.43	35.23
Per cent of total bitumen soluble.....	78.60	65.83
Softens at	190° F.	210° F.
Flows at	205° F.	230° F.

The color is black with a homogeneous appearance. At a temperature of about 70° F. it is very brittle and breaks with a conchoidal fracture; it burns with a yellowish-white flame, and in burning emits an empyreumatic odor, and possesses little cementitious quality; to give it the required plasticity and tenacity it is mixed while liquid with from 16 to 21 pounds of residuum oil to 100 pounds of asphaltum in the manner described in Art. 96.

100o. The product resulting from the combination is called *asphalt paving-cement*; its consistency should be such that, at a temperature of from 70° to 80° F., it can be easily indented with the fingers and on slight warming be drawn out in strings or threads.

100p. The relative quality of Trinidad *lake* and *land* asphaltum for paving has been the subject of much discussion and investigation, but without any positive decision being reached.

100q. That there is no essential difference in the chemical composition will be seen by an examination of the analyses given in Table XV α and Art. 100n.

100r. The difference between the two varieties consists not in a material variation in the proportion of the constituents, but in a variation or change in the character of the bitumen. This change is due to evaporation, volatilization and oxidation of the light and volatile oils, thus hardening it and necessitating a larger amount of flux to soften the land asphaltum for use as a cement. This larger percentage of flux is by some authorities said to reduce the enduring qualities of the cement; others claim that no amount of flux will restore the lost qualities. Hence the object in selecting *lake* asphaltum, in which a large percentage of the natural oils still remains, and rejecting the *land* asphaltum which, has lost these oils in a large degree.

100s. In Europe crude Trinidad asphaltum is used for mixing with the bituminous limestones in the manufacture of *asphalt mastic*; for this purpose it is refined as follows: The crude asphaltum is melted in suitable vessels and to it is added the residue or by-products from the petroleum distilleries and paraffine factories in the proportion of about 2 parts of residue to 3 parts of asphaltum; the mixture is boiled for 8 or 9 hours, during which time the earthy and mineral substances in the asphaltum settle to the bottom; the liquid asphaltum is then drawn off and is ready for use. This preparation is known in England as *refined bitumen*; in France as *bitume raffiné*, *bitume composé*, and *goudron composé*; in Germany as *goudron*.

101. **Bermudez Asphalt.**—This is the name given to the asphaltum obtained from a lake or deposit situated in the state of Bermudez, Venezuela. This deposit is said to have an area of over 1000 acres. It is situated about 60 miles from the coast up the San Juan River, and about 51 miles distant from it; a narrow-gauge steam railroad connects the deposit with the shipping point, and vessels drawing 18 feet of water can be loaded directly from the cars.

The crude asphaltum is of the same variety as the Trinidad,

namely, bitumen mixed with sand, clay, and vegetable matter; its average specific gravity is 1.09, and its average composition is as follows:

	Per cent.
Bitumen.....	98.54
Mineral matter.....	2.16
Organic matter not bituminous.....	1.15
Water.....	3.15
	<hr/> 100.00
Petrolene.....	77.90
Asphaltene.....	21.08
Retine.....	1.02
	<hr/> 100.00

The refining process is practically similar to that described under Trinidad asphaltum, but is much more rapid, owing to the small amount of water and mineral matter present. In manufacturing the cement it requires much less petroleum residuum than the Trinidad on account of the large amount of oil that it contains; it melts at a lower temperature than the Trinidad, and the following are some of its characteristics: At 60° F. compressible; at 70° F. viscous and malleable; at 100° F. flowing, and can be stretched in hairlike threads; at 189° F. melts; at 400° F. gives no flash. (See also Art. 265a.)

102. California Asphaltum.—Asphaltum is produced in California by refining the bitumen from the extensive sandstone and other deposits which are found in various parts of the State. The characteristics of both the crude and refined asphaltum from some of the more important deposits are shown by the following analysis:

ANALYSIS OF ASPHALTUM FROM BAKERSFIELD, CAL.

	Crude.	Refined.
Specific gravity.....	1.182	1.240
Softens at.....	180° F.	150° F.
Flows at.....	220° F.	180° F.
Inorganic matter.....	9.57 p. c.	9.77 p. c.
Bitumen soluble in CS ₂	85.49 p. c.	90.16 p. c.
Bitumen soluble in ether.....	69.98 p. c.	86.45 p. c.
Percentage of total bitumen soluble in ether.....	81.85 p. c.	95.88 p. c.

ANALYSIS OF ASPHALTUM FROM ASPHALTO, CAL.

	Crude.	Refined.
Moisture.....	6.51 p. c.	0.43 p. c.
Bitumen soluble in chloroform.....	84.79 p. c.	98.27 p. c.
Organic matter (not bitumen).....	trace	0.54 p. c.
Inorganic matter consisting of infusorial earth with traces of iron.....	8.70 p. c.	5.77 p. c.
Petrolene soluble in acetone.....	67.50 p. c.	71.27 p. c.
Asphaltene insoluble in acetone.....	33.50 p. c.	28.73 p. c.
Combined sulphur (chemically held in the bitumen).....	0.73 p. c.	

ANALYSIS OF ASPHALTUM FROM SANTA BARBARA CO., CAL.

	Crude.	Refined.
Specific gravity.....	1.250	
Organic non-bituminous matter.....	1.10 p. c.	
Inorganic matter consisting of finely divided quartz with oxide of iron and alumina.	39.75 p. c.	
Bitumen soluble in CS ₂	59.15 p. c.	
Bitumen soluble in petroleum naphtha (petrolene).....		42.50 p. c.
Asphaltene.....		7.85 p. c.

ANALYSIS OF ASPHALTUM FROM KERN CO., CAL.

Bitumen soluble in CS ₂	78.90 p. c.
Mineral substances—sand, clay, and silica.....	9.40 p. c.
Coky and volatile matter.....	4.53 p. c.
Water and loss.....	7.17 p. c.

ANALYSIS OF BITUMINOUS SANDSTONE FROM VENTURA CO., CAL.

Bitumen.....	24.00 p. c.
Silica.....	64.00 p. c.
Oxide of iron	} 12.00 p. c.
Calcium carbonate }	

Cements for paving and other purposes are manufactured from the refined asphaltum described above by the admixture of *maltha*; the two substances are combined at a very low temperature, the heat being applied indirectly, and the mixing is performed mechanically; the degree of softness can be made to suit any requirement.

102a. Buena Vista Asphalt.—The asphaltic paving cement sold under this name is prepared from a liquid asphaltum obtained from California and a hard asphaltum from Utah, and contains no

Softening-point of the bitumen.

Flowing-point " " "

Stability of the bitumen at high temperature.

Action of water and ammonia on the bitumen.

Change in bitumen due to aging.

Susceptibility of bitumen due to change with variations in temperature.

The examination of the physical properties (mechanical tests) involve the following determinations:

(1) The refining of the crude material and making of an asphaltic cement.

(2) Determining the viscosity or softness of the cement.

(This investigation is commonly called the "penetration" test; its purpose is to ascertain whether the cement is of the proper degree of softness to produce a good pavement. The degree of softness or viscosity depends partly upon the quality of the asphaltum and partly upon the character and proportion of the flux; it also increases and diminishes as the temperature is raised or lowered; hence great care is required when examining several samples of the same cement or comparing samples of different cements to have them all at the same temperature. Experience shows that to secure the best results the viscosity or softness of the cement must differ in different localities according to the climate, and also according to the character of the sand and dust used.)

(3) Making a paving mixture and testing it for tensile and crushing strength.

Amount of Bitumen.—The amount of bitumen contained in the crude material is ascertained by extracting it with a solvent (carbon disulphide is the most commonly used). This extraction may be made in numerous ways. The method requiring the least experience and giving the least trouble is by extracting in large test-tubes or cylinders, and decanting off the solvent containing the dissolved bitumen from the insoluble portions.

The method of procedure is as follows: The sample of asphaltum is spread in a thin layer in a suitable dish (nickel or iron), and kept at a temperature of 225° F., until it practically stops losing weight. The greater part, and in some cases all the water and some light oils are expelled in this way. From 2 to 10 grams

(depending on its richness in bitumen) of the sample is weighed in a large sized test-tube (8 inches long by 1 inch diameter), the tare of which has been previously ascertained. The tube containing the sample is then filled to within $1\frac{1}{4}$ inches of the top with carbon disulphide and allowed to stand for a few minutes. Then the tube is tightly corked with a good sound cork. It is then shaken vigorously until no material can be seen adhering to the bottom. Care should be taken while shaking to keep one finger on the cork to prevent its being blown out. The tube should then be put away in an upright position and not disturbed in the slightest way for two days, after which the solvent is decanted off into a small bottle. As much of the solvent should be poured off as is possible without losing any of the residue. The tube is again filled and shaken as before, and put away for two more days. After the liquid has been carefully decanted the second time, the tube, with the residue, is dried at a low temperature. After cooling it is weighed. As there is always a small portion of the residue poured off in the solution with the bitumen, this solution must be evaporated and the bitumen burned off in a platinum dish and the weight of the residue added to that in the tube. The weight of the sample taken, less the sum of these two weights, is the weight of the bitumen extracted, from which can be calculated the percentage of bitumen contained.

Stability of the Bitumen at High Temperature.—The necessity of stability at high temperature for a length of time is owing to the length of time the bitumen must remain in a heated condition during the course of the manufacture of the asphalt mixture, which may cause it to lose valuable properties. The effect of this heat is rendered much more severe on the bitumen because of its great area exposed to evaporation when mixed with sand. The lack of stability resulting from the loss of light oils is manifest in different ways in different bitumens. Although generally so, it does not of necessity follow that the bitumen losing the most oil undergoes the greatest change in consistency. There are two methods of testing stability, and it is advisable to use both.

The first consists in making the asphalt cement into a mixture with standard sand in such proportions that the mixture will contain 10 per cent of bitumen; the materials for the mixture are

kept for fifteen minutes in an oven heated to 300° F., then incorporated by stirring. One portion of the mixture is put aside to cool, while the other is kept at the temperature of 300° F. for one-half hour longer. The bitumen is then extracted from both, and after reaching the same temperature their penetrations are compared.

The second method consists in keeping a quantity of the substance, equivalent to 20 grams of bitumen, at a temperature of 400° F. for thirty hours. The method of procedure is as follows: The substance is weighed in a short-necked, tabulated, 2-ounce retort, the tare of which has been previously taken. The retort is then hung in a copper cylinder so that the neck just protrudes. The copper cylinder is then jacketed with asbestos and provided with a thermometer. After being heated up to 400° F., at which temperature it is maintained for thirty hours, the retort is allowed to cool, then weighed and the per cent of loss ascertained. The retort is then broken and the character of its contents compared with that of the original substance.

Action of Water and Ammonia on the Bitumen.—The action of water and dilute ammonia is determined by moulding an inch cube of the mixture under a pressure of 1000 pounds, then breaking it into two pieces, one of which is immersed in water or dilute ammonia, while the other is kept in air. The two pieces are compared from time to time. If acted on by the liquid, the corners will be found to give away readily with a slight pressure of the finger. After soaking some time it is well to evaporate the liquid to dryness and note if any bituminous residue remains.

Changes in Bitumen due to Age.—All bitumens undergo a more or less rapid change with aging, that appears to be due to two or, possibly, more causes. Two distinct changes manifest themselves. One is the surface hardening, which is likely due to indirect oxidation, and possibly to the volatilization of light oils. It begins at the surface and gradually extends into the bitumen. The other is a hardening of the entire mass, evidently due to polymerization. Both these changes take place in all bitumens, but one or the other may predominate. The former is much the less objectionable, as it makes slow progress into the mass. In making a test to ascertain the effect of aging, it is preferable to

use the asphalt cement, as there is some danger in using extracted bitumen of the solvent not having been entirely removed, and its slow evaporation might be interpreted as a true change, due to the hardening of the bitumen.

The test for aging is made as follows: The penetration of the sample is determined, after which it is put away for a week, when it is again ascertained. If the sample shows an appreciable hardening, a slanting cut is made into it with a sharp knife, laying over the upper piece, thus exposing a gradual descent from the surface into the interior. Penetrations are now taken down the side of this cut, beginning at the surface. In this way the increase in hardness of the surface and the interior over its original consistency is determined; also the hardening of the surface over the interior and the depth that the surface hardening has entered the sample.

It is well to continue this test for as long a period as possible, making examinations at intervals of every few weeks.

Susceptibility of Bitumen to Change with Variations in Temperature.—This is determined by making penetration tests of the sample at several different degrees of temperature and noting the changes in its condition.

Penetration Tests.—The softness or viscosity of an asphalt cement was, in the early days of asphalt paving, determined by chewing a small piece and judging by the resistance it offered to the teeth; the rule was that if it chewed easily and yet was not soft enough to adhere to the teeth, it was of the proper consistency for paving.

Bowen's Apparatus.—In 1888 Prof. Bowen devised a machine for testing the viscosity of asphaltic cements which has been extensively employed. This machine consists of a lever about 17 inches long, having the fulcrum at one end and a cambric needle inserted in the other end, above which is placed a weight of 100 grams. The end near the needle is connected by a steel rod and waxed cord with a spindle having a long hand which moves about a dial divided into 360 degrees. Another cord and weight upon an enlarged part of the spindle keeps the first-mentioned cord taut. By a suitably contrived spring clip the steel rod can be released for any length of time, and the needle, which has first been

brought to coincide with the surface of the asphalt cement placed under it in a tin box, allowed to penetrate under the action of the weight into the cement. The number of degrees through which the hand moves on the dial records the penetration of the cement; the length of time for which the needle is released is one second. Originally Prof. Bowen selected 77° F. as the proper temperature at which the test should be made, and brought the cement and machine to this degree by keeping them in a room warmed to this point. But as it is sometimes inconvenient or impossible to have a room temperature of 77°, other temperatures may be made available by placing the tin sample-box of asphalt cement in water at 77° and allowing it to acquire that temperature, when the test can be made as before, certain allowance being made to reduce the result to the normal temperature of 77° F.

Dow's Apparatus.—Mr. A. W. Dow, Inspector of Asphalts and Cements at Washington, D. C., has devised a testing-machine in which he has endeavored to overcome the objections raised against Professor Bowen's. The tests are made in a water-jacketed copper box; any temperature can be obtained in this box by running through the jacket water cooled or heated as desired. The needle penetrates under a direct weight with practically no friction. The description of this apparatus in detail is as follows: The penetrating needle, which is an ordinary No. 2 sewing needle, is rigidly fastened in the end of a small brass rod. This rod is inserted in the end of an aluminum tube, about 40 centimetres in length and 1 centimetre in diameter, where it is securely fastened by means of a binding-screw. By filling or partially filling this tube with mercury, it can be made of any desired weight from 30 to 300 grams, after which it is closed by a cap which screws on to the end opposite the needle. When this cap is screwed into place, its surface, which is perfectly flat, is absolutely at right angles to the sides of the tube. The aluminum tube holding the needle passes down through a wooden framework in which it is held in a vertical position, with the needle-end down, by means of a jaw-clamp. When this clamp is released the tube can move freely up and down, while it is retained in its vertical position by two guides. These guides are each made of two metal plates a fraction of a centimetre in thickness. Each plate has a semicircular piece cut out of one

side, so that when the two are placed together it leaves a circular opening through which the aluminum tube passes freely, but yet not so freely as to get out of the vertical. To facilitate the removal of the needle-tube from the framework, as it must be slightly inclined while withdrawing so as to clear the measuring device, the guides are constructed so that one plate in each can be pushed a short distance from the other, thus allowing the inclination of the tube. These plates are returned to their original position by springs.

In the upper part of the framework directly over the tube is a spindle 3.17 millimetres in diameter, with a pointer on one end which turns on a dial. A small plumb-weight is suspended from the spindle by a fine platinum thread which winds on it. This weight is partly counterbalanced by a second weight suspended from the spindle by a linen thread. These weights are so that if they be allowed to move freely the former is just sufficiently heavy to cause it to fall gradually, and when the aluminum tube is in position this weight will fall until it just touches the surface of the cap on the top of the tube. The fall of one centimetre of this weight causes the spindle to make one revolution, thus making one revolution of the pointer on the dial equivalent to one centimetre. The above framework is fastened on to the cover of a copper chamber, the aluminum tube projecting through this cover into the chamber, needle-end down. This cover, which is of wood, is made in two thicknesses, with an air-chamber between, thus more perfectly insulating the interior of the chamber from the outside air. It is supplied with two large windows on each side of where the needle-tube passes in, admitting light and allowing the operator to see the sample. The chamber to hold the samples, which is of thin sheet copper, is constructed with a rounded bottom like a kettle, and is fitted with a flat false bottom or flooring of sheet iron. Raised above the flooring about an inch, resting on three rollers, is a circular disk, on which the samples to be tested are placed in a circle about half an inch from the edge. This disk can be rotated like a turntable by means of an iron rod which passes through its centre into a bearing on the floor and out through the cover of the chamber, where it is fitted with a wheel. By turning this wheel, thus revolving the disk,

each sample on it can be brought in turn under the penetrating needle. In this way twelve samples can be tested by this particular apparatus without opening the chamber. Two swinging mirrors are fastened, one on each side of the copper chamber, one mirror being so adjusted as to throw light on the sample to be tested, while the other reflects the image of the sample so that it can be seen by looking in through a window in the cover. This copper chamber is fastened into a lead-lined tank, which is filled with water of any degree, or a freezing mixture, as the case may be, to produce the desired temperature in the chamber. To keep this temperature constant the tank is supplied with one inlet, in the centre of the bottom, and four outlet pipes, one on each side near the top. The temperature of the copper chamber is regulated by a simple electrical thermostat suspended in it, which will cut off or let on a supply of liquid or water entering the tank as the temperature requires.

In making a test or tests the samples are placed in position on the disk in the copper chamber, the cover with the apparatus put in place, and the chamber secured in the lead-lined tank. The water or liquid of the desired temperature is run into the tank, which is allowed to fill and run off by the overflow pipes. The entire apparatus is then levelled by levelling-screws in the feet of the tank until the needle-tube is perfectly vertical. When asphalt is to be tested it is, for convenience, put into small round tins like small blacking boxes. By heating just sufficiently to melt it a smooth surface is obtained with quite a gloss. These boxes containing the samples are placed on the revolving disk, each sample resting on two raised points on the surface of the disk, this giving them a slight incline. The table is then revolved until the desired sample is directly under the needle-tube, when it is lowered until the needle is very nearly in contact with the surface. The surface of the sample being slightly inclined, it can be brought just in contact with the needle by a slight revolution of the disk. By arranging the mirror on top of the cover so that it will reflect the light from a window down upon one of the mirrors in the chamber, which in turn reflects it on the surface of the sample, and then having the other mirror in the chamber in such a position as to reflect the image of the sample up, the needle can be set accurately

to the surface by watching its reflection in the surface of the sample. To determine the penetration the reading of the dial is taken, the clamp is released, which allows the needle to sink in the asphalt under the weight of the tube. The apparatus is so constructed that when the clamp is released from the tube another clamp closes on the thread of the counterbalance weight, thus preventing the plumb-weight from falling and adding its weight to that of the tube. On clamping the tube again at the expiration of the desired time the thread of the counterweight is released, which allows the plumb-weight to sink until it is checked by the top of the tube. The present reading of the dial, less that before taken, is the distance the needle penetrated into the sample. Readings can be made with accuracy to one-fiftieth millimetre.

District of Columbia Standard.—The present standard employed for penetration tests by the Engineer Department of the District of Columbia is the distance (on Dow's apparatus) expressed in hundredths of a centimetre that a No. 2 needle will sink or penetrate into an asphalt paving cement in five seconds when weighted with 100 grams, the cement and apparatus being at a temperature of 25° C.

The average penetration (measured by the above standard) of the paving cements used in Washington, D. C., during 1899 was :

Eastern Bermudez Asphalt Paving Co.	45
Cranford Paving Co.	36

The physical tests are performed in the usual machines employed for testing other cements.

Tensile Strength of Asphaltum.—Tests of the tensile strength of asphalt are frequently made from the mixture prepared for laying in the street, moulded into briquettes, and broken in a similar manner to Portland cement briquettes. This method is imperfect, as it is quite impossible, without enormous pressure, to get the particles of sand as firmly consolidated in briquette as they are by the kneading and rolling motion imparted to the surface mixture under a steam-roller, and whatever advantage is to be found in this method of examination it is complicated by any variation which may occur in the method of mixing.

A method successfully employed to obtain the tensile strength of asphalt is by using the broken halves of Portland cement

briquettes. These are united with the asphalt or asphaltic cement, and broken in a testing-machine in the following manner: The broken halves of a Portland cement briquette, which was broken clean and at right angles to the line of stress, are heated to drive off all moisture; the two halves are then dipped in molten asphalt and pressure applied by hand until the thickness of the asphalt is reduced to less than $\frac{1}{8}$ of an inch. The briquettes are then allowed to cool slowly, and after standing 24 hours are broken in a cement testing-machine.

Brass briquettes cast from the pattern of a Portland cement briquette are also used. The surfaces upon which the asphalt is to adhere are left rough. When using these briquettes they are heated to about 140° F. in water, taken out and dried, and the separate ends dipped in the molten asphalt. The two ends of the briquette are then stuck together and allowed to cool slowly in the same manner as the Portland cement briquettes.

When testing asphaltic cement for tensile strength the penetration of the cement must be taken into consideration as well as the temperature at which the test is made. Below 50° F. the results obtained will be very much more regular than with tests made above that temperature; the higher the temperature the greater will be the variation.

An asphaltic cement made from well refined Trinidad Lake asphaltum should have with a penetration between 70 and 80 degrees (Bowen's scale) a tensile strength of over 450 lbs. per sq. in. at a temperature of 35 degrees Fahr., and 300 lbs. per sq. in. at 50 degrees Fahr., the strength being determined with a one-inch section, the strain to be applied at the rate of 1000 lbs. per minute.

The *ductility* or property of being drawn out in long threads or strings has been referred to in Art. 1000 as a measure of the proper consistency of a paving cement. Mr. W. H. Broadhurst, in Proc. A. S. M. I., describes the method employed by him to measure this property as follows:

Twenty grams of pure bitumen were extracted from Trinidad, Bermudez, and Alcatraz asphaltums with chloroform. To the pure Trinidad bitumen petroleum residuum was added to the amount of 33 per cent of its weight (this percentage being calculated from the usual proportion of 18 lbs. of residuum to 100 lbs.

of refined Trinidad asphalt, containing 55 per cent bitumen). The penetration was then taken with the Bowen apparatus, and found to be 40° at 80° F. The pure Bermudez was brought to the same degree of penetration, requiring approximately 13 per cent of its weight of petroleum residuum. The pure Alcatraz bitumen required approximately 24 per cent of Alcatraz maltha (2X grade) to give a penetration of 40°. As a matter of technical interest, a separate portion of Trinidad bitumen was brought to 40° penetration with Alcatraz maltha. These four cements were poured while hot into glass tubes $2\frac{1}{2}$ inches in length and $\frac{1}{8}$ inch in internal diameter, closed at one end with a cylindrical cork. These tubes had previously been cut in half, the edges ground true to plane, and cemented together with a thin film of plaster of Paris. This cement joint being easily broken by a slight side pressure, the tubes were kept at a temperature of 80° F. for one hour; they were then clamped in a vertical position and separated a distance of exactly $\frac{1}{4}$ of an inch. The lower half of the tube was then allowed to draw apart from the upper by its own weight, thus pulling the cement out into a string, the cross-section decreasing as the length increased. The distance between the tubes at the time of rupture was noted, and the following results were obtained:

RELATIVE DUCTILITY OF ASPHALT CEMENTS.

Composition of Cement.	Penetration at 80° F. Bowen's Scale.	Ductility at 8° F. Length.	Ductility at 90° F. Length.
Trinidad asphaltum and petroleum residuum.	40°	$\frac{1}{2}$ in.	$\frac{3}{4}$ in.
Bermudez asphaltum and petroleum residuum.	40	$1\frac{1}{2}$ "	$2\frac{1}{2}$ "
Alcatraz asphaltum and Alcatraz maltha.....	40	$2\frac{1}{2}$ "	$4\frac{1}{2}$ "
Trinidad asphaltum and Alcatraz maltha.....	40	$2\frac{1}{2}$ "	$4\frac{1}{2}$ "
Pure Alcatraz asphaltum (soft).....	50	$4\frac{1}{2}$ "	
Uvalde asphaltum (refined) and Alcatraz maltha	50	$5\frac{1}{2}$ "	
Trinidad asphaltum and petroleum residuum..	55	$\frac{1}{2}$ "	
Bermudez asphaltum and petroleum residuum.	55	8 "	
Alcatraz asphaltum and Alcatraz maltha.....	55	$4\frac{1}{2}$ "	
Bakersfield asphaltum and Bakersfield maltha.	55	$2\frac{1}{2}$ "	

As asphalt cement possesses the same qualities and can be used for the same purposes as hydraulic and other cements, its physical qualities can be tested in a similar manner; but the tests which

have been made and published have been conducted without any regard to uniformity and under widely different conditions; therefore they are of little or no value in determining the relative merits of the cements.

Uniformity in making the tests would accumulate much valuable data which could be compared, and much definite information would thus be gradually collected from which definite conclusions could be ultimately drawn.

A regular system of analysis and examination of both the crude and refined asphaltum, the oils or other agent used for fluxing, the method of refining the asphaltum, the method of manufacturing the asphaltic cement, the sand, stone-dust, etc., should be maintained in all cities using asphalt pavements. The experience thus gained of the success or failure of pavements made of different asphalts will serve as a guide for similar work in the future. This experience, however, will not serve as a criterion for all cities, because, owing to different climatic and local conditions, the proportions of the ingredients in the cement and paving mixture must be varied to suit the conditions of the place where used; therefore the mixtures which are successful in one locality may become failures in another.

In comparing the relative qualities of asphaltums for paving purposes much stress is frequently laid upon the amount of bitumen they contain. As the amount of bitumen entering into the paving mixture is less than 20 per cent of the whole, the amount of bitumen contained in a crude asphaltum can in no way affect the quality of the pavement; but its quantity does affect the commercial value or price of the crude material in regard to the amount of refined asphaltum that it will yield. As far as the qualities of the paving mixture are concerned, it is the character and condition of the bitumen, and not its quantity, that affect the results.

Essential Characteristics of a Bitumen.—The necessary characteristics for a bitumen to possess to produce a satisfactory pavement are adhesiveness, cohesiveness, and elasticity—to a certain degree. It must not show too rapid a change with aging, must be practically unaffected by water or dilute ammonia, and have a proper degree of consistency or softness. Its consistency should not be greatly altered by changes in temperature; and lastly, a

certain degree of stability upon being kept at a high temperature for a length of time.

104. Prices, Production, and Imports of Asphaltum.—The following tables show the comparative prices of different varieties of asphaltum, the amount of the domestic production, and the imports to the United States during the year 1897–98:

TABLE XVII.

PRICES OF ASPHALTUM IN 1897–98.

Trinidad crude, at New York.....	\$13.00	per ton
“ refined, at New York.....	\$30.00 to \$40.00	“
Hard Cuban, at New York.....	28.00	“
Gilsonite, at the mines.....	60.00	“
Bituminous rock:		
California, at the mines.....	3.25 to 12.00	“
Kentucky, at the mines.....	3.25	“
California refined (hard), at the works....	17.50 to 19.50	“
at New York....	26.50 to 32.00	“
California refined (maltha), at the works...	20.00 to 22.00	“
at New York..	29.00 to 34.50	“
Wasatch bituminous limestone, at the works	18.00	“

TABLE XVIII.

PRODUCTION OF ASPHALTUM IN THE UNITED STATES.

State.	1897.		1898.	
	Short Tons.	Value.	Short Tons.	Value.
California.....	68,650	\$598,502	71,086	\$605,451
Kentucky.....	3,250	15,150	1,450	7,800
Indian Territory, Oklahoma, and Texas.....	845	8,480	1,685	7,952
Colorado and Utah.....	8,700	47,500	2,166	54,446
Total.....	75,945	\$664,632	76,337	\$675,649

TABLE XVIIIa.

VARIETIES OF ASPHALTUM, ETC., PRODUCED IN THE UNITED STATES.

Variety.	1897.		1898.	
	Short Tons.	Value.	Short Tons.	Value.
Crude asphaltum.....	5,971	\$71,404	11,300	\$179,900
Bituminous sandstone.....	48,801	158,914	43,624	126,831
Bituminous limestone.....	2,100	10,600	5,502	26,418
Mastic.....	483	9,864	1,158	17,840
Hard and refined or gum.....	8,940	102,500	1,878	53,668
Liquid or maltha.....	14,650	811,350	12,875	271,000
Total.....	75,945	\$664,682	76,337	\$675,649

TABLE XIX.

IMPORTS OF ASPHALTUM TO THE UNITED STATES.

Country.	1897.		1898.	
	Long Tons.	Value.	Long Tons.	Value.
West Indies:				
British (Trinidad).....	85,084	\$198,786	71,992	\$217,660
Danish.....	400	2,000		
Cuba.....	223	4,180	137	2,172
Switzerland.....			98	530
Italy.....	14,580	77,456	1,260	7,531
Venezuela (Bermudez).....	13,807	75,943	2,000	10,006
Germany.....	6,896	25,986	2,302	9,066
France.....	861	3,327	779	3,377
Mexico.....	273	3,992	438	5,773
Turkey in Asia.....	31	3,439	41	3,744
Great Britain.....	11	309	13	597
United States of Colombia.....	3	130		9
Canada.....	2	6		
Total.....	122,122	\$395,554	79,060	\$260,765

105. **Uses of Asphaltum.**—Refined asphaltum and asphaltic cement are extensively used in all branches of engineering. The paving industry absorbs about 60 per cent of the domestic production and about 80 per cent of the imported. Of the imports from Trinidad about 90 per cent is employed for street-paving.

106. **Paving-pitch.**—This is the name given to the tar produced in the manufacture of gas. It is also known as *gas-tar*, *coal-*

tar, etc. When the tar is redistilled, the product is called *coal-tar distillate*, and is numbered *Distillate No. 1, 2, 3, 4, etc.*, according to the density or specific gravity. The character of the tar varies with the system of carbonization and temperature employed. There are several tars on the market which show to the analyst no material difference, although the grouping and character of the constituents are different. Some, when used for paving purposes, will become hard and brittle in a few months, and others will not harden or set.

The pitch known as No. 4 is used mainly as a filler for granite and Belgian block. It is very soft, and frequently becomes semi-fluid under the heat of summer; for this reason it is put up in oil barrels which contain about 50 to 52 gallons.

The No. 6 is generally used as a filler for brick pavement; it is termed medium hard, and is commonly put up in cement and lime barrels. The cement barrels contain about 28 gallons, and the lime barrels from 30 to 32 gallons. The pitch is sold by the ton, and the weight of the package is figured in.

A square yard of brick paving requires from 1 to 1½ gallons, according to the spacing and the manner in which the work is done. A square yard of stone-block paving will take from 2 to 4 gallons.

Paving-pitch is frequently adulterated with wood-pitch, which serves to reduce its cost considerably, and also serves to make it very inferior for paving purposes. A paving-pitch suitable for stone pavements should be soft enough to almost stick to the fingers when worked in the hand at a temperature of about 70° F. For brick pavements it should be somewhat harder, so as to check the tendency to flow during hot weather.

The use of coal-tar as a cementing medium for carriageway pavements has been practically abandoned in the United States, but in the country towns of England it is still extensively employed for foot-paths, floors, etc.

Analysis of No. 4 pitch gives the following composition: Specific gravity, 1.284 to 1.309; matter soluble in carbon bisulphide, 64.84 to 72.50; insoluble matter, 27.50 to 35.16.

The price per gallon at the gas-works during 1898 varied from 2.23 cents in Indiana to 10.17 in Montana and New Mexico.

Many persons consider that the enduring quality of the tar is increased by the addition of refined asphaltum, and specifications frequently call for the addition of from 10 to 20 per cent of asphaltum; but this clause is rarely complied with, and it is doubtful if the mixture would prove beneficial, because the materials, although very similar in appearance and in some of their characteristics, are entirely different in composition.

(See also Art. 160.)

107. Brick—Clay.—Pure clay consists of a hydrated silicate of alumina in combination more or less with other substances derived from the felspathic rocks, which by their disintegration and decomposition have formed the clay. The chemical formula of the most prominent varieties of clay according to Brogniart and others may be expressed by $2\text{Al}_2\text{O}_3, 3\text{SiO}_2, 4\text{H}_2\text{O}$.

108. Pure clay is soft, more or less unctuous to the touch, white and opaque, and when breathed upon emits a characteristic odor. It is infusible, and insoluble either by water, nitric or hydrochloric acids. It may be converted by water into a doughy, tenacious, plastic paste. It absorbs water with avidity, but when burned at a sufficiently high temperature it becomes hard and gritty and loses almost wholly or altogether this property of combining with water. When slowly dried and exposed to red heat, the particles of clay are augmented in volume and possess less density. At the same time, however, the interstitial spaces are diminished and they approach more closely together, giving an increase of density to the whole mass of burnt clay, which is practically observed by a diminution of surface and technically called the shrinking of the clay. This shrinkage is very materially modified and affected by the admixture and proportion of foreign matters possessing other properties.

109. In nature the greater number of clays is found intermingled with other substances foreign to them in their original localities. The usual constituents of clay are alumina, silica, iron, lime, magnesia, and alkalies, all of which modify the character of the clay and its applications, according as one or other of these ingredients predominates.

110. The ingredients which most affect the character of the clay are the silica, iron, and lime, and its plasticity diminishes in proportion to the amount of any one of these substances which it contains, as they are not plastic. Sand exercises the most marked

effect; it possesses no binding properties, and alone it is infusible except at the highest temperatures of the oxyhydrogen blowpipe. Bricks made of clay containing an excess of sand are rough and weak. Iron renders clay fusible, and its presence is objectionable in brick intended for furnace-lining; but in paving-brick it is advantageous, making the brick more homogeneous. Lime, although infusible, is at high temperatures changed into caustic lime, renders the clay fusible, and when exposed to the action of the weather absorbs moisture and causes disintegration. Its presence is to be avoided in clay used for the manufacture of paving-brick. Magnesia exerts but little influence on the character of the clay; in small quantities it renders the clay fusible; at 60 degrees Fahr. its crystals lose their water of crystallization and cold water decomposes them, forming an insoluble hydrate in the form of a white powder. In air-dried brick this action causes them to crack. The alkalis are found in small quantities in the best of clays; from 1 to 3 per cent renders the clay fusible. The greater the amount of quartz and silica that enters into the composition of the clay, the more difficult it will be of fusion.

111. Clay, to make a good paving-brick, must be rich in silica, free from lime, and able to withstand without fusing a red heat for a sufficient length of time to render the bricks hard, homogeneous, and impervious to water.

112. Common hard-burned brick is not suitable for paving purposes, although such brick makes a smooth pavement under light traffic and lasts for a number of years; still, under the influence of moisture and frost, disintegration is inevitable in the end. Nor will such brick sustain constant heavy traffic, aside from climatic influences. Brick made of suitable clay, however, will stand the severest frosts, and crushing tests show it to be equal to many granites.

The shales or rock-like clays are now almost exclusively used in the manufacture of paving-brick. They usually contain a high percentage of fluxing impurities, which enables them to be readily

A very elaborate discussion of the chemical composition and the influence of impurities of clays is given by H. A. Wheeler, Assistant Geologist in Part I of the "Report on the Missouri Clays."

vitrified. The average composition of the shales that have proved satisfactory for the manufacture of paving-brick is as follows:

Silica (SiO_2).....	56.00
Alumina (Al_2O_3).....	22.00
Water chemically combined and loss on ignition.....	7.00
Moisture (H_2O).....	2.00
Sesquioxide of iron (Fe_2O_3).....	7.00
Lime (CaO).....	1.00
Magnesia (MgO).....	1.00
Alkalies (K_2O , Na_2O).....	4.00
	<hr/> 100.00

113. The color of clay is of no practical importance ; it is due to the presence of metallic oxides and organic substances. Clay containing iron produces bricks which are either red, yellow, or blue, according to the quantity of the oxide present and the degree of heat to which they have been subjected; some organic substances produce a blue, bluish-gray, or black color.

The color of the brick is largely influenced by the burner in the manipulation of the fires, and cannot be relied upon as a guide to the quality of the brick; for a specific clay and a given burner it aids in estimating the degree to which the brick has been burned, and the care with which it has been handled.

114. The Manufacture of Paving-brick may be classified under the following heads:

Excavation of the clay either by hand labor or mechanical appliances.

Preparation of the clay consists in (a) removing gravel, stones, or other mechanical impurities; (b) pulverizing the clay. This is performed either by toothed rolls, centrifugal disintegrators, or crushing-rolls in the revolving dry or wet pan. The dry pan with a perforated grate bottom is generally employed for shales and fire clays.

The pulverized clay is usually screened in either revolving trammels or fixed or shaking riddles, with 4 to 16 meshes to the linear inch. The degree of fineness of the screen is a very important matter, as the finer the clay the more plastic it is, and hence the more homogeneous and stronger the brick. The fineness of the screen, however, must be determined for each specifically, as ex-

cessive fineness in some clays causes checking and cracking in drying or burning, and aggravates the trouble from laminations. In some works the clay is not screened any further than is accomplished by the screen-plates of the dry pan, which are usually $\frac{1}{8}$ to $\frac{1}{4}$ inch in width.

Tempering.—The screened clay is mixed with water and worked to a more or less plastic mass in a pug-mill. The operation should be performed in such a way as to secure a *thorough, uniform mixture* of the clay and water; if this is not attained the clay leaves the machine with variable amounts of water. This causes checking and cracking in the drying, and sometimes in the burning, with marked variations in the strength of the brick. The more thoroughly a clay is pugged, the more plastic it is rendered, and the more uniform and reliable will be the quality of the brick.

Moulding.—The process most generally employed for moulding paving-brick is that called the “stiff-mud process.” The clay is made into a stiff, plastic mud, which is forced through a die by a continuous-working auger or intermittent plunger as a bar of clay, which is then cut by wires into suitable lengths.

For forming the bar of clay two types of dies are employed; in one the die is approximately $3'' \times 4''$ in section, and the bar of clay is cut into 9'' lengths; this is known as the “end-cut system”: in the other the die is approximately $4'' \times 9''$ in section, and the bar of clay is cut into 3'' lengths; this is called the “side-cut system.” There is considerable difference of opinion as to the relative merits of these two methods of moulding.

Drying.—The moulded brick are packed in cars, in open checkerwork, direct from the brick-machine, which are run into chambers or tunnels heated by open fires, steam-coils, or a heated blast. The time required for drying depends upon the character of the clay; the finer and more plastic the clay the greater the time required, the coarser and leaner the clay the more rapidly it can be dried. Some clays can be safely dried in 24 hours, while others require from 60 to 72 hours.

Burning.—After being sufficiently dried the bricks are piled in the kilns, and the firing is conducted with the utmost care, as upon it the perfection of the brick largely depends. Two classes of kilns are in use for burning paving-brick, the down-draft and the

continuous. The down-draft type seems to be the most preferred, as with careful handling from 60 to 90 per cent of No. 1 brick can be obtained. The continuous type has greater economy of fuel, but the shrinkage and the difficulty of securing uniformity in burning is so great that they only yield from 40 to 70 per cent of No. 1 brick. After the brick are burned, the kiln is tightly closed to shut off the access of cold air, and the longer the time given the brick to cool and anneal the tougher the brick will be.

Sorting.—In emptying the kiln there are usually three grades of brick found: (1) Those which have received the highest heat, and, while hard, are not generally tough enough for paving purposes; (2) those which have not received sufficient heat to be properly vitrified; and (3) those which have been properly burned, and which are designated as No. 1, or strictly first-class paving-brick. They are distinguished by the fracture, toughness, and the color from the other two grades of brick. They should be perfectly uniform in the fracture, homogeneous, very dense, very hard, tough, and reasonably free from "kiln-marks," or indentations made by the overlying brick. The depth of the kiln-mark is considered a gauge for the degree of the vitrification; the deeper the mark the more thorough the vitrification, but if too deep they make a rough uneven pavement; the allowable limit ranges from $\frac{1}{8}$ to $\frac{3}{8}$ inch. The absence of kiln-marks usually indicates underburning. Except in fire-clays, it is seldom that a properly vitrified brick is entirely free from slight indentations.

115. Repressed Brick are produced by subjecting the brick immediately after it leaves the brick-machine, and while still in a plastic condition, to a moderate vertical pressure in a metal mould-box. The operation fills out the edges and angles, and rounds them if desired. The appearance of the brick is much enhanced, but there is much difference of opinion as to whether the quality is improved; the tests by Professor Orton indicate that repressing an end-cut brick improves it, while repressing a side-cut brick injures it.

116. Analyses of Clay.—Table XX shows the composition of some of the clays used in the manufacture of paving-brick.

TABLE XX.
ANALYSES OF CLAYS.

Locality.	Silica.	Alumina.	Iron.	Lime.	Magnesia.	Potash.	Soda.	Sulphur.	Chlorides.	Water combined.	Water Hygro-metric.	Titanic Acid.	Phosphoric Acid.	Silica Quartz.
Woodbridge, N. J.	42.23	39.53	0.5	0.1	0.41	0.08	13.59	1.21	1.40	0.56
Phillipsburg, "	42.05	35.83	0.77	0.11	0.44	12.20	1.50	1.10	5.70
Winchester, Ill.	56.78	17.38	6.50	4.14	3.15	3	42	0.89	7	60	0.18
Bloomington, Ill.	23.15	17.08	3.47	0.28	1.10	6.80	1.20	0.90	46.70
Cheltenham, Mo.	67.80	11.55	4.31	8.90	5.32	2	42	trace	0	30	trace
	61.22	25.64	1.70	1	31	0.4	9.68
	38.10	31.53	2.32	tr.	0.40	11.80	2.50	1.50	18.70
Montgomery, Mo.	43.93	40.09	0.88	0.20	13.80	0.80	tr.*	0.80
Woodlawn, Penn.	42.15	31.43	1.57	0.32	2.01	9.40	1.20	1.00	10.25
Mt. Savage, Md.	39.90	30.08	1.67	2.30	7.00	6.90	1.15	16.90
Carter Co., Ky.	46.75	38.17	0.29	0.57	0.12	0	07	14	08
Marion Co., W. Va.	59.25	32.26	7.16	1	83
San Fran., Cal.	56.51	21.33	12.31	3.53	tr.	6.80
Haydensville, O.	72.24	16.87	0.16	0.50	tr.	1.09	5.14
Burlington, Ia.	77.40	11.74	3.29	1.60	1.91	3.76	0.47
Clinton, "	73.82	15.88	2.92	tr.	tr.	4.5	3.0
Morrison, Colo.	71.8	15.0	tr.	3.8	3.3
Golden, "	52.41	32.21	0.66	0.20	0.61	0.61	14.05
Stourbridge, Eng.	67.34	23.08	2.03	1	38	8.24
"	64.06	23.15	1.85	0	10	10.00

* With Al_2O_3 .

117. The Characteristics of Brick suitable for Paving are:

- (1) Not to be acted upon by acids.
- (2) Not to absorb more than $\frac{1}{8}$ of its weight of water in 48 hours.
- (3) Not susceptible to polish.
- (4) Rough to the touch, resembling fine sandpaper.
- (5) To give a clear ringing sound when struck together.
- (6) When broken to show a compact, uniform, close-grained structure, free from air-holes and pebbles.
- (7) Not to scale, spall, or chip when quickly struck on the edges.
- (8) Hard but not brittle.

118. Tests of Paving-brick. To ascertain the quality of paving-brick they are now generally subjected to four tests, namely:

- (1) Abrasion by impact (commonly called the "Rattler" test);
 - (2) absorption; (3) transverse or cross-breaking; (4) crushing.
- With the view of securing uniformity in the methods of making

the above tests the National Brick Manufacturers' Association have adopted and recommend the following:

118a. Standard Tests Adopted by the National Brick Manufacturers' Association (Chicago, Jan. 27, 1900).

RATTLER TEST.

1. *Dimensions of the Machine.*—The standard machine shall be 28 inches in diameter and 20 inches in length, measured inside the chamber.

Other machines may be used varying in diameter between 26 and 30 inches, and in length from 18 to 24 inches, but if this is done, a record of it must be attached to the official report. Long rattlers may be cut up into sections of suitable length by the insertion of an iron diaphragm at the proper point.

2. *Construction of the Machine.*—The barrel shall be supported on trunnions at either end; in no case shall a shaft pass through the rattling chamber. The cross-section of the barrel shall be a regular polygon having fourteen sides. The heads shall be composed of gray cast iron, not chilled or case-hardened. The staves shall preferably be composed of steel plates, as cast-iron peans and ultimately breaks under the wearing action on the inside. There shall be a space of one-fourth of an inch between the staves for the escape of dust and small pieces of waste. Other machines may be used, having from twelve to sixteen staves, with openings from one-eighth to three-eighths of an inch between staves, but if this is done a record of it must be attached to the official report of the test.

3. *Composition of the Charge.*—All tests must be executed on charges containing but one make of brick or block at a time. The charge shall consist of nine paving-blocks or twelve paving-bricks, together with 300 pounds of shot made of ordinary machinery cast iron. This shot shall be two sizes, as described below, and the shot charge shall be composed of one-fourth (75 pounds) of the larger size, and three-fourths (225 pounds) of the smaller size.

4. *Size of the Shot.*—The larger size shall weigh about $7\frac{1}{4}$ pounds and be about $2\frac{1}{2}$ inches square and $4\frac{1}{2}$ inches long, with slightly rounded edges. The smaller size shall be cubes of $1\frac{1}{2}$ inches on a side, with rounded edges. The individual shot shall

be replaced by new ones when they have lost one-tenth of their original weight.

5. *Revolutions of the Charge.*—The number of revolutions of a standard test shall be 1800, and the speed of rotation shall not fall below 28 nor exceed 30 per minute. The belt-power shall be sufficient to rotate the latter at the same speed, whether charged or empty.

6. *Condition of the Charge.*—The bricks composing a charge shall be thoroughly dried before making the test.

7. *Calculation of the Results.*—The loss shall be calculated in per cents of the weight of the dry brick composing the charge, and no results shall be considered as official unless it is the average of two distinct and complete tests made on separate charges of brick.

ABSORPTION TEST.

1. The number of bricks for a standard test shall be five.

2. The test must be conducted on rattled brick. If none such are available, the whole brick must be broken in halves before treatment.

3. Dry the bricks for forty-eight hours at a temperature ranging from 230° to 250° F. before weighing for the official dry weight.

4. Soak for forty-eight hours completely immersed in pure water.

5. After soaking, and before weighing, the bricks must be wiped dry from surplus water.

6. The difference in the weight must be determined on scales sensitive to one gram.

7. The increase in weight due to water absorbed shall be calculated in per cents of the initial dry weight.

CROSS-BREAKING TEST.

1. Support the brick on edge, or as laid in the pavement, on hardened steel knife-edges, rounded longitudinally to a radius of twelve inches and transversely to a radius of one-eighth inch, and bolted in position so as to secure a span of six inches.

2. Apply the load to the middle of the top face through a har-

dened steel knife-edge, straight longitudinally and rounded transversely to a radius of one-sixteenth inch.

3. Apply the load at a uniform rate of increase till fracture ensues.

4. Compute the modulus of rupture by the formula $f = \frac{3wl}{2bd^2}$

in which f = modulus of rupture in pounds per square inch;

w = total breaking load in pounds;

l = length of span in inches = 6";

b = breadth of brick in inches;

d = depth of brick in inches.

5. Samples for test must be free from all visible irregularities of surfaces or deformities of shape, and their upper and lower faces must be practically parallel.

6. Not less than ten brick shall be broken, and the average of all be taken for a standard test.

CRUSHING TEST.

1. The crushing test should be made on half-bricks, loaded edgewise, or as they are laid in the street. If the machine used is unable to crush a full half-brick, the area may be reduced by chipping off, keeping the form of the piece to be tested as nearly prismatic as possible. A machine of at least one hundred thousand pounds capacity should be used, and the specimen should not be reduced below four square inches of area in cross-section at right angles to direction of load.

2. The upper and lower surfaces should preferably be ground to true and parallel planes. If this is not done, they should be bedded while in the testing-machine in plaster of Paris, which should be allowed to harden ten minutes under the weight of the crushing planes only, before the load is applied.

3. The load should be applied at a uniform rate of increase to the point of rupture.

4. Not less than an average obtained from five tests on five different bricks shall constitute a standard test.

119. Specific Gravity, Weight, Resistance to Crushing, and Absorptive Power of Paving-brick. In regard to these qualities the paving-bricks made by different manufacturers and by the same manufacturer vary considerably, as will be seen from Table XXI. In weight they vary from 5 to 7½ pounds; in specific gravity, from 1.91 to 2.70; in resistance to crushing, from 7000 to 18,000 pounds per square inch; in absorption, from 0.15 to 5.00 per cent.

Tests of Ohio Paving-brick.—Table XXIa contains the results of a series of tests conducted by Prof. Edward Orton, Jr., at the solicitation of the Geological Survey of the State of Ohio. The tests were performed with the greatest care and absolutely without interest or bias of any kind, and the results are solely on the merits of the samples furnished. The tests are interesting and valuable in several ways. It is the first work of the kind undertaken by the State, and it is also probably the first large and general test in which the results could not be attacked as being *ex parte*. It is of great interest to those who compete for standing, of course, and it should be equally interesting to all clay-workers to see so large a list of factories, representing an annual capacity of three hundred millions of brick, showing so high an average quality of material. The samples were selected by the manufacturers themselves, and therefore represent their best. It was the intention to make this so; the public does not desire to know how poorly the brick-makers can do, but how well, and, having shown their ability to produce goods of this quality, it should be their constant endeavor to hold their average output up to the same high grade.

TABLE XXI.

TESTS OF PAVING BRICKS MADE AT THE LABORATORY OF LATHBURY & SPACKMANN, IN PHILADELPHIA, IN ACCORDANCE WITH THE REQUIREMENTS OF THE SPECIFICATIONS OF THE NATIONAL BRICK MANUFACTURERS' ASSOCIATION.

	Catakill Shale Paving Bricks from Canal Street, July 26, 1897.	Canton Shale "Red Granite" Bricks from Jefferson Street, July 26, 1897.	Corning Shale Paving Bricks from Second Street, Sept. 6, 1897.
Average size, in inches.....	8.50×4.00×2.50	8.50×4.00×2.50	8.06×3.91×2.47
Average weight, in pounds.....	7.46	6.99	6.69
Average area of top surface, sq. in....	21.25	21.25	20.0
Average volume of one brick, cu. in....	85.00	85.00	78.0
Average specific gravity	2.38	2.45	2.63
Absorption of water, average of 5:			
Weight in lbs. after drying 48 hours...	18.00	15.78	17.95
Weight in lbs. after immersion 48 hrs.	18.89	16.61	18.65
Weight in lbs. of water absorbed	0.89	0.83	0.70
Percentage of water absorbed.....	4.9	5.26	3.9
Cross-breaking strength, bricks on edge. Centre load between supports 6 inches apart:			
First.....	6,840	8,120	8,810
Second.....	8,610	8,570	6,390
Third.....	8,850	8,950	6,300
Fourth.....	8,510	9,080	6,660
Fifth.....	8,950	9,490	6,720
Sixth.....	9,940	10,270	8,480
Seventh.....	9,120	11,120	8,510
Eighth.....	11,470	11,330	9,260
Ninth.....	11,620	11,690	12,450
Tenth.....	13,210	12,930	12,460
Average strength in lbs.....	9,712 ± 1,778	10,155 ± 1,486	8,112 ± 2,005
Modulus of rupture.....	2,185 ± 400	2,285 ± 334	1,984 ± 621
Impact tests (two), 28-inch rattler, 20 inches long, making 30 revolutions per minute:			
Weight before test, lbs.....	(1) 156.65 (2) 161.09	(1) 146.87 (2) 146.84	(1) 153.37 (2) 158.56
Weight after 300 revolutions.....	146.96 141.93
Weight after 1,800 revolutions.....	128.36 128.20	120.98 118.98	123.34 125.75
Loss in lbs. after 300 revolutions.....	6.41 11.63
Loss in lbs. after 1,800 revolutions.....	28.09 37.89	25.89 27.86	30.08 27.81
Loss per cent after 300 revolutions.....	4.17 7.57
Loss per cent after 1,800 revolutions..	17.9 23.5	17.6 18.9	19.57 18.11
Average per cent after 1,800 revol.	20.7	18.3	18.84

TABLE XXIA.
TESTS OF OHIO PAVING BRICK.

Number.	Name of the Firm Furnishing Sample.	Kind of Material Furnished.	Kind of Machinery Used in its Manufacture.	Kind of Clay Used in its Manufacture.	Per cent Absorption, Gain.	Per cent Loss.	Crushing Strength, Sq. Inch.	Crushing Strength, Cu. Inch.
1	Wassall Fire Clay Co., Columbus, O.	Hallwood Block, 3x1x9	Sewer-pipe press.	Zanesville shales, with some local plastic clays.	.60	8.92	5,300	1,815
2	Ohio Paving Co., Columbus, O.	Hallwood Block, 3x1x9	Penfield plunger machine.	Zanesville shales, from Kittanning horizon.	1.08	25.77	4,465	1,138
3	Logan Fire-Clay Co., Logan, O.	Hallwood Block, 3x1x9	Frey-Sheckler auger machine. Side-cut Raymond press.	Shales and fire-clay from vicinity. Small amount surface clays.	1.32	10.08	5,462	1,343
4	Nelsonville Sewer-Pipe Co., Nelsonville, O.	Hallwood Block, 3x1x9	Sewer-pipe press and Raymond press.	Fire clay from Kittanning horizon.	1.75	7.12	7,499	1,888
5	Athens Paving-Brick Co., Athens, O.	Hallwood Block, 3x1x9	Frey-Sheckler auger machine. End-cut Raymond press.	Shales from above the Freeport horizon.	.47	12.80	5,308	1,277
6	Portsmouth Paving-Brick Co., Portsmouth, O.	Hallwood Block, 3x1x9	Penfield auger machine. End-cut Raymond presses.	Sub-carboniferous shales of vicinity.	.24	30.27	6,032	1,694
7	Cincinnati Brick Co., Ad-dynton, O.	Hallwood Block, 3x1x9	Penfield auger machine. End-cut Raymond presses.	Sedimentary clays from Ohio river valley.	1.23	21.30	4,806	1,249
8	W. B. Harris & Brothers, Zanesville, O.	Hallwood Block, 2 1/4 x 1 1/2 x 9	Penfield auger machine. End-cut Raymond presses.	Shales from Kittanning horizon, with surface plastic clays.	.83	21.38	4,639	1,181
9	T. B. Townsend & Co., Zanesville, O.	Hallwood Block, 3x1x9	Penfield auger machine. End-cut Raymond presses.	Shales from Freeport horizon and fire clay from Kittanning horizon.	1.34	15.51	5,206	1,302
10	Middleport Granite-Brick Co., Middleport, O.	Hallwood Block, 3x1x9	Grant-Murray brick machine, Raymond presses.	Sedimentary clays from Ohio river valley.	1.77	14.30	4,568	1,100
11	Hocking Clay Co., Logan, Ohio.	Hayden patent sidewalk brick, 2 1/4 x 1 1/2 x 9	Sewer-pipe press and Hayden press.	Fire-clays and shales from vicinity.	.60	23.94	6,125	1,491
12	Haydenville Mining and Manufacturing Co., Haydenville, O.	Hayden patent paving-block for sidewalk use, 10 1/2 x 4 1/2 x 9 1/2	Sewer-pipe press and Hayden press.	Fire-clays, with little shale from Mercer and Kittanning horizon.	.84	17.49	No crushing tests made.	

TABLE XXIA—Continued.

Number.	Name of the Firm Furnishing Sample.	Kind of Material Furnished.	Kind of Machinery Used in its Manufacture.	Kind of Clay Used in its Manufacture.	Per cent Absorption.	Per cent Hauling, Loss.	Crushing Strength, Sq. Inch.	Crushing Cu. Inch.
13	East Clayton Manufactur- ing Co., Lick Run, O.....	East Clayton Block, 2½x 4x9	Sewer-pipe press and Ray- mond repress.....	Fire-clay, with little shale from Kittanning horizon	1.19	17.37	4,302	1,288
14	Scioto Star Fire-Brick Co., Sciotoville, O.....	Grant Star Block, 3x4x9...	Freese auger machine. Side-cut Raymond re- press.....	Sub-carboniferous shales, with little fire-clay added	.65	11.73	6,733	1,656
15	Standard Brick and Terra- Cotta Co., New Straite- ville, O.....	Parto Block, 3x4x9	Freese auger machine. Side-cut Raymond re- press.....	Fire-clay and shales from Kittanning horizon.....	.51	22.25	5,399	1,308
16	Roseville Brick and Terra- Cotta Co., Roseville, O.....	Roseville Block, 3x4x9...	Frey-Sheckler auger ma- chine. Side-cut Eagle repress.....	Shales from Putnam Hill horizon	1.47	10.74	7,749	1,761
17	The A. O. Jones Brick and Terra-Cotta Co., Zanes- ville, O.....	Jones Block, 3x4x9	Freese auger machine. Side-cut Raymond re- press.....	Mixture of fire-clay and shales from Kittanning horizon95	20.90	7,307	1,808
18	The Imperial Brick Co., Canton, O.....	Metropolitan Block, 3x4x9.	Side-cut Raymond re- press and Eagle repress.	Shales from the Putnam Hill horizon64	16.32	5,653	1,362
19	Logan Granite-Clay Co., Logan, O.....	Logan Granite Paver, 2½x 4x9	Brewer brick machine. Raymond repress.....	Shales and fire-clays from vicinity96	19.18	8,727	2,098
20	The Ironton Fire-Brick Co., Ironton, O.....	Ironton F. B. Paver, 2½x 4½x9	Freese auger machine. Side-cut Raymond re- press.....	Shales from vicinity, Kit- tanning horizon.....	.35	20.21	5,995	1,342
21	The Ironton Fire-Brick Co., Ironton, O.....	Ironton F. B. Paver, 2½x 4½x9	Freese auger machine. Side-cut Raymond re- press.....	Fire-clays from same hori- zons in vicinity00	34.40	3,548	897
22	The Riverside Brick Co., Middleport, O.....	Riverside Paver, 2½x4x8½	Grant brick machine. Eagle repress	Sedimentary clays from Ohio river valley.....	1.03	21.36	4,386	1,119
23	Canton Brick Co., Canton, Ohio.....	Red Granite Paver, 2½x 4x8½	Frey-Sheckler auger ma- chine. Side-cut Raymond repress	Shales from Putnam Hill horizon45	13.26	10,983	2,604
24	Royal Brick Co., Canton, Ohio.....	Repressed Paver, 2½x4x8½	Freese auger machine. Side-cut Raymond re- press.....	Shales from Putnam Hill horizon30	16.79	8,754	2,116

TABLE XXIA—Continued.

Number.	Name of the Firm Furnishing Sample.	Kind of Material Furnished.	Kind of Machinery Used in its Manufacture.	Kind of Clay Used in its Manufacture.	Per cent Absorption, (min.)	Per cent Rattling, (Loss.)	Crushing Strength, Sq. Inch.	Crushing Strength, Cu. Inch.
25	W. S. Williams, Canton, Ohio	C. W. Williams' Paver, 2½ x128½	Frey-Sheckler auger ma- chine, Side-cut Raymond repress	Shales from Lower Mercer horizon.....	.43	15.80	7,741	1,705
26	Holloway Paving-Brick Co., North Industry, O.	Holloway Paver, 3½x128½	Frey-Sheckler auger ma- chine, Side-cut Raymond repress	Shales from the Lower Mercer horizon.....	1.82	19.79	8,074	1,883
27	Canton Brick Co., Canton, Ohio	Plain Side-cut Brick Paver, 2½x128½	Frey-Sheckler auger ma- chine	Shales from Putnam Hill horizon.....	.75	16.80	7,701	1,897
28	Royal Brick Co., Canton, Ohio	Plain Side-cut Brick Paver, 2½x128½	Freese auger machine.....	Shales from Putnam Hill horizon.....	.57	12.41	8,883	2,208
29	W. S. Williams, Canton, Ohio	Plain Side-cut Brick Paver, 2½x128½	Frey-Sheckler auger ma- chine	Shales from Lower Mer- cer horizon.....	1.57	16.37	7,341	1,753
30	Holloway Paving-Brick Co., North Industry, O.	Plain Side-cut Brick Paver, 2½x128½	Frey-Sheckler auger ma- chine	Shales from Lower Mer- cer horizon.....	2.14	21.15	7,205	1,733
31	Standard Paving-Brick Co., North Industry, O.	Plain Side-cut Brick Paver, 2½x128½	Frey-Sheckler auger ma- chine	Shales from Lower Mer- cer horizon.....	1.37	18.37	8,928	2,094
32	Waynesburg Brick and Clay Co., Waynesburg, O.	Plain Side-cut Brick Paver, 2½x128½	Freese auger machine.....	Shales from Middle Kit- tanning horizon.....	.28	21.35	8,754	2,092
33	Waynesburg Brick and Clay Co., Waynesburg, O.	Plain Side-cut Brick Paver, 2½x128½	Freese auger machine.....	Fire-clay from Middle Kit- tanning horizon.....	.88	19.77	6,807	1,668
34	Malvern Clay Co., Mal- vern, O.	Plain Side-cut Brick Paver, 2½x128½	Frey-Sheckler auger ma- chine	Fire-clay from Middle Kit- tanning horizon.....	1.92	15.95	6,806	1,668
35	Canton and Malvern Brick and Paving Co., Mal- vern, O.	Plain Side-cut Pavers, 2½ x128½	Frey-Sheckler auger ma- chine	Fire-clay from Middle Kit- tanning horizon.....	.96	18.73	5,612	1,480
36	Massillon Stone and Fire- Brick Co., Massillon, O.	Plain Side-cut Pavers, 2½ x128½	Frey-Sheckler auger ma- chine	Fire-clay and shales from Quakertown horizon.....	1.89	13.90	9,513	2,354
37	State Line Fire-Brick Co., East Palestine, O.	Plain Side-cut Pavers, 2½ x128½	Frey-Sheckler auger ma- chine	Fire-clay from Upper Freepport horizon.....	1.09	15.30	8,986	2,111
38	Salem Garfield Mining and Manufacturing Co.	Plain Side-cut Pavers, 2½ x128½	Freese auger machine.....	Shales from vicinity, with little fire clay added.....	3.56	19.76	6,355	1,528
39	Congo Fire-Clay Co., Em- pire, O.	Plain Side-cut Pavers, 2½ x128½	Freese auger machine.....	Fire-clay from Kittanning horizon.....	4.47	12.50	7,887	1,995

TABLE XXIA—Continued.

Number.	Name of the Firm Furnishing Sample.	Kind of Material Furnished.	Kind of Machinery Used in its Manufacture.	Kind of Clay Used in its Manufacture.	Per cent Absorption.	Per cent Ratting, Loss.	Crushing Strength, Sg. Inch.	Crushing Strength, Cu. Inch.
40	Vulcan Fire-Clay Co., Wallsville, O.	Plain Side-cut Pavers, $2\frac{1}{4}$ $\times 12\frac{1}{2}$	Frey-Sheckler auger ma- chine.	Fire-clay from Kittanning horizon.	3.14	13.66	1,581	1,880
41	Buckeye Brick Co., Wells- ville, O.	Plain Side-cut Pavers, $2\frac{1}{4}$ $\times 12\frac{1}{2}$	Freyse auger machine. Raymond repress.	Fire-clay from Kittanning horizon.	3.32	20.79	None made.	
42	De Haven Brick Co., Akron, Ohio	Plain Side-cut Pavers, $2\frac{1}{4}$ $\times 12\frac{1}{2}$	Shales from horizon of lowest coal vein.	5.11	20.34	1,627	1,877
43	Bucyrus Brick and Terra- Cotta Co., Bucyrus, O.	Plain Side-cut Pavers, $2\frac{1}{4}$ $\times 12\frac{1}{2}$	Frey-Sheckler auger ma- chine.	Shales from Gloucester, O., mixed $\frac{1}{4}$ drift clay.	.28	14.56	9,942	2,485
44	South Zanesville Brick and Paving Co., South Zanes- ville, O.	Side-cut Blocks, $8\frac{1}{2} \times 12$, not repressed.	Freyse auger machine.	Shale and fire-clay from Putnam Hill horizon.	2.97	16.47	5,271	1,280
45	Trimble Brick Manufac- turing Co., Trimble, O.	Plain Side-cut Pavers, $2\frac{1}{4}$ $\times 12\frac{1}{2}$	Frey-Sheckler auger ma- chine.	Shales from horizon of Cambridge limestone.	2.30	22.89	7,617	1,890
	Averages	1.36	17.71	6,847	1,663

120. Wood.—Both the hard and soft varieties of wood have been employed for paving. In the United States, cedar and cypress, on account of their abundance and cheapness, are more generally used. Recently mesquite, which grows in abundance in both Texas and Mexico, has been used. In Europe nearly all varieties of the

TABLE XXII.

SPECIFIC GRAVITY, WEIGHT, AND RESISTANCE TO CRUSHING OF VARIOUS WOODS.

	Specific Gravity.	Average Weight, pounds per cubic foot.	Resistance to Crushing, pounds per square inch.
Acacia.....	.71 to .79	44	16,000
Ash, American white, dry.....	.61	38	8,900
Beech.....	.69	43	7,700
Cedar, American white.....	.86	22.45	4,400
Chestnut, ".....	.46	23.80	5,800
Chestnut.....	.60	38
Cypress, American.....	.406	24.4	6,000
Deal, Christiania.....	.689	48	5,850
Ebony.....	1.187	74	19,000
Elm.....	.56	35
Fir, American (Pacific region).....	.405	25.28
Fir, European.....	.512	32	6,500
Hemlock, Am. (Atlantic region).....	.409	25.5	5,800
Hickory.....	.85	58
Lignum vitæ.....	1.83	88	10,000
Mahogany, Spanish.....	.85	58	8,200
" Honduras.....	.56	35	8,000
Maple.....	.79	49
Mesquite, American (Texas)....	.756	47	10,450
Oak " white (Atlantic).....	.763	46.5	7,000
" " chestnut ".....	.711	44	7,500
" " red ".....	.751	46.7	7,000
" " black ".....	.687	48.8	7,000
" English.....	.777	48	6,400
" ".....	.984	58	10,000
Pine, American white.....	.85 to .45	21 to 25	5,400
" " red.....	.485	30	6,800
" " yellow (Pacific).....	.590	38	12,000
" " pitch (Atlantic).....	.682	39	5,000
" Dantzic.....	.649	40	5,400
Redwood, American (California).....	.478	29.5	9,500
Spruce, " (Atlantic).....	.408	25.4	5,700

pine species have been tried, as well as oak, ash, and elm, but Memel and Dantzic fir appears to be the favorite.

Recently *jarrah* from Australia and *pyingado* (*xylia dolabr-*

formis) from India have been introduced in London; the results are still indefinite.

121. Whichever kind is used, it should be sound, close-grained, uniform in quality, free from knots and sap and from the blue tinge which is a sign of incipient decay. All sappy wood should be rejected.

TABLE XXIII.

ABSORPTIVE POWER OF WOOD.

(E. R. ANDREWS in "Engineering News.")

	Percentage of Water absorbed.	
	Dry Wood.	Creosoted.
Black gum.....	1.0000	.1250
Cottonwood.....	.7140	.3470
Oak.....	.2000	.0625
Spruce.....	.1754 to .3888	.0286 to .0906
" (Burnettized .2500).....		
Hard pine.....	.1600	.0000
White birch.....	.4800	.1240
Sesquicia gigantea (tree of California).....	.4722	.0000

122. The use of creosote or other preserving processes makes it difficult to discover defects in the wood, and on this account is objectionable. It is doubtful if creosoting, etc., adds to the life of wood employed for paving.

123. **Sand.**—Sand is an aggregation of loose incoherent grains crystalline in structure and angular in shape, of silicious, argillaceous, calcareous, or other material, derived from the disintegration of rocks or other mineral matter, and unmixed with earth or organic matter. For road purposes the grains should not exceed one eighth of an inch in size.

124. The principal use of sand is as a foundation for broken stone, a cushion and bed for stone paving-blocks, and as a joint filling. For these purposes it is eminently suitable, because when confined so that it cannot escape or spread it possesses the valuable properties of incompressibility, and mobility or the quality of assuming a new position when any portion of it is disturbed.

As a base or cushion for blocks it quickly adjusts itself to every irregularity of their inferior surfaces, and when the blocks finally

settle in place it furnishes a solid incompressible medium to transfer the pressure to the foundation below. For this purpose it should be fine and dry; if coarse and damp, the blocks will adjust themselves with difficulty and the fewer will be the points of support between them and the foundation, and the greater will be the pressure of contact and liability to unequal settlement.

125. Sharp sand, i.e., sand with angular grains, is much better than that with rounded grains, although it is often difficult to obtain. The sharpness of sand can be determined approximately by rubbing a few grains in the hand or by crushing it near the ear and noting if a grating sound is produced.

126. The sand for bedding blocks and jointing should be clean, i.e., free from loam or clay. The cleanness may be tested by rubbing a little of the dry sand in the palm of the hand and, after throwing it out, noticing the amount of dust left on the hand. The cleanness of sand may also be judged by pressing it together between the fingers while it is damp; if the sand is clean, it will not stick together, but immediately fall apart when the pressure is removed.

127. For concrete used for foundation it is not necessary that the sand should be free from clay; indeed a small amount of clay may be beneficial. Clay when dissolved or finely pulverized consists of an almost impalpable powder, and when mixed with sand its particles occupy the interstices between the particles of cement and sand, and are also completely enveloped by the cementing paste. Clay, dissolved or finely pulverized, mixed with cement up to the proportion of 1 to 1, appears to affect the strength essentially the same as an equal quantity of sand, and the mortar is much more dense, plastic, and water-tight. Such mortar is not affected by the presence of water.

The voids of ordinary sand average from 0.3 to 0.5 of the volume; the more uneven the sizes the smaller the voids.

128. The quantity of sand required for bedding paving-blocks is about one cubic yard to six square yards of paving.

129. The price of sand varies from 40 cents to \$1.60 per yard, according to locality.

130. Sand is sometimes sold by the ton. It weighs when dry

from 80 to 115 pounds per cubic foot, or about 1 to 1½ tons per cubic yard.

131. Gravel is an accumulation of small stones which vary in size from a small pea to a walnut or something larger. It is often intermixed with other substances, such as sand, clay, loam, etc., from each of which it derives a distinctive name. In selecting gravel for road purposes the chief quality to be sought for is the property of binding (see Art. 424).

Gravel in general is unserviceable for road-making. This is due mainly to the fact that the surface of the pebbles is smooth, so that they will not bind together in the manner of broken stone. There is also an absence of dust or other material to serve as a binder, and even if such binding material is furnished it is difficult to effectively hold the rounded and polished surfaces of the pebbles together.

In certain deposits of gravel, particularly where the pebbly matter is to a greater or less extent composed of limestone, a considerable amount of iron oxide has been gathered in the mass. This effect is due to the tendency of water which contains iron to lay down that substance and to take lime in its place when the opportunity for so doing occurs. Such gravels are termed ferruginous. They are commonly found in a somewhat cemented state, and when broken up and placed upon roads they again cement, even more firmly than in the original state, often forming a roadway of very good quality.

The gravel found in western Kentucky and known in commerce as Paducah gravel is of this variety and is extensively used for road-making.

"The so-called Tomkins Cove gravel, which is much used about New York, is a broken limestone, apparently of the cement series. It is usually spread over the road, and compacted by the traffic. The darker-colored stone is very pleasant to the eye, and it readily makes a smooth wheelway singularly free from either mud or dust even when subjected to rather heavy traffic, though it is too friable for economical use in such situations. Its performance is so different from that of the ordinary limestones that an analysis is appended:

Lime.....	60.20	per cent
Alumina.....	11.22	"
Silica	6.18	"
Magnesia.....	10.45	"
Carbonic acid.....	8.00	"
Water.....	4.00	"
	<hr/>	
	100.00	per cent

132. Shingle is the gravel or accumulation of small stones found on the shores of rivers or the sea.

132a. Chert is a silicious material approaching the character of flint; it is composed of lime, silica, iron and alumina, its appearance varies from that of limestone to sand-stone; in color it ranges from pure white to milky blue, in texture from porous to flinty. The name chert is also frequently applied to the slag derived from blast furnaces.

TABLE XXIV.

SPECIFIC GRAVITY, WEIGHT, AND RESISTANCE TO CRUSHING OF VARIOUS SUBSTANCES.

Substance.	Specific Gravity.	Weight, pounds per cubic foot.	Resistance to Crushing, lbs. per sq. in.
Asphaltum.....	1.277	80 to 87.3
Basalt (greenstone).....	2.9	181	17,900
" Scotch.....	2.95	184	8,300
Bitumen, liquid.....	.848	53
Bituminous limestones.....	2.25	156
Brick, best pressed.....	2.4	150	14,973
" common hard.....	1.6 to 2	125	12,000
" soft inferior.....	1.4	100	609 to 8,000
" Stourbridge fire.....	2.2	137	1,717
" paving.....	9,000 to 18,000
" work in cement-mortar masonry.....	1.8	112.5
Chalk.....	2.5	156	501
Clay.....	1.8 to 2.1	119
" dry, in lumps loose.....	68
" with gravel.....	2.48	155
Cement, hydraulic American Rosendale.....	56.60
" English Portland.....	1.6 to 1.76	81 to 102
" French.....	76 to 85
" Roman.....	1.6	100
Concrete, ordinary.....	1.9	119
" cement (Portland).....	2.2	137
Earth, common loam, dry, loose.....	1.25 to 2	72 to 80
" common loam perfectly dry, shaken.....	58 " 58
Earth, common loam, perfectly dry, moderately rammed.....	90 " 100
Earth, common loam, slightly moist, loose.....	70 " 70
" " " more moist loose.....	66 " 68
" " " shaken.....	75 " 90
" " " mod. packed.....	90 " 100
" " " as a soft flowing mud.....	104 " 112
Earth, common loam as a soft flowing mud well pressed into a box.....	110 " 120
Flint.....	2.6	126
Feldspar.....	2.5 to 2.8	166
Glass.....	2.5 to 3.45	166	27,000-30,000
Gneiss.....	2.69	168
" in loose piles.....	96
" hornblende.....	2.8	175
" quarried in loose piles.....	100
Gun-powder, loose.....	.900	56.25
" shaken.....	1.000	62.5
Iron, cast.....	7.21	450	110,000
" wrought.....	7.69	485	45,000
Ice.....	.917 to .923	57.4
Lead.....	11.30 to 11.47	709.6	6,944-7,730
Lime, quick, of ordinary limestones.....	1.5	95
" quick, ground, loose.....	53
" well shaken.....	64
" thoroughly shaken.....	75
Masonry of granite or limestone dressed.....	165
" of rubble, $\frac{1}{2}$ of the mass being mortar.....	164
" of dry rubble.....	138
" of sandstone dressed.....	144
" of brickwork, close joints.....	140
" " " medium quality.....	125
" " " soft bricks.....	100
Mica.....	2.75 to 3.1	188
Mortar.....	1.88 to 1.9	106
Mud, dry, close.....	89 to 110
" wet, moderately pressed.....	1.63	110 " 130
" wet, fluid.....	104 " 130
Naphtha.....	.848	52.9

TABLE XXIV.—*Continued.*

SPECIFIC GRAVITY, WEIGHT, AND RESISTANCE TO CRUSHING OF VARIOUS SUBSTANCES.

Substance.	Specific Gravity.	Weight, pounds per cubic foot.	Resistance to Crushing, lbs. per sq. in.
Petroleum.....	.878	54.8
Peat, dry, unpressed.....		90 to 30
Pitch.....	1.15	69
Porphyry.....	2.66 to 2.8	170
Quartz, pure.....	2.65	165
" " " finely pulverized, loose.....		90
" " " shaken.....		105
" " " packed.....		112
" quarried, loose.....		94
Sand of pure quartz, dry and loose.....	2.75	90 to 106
" " " perfectly wet.....		118 " 129
" river.....	1.88	117
" pit, coarse.....	1.61	100
" " fine.....	1.52	95
" (Thames) England.....	1.64	102
Serpentines.....	2.5 to 2.6	162
Shales, red or black.....	2.6	163
" quarried in piles.....		92
Shingle.....	1.42	88
Slate.....	2.7 to 2.9	175	10,000-21,000
Soapstone or steatite.....	1.73	170
Steel.....	7.85	490	336,000
Snow, freshly fallen.....		5 to 12
" compacted.....		15 " 30
Water, pure rain, or distilled at 32° Fah., barom. 30 inches.....		62.417
Water, pure rain, or distilled at 62° Fah., barom. 30 inches.....	1.00	62.365
Water, pure rain, or distilled at 212° Fah., barom. 30 inches.....		59.7
Water, sea.....1.025 to 1.030	1.025	64.06

CHAPTER III.

STONE PAVEMENTS.

133. Stone Pavements.—Stone in a variety of forms has been employed as a paving material for more than 2500 years. The Romans used it in the form of large, irregularly-shaped blocks laid on a massive foundation of concrete. In this form it is unsurpassed in regard to solidity and durability, but it is objectionable for modern traffic. The surface of the large blocks wears smooth, and hence affords but an uncertain foothold for horses. These large blocks were superseded by round pebbles or cobblestones, obtained from the beach and gravel-pits. This class of pavement has been used extensively in the United States. It is recorded that Boston, Mass., in 1663 had many streets paved with pebbles. In 1718 cobblestone pavements were introduced into Philadelphia, and this city is the only one to retain them on a large scale at the present day.

134. Cobblestone Pavement.—Cobblestones bedded in sand possess the merit of cheapness and afford an excellent foothold for horses, but the roughness of such pavements requires the expenditure of a large amount of tractive energy to move a load over them. Aside from this, cobblestones are entirely wanting in the essential requisites of a good pavement. The stones being of irregular size, it is almost impossible to form a bond or hold them in place. Under the action of the traffic and frost the roadway soon becomes a mass of loose stones. Moreover, cobblestone pavements are difficult to keep clean, and very unpleasant to travel over.

135. Specifications for Cobblestone Pavement.—The following is the common form of specification for this class of pavement:

Stone.—The stones are to be the best selected water or bank paving-stones, of a durable and uniform quality.

TYPES OF STONE PAVEMENTS




FIG. 1. ROMAN.




FIG. 2. COBBLESTONE.




FIG. 3. BELGIAN BLOCK.




FIG. 4. EARLY GRANITE BLOCK.

Size of Stone.—No stone shall be less than four (4) inches nor more than eight (8) inches in any direction on the surface. No triangular or split stone will be allowed. All stones shall be set perpendicular and on their small ends, the large stones to be placed on the sides of the street, and the small ones in the center.

Foundation and Laying.—The pavement shall be laid on a bed of good sharp sand or fine gravel, at least ten (10) inches in depth, except where clay or a similar substance is met with, when the sand must be eighteen (18) inches deep. The bed of sand or gravel shall be laid ready for the pavement at least thirty (30) feet in advance of the pavement. The stones after being set in position must be rammed with a heavy rammer until they are firmly settled in their beds. After the pavement is rammed a layer of sand or gravel two (2) inches thick is spread over it and left to work its way in between the stones.

In consequence of the many defects of this class of paving its construction has been practically abandoned, but large areas still remain, which are being gradually removed.

136. Belgian Block Pavement.—Cobblestones were displaced by pavements formed of small cubical blocks of stone. This type of pavement was first laid in Brussels, thence imported to Paris, and from there to the United States, where it has been widely known as the "Belgian block" pavement. It has been largely used in New York City, Brooklyn, and neighboring towns, the material being trap-rock obtained from the Palisades on the Hudson River.

137. The stones being of regular shape remain in place better than the cobblestones, but the cubical form (usually five inches) is a mistake. The foothold is bad, the stones wear round, and the number of joints is so great that ruts and hollows are quickly formed. This pavement offers less resistance to traction than cobblestones, but it is rough and noisy.

138. Specification for Belgian Block Pavement.—The following is the common form of specifications for the Belgian block:

Stone.—The stones are to be obtained from the trap or other durable rocks.

Size of Stones.—Each block shall measure not less than five (5) inches nor more than seven (7) inches in length; nor less than five (5) inches nor more than six (6) inches in width; in depth not less than six (6) inches nor more than seven (7) inches; nor shall

the difference between the base and the top surface of any block exceed one inch in either direction.

139. The blocks are laid upon a foundation of sand six inches thick, in parallel courses, perpendicular to the axis of the street. When so laid the blocks are thoroughly rammed to the required grade and cross-section. No ramming should be done within twenty-five feet of the work that is being laid. After ramming the surface is covered with a coat of clean sand which is broomed into the joints.

140. Granite Block Pavement.—The Belgian block has been gradually displaced by the introduction of rectangular blocks of granite. Blocks of comparatively large dimensions were at first employed. They were from 6 to 8 inches in width on the surface, by from 10 to 20 inches in length, with a depth of 9 inches. They were merely placed in rows on the subsoil, perfunctorily rammed, the joints filled with sand, and the street thrown open to traffic. The unequal settlement of the blocks, the insufficiency of the foothold, and the difficulty of cleansing them led to the gradual development of the latest type of stone-block pavements, which consists of narrow rectangular blocks of granite, properly proportioned, laid on an unyielding and impervious foundation, with the joints between the blocks filled with an impermeable cement. This type is practically a return to the system of the Romans, but with blocks of lesser dimensions than they used.

141. Experience has proved beyond doubt that this latter type of pavement is the most enduring and economical for roadways subjected to heavy and constant traffic. Its advantages are many, while its defects are few.

142. Advantages.

- (1) Adaptability to all grades.
- (2) Suits all classes of traffic.
- (3) Exceedingly durable.
- (4) Foothold, fair.
- (5) Requires but little repair.
- (6) Yields but little dust or mud.
- (7) Facility for cleansing, fair.

143. Defects.—(1) Under certain conditions of the atmosphere its surface becomes greasy and slippery.

- (2) The incessant din and clatter occasioned by the movement

IMPROVED GRANITE-BLOCK PAVEMENT.




Fig. 5. CROSS SECTION.




Fig. 6. PLAN.




Fig. 7. LONGITUDINAL SECTION.

of traffic over it is an intolerable nuisance, and it is claimed by many physicians that the noise injuriously affects the nerves and health of persons who are obliged to live or do business in the vicinity of streets so paved.

(3) Horses constantly employed upon it soon suffer from the continual jarring produced in their legs and hoofs, and quickly wear out.

(4) The discomfort to persons riding over it is very great because of the continual jolting to which they are subjected.

(5) If stones of an unsuitable quality are used, i.e., those that polish, the surface quickly becomes slippery and exceedingly unsafe for travel.

144. Quality of the Stone.—The harder and more durable rocks like basalt and true granite are unsuitable; they have the fault of wearing smooth and more or less spherical when subjected to heavy traffic, and under certain conditions of the weather they become greasy and slippery.

145. The less durable rocks, such as syenite, the granites in which hornblende predominates, and the harder sandstones, are the most suitable; they do not polish and afford a good foothold for the horses. Where the harder and more durable rocks have been used, they have caused dissatisfaction, and have been removed before they had been down many years.

146. Size and Shape of the Blocks.—The proper size of the blocks for paving purposes has been a subject of much discussion, and a great variety of forms and dimensions are to be found in all cities.

For stability a certain proportion must exist between the depth, the length, and the breadth. The depth must be such that when the wheel of a loaded vehicle passes over one edge of its upper surface it will not tend to tip up. The resultant direction of the pressure of the load and adjoining blocks should always tend to depress the whole block vertically; where this does not happen the maintenance of a uniform surface is impossible. To fulfil this requirement it is not necessary to make the block more than seven (?) inches deep.

147. Width of the Blocks.—The maximum width of the blocks is controlled by the size of horses' hoofs. To afford good foothold to horses drawing heavy loads, it is necessary that the width of each block measured along the street shall be the least possible consistent with stability; if it is large, a horse drawing a heavy load attempt-

ing to find a joint slips back, and requires an exceptionally wide joint to pull him up. It is therefore desirable that the width of a block should not exceed three (3) inches, or that four taken at random and placed side by side will not measure more than fourteen (14) inches.

148. Length of the Blocks.—The length measured across the street must be sufficient to break joints properly, for two or more joints in a line lead to the formation of grooves. For this purpose the length of the block should be not less than nine (9) inches nor more than twelve (12) inches.

149. Form of the Blocks.—The blocks should be well squared and must not taper in any direction; sides and ends should be free from irregular projections. Blocks that taper from the surface downwards (wedge-shaped) should not be permitted in the work; but if any are allowed, they should be set with the widest side down.

150. Manner of Laying the Blocks.—The blocks should be laid in parallel courses, with their longest side at right angles to the axis of the street, and the longitudinal joints broken by a lap of at least two inches (see Fig. 6). The reason for this is to prevent the formation of longitudinal ruts, which would happen if the blocks were laid lengthwise. Laying the blocks obliquely and "herring-bone" fashion has been tried in several cities with the idea that the wear and formation of ruts would be reduced by having the vehicles cross the blocks diagonally. The method has failed to give satisfactory results; the wear was irregular and the foothold defective, the difficulty of construction was increased by reason of the labor required to form the triangular joints, and the method was wasteful of material.

151. The gutters should be formed by three or more courses of block, laid with their length parallel to the curb.

152. At junctions or intersections of streets the blocks should be laid diagonally from the centre, or "herring-bone" fashion, as shown in Fig. 7a. The reason for this is (1) to prevent the traffic crossing the intersection from following the longitudinal joints and thus forming depressions and ruts; (2) laid in this manner they afford more secure foothold for horses turning the corners. The ends of the diagonal blocks where they abut against the straight blocks must be cut to the required bevel. The method of paving junctions shown in Fig. 7b while extensively employed is erroneous for the above reasons.




FIG. 7A. INTERSECTION PAVED WITH GRANITE BLOCKS.




FIG. 7B.—INTERSECTION PAVED WITH GRANITE BLOCKS.

153. The blocks forming each course must be of the same depth, and no deviation greater than one quarter ($\frac{1}{4}$) of an inch should be permitted. The blocks should be assorted as they are delivered, and only those of corresponding depth and width should be used in the same course. The better method would be to accurately gauge the blocks at the quarry: the cost would be considerably less; it would also avoid the inconvenience to the public by the stopping of travel resulting from the rejection of defective material on the ground. This method would undoubtedly be preferable to the contractor, who would be saved the expense of handling unsatisfactory material, and it would also leave the inspectors free to pay more attention to the manner in which the work of paving is performed.

The accurate gauging of the blocks is a matter of much importance. If good work is to be executed, the blocks when laid must be in parallel and even courses; and if the blocks be not accurately gauged to one uniform size, the result will be a badly paved street with the courses running unevenly.

The cost of assorting the blocks into lots of uniform width, after delivery on the street, is far in excess of any additional price which would have to be paid for the accurate gauging at the quarry.

154. Foundation.—The foundation of the blocks must be solid and unyielding, a bed of hydraulic cement concrete is the most suitable, the thickness of which must be regulated according to the traffic; the thickness, however, should not be less than four (4) inches and need not be more than nine (9) inches. A thickness of six (6) inches will sustain a traffic of 600 tons per foot of width.

155. Cushion-coat.—Between the surface of the concrete and the base of the blocks there must be placed a cushion-coat formed of an incompressible but mobile material, the particles of which will readily adjust themselves to the irregularities of the base of the blocks and transfer the pressure of the traffic uniformly to the concrete below: A layer of dry, clean sand $\frac{3}{4}$ of an inch thick forms an excellent cushion-coat. Its particles must be of such fineness as will pass through a No. 8 screen; if coarse and containing pebbles, they will not adapt themselves to the irregularities of the base of the blocks, hence the blocks will be supported only at a few points and unequal settlement will take place when the pavement is subjected to the action of traffic. The sand must also be perfectly free from moisture, artificial heat must be used to dry it if necessary. This requirement is an absolute necessity. There should be no moisture below the blocks when laid, nor should water be allowed to penetrate below the blocks; if such happens, the effect of frost will be to upheave the pavement and crack the concrete.

Where the best is desired without regard to cost, a layer half an inch thick of asphaltic cement may be substituted for the sand with superior and very satisfactory results.

156. Laying the Blocks.—The blocks should be laid stone to stone, so that the joint may be of the least possible width; wide joints cause increased wear and noise and do not increase the foothold. The courses should be commenced on each side and worked toward the middle, and the last stone should fit tightly.

157. Ramming.—After the blocks have been set they should be well rammed down, and the stones which sink below the general level should be taken up and replaced with a deeper stone or brought to level by increasing the sand-bedding.

158. The practice of workmen is invariably to use the rammer so as to secure a fair surface. This is not the result intended to be secured, but to bring each block to an unyielding bearing. The result of such a surfacing process is to produce an unsightly and uneven roadway when the pressure of traffic is brought upon it. The rammer used should not weigh less than fifty pounds and have a diameter of not less than three inches.

159. Joint-filling.—All stone-block pavements depend for their water-proof qualities upon the character of the joint-filling. Joints filled with sand and gravel are of course pervious. A grout of lime or cement mortar does not make a permanently water-tight joint; it becomes disintegrated under the vibration of the traffic. An impervious joint can only be made by employing a filling made from bituminous or asphaltic material; this renders the pavement more impervious to moisture, makes it less noisy, and adds considerably to its strength.

160. Bituminous Cement for Joint-filling.—The bituminous materials employed are (1) the tar produced in the manufacture of gas, which, when redistilled, is called *distillate*, and is numbered 1, 2, 3, 4, etc., according to its density; this material under the name of *paving-pitch* is extensively used both alone and in combination with other bituminous substances; (2) combinations of gas- or coal-tar with refined asphaltum; (3) mixtures of refined asphaltum, creosote, and coal-tar.

The formula for the bituminous joint-filling used in New York City is:

Refined Trinidad asphaltum.....	20 parts
No. 4 coal-tar distillate.....	100 "
Residuum of petroleum.....	3 "

In Washington, D. C., coal-tar distillate No. 6 is used alone.

In Europe a bituminous cement much used is composed of coal-tar, asphaltum, gas-tar, and creosote oil, in the proportion of 100 pounds of asphaltum to 4 gallons of tar and 1 gallon of creosote. These proportions are varied somewhat, according to the quality of the asphaltum employed. The mixture is melted, and boiled from

one to two hours in a suitable boiler, then poured into the joints in a boiling state. This mixture is impervious to moisture, and possesses a degree of elasticity sufficient to prevent it from cracking.

161. The mode of applying the bituminous cement is as follows: After the blocks are rammed the joints are filled to a depth of about two inches with clean gravel heated to a temperature of about 250° F., then the hot cement is poured in until it forms a layer of about one inch on top of the gravel, then more gravel is filled in to a depth of about two inches, then cement is poured in until it appears on top of the gravel, then more gravel is added until it reaches to within half an inch of the top of the blocks; this remaining half inch is filled with the cement, and then fine gravel or sand is sprinkled over the joints.

In some cases the joints are first filled with the heated gravel, then the cement poured in until the sand beneath and the gravel between the blocks will absorb no more and the joints are filled flush with the top of the pavement. This method is open to objection, for if the gravel is not sufficiently hot the cement will be chilled, and will not flow to the bottom of the joint, but instead will form a thin layer near the surface, which, under the action of frost and the vibration of traffic, will be quickly cracked and broken up, the gravel will settle and the blocks will be jarred loose, and the surface of the pavement will become a series of ridges and hollows.

The quantity of cement required per square yard of pavement will vary according to the shape of the blocks, width of the joints, and depth of the sand-bed; with well-shaped blocks, close joints, and one half inch sand-bed the quantity will vary from 3½ to 5 gallons; with ill-shaped blocks, wide joints, and heavy sand-bed 10 to 12 gallons would not be an excessive amount to use to secure the result obtained by employing well-shaped blocks and close joints.

The cost of paving-pitch is variable; it ranges from six to ten cents per gallon.

A joint-filling known as "Murphy's Grout Filling" has been and is extensively used in the Central States. This filling is composed of Portland cement, iron-slag, and sand. It is said to be waterproof, durable, and cheap. It can be used with equal advantage for block, brick, cobblestone, and macadam pavements.

In manner of application it differs but little from that of the bituminous cement. It is mixed in a portable box, and when of a good flowing (but not liquid) consistency it is thrown upon the pavement with shovels and swept into the joints with steel brooms, and after forty-eight hours it is set and the pavement is ready for traffic.

162. Sandstone-block Pavements.—Block pavements formed of Medina and Berea sandstones are used in several of the Lake cities, While not as lasting as granite, the sandstone is very durable, is less noisy, and does not become polished or slippery under traffic, wears evenly, and is adapted to all classes of traffic.

163. The best examples of this kind of pavement are found in Buffalo, N. Y., where two classes are used. For first class the specifications call for a foundation of six inches of concrete with a three-inch cushion of sand. The blocks are of dressed stone, four inches wide, seven inches deep, and not less than eight inches long. The joints are filled with bituminous cement. For the second class the blocks are of irregular size laid on a foundation of ten to eighteen inches of sand, depending upon the character of the sub-soil, the joints are filled with sand."

164. The cost of first-class Medina in Buffalo is \$4 per square yard; Cleveland, \$3.50; Columbus, with a 10-inch broken-stone foundation, \$3.25. Second-class average \$1.75, and with asphalt filling cost 36 cents per yard more.

165. Limestone-block Pavements.—Limestone block was tried in Kansas City on a concrete foundation, but being set on edge it wore unevenly, and in a year or two was shivered and split by the frost. This is the universal experience of all cities using limestone blocks.

166. Pavements on Steep Grades.—Stone blocks may be employed on all practicable grades, but on grades exceeding 10% cobblestones afford a better foothold than blocks. The cobblestones should be of a uniform length, the length being at least twice the breadth, say stones 6 inches long and $2\frac{1}{2}$ to 3 inches in diameter. These should be set on a concrete foundation, laid stone to stone, and the interstices filled with cement grout or bituminous cement; or a bituminous concrete foundation may be employed and the interstices between the stones filled with

STONE PAVEMENTS ON GRADES.




FIG. 8. COBBLE ON CONCRETE.




FIG. 9. GRANITE BLOCKS—STEPPED.




FIG. 10. GRANITE BLOCKS—WIDE JOINTS.

asphaltic paving-cement. Should stone blocks be preferred, they must be laid, when the grade exceeds 5%, with a serrated surface by either of the methods shown in Figs. 9 and 10. The method shown in Fig. 9 consists in slightly tilting the blocks on their bed so as to form a series of ledges or steps, against which the horses' feet being planted, a secure foothold is obtained. The method shown in Fig. 10 consist in placing between the rows of stones a course of slate, or strips of creosoted wood, rather less than one inch in thickness and about an inch less in depth than the blocks; or the blocks may be spaced about one inch apart, and the joints filled with a grout composed of gravel and cement. The pebbles of the gravel should vary in size between one quarter and three quarters of an inch.

167. Durability of Granite Blocks.—The average life or durability of granite blocks under heavy traffic may be taken at fifteen years; but since the nature of the traffic, the state of cleanliness and other conditions must be taken into account when inquiring into the durability, it follows that in no two streets is the endurance or the cost the same, and the difference between the highest and the lowest period of endurance and amount of cost is very considerable. The practice followed almost uniformly in the English cities is to remove the worn blocks, re-dress them and relay them in other and secondary thoroughfares. Thus the duration or life of the blocks may be doubled or more than doubled. Indeed, with the exception of the portion worn off by the friction of the traffic, not a fragment of granite paving may be said to be lost. After passing its first years in a leading thoroughfare it goes into a secondary thoroughfare until completely worn down and rounded, and will even then command a price of from 30 to 60 cents per square yard. Not even a fragment that is knocked off the component stones when undergoing the operation of being dressed into shape is lost, as it is made available either for macadamizing or for concrete to form the foundation of other pavements. "In truth granite can only be said to be worn out when it has been broken up for macadamization and then crushed into powder by the vehicles."

168. Wear of Granite Blocks.—Stones from different quarries and even from the same quarry will show considerable variation in the amount worn away in a given time under exactly similar conditions. Therefore no statement of wear can be given which

will be applicable to all varieties of stones. On London bridge, which has a traffic of over 15,000 vehicles in 12 hours, the wear of granite blocks has been found to be at the rate of .222 inch per year, or the number of years required to wear away one inch is four and one half.

TABLE XXV.

WEAR AND DURATION OF ABERDEEN GRANITE PAVEMENTS IN THE CITY OF LONDON. BLOCKS 3 INCHES WIDE, 9 INCHES DEEP.

Aberdeen Granite Pavements.	Vertical Wear. Inches.	Duration. Years.
Vertical wear per 100 vehicles in 12 hours, per foot of width per year.....	$\frac{1}{4}$	1
Total vertical wear in principal streets.....	2	15
Total additional wear in minor streets.....	2	20
Total vertical wear when laid aside.....	4	35
Remaining depth when laid aside.....	5	
Depth of new blocks.....	9	

In Liverpool, under a traffic of 216,570 tons per yard of width per annum, the wear was not measurable.

169. Cost of Maintaining Granite-block Pavements.—As to the durability and cost of maintaining granite-block pavements in America no satisfactory statistics can be obtained.

The annual cost of maintenance in London varies from six to nineteen cents per square yard, depending upon the traffic. In Liverpool repairing costs four cents per annum, and cleaning and sprinkling fourteen cents. In London the cost of maintenance, including interest, etc., on first cost is from 25 to 69 cents per square yard per annum. In St. Louis, Mo., maintenance costs from $\frac{1}{2}$ to $2\frac{1}{2}$ cents per annum.

The average cost of maintaining granite-block pavements in the United States, irrespective of traffic tonnage, and exclusive of cleaning and sprinkling, appears to be about $1\frac{1}{2}$ cents per square yard per annum.

170. Method of Paying for Granite-block Pavements.—The present system of paying for granite-block paving is erroneous. The contractor buys his blocks at so much a thousand, and sells them at so much a square yard laid; thus it is his interest to have as few blocks to the square yard as possible and joints as large as he can. Or he may purchase them from the stone man at so much a square yard: in this case the stone man is interested in having as

few blocks as possible; as is also the contractor, for the fewer blocks to be laid to the yard the more yards of paving will the pavior lay in a day, thus increasing the profits of the contractor. In some cases the pavior is paid by the square yard of paving; then it becomes his interest to have as few blocks to handle as possible and as wide joints as he may, thus increasing the number of square yards of paving he can lay in a day, and thereby increasing his wages. No matter how looked at, all parties concerned in furnishing and laying the blocks are deeply interested in having as few blocks and as wide joints as possible to the square yard. As both of these are serious defects, the temptation to adopt them should be removed. The number of blocks to be laid per square yard should be clearly stated in the specifications; a sum should also be designated to be deducted from the estimate, by way of a penalty or forfeit, for every block less than that is used than the number called for. As the labor expended in ascertaining the number of blocks laid to each square yard would be very great, it would be better to specify, as is the custom in Liverpool, that four courses of block shall not measure more than fourteen (14) inches. Under this rule the number of blocks laid can be very quickly determined by measuring any four courses at random over the length of the street.

City Engineer Horace Andrews of Albany has introduced with considerable success a reform in the manner of paying for granite block pavements.

The following unusual clauses are taken from his specifications, under which a large area of granite-block pavement has been laid:

"It is expressly understood and agreed, by and between the parties hereto, that the sum paid per square yard for granite block pavement shall be ascertained and fixed as follows—namely: The number of granite blocks per square yard, upon which the bid of the proposer is based, shall be 24. The actual average number of blocks laid per square yard by the contractor on the whole street shall be determined as follows: The City Engineer shall, from time to time, during the progress of the work, measure the width of the blocks as laid (by measuring the aggregate width of 50 to 100 courses, from this deducing the average width), which he shall combine with the average length of block as laid (hereby fixed and determined as $12\frac{1}{4}$ inches), for the purpose of computing the number of blocks laid per square yard.

"For each block, or fractional part thereof, that the average number laid per square yard shall exceed 24 there shall be added to the contractor's bid per square yard an amount computed at the rate of $9\frac{1}{2}$ cents per block. For each block, or fractional part thereof, that the average number laid per square yard shall fall short of 24, there shall be deducted from the contractor's bid per square yard an amount computed at the rate of $9\frac{1}{2}$ cents per block.

"In order to lay 24 to the square yard, the width of five courses, including the joints between the stones, should not exceed 22 inches."

The number of blocks specified per square yard differed on the individual streets; otherwise there were few changes in the above clauses.

The results obtained by the use of these clauses in the specifications during the last two years are indicated in the following

TABLE
SHOWING OPERATION OF SPECIFICATIONS REGARDING JOINTS IN GRANITE
PAVEMENT IN 1890 AND 1891.

	Area in Square Yards.	Width of Five Courses as laid. Inches.	Number of Blocks laid per Square Yard.	Excess or Deficiency.	Contractor's Gain.	Contractor's Loss.
1	3,624	23.38	22.63	+ 0.13	\$43.40	
2	1,588	23.13	22.87	+ 0.87	55.56	
3	879	23.50	22.50	0.00		
4	11,202	23.28	22.73	+ 0.23	238.61	
5	3,918	22.99	23.01	- 1.99		\$740.09
6	15,218	23.86	22.17	- 0.33		471.75
7	1,641	24.57	21.53	- 0.98		150.98
8	2,363	21.69	24.39	+ 0.39	87.44	
9	2,146	22.06	23.96	- 0.02		4.29
10	2,679	24.18	21.88	- 0.62		158.08
11	5,120	24.91	21.23	- 1.27		614.38
12	2,846	23.31	22.70	- 1.30		350.01

NOTE.—The specified number of blocks per square yard varied on different streets. It can be easily found from columns 4 and 5.

From an inspection of this table it is evident that close paving can be secured. Mr. Andrews believes that it might be more beneficial if the amount of deduction for non-fulfilment were increased, to guard against the contingency of wide blocks being

obtainable at so low a rate as to make it profitable for a contractor to use them notwithstanding the deduction from his contract price per square yard.

171. Number of Granite Blocks per Square Yard.---Table XXVI shows the average number of granite blocks of different sizes

Width.	Length.	Average Number of Blocks per sq. yd. Exclusive of Joints.	Number of Square Yards 1 ton will cover at a depth of	
			7 inches.	9 inches.
8 inches	7 inches	62	2.50	2.00
8 "	9 "	48	"	"
8 "	10 "	40	"	"
8 "	12 "	36	"	"
3½ "	7 "	58	"	"
3½ "	9 "	41	"	"
3½ "	10 "	37	"	"
3½ "	12 "	30	"	"

per square yard, and the average number of square yards that one ton of granite will cover, but these quantities will vary with the specific gravity of the stone employed.

172. Cost of Construction.—The cost of granite-block pavements varies greatly; it is materially affected by the weight of the blocks when their transportation for any considerable distance has to be taken into account, by the character of the foundation and kind of joint-filling, and frequently by the condition of the labor market, demand, etc.

Tables XXVII, XXVIII, XXIX, and XXX show the extent and cost of granite-block, trap-block, sandstone-block, and cobblestone pavements in some of the principal cities of the United States in 1890.

TABLE XXVII.

EXTENT AND COST OF GRANITE-BLOCK PAVEMENTS IN SEVERAL OF THE
PRINCIPAL CITIES OF THE UNITED STATES IN 1890.

Cities.	Extent. Miles.	Cost of Construction per square yard.
New York, N. Y.....	140.00	\$2.50 to \$4.50 †
Boston, Mass.....	62.00	2.75 " 4.00 †
Brooklyn, N. Y.....	55.80	2.75
St. Louis, Mo.....	43.71	3.52
Atlanta, Ga.....	33.00	1.50
Cincinnati, Ohio.....	30.00	4.25
Washington, D. C.....	23.20	2.85 to 3.47 †
Chicago, Ill.....	20.43	3.13
Richmond, Va.....	16.58	2.48
Albany, N. Y.....	16.39	2.78 to 3.45 †
Newark, N. J.....	13.86	2.75
Lowell, Mass.....	10.00	1.80 to 2.25
Providence, R. I.....	9.20	2.50 " 4.00 †
Troy, N. Y.....	9.12	
Milwaukee, Wis.....	7.50	2.15 to 2.45
Worcester, Mass.....	7.00	2.25
Omaha, Neb.....	6.00	1.98
New Haven, Conn.....	4.25	2.50
Minneapolis, Minn.....	4.16	1.80 to 2.57
Cambridge, Mass.....	3.63	2.20
Trenton, N. J.....	3.50	3.00
Los Angeles, Cal.....	1.50	2.52
Wilmington, N. C.....	1.25	2.50
Nashville, Tenn.....	1.25	3.15
Waterbury, Conn.....	1.10	2.75 to 2.95
St. Paul, Minn.....	0.89	2.10
*Toronto, Can.....		3.00 to 3.85 †
*London (City), Eng.....	29.00 }	
" (Vestries), Eng.....	251.00 }	3.60 " 4.08 †
*Birmingham, Eng.....	26.00	2.88
*Liverpool, ".....		3.75

* Foreign cities for comparison.

† Concrete foundation. Where not noted the foundation is either sand or gravel.

TABLE XXVIII.

EXTENT AND COST OF BELGIAN BLOCK (TRAP) PAVEMENTS IN SOME OF THE
PRINCIPAL CITIES OF THE UNITED STATES IN 1890.

Cities.	Extent. Miles.	Cost of Construction per square yard.
New York, N. Y.....	199.07	\$2.50
Philadelphia, Pa.....	119.60	2.37
Brooklyn, N. Y.....	22.41	
Paterson, N. J.....	2.75	1.80 to \$2.14
Camden, N. J.....	2.03	2.00
Albany, N. Y.....	1.42	2.60
Kingston, N. Y.....	1.90	

TABLE XXIX.

EXTENT AND COST OF SANDSTONE-BLOCK PAVEMENTS IN SOME OF THE
PRINCIPAL CITIES OF THE UNITED STATES IN 1890.

Cities.	Extent. Miles.	Cost of Construction per square yard.
Buffalo, N. Y.....	188.00	\$2.00
Toledo, Ohio.....	17.48	1.34
Rochester, N. Y.....	16.50	2.25
Omaha, Neb.....	11.00	1.98
Erie, Pa.....	6.81	2.78
Elmira, N. Y.....	5.00	
Utica, N. Y.....	4.63	
Lockport, N. Y.....	4.00	
Syracuse, N. Y.....	3.40	1.80 to \$3.69 *
Columbus, Ohio.....		2.98 " 3.94 *

* Concrete foundation.

TABLE XXX.

EXTENT OF COBBLESTONE PAVEMENT IN THE UNITED STATES IN 1900.*

City.	Square Yards.	City.	Square Yards.
Baltimore, Md.	5,815,610	Memphis, Tenn.	56,073
New York, N. Y.	4,213,616	Troy, N. Y.	55,400
Philadelphia, Pa.	2,920,664	Springfield, Mass.	50,790
Cincinnati, O.	1,213,000	Columbus, O.	50,450
Pittsburg, Pa.	1,147,415	Chicago, Ill.	45,800
New Orleans, La.	712,513	Paterson, N. J.	42,240
Louisville, Ky.	457,207	Scranton, Pa.	32,860
San Francisco, Cal.	429,289	Utica, N. Y.	29,082
Albany, N. Y.	413,737	Rochester, N. Y.	27,780
Allegheny, Pa.	397,690	Detroit, Mich.	24,525
Newark, N. J.	297,513	Sacramento, Cal.	23,040
Reading, Pa.	262,494	Portland, Me.	22,355
Camden, N. J.	256,566	Dubuque, Ia.	19,941
Washington, D. C.	251,645	Holyoke, Mass.	18,000
New Bedford, Mass.	210,140	Newport, Ky.	18,000
Savannah, Ga.	178,291	Peoria, Ill.	16,670
Johnstown, Pa.	154,021	Wilkesbarre, Pa.	15,178
Saginaw, Mich.	108,541	Grand Rapids, Mich.	13,288
Wheeling, W. Va.	101,044	Boston, Mass.	12,471
Providence, R. I.	89,408	Fall River, Mass.	8,700
Erie, Pa.	86,371	Bay City, Mich.	6,444
Norfolk, Va.	85,000	Elizabeth, N. J.	5,280
Covington, Ky.	83,700	Manchester, N. H.	2,790
Charleston, S. C.	82,530	Trenton, N. J.	2,579

* Cost of construction ranges from \$0.65 to \$1.50 per square yard.

173. Heads of Specifications for Granite-block Pavement.(1) *Preparation of Roadbed.*(2) *Foundation.*

(3) *Quality of the Blocks.*—The paving-blocks shall be of syenite or granite from or other approved quarries. All the blocks shall be of the same quality as to hardness, color, and grain; no outcrop, soft, brittle, or laminated stone will be accepted. When stone is obtained from more than one quarry, that from each quarry shall be piled and laid in separate sections of the work. In no case shall the stones from different quarries be mixed.

(4) *Dressing.*—The blocks are to be split and dressed so as to present regular and true surfaces on all sides, with straight edges on top, bottom, and sides. All sides of the block must be free from depressions or projections, and all blocks whose faces vary more than one half inch from rectangular shape will be rejected.

(5) *Size of the Blocks.*—The blocks shall measure $3\frac{1}{4}$ inches wide, 7 inches deep, and may vary between 9 and 12 inches in length. In no case will any variation in the width be permitted. In some cases, as paving around man-hole heads, etc., blocks of lesser depth may be required, and will be used as directed by the engineer.

(6) *Inspection and Culling.*—The blocks will be inspected after they are brought on the line of the work, and all blocks which in quality and dimensions do not conform strictly to these specifications will be rejected, and must be immediately removed from the line of the work. The contractor must furnish such laborers as may be necessary to aid the inspector in the examination and the culling of the blocks; and in case the contractor neglect or refuse to furnish said laborers, such laborers as in the opinion of the _____ may be necessary will be employed by said _____, and the expense thus incurred by _____ will be deducted and paid out of any money then due or which may thereafter become due to said contractor under the contract to which these specifications refer.

(7) *Cushion-coat.*—On the concrete foundation a layer of clean sharp sand free from moisture will be evenly spread to a depth of one half inch. The sand if not dry must be made so by the application of artificial heat, in such apparatus as may be suitable for the purpose and approved of by the engineer.

(8) *Laying the Blocks.*—The blocks will be bedded in the sand, laid stone to stone in parallel courses at right angles to the axis of the street (except at intersecting streets, where they will be laid on the diagonal as shown on the plans). Each course shall consist of blocks of uniform width and depth. The blocks shall be so laid that the longitudinal joints shall be broken by a lap of at least two inches.

(9) *Jointing.*—After the blocks are so laid, the joints between them shall be filled to a depth of two inches with clean, dry gravel, then rammed to an unyielding bearing with a hand rammer weighing not less than fifty pounds. All blocks which sink below the general level must be removed and replaced with blocks of greater depth. After the blocks are rammed the paving cement will be poured into the joints, to a depth of two inches; the joints will then be filled flush with gravel and the cement poured in until the

joints are filled and will absorb no more. Dry sand will then be poured along the joints and spread over the entire pavement. The quantity of paving cement required per square yard of pavement will not be less than four gallons. This quantity must be brought upon the ground, and whatever may remain after the completion of the work will be the property of the city. Any wastage of paving cement by pouring over the surface instead of between the blocks must be covered with a sufficient quantity of fine dry gravel to absorb it. The amount so wasted will be estimated, and the quantity so estimated must be replaced by the contractor at his expense.

(10) *Composition of Paving Cement.*—The paving cement will be composed of the residuum obtained from the direct distillation of coal-tar and creosote oil, in the proportion of fifty gallons of oil to one ton of residuum; the two ingredients will be melted together in suitable iron boilers having a capacity of not less than one ton. It shall be poured into the joints while in a boiling state.

(11) *Quality of the Gravel.*—The gravel used for filling the joints shall be free from sand, clay, or other objectionable substances; it shall be of such size as will pass entirely through a sieve of three quarters of an inch mesh and be retained by a quarter-inch mesh.

(12) *Materials to be Kept Dry.*—The stone for the pavement, the sand for the bed, and the gravel for the joints shall each and severally be laid only when dry and free from moisture. After being laid the contractor shall protect them from the weather until the joints have been filled with the paving cement; should they become moist from any cause previous to filling the joints with the said cement, the contractor shall at his own expense remove that portion of the work so moistened and replace and complete the same with dry materials.

(13) *Laying Granite Blocks adjacent to Railway Tracks, etc.* Between, and one foot outside of railroad tracks, over vaults, around sewer-manhole frames, and in such other places as the engineer may designate, the contractor shall furnish and use for the pavement blocks of such lesser depths as the engineer may direct. The general dimensions of such blocks on the top surface shall be the same as for the main pavement.

(14) The number of blocks laid per square yard shall be thirty, so laid that ten courses measured lengthwise of the street shall measure not more than 35 inches. The actual average number of

granite blocks laid per square yard shall be ascertained by the city engineer; and for each block, or fractional part thereof, that the average number of blocks laid per square yard shall fall short of thirty there shall be deducted from the contractor's bid price an amount computed at cents for each block less than thirty.

- (15) Interpretation of specifications.
- (16) Omissions in specifications.
- (17) Engineer defined.
- (18) Contractor defined.
- (19) Notice to contractors, how served.
- (20) Preservation of engineer's marks, etc.
- (21) Dismissal of incompetent persons.
- (22) Quality of materials.
- (23) Samples.
- (24) Inspectors.
- (25) Defective work, responsibility for.
- (26) Measurements.
- (27) Partial payments.
- (28) Commencement of work.
- (29) Time of completion.
- (30) Forfeiture of contract.
- (31) Damages for non-completion.
- (32) Evidence of the payment of claims.
- (33) Protection of persons and property.
- (34) Bond for faithful performance of work.
- (35) Power to suspend work.
- (36) Right to construct sewers, etc.
- (37) Loss and damage.
- (38) Old materials, disposal of.
- (39) Cleaning up.
- (40) Personal attention of contractor.
- (41) Payment of workmen.
- (42) Prices.
- (43) Security retained for repairs.
- (44) Payment, when made. Final acceptance.

CHAPTER IV.

WOOD PAVEMENTS.

174. Wood Pavements.*—Pavements formed of wood have been extensively employed both in Europe and the United States, but with widely differing results in the two countries. The experience in the United States has been, with but few exceptions, unsatisfactory, while in Europe, especially in the city of London, wood pavements have proved very successful and are quite popular.

175. The success of wood pavements in Europe is due to the fact that more care is exercised in their construction and maintenance. There, a solid concrete foundation, well-seasoned wood, and water-proof cement filling for the joints are employed, with constant and careful attention to keep them in repair.

176. The unsatisfactory results obtained in the United States are attributable, first, to the methods of construction; second, to the employment of green wood; and third, to the lack of careful maintenance.

177. The advantages of wood pavement may be stated as follows:

- (1) It affords good foothold for horses.
- (2) It offers less resistance to traction than stone and slightly more than asphalt.
- (3) It suits all classes of traffic.
- (4) It may be used on grades up to five per cent.
- (5) It is moderately durable.
- (6) It yields no mud when laid upon an impervious foundation.
- (7) It yields but little dust.
- (8) It is moderate in first cost.
- (9) It is not disagreeably noisy.

178. The principal objections to wood pavement are:

- (1) It is difficult to cleanse.
- (2) Under certain conditions of the atmosphere it becomes greasy and very unsafe for horses.

* Wood as a paving material appears to have been first employed in Russia, where, according to the testimony of Baron de Bode, it has been, though rudely fashioned, used for some hundreds of years.

Wood pavement was first laid in New York during the year 1835-36, and in London, Eng., in 1839.

(3) It is not easy to open for the purpose of gaining access to underground pipes, and rather a large surface has to be removed for this purpose, and it has to be left a little time after being repaired before traffic is again allowed upon it.

(4) It is absorbent of moisture.

(5) It is claimed by many that wood pavements are unhealthy.

179. Objections to Wooden Pavements on Hygienic Grounds.—

Dr. O. W. Wight, Health Officer of Detroit, in a report to the City Council, says:

"On sanitary grounds, therefore, I must earnestly protest against the use of wooden-block pavements. Such blocks, laid endwise, not only absorb water which dissolves out the albuminoid matter that acts as a putrefactive leaven, but also absorbs an infusion of horse-manure and a great quantity of horse-urine dropped in the street. The lower end of the blocks, resting on boards, clay, or sand, soon becomes covered with an abundant fungoid growth, thoroughly saturated with albuminous extract and the excreta of animals in a liquid putrescible form. These wooden pavements undergo a decomposition in the warm season, and add to the unwholesomeness of the city. The street, in fact, might as well be covered a foot deep with rotting barnyard manure, so far as unwholesomeness is concerned. Moreover, the interstices between the blocks and the perforation of decay allow the foul liquids of the surface to flow through, supersaturating the earth beneath, and constantly adding to the putrefying mass."

M. Fonssagrives, Professor of Hygiene at Montpellier, France, objects to wooden pavements because they "consist of a porous substance capable of absorbing organic matter and by its own decomposition giving rise to noxious miasma, which, proceeding from so large a surface, cannot be regarded as insignificant. I am convinced that a city with a damp climate, paved entirely with wood, would become a city of marsh-fever."

Professor Brewer, of Yale College, says that "even in the free air and full sunlight, along with the putrescence a white fungous growth begins on the surface of the wood, which rapidly becomes slimy. This forms much more rapidly on the ends of the grain of the wood than on the radial or tangential sides. The fungous growth goes on, modified, of course, by the temperature and the degree of concentration, and it continues for an unknown period, or until the

decay has become complete. Heartwood and sapwood act essentially alike in this matter; the difference is one of degree rather than character."

The following comments are from the report of a Board appointed by the Legislature of New South Wales to inquire into the alleged deleterious effects of wood pavement upon the public health.

"The Board examined specimens of wood pavement as laid in the city of Sydney, taking up blocks at different points. In all cases the concrete bed underneath was moist; in three cases a large amount of slimy mud was found giving off an ammoniacal odor. In all these the joints and blocks appeared to be uninjured. The blocks were chemically examined to determine whether they had absorbed organic matter, with the result that some were found impregnated with filth to the very centre, while others were comparatively free from it.

"The Board comes to the conclusion that wood is a material which cannot safely be used for paving unless it can be rendered absolutely impermeable to moisture, and so laid that while the entrance of water between the blocks is rendered impossible, the separation of the fibres at the surface by the concussion of traffic is also effectually prevented. These conditions have nowhere, to the knowledge of your Board, been fulfilled.

"So far as the careful researches of your Board go, the porous, absorbent, and destructible nature of wood must, in its opinion, be declared to be irremediable by any process at present known; nor, were any such process discovered, would it be effectual unless it were supplemented by another which should prevent fraying of the fibres. Still less can the defects of wood be considered to be of less consequence than the defects of other kinds of material.

"In this city it may perhaps be considered that an amount of wood has not yet been laid sufficient to affect the public health whatever its condition within reasonable limits may be; and upon this ground your Board does not recommend that the present paving should be removed, but that the Board of Health should be empowered to examine it, and to report upon it, from time to time, with a view of ascertaining its behavior under longer exposure to weather and traffic than it has yet had, and that it should be no longer watered, but cleansed by sweeping at least twice a day (the sweeping to be done at right angles to the direction of the street, or

parallel to the courses, so that the latter may be cleared out by the broom), in order that destructive dampness and penetration of dissolved organic matter may be reduced as much as possible. But the presumption is, upon the evidence here adduced, that in this climate the results alluded to would ensue if the extent of surface were sufficiently enlarged or fouling and decay sufficiently extensive. Your Board therefore recommends that the paving of the streets of this city with wood should be discontinued, and desires to add that this recommendation is extended to apply not to the particular mode of construction here adopted alone, but to the material itself, and to every known method of construction."

180. Opinion of Col. Haywood, Engineer of the City of London.—

"It has been said that wood pavements at times smell offensively and may be unhealthy; but although some city streets have been paved with wood for thirty years, no complaints that I am aware of have been made to the commission on this head, and the inhabitants at all times have not only expressed great anxiety lest the wood should be replaced by other materials, but have subscribed toward the cost of its renewal. . . . I have at times noticed offensive emanations from it near cab-stands, but am unable to find further evidence of its unhealthiness. These remarks must be held to apply only to public streets open to the sun, air, and traffic; in confined places and under some conditions wood might be objectionable. I have seen it decaying in confined places without traffic."

181. Wood Pavements and Death-rate.—A comparison of the death rate in cities using wood pavements with that in cities where little or no wood is employed seems to show that wood pavements do not cause an increase in the death-rate.

Death-rate per 1000.	City.	Percentage of Wood Pavements.
17.48	Chicago	80
25.19	New York	0
23.81	Boston	0
19.74	Philadelphia	0
14.70	Detroit	91
16.90	Milwaukee	48
23.70	Nashville	0
19.87	Atlanta	0
9.17	Duluth	95




FIG. 12.—SECTION SHOWING JOINT FILLING.




FIG. 13. PLAN OF STREET PAVED WITH WOOD BLOCKS.

SHOWING ARRANGEMENT OF BLOCKS AT STREET JUNCTIONS. A B SHOWS THE LINE OF TRAVEL IN TURNING CORNERS.

182. Variety of Systems.—Since the introduction of wood for paving, upwards of forty patented systems of construction have been experimented with. The difference between these systems consisted in the shape of the blocks and the treatment of the wood with chemicals. The shape given to the block has been very varied; round, square, rectangular, oblique, hexagonal, octagonal, and many complicated forms and interlocking devices have been tried. But experience has demonstrated that with a solid foundation there is no reason for complicated shapes or interlocking contrivances; and wood pavements in their modern form consist of either rectangular or cylindrical blocks set with the fibre of the wood vertical, with the joints between the blocks as narrow as possible and filled with a water-proof cement.

The rectangular blocks are prepared by cutting with circular saws blocks of the required depth from planks 3 inches thick by 9 or 12 inches wide.

The cylindrical blocks are prepared by sawing from round logs pieces of the required length, usually 6 inches. These 6-inch pieces are passed through cylinders furnished with steel knives that remove the bark and sap-wood, and leave the blocks perfectly round and free from all unevenness. The blocks so prepared are known as




FIG. 13A. PAVEMENT OF ROUND BLOCKS.

“sapless” cedar blocks. Figs. 12 and 13 show the manner of constructing wood pavements as practised in Europe. Fig. 13a shows a typical pavement of round blocks as laid in the United States.

183. Number of Wood Blocks per Square Yard.—The number of rectangular blocks 9 inches long by 3 inches wide required per square yard is 44, and the area occupied by the joints will be equal to 108 square inches.

The number of round blocks 6 inches in diameter required per square yard is 30, and the area occupied by interspaces will be 278.28 square inches.

184. The essentials necessary to the successful construction of wood pavements may be summed up as follows:

- (1) An unyielding and impervious foundation (concrete).
- (2) Sound and seasoned wood, either in its natural state or treated with a preserving compound.
- (3) An impervious filling for the joints between the blocks.

185. **Foundations.**—As with all other paving materials so with wood, without an unyielding foundation it is impossible to preserve a smooth surface. The foundations most commonly employed in the United States are wanting in solidity; in the majority of cases the blocks are set in sand spread on the natural soil; in others they are set on one or two layers of plank laid on sand. The advantage claimed for the first method is cheapness; the advantages claimed for the second method are, first, that the flooring of planks distributes the weight or pressure applied to one block over a large surface, and, second, that the boards by their elastic action reduce the wear of the blocks. This latter claim is fallacious and inconsistent with the method of construction, for the sand bed on which the planks are laid is supposed to solidly support them, if it does so the planks cannot yield elastically under pressure.

186. **The Chief Cause of Failure** in pavements laid on a foundation of sand and planks is that, as soon as leakage, even to the slightest extent, commences and the surface-water finds its way downward between the blocks, there is nothing to prevent its reaching and saturating the substratum of sand; since the boards, although close-laid, have not water-tight joints, the water will pass through them with comparative freedom. The saturated substratum becomes mobile and subject to movement under variations of pressure. Consequently when a load passes over the surface, the boards, opposing an inconsiderable resistance to deflection, are pressed downwards by the load, and they recover their normal position when the load passes away. In this manner a pumping action is set up, and the sand and water, mixed with other loose matter at the bottom, is pumped up to the surface in the form of mud and slime. Thus the pavement becomes gradually undermined, and the undermining process is accelerated by the form of the pavement itself, which

presents a continuous diaphragm under which the exhausting process is extended as by a diaphragm-pump. The wetter the weather the greater is the action of undermining.

In addition to the general liability of leakage through the pavement, there is a special difficulty in keeping it water-tight at the curb, where it is comparatively overhung and unsupported, and where there is at the same time a constant supply of water for penetration so long as there is any water in the gutter.

A serious consequence of the flexibility of the pavement is the numerous breakages of the blocks by splitting, caused by the unequal strain and leverage of the load on blocks which are supported by a floor partly non-resisting and partly resisting.

187. Quality of Wood.—The question as to which of the various kinds of wood available is the most durable and economical has not been satisfactorily determined. Many varieties have been tried. In England preference is given to Baltic fir, yellow pine, and Swedish yellow deal. In the United States the variety most used (on account of its abundance and cheapness) is cedar; yellow pine, tamarack, and mesquite have also been used to a limited extent. Cypress and juniper are being largely used in some of the Southern States.

Hard woods, such as oak, etc., do not make the best pavements; such woods become slippery. The softer, close-grained woods, such as cedar, cypress, and pine, wear better and give good foothold.

The wood employed should be sound and seasoned, free from sap, shakes, and knots. Defective blocks laid in the pavement will quickly cause holes in the surface, and the adjoining blocks will suffer under wear and the whole surface will become bumpy.

188. Chemical Treatment of Wood.—The great enemy of all wood pavements is decay, induced by the action of the air and water. Wood is porous, absorbs moisture, and thus hastens its own destruction. Many processes have been invented to overcome this defect, such as:

(1) *Burnettizing*.—This process consists in impregnating the wood with a solution of 1 pound of chloride of zinc to 4 gallons of water. Timber treated by simple immersion requires to remain in the solution for about two days for each inch in thickness, and after removal requires to be left to dry for about 14 to 20 days.

The process is more expeditiously performed by forcing the

solution into the pores of the wood with a pressure of 150 pounds to the square inch.

The chief advantage of this process is that it renders the wood incombustible.

(2) *Kyanizing*.—In this process the timber is immersed in a saturated solution of corrosive sublimate (bichloride of mercury) in a wooden tank, put together so that no metal of any kind can come in contact with the solution.

One pound of corrosive sublimate to 10 gallons of water is used when a maximum strength is required, and 1 pound to 15 gallons of water when a minimum, according to the porosity of the timber; with the latter proportion, $1\frac{1}{2}$ pounds will be sufficient for 50 cubic feet of timber.

The time required to saturate the timber depends on its thickness. Twenty-four hours are usually allowed for each inch in thickness for boards and small timber; large timber requires from a fortnight to three weeks.

(3) *Creosoting*.—This process consists in impregnating the wood with the oil of tar called *creosote*, from which the ammonia has been expelled, the effect being to coagulate the albumen and thereby prevent its decomposition, also to fill the pores of the wood with a bituminous substance that excludes both air and moisture, and which is noxious to the lower forms of animal and vegetable life. In adopting this process all moisture should be dried out of the pores of the timber. The softer woods, while warm from the drying-house, may be immersed at once in an open tank containing hot creosote oil, when they will absorb about 8 or 9 pounds per cubic foot. For hard woods, and woods which are required to absorb more than 8 or 9 pounds of creosote per cubic foot, the timber should be placed in an iron cylinder with closed ends, and the creosote, which should be heated to a temperature of about 120° Fahr., forced in with a pressure of 170 pounds to the square inch. The heat must be kept up until the process is complete, to prevent the creosote from crystallizing in the pores of the wood. By this means the softer woods will easily absorb from 10 to 12 pounds of the oil per cubic foot.

The most effective method, however, is to exhaust the air from the cylinder after the timber is inserted, then to allow the oil to flow in, and when the cylinder is full to use a force-pump with a

pressure of 150 to 200 pounds per square inch, until the wood has absorbed the requisite quantity of oil, as indicated by a gauge which should be fitted to the reservoir-tank.

The oil is usually heated by coils of pipe placed in the reservoir, through which a current of steam is passed.

The quantity of creosote oil recommended to be forced into the wood is from 8 to 12 pounds per cubic foot.

Into oak and other hard woods it is difficult to force, even with the greatest pressure, more than 2 or 3 pounds of that oil.

The advantages of this process are, the chemical constituents of the oil preserve the fibres of the wood by coagulating the albumen of the sap; the fatty matters act mechanically by filling the pores and thus exclude water; while the carbolic acid contained in the oil is a powerful disinfectant.

The life of the wood is extended by any of the above processes by preserving it from decay, but such processes have little or no effect on the wear of the blocks under traffic.

The process of dipping the blocks in coal-tar or creosote oil is injurious; besides affording a cover for the use of defective or sappy wood it hastens decay, especially of green wood; it closes up the exterior of the cells of the wood so that moisture cannot escape, thus causing fermentation to take place in the interior of the block, which quickly destroys the strength of the fibres and reduces them to punk.

The best European practice of to-day favors untreated blocks.

Considering the fact that in the United States large quantities of seasoned timber for paving cannot be obtained, it seems advisable that some artificial process of seasoning be employed. The most desirable process from an economic and sanitary point of view is the process of impregnation with oil of creosote. The success of this process depends upon the elimination of all moisture from the wood before the oil can be injected.

The woods which are best adapted to this treatment are those which are most absorbent and therefore the easiest and quickest destroyed, as the gums and cottonwoods. Cypress, cedar, pine, and porous oak are absorbent and can be successfully treated.

The cost of creosoting is about from \$12 to \$18 per 1000 feet, board measure.

189. Dimensions of the Blocks.—As with the stone-block pave-

ments so with wood blocks, the gauge of a horse's hoof is the measure of the maximum width. After numerous experiments with widths varying from 3 inches to $4\frac{1}{2}$ inches, European engineers have decided upon the following dimensions: for rectangular blocks, width 3 inches, depth 6 inches, length 9 inches.

The advantage of the narrower width is that, besides affording a more ready foothold when the pavement is slippery, narrow blocks have more stability than wide ones of the same depth.

The length of a block should be suitably proportioned to the width; a length of 12 inches has been tried and found to be too much: the blocks were subject to splitting across. Nine inches appears to be the most suitable length.

For round blocks the diameter should not exceed 6 inches; the depth may be the same as for the rectangular blocks, 6 inches. There is no advantage gained by a greater depth, for few wood pavements under the most favorable conditions retain a sufficiently good surface after about six years' wear without extensive repairs, and it is therefore not advantageous to lay blocks of a greater depth than will provide for a duration of seven years. Six inches is sufficient for this.

190. Expansion of Blocks.—Wood blocks expand on exposure to moisture, and when laid end to end across the street the curb-tones are liable to be displaced, or the courses of blocks will be bent into reverse curves. To avoid this the joints of the courses near the curb may be left open, or the courses next the curb may be left out until expansion has ceased, the space being temporarily filled with sand. The rate of expansion is about 1 inch in 8 feet, but varies for different woods. The time required for the wood to become fully expanded varies from 12 to 18 months. By employing blocks impregnated with the oil of creosote this trouble will be avoided. Blocks so treated do not contract or expand to any appreciable extent.

The comparative expansion of creosoted and plain wood blocks after immersion in water for forty-eight hours in percentage on original dimensions was:

	Creosoted.	Plain.
On length of block.....	.099	.6
On width " "57	.83
On depth " "15	.31

These expansions would represent in a carriageway 30 feet wide $2\frac{1}{2}$ inches for plain blocks, and practically $\frac{3}{8}$ inch for creosoted blocks.

In London expansion is provided for by leaving a space of $1\frac{1}{2}$ inches between the blocks and the curb. This space is filled with clean, dry sand, and coated over with a film of Portland-cement mortar.

191. Width of Joints.—Experience has demonstrated that the wide joints once thought necessary for foothold are not required. The best European practice of to-day is to make the joints as near one-quarter of an inch as possible. Wide joints hasten the destruction of the wood by permitting fibres to spread under the traffic. With the hard-wood blocks from Australia the most satisfactory results are secured by laying them as closely together as possible.

192. Filling for Joints.—The best materials for filling the joints are bitumen for the lower two or three inches, and hydraulic cement-grout for the remainder of the depth. The cement-grout protects the pitch from the action of the sun and does not wear down very much below the surface of the wood.

193. Durability.—The life of wood pavements depends upon the quality of the wood used, the amount and weight of the traffic, the width of the carriageway, the locality (whether open or confined), the presence of street-railway tracks, and the frequency of openings. In London the life of plain or untreated blocks has varied from five to twelve years. In the United States the life has varied from three to seven years.

The life of creosoted blocks is about fifteen years.

Table XXXI (p. 136) shows the actual duration and cost of certain wood pavements in the city of London.

"The average life of the pavements, in the three streets with the largest traffic was about 9 years, that of the three streets with the least traffic about $11\frac{1}{2}$ years. Nearly all before they were removed had been relaid over their entire surface, and some new wood introduced from time to time in lieu of that found too defective to relay."

"It will be observed that the wood pavements last removed had a shorter life than the previous pavements. There is more than one reason for this, but it should be stated that nearly all would by

TABLE XXXI.

DURATION AND COST OF WOOD PAVEMENTS IN THE CITY OF LONDON. *

(Foundations are included, but no excavation.)

Situation.	Date when laid new.	Life.		First Cost per square yard.	Total Cost of Repairs per sq. yd. during life.	Average Cost per sq. yd. per annum.
		Yrs.	Ms.			
Cornhill.....	May 1855	10	2	\$2.92	\$4.17	\$0.70
	July 1865	6	8	2.76	2.35	0.73
Gracechurch St.....	Nov. 1853	11	7	3.04	4.11	0.61
	June 1865	6	0	2.76	1.66	0.73
Lombard Street.....	May 1851	9	4	2.28	1.44	0.39
	Sept. 1860	10	7	2.20	4.90	0.66
Lothbury Street.....	May 1854	12	3	3.00	6.87	0.80
	Sept. 1860	6	1	3.00	0.83	0.63
Mincing Lane.....	July 1841	19	1	3.44	3.20	0.35
	Aug. 1860	13	0	2.20	5.47	0.59
Bartholomew Lane....	May 1854	12	3	3.00	4.19	0.59
	Aug. 1866	5	5	3.00	0.95	0.78

* Report of Col. Haywood.

relay and the introduction of some new wood have endured a few years longer."

194. The wood pavements of Berlin have not proved as durable as those of London and Paris, and their use is practically abandoned. Those of Frankfort (Ger.) laid under the Kerr system are giving satisfaction, and are said to be in as good condition to-day as when laid five years ago. The traffic on them is said to be constant and heavy.

195. W. Weaver, Chief Engineer and Surveyor, Kensington, London, says wood pavement of 5-inch creosote blocks will last ten years.

196. In Chicago, Ill., in some streets wood pavements have lasted upward of ten years; in others they have become very rough and uneven in three or four years, while in the river-tunnels they have worn out in two years.

197. The wood pavements of Washington, D. C., were of green

hemlock, very badly constructed, and were destroyed by decay and dry-rot in about four years.

198. In St. Louis, Mo., the average life of the Nicholson pavements was six years.

199. In Detroit, Mich., the Board of Public Works consider that cedar-block pavements will last eight years before extensive repairs are necessary, but that it is better to make repairs earlier.

200. Mr. R. W. Roberts, City Surveyor of East Saginaw, Mich., in his report for 1889 says: "Eight to ten years is the estimated life of cedar-block pavement laid on sand and board foundation."

201. Duluth, Minn.—Experience shows that on grades between 4 and 13 per cent the best surface is formed of blocks not more than 6 inches in diameter, laid on concrete foundation, and joints filled with Portland-cement grout.

Tar composition is found to hasten rather than retard decay.

• On light grades and clay subsoil a broken-stone or "telford" foundation is considered to have an advantage over concrete for the reason that every portion of the subgrade is thoroughly compacted by the roller, the broken stone being forced down into the numerous soft spots. Openings for repairs to underground structures cannot be as completely restored to their original condition as can concrete, it being impracticable to thoroughly consolidate the broken stone without the use of a heavy roller.

The broken-stone or telford foundation consists of two layers of stone; the first 6 inches thick, composed of large stones thoroughly wedged together, all chinks filled with smaller stones, and the whole surface covered with a layer of wet gravel and compacted with a 20-ton steam-roller. The second layer is 2 inches thick, composed of broken stone not more than 2 inches in the greatest dimension. It is spread, covered with wet gravel, and rolled like the first course. On top of this is sprinkled a thin layer of sand, which is covered by a course of 1-inch plank, making a smooth and uniform surface on which to lay the blocks.

202. Wear.—The wear of wood pavements is generally considered to be as much due to the action of the horses' feet as to that of the wheels, and the action of the former is more destructive on steep grades; the wear is also increased by wide joints.

The wear of wood pavements by the abrading action of traffic is stated by various authorities as follows:

TABLE XXXII.
WEAR OF WOOD PAVEMENTS.

Wear per annum under a traffic tonnage, per yard of width.	Locality and Authority.
1200 vehicles, per 12 hours.... .81 inch	{ King William Street, London. { Col. Haywood.
1106 tons..... ½ "	{ Parliament Street, London. { G. H. Stayton, Engineer.
1860 "456 "	{ Fleet Street, London. { G. H. Stayton, Engineer.
279 "065 "	{ Sloane Street, London. { G. H. Stayton, Engineer.
94,000 " ½ "	{ Great Howard Street, Liverpool.
802,000 tons58 "	{ G. Dunscombe, Engineer.

The wear in the latter years of the life of the wood was found to be greater than in the first years. The wear between street-car rails is about one third more than the remainder of the roadway.

Experiments made to ascertain in which position the fibre of wood offered the greatest resistance to the wear of traffic gave the following results:

Vertical fibre.....	wore .125 of an inch
At angle of 75 degrees.....	" .147 " "
" " " 60 "	" .182 " "
" " " 45 "	" .250 " "
" " " 30 "	" .310 " "
" " " 15 "	" .375 " "
Horizontal.....	" .500 " "

203. St. Paul, Minn.—The cedar-block pavement laid in 1882, on a plank and sand foundation, shows after seven years' use a wear of 2 to 2½ inches under ordinary traffic; on recent investigation the blocks showed very little decay, but the one-inch foundation-plank showed considerable. Two-inch planks are now used.

204. St. Louis, Mo.—On Third Street, with a traffic of 2400 vehicles in 24 hours, 6-inch blocks of prepared cottonwood wore down 1½ inches in seven years.

205. The cost of construction of wood pavements ranges between \$1.00 and \$4.00, depending upon the quality of the wood and whether it be plain or creosoted, and upon the character of the foundation.

Table XXXIII shows the cost in various localities in the United States.

TABLE XXXIII.

EXTENT AND COST OF WOOD PAVEMENTS IN VARIOUS LOCALITIES IN THE UNITED STATES.

Cities.	Extent. Miles.	Cost of Construction per square yard.
Chicago, Ill.....	410.00	\$1.15
Detroit, Mich.....	116.19	1.82
St. Paul, Minn.....	35.97	\$1.20 to \$1.40
Milwaukee, Wis.....	80.00	1.05 " 1.25
Minneapolis, Minn.....	25.85	0.95 " 1.99
Omaha, Neb.....	25.00	1.80
Springfield, Ill.....	20.00	1.30
Grand Rapids, Mich.....	14.63	1.00
Toledo, Ohio.....	12.09	1.96
Washington, D. C.....	0.60	
St. Louis, Mo.....	0.19	3.56†
Elmira, N. Y.....		3.06
St. Joseph, Mo.....		1.53
East Saginaw, Mich.....	16.59	1.40†
		1.10‡
*Toronto, Can.....	109.57	1.80
		2.65¶
		1.40†
*London, Eng. (City).....	6.00	\$3.00 to \$4.80
" (Vestries).....	47.00	
*Birmingham, Eng.....	6.00	2.52
*Paris, France.....		4.60**

* Foreign cities for comparison.

† Treated blocks.

‡ Plank foundation.

§ Gravel foundation.

¶ Cedar on concrete.

¶ Tamarack on concrete.

** Includes about 30 cents for the municipal tax on the material used.

206. **Cost of Maintenance.**—With regard to the cost of maintenance in the United States but little information can be obtained. St. Louis, Mo., reports the cost of maintaining pine-block pavement as 5 cents per square yard per annum, burnettized cottonwood at 4½ to 6 cents. London, England, reports the cost of maintenance at

from 16 to 36 cents per square yard per annum, or including all renewals 44 cents per annum. In Paris the cost ranges from 46 to 54 cents.

The practice of the companies engaged in the construction of wood pavements in Europe is to guarantee to keep the pavement in repair free of charge for one or two years, and then for so many years after at so much per annum. About \$3.36 per square yard is generally the first cost of construction, and 24 cents the annual charge for maintenance.

Table XXXIV shows the annual cost of maintaining certain wood pavements in London.

TABLE XXXIV.

FIRST COST AND TENDERED COST PER ANNUM FOR MAINTAINING CERTAIN WOOD CARRIAGEWAY PAVEMENTS IN THE CITY OF LONDON.

Situation.	Date when laid.	Name of Contractor.	Years to be maintained by contractor.	First Cost per square yard.	Agreed Cost of Maintenance per square yard for the contract term.	Total Cost of Pavement during contract term per sq. yd.	Average Cost per sq. yd. per annum.
King William St.	Feb. 1873	{ Improved Wood. Pav. Co. }	16	\$4.32	{ 1 yr. free, 15 yrs. } at 36 cts. = \$5.40 }	\$9.72	\$0.61
Ludgate Hill.	Nov. 1873	Ditto	16	4.32	{ 1 yr. free, 15 yrs. } at 36 cts. = \$5.40 }	9.72	0.61
Portions of Great Tower St. and Seething Lane.	Sept. 1873	Ditto	16	3.84	{ 1 yr. free, 15 yrs. } at 30 cts. = \$4.50 }	8.34	0.52

207. Assuming the life to be 7 years, Mr. Stayton estimates the annual cost of wood paving in Chelsea, England, with a traffic of 500 to 750 tons per square yard of width per day, to be 42 cents per square yard, which includes the cost of original construction, repairing, renewals, and interest spread over 15 years. Cleansing and sanding are estimated to cost 10 cents per square yard in addition.

208. Description of Various Systems of Wood Paving.—Cedar-block Pavement, Detroit, Mich.—The cedar-block pavements used here are made of sound blocks, stripped of bark, cylindrical in

shape and not more than 9 inches nor less than 5 inches in diameter and 7 inches deep. These blocks rest on a bed of bank sand and gravel 6 inches deep, well compacted with a roller weighing 2400 pounds. After the blocks are set they are rammed to a solid bearing with a rammer weighing 80 pounds; the spaces between them are filled with screened gravel rammed in with steel bars. The surface of the finished pavement is finally covered with gravel and sand to a depth of $\frac{3}{4}$ of an inch.

209. Mesquite-block Paving in San Antonio, Tex.—The blocks are hexagonal in shape, the minimum diameter being 4 inches and the maximum 8 inches, with a depth of 5 inches. The blocks are sawed with a slight batter, making the top about $\frac{1}{4}$ of an inch smaller than the bottom.

The roadbed is excavated to the required depth and rolled with a steam-roller.

The foundation is 6 inches of cement concrete. A cushion-coat of sand 1 inch in depth is spread over the concrete and the blocks bedded thereon. The joints are sand-filled. The cost per square yard, including foundation, is about \$2.80.

210. Asphalt Wood Pavement.—This is one of the more recently adopted pavements in England. It consists of a concrete foundation, on which is placed a coating of asphalt mastic one-half inch thick; the blocks are creosoted and are placed on the asphalt with spaces of half an inch between rows, and the joints are broken by a lap of at least two inches. The lower portion of the spaces for 2 to 2½ inches up is filled with melted asphalt and the remainder with cement-grout and gravel. In London this costs \$4.00 per square yard.

211. Henson Pavement.—The Henson system, which has been largely used in London, is as follows: The blocks are bedded and jointed with ordinary roofing-felt, a strip of which, cut to a width equal to the depth of the blocks, is placed between every two courses. The joint is made as close as possible by driving up the blocks, as every eight or ten courses are laid, with heavy mallets, a plank being laid along the face of the work; a perfectly close and slightly elastic joint is thus formed. A continuous layer of felt is likewise laid over the concrete foundation to give a slightly elastic bed to the blocks. The surface of the pavement is dressed over with a hot bituminous compound, and covered with fine clean grit. The

blocks are laid in courses at right angles to the curb, any change in the latter being accommodated by shorter courses ending with wedge-shaped blocks. At street-intersections the courses are laid diagonally or meeting at right angles. Two or three courses are laid parallel with the curb to form the gutter.

212. Improved Wood-pavement Company.—The method employed by this company in constructing the wood pavements in Paris is as follows :

(1) *Foundation.*—This consists of a bed of Portland-cement beton 0.15 m. (6 inches) thick, with a top coat of cement mortar about 0.01 m. ($\frac{3}{8}$ inch) thick. The beton is thus proportioned: A mixture of about one third sand and two thirds gravel is put in a bottomless box containing half a cubic meter (0.65 cubic yard), and after the removal of the box 100 kilograms (220 pounds) of cement are emptied on the heap. This is in the proportion, by volume, of about one seventh as much cement as there is sand and gravel, since 1400 kilos is the mean weight of a cubic meter of good Portland cement heaped loosely.

The sand was dredged from the bed of the Seine, and the gravel taken from pits on the seashore. The cement was furnished by the manufactory of Demarle & Lonquety, of Boulogne-sur-Mer.

The paving-blocks have a uniform thickness and are not laid on the bed of beton until after it has set, in order to exactly preserve the curvature of the surface of the beton required for the convexity of the roadway. In the Avenue des Champs Élysées the convexity was 0.42 m. ($16\frac{1}{2}$ inches) in a width of 27 m. (87 feet 7 inches), which represents a mean transverse slope of a little more than 3 in 100. This convexity, though less than first proposed by the company, appears to be a little excessive, and it seems that for roads under satisfactory drainage conditions the convexity might be diminished: 0.42m. is only a mean convexity, for, on account of the small longitudinal slope of the avenue, the grade of the gutters is not parallel to the grade of the street, but presents a series of short slopes from the hydrants to the sewer-openings; consequently the convexity varies from 0.39 m. ($15\frac{1}{4}$ inches) at the hydrants to 0.45 m. ($17\frac{3}{4}$ inches) at the sewers.

To exactly regulate the surface of the beton a series of transverse profiles were defined by stakes levelled to the grade of the top of the bed. Along each profile a strip of stiff beton was laid. The

top of this beton was carefully levelled and smoothed and received a guide-rule, laid flat, whose thickness exactly corresponded with that of the beton coating. This series of rules thus formed a set of guides close together, between which it was easy with large straight-edges to level the beton to the required surface. The first levelling could never be more than approximate, the surface of the beton naturally remaining somewhat rough. The exact level required, as fixed by the tops of the rules, was secured by the top coat of cement mortar which filled the spaces between the pebbles and made an exact surface. This mortar was first composed of 200 kilos of cement to a cubic meter of sand (336 pounds to the cubic yard), but this proportion proving too small it was increased to 300 kilos. It was always mixed with a great excess of water, so as to penetrate the interstices of the gravel.

(2) *Paving*.—The covering is formed of small uniform blocks of red Northern fir, 0.15 m. (6 inches) high, 0.22 m. (8½ inches) long, and 0.08 m. (3¼ inches) wide. These are set close lengthwise, with joints, transverse to the street, of about 1 centimeter (⅜ inch). The blocks are sent, ready for use, from England, where they were cut from planks of the ordinary size, 0.08 m. thick by 0.22 m. wide. The third dimension, taken in the length of the plank, forms the height of the block, so that in position the fibres of the wood are placed upright. The blocks are superficially creosoted after being cut.

When the foundation has set, two or three days after being laid, the blocks are set by the pavers. Owing to the light weight of the blocks the work of paving is very rapid. Between crossings the blocks are set in rows perpendicular to the axis of the street, with their longitudinal joints staggered exactly half the length of a block. The methods used at crossings to avoid a continuous joint parallel to the traffic are analogous to those used in stone-paving. Special precautions are taken to insure exact spacing and regularity of the rows. Before commencing a new row, a strip of wood whose thickness is exactly that of the required joint is set edgewise in contact with the last row, and the paver has only to set the adjacent blocks in contact with it.

The blocks do not at first adhere to the foundation and are easily displaced after the removal of the strips; to maintain them in place, as soon as the strips are taken out a small quantity

of bitumen is poured into the joints. This liquid material fills the small spaces that may exist under the blocks and partially fills the joints, and in solidifying effectually seals the blocks.

The joints are then filled by a thin grouting of neat Portland cement, distributed by the aid of a broom. This is done at least twice to insure perfect filling and the essential impermeability.

The pavement cannot be opened for traffic until after the cement in the joints has completely set, for which a delay of four or five days is considered necessary. During this interval the last operation is performed, viz., spreading a thin layer of dry sharp sand over the surface. The company claims that this dressing, crushed under the action of the wheels, incrusts itself in the wood and lends resistance to the wearing surface. It seems more probable that this coating is simply to protect the fresh mortar from the direct action of the wheels, for it can be maintained but a very short time on a travelled road, and is soon transformed into a disagreeable greasy mud.

213. Heads of Specifications for Wood-block Pavement.

(1) *Preparation of Roadbed.*

(2) *Foundation.*

(3) *Cushion-coat.*—The cushion-coat shall consist of a layer of dry, clean, sharp sand evenly spread on the concrete to a depth of one-half inch.

NOTE.—Asphaltic paving-cement may also be used for the cushion-coat; or the blocks may be laid directly upon the concrete.

(4) *Quality of the Blocks.*—The blocks shall be of timber, sound and thoroughly well seasoned, free from all sap, shakes, large and loose knots or other defects.

NOTE.—If the blocks are to be creosoted, the number of pounds of creosote that should be absorbed in a cubic foot of the wood should be specified; this is generally about 10 lbs. of creosote to 1 cubic foot of wood.

(5) *Size of the Blocks.*—(Rectangular:) The blocks must not be less than 6 inches nor more than 12 inches in length by 3 inches in width and 6 inches in depth. (Round Blocks:) The blocks shall not be less than 4 inches nor more than 8 inches in diameter, with a uniform length of 6 inches. Each block to be of uniform cross-section from end to end, the ends to be sawn off at right angles to the axis. The diameter of the block preferred is 4 inches,

and 70 per cent of the whole number of blocks furnished must be of this size.

(6) *Inspection and Culling.*—The blocks will be inspected after they are brought on the line of the work, and all blocks which in quality and dimensions do not conform strictly to these specifications will be rejected and must be immediately removed from the line of the work. The contractor must furnish such laborers as may be necessary to aid the inspector in the examination and culling of the blocks; and in case the contractor neglect or refuse to furnish said laborers, such laborers as in the opinion of the _____ may be necessary will be employed by said _____, and the expense thus incurred by _____ will be deducted and paid out of any money then due or which may thereafter become due to said contractor under the contract to which these specifications refer.

(7) *Cushion-coat.*—On the concrete foundation a layer of clean sharp sand, free from moisture, will be evenly spread to a depth of one-half inch. The sand, if not dry, must be made so by the application of artificial heat in such apparatus as may be suitable for the purpose and approved of by the engineer.

(8) *Laying the Blocks.*—The blocks (rectangular) shall be set on the cushion-coat with the fibre vertical, in parallel courses, with the length of the blocks at right angles to the axis of the street; any change in the direction of the latter being accommodated by shorter courses ending in wedge-shaped blocks. No joints shall exceed $\frac{3}{8}$ of an inch in width. The blocks shall be so laid that all longitudinal joints will be broken by a lap of at least 2 inches. At street-intersections the courses are to be laid diagonally as shown in Fig. 13.

The gutters will be formed by three courses of blocks laid parallel to the curb; the course adjoining the curb will be left out until expansion has ceased. The space so left unpaved will be filled with sand.

(9) *Laying the Blocks (round blocks).*—The blocks will be laid on the cushion-coat, in parallel rows across the street and in close contact with each other. Split blocks shall be used adjoining the curbs, around sewer-manhole heads, and at such other places as the engineer may direct but no split blocks shall be laid in the main pavement.

(10) *Ramming*.—After the blocks are so laid they shall be rammed to a solid bearing with a hand rammer weighing not less than 50 pounds. All blocks which sink below the general level shall be taken out and sufficient sand poured in to bring them to the required level.

(11) *Jointing* (rectangular blocks).—The joints shall be carefully filled with a grout composed of two parts of fine, sharp, clean sand and one part of Portland cement of an approved brand.

(12) *Jointing* (round blocks).—The interstices between the blocks shall be filled for a depth of 2 inches from the bottom with clean, screened gravel, the pebbles of which shall not be less than $\frac{1}{4}$ inch nor more than $\frac{1}{2}$ inch in diameter, then hot paving-cement shall be poured in to a depth of 2 inches and sufficient gravel poured in to fill the joints flush with the top of the pavement, then more paving cement poured in until the joints are full and will absorb no more. After which a layer half an inch deep of dry, sharp sand will be spread uniformly over the surface of the pavement.

The quantity of paving-cement required per square yard will not be less than $3\frac{1}{2}$ gallons. This quantity must be brought upon the ground, and whatever may remain after the completion of the work will be the property of the city. Any wastage of paving-cement by pouring over the surface instead of between the blocks must be covered with a sufficient quantity of fine dry gravel to absorb it. The amount so wasted will be estimated, and the quantity so estimated must be replaced by the contractor at his own expense.

(13) *Composition of Paving-cement*.—The paving-cement will be composed of the residuum obtained from the direct distillation of coal-tar and creosote oil, in the proportion of 50 gallons of oil to 1 ton of residuum. The two ingredients will be melted together in suitable iron boilers having a capacity of not less than 1 ton. The cement shall be poured into the joints when in a boiling state.

(14) *Quality of the Gravel*.—The gravel used for filling the joints shall be free from sand, clay, or other objectionable substances.

(15) Interpretation of specifications.

(16) Omissions in specifications.

(17) Engineer defined.

- (18) Contractor defined.
- (19) Notice to contractors, how served.
- (20) Preservation of engineer's marks, etc.
- (21) Dismissal of incompetent persons.
- (22) Quality of materials.
- (23) Samples.
- (24) Inspectors.
- (25) Defective work.
- (26) Measurements.
- (27) Partial payments.
- (28) Commencement of work.
- (29) Time of completion.
- (30) Forfeiture of contract.
- (31) Damages for non-completion.
- (32) Evidence of the payment of claims.
- (33) Protection of persons and property.
- (34) Indemnification for patent claims.
- (35) Indemnity bond.
- (36) Bond for faithful performance of work.
- (37) Power to suspend work.
- (38) Right to construct sewers, etc.
- (39) Loss and damage.
- (40) Old materials, disposal of.
- (41) Cleaning up.
- (42) Personal attention of contractor.
- (43) Payment of workmen.
- (44) Prices.
- (45) Security retained for repairs.
- (46) Payment, when made. Final acceptance.

214. Maintenance of Wood Pavements by Contract.—The contractor will undertake the maintenance of the pavement for years (usually eighteen) from day of 189 . This maintenance will consist in preserving the surface and regularity of the profile, and in making all general or partial repairs necessary to keep the roadway in a perfect state, even if the dilapidations are the result of accidental causes, as fires, sinking of the subsoil, etc., excepting only defects caused by the digging of trenches.

The contractor will be required to make general repairs on all

portions of the road where there is: (1) A reduction of the curve diminishing the original pitch by at least one fourth. (2) Where the thickness of the paving-blocks has been worn away $\frac{1}{2}$ of an inch or more. (3) Depressions or partial defects of the road numerous enough to make it rough, the engineer being judge of the time when it shall be required for this reason.

The concrete foundation will generally be preserved by simply adding Portland-cement mortar on top if there is room for it; the removal of the foundation is not obligatory except in case of its bad condition.

Besides the general repairs the contractor must insure the constant good state of the pavement by partial repairs that may be necessary. He must immediately replace paving-blocks that are decayed, crushed, broken, or depressed by any cause whatever, also those which have become impregnated with urine or other offensive liquids and emit a bad odor.

He must repair holes whose depth reaches $\frac{1}{2}$ of an inch for a length of 3 feet in any direction.

At the junction-lines of the wooden pavement with the stone or asphalt pavement, paving-blocks will be replaced when they shall have been worn away $\frac{1}{8}$ of an inch.

In all partial repairs the new pavement must have the same level as the adjacent pavement; no projections will be permitted. If any of the defects enumerated in this article are not repaired within three days after notification, a charge of dollars per day will be deducted from the contract price for each day's delay.

Renewals of the pavement over trenches opened for any cause must be executed in the same time and under the same restrictions as above. The renewed portions will immediately pass into the maintenance of the contractor, who must preserve them in accordance with the foregoing conditions. No claims will be allowed for repairs required by sinking of the earth. The contractor will only be paid for the area of the trenches measured when filled up.

The old material and rubbish from repairs must be entirely removed from the street on completion of the work, in default of which the contractor will be subjected to a penalty of dollars per day for each deposit not removed.

At the expiration of the maintenance period the pavement must be delivered in perfect condition. Three months before the

expiration of the contract term the engineer will make a statement showing the condition of the pavement. The pavement shall not be received unless it satisfies the following requirements: (1) There must be no holes having a depth of $\frac{3}{8}$ of an inch in any square yard of the pavement. (2) The transverse contour of the surface must not at any point be reduced so that the rise is less than four fifths of its original value. (3) The thickness of the blocks must at no place be less than 2 inches. After the engineer's inspection and report the contractor will be allowed three months to place the work in the required condition.

The contract price fixed for the renewal of the pavement will be paid for the repairs over trenches, the demolition of the pavement being at the expense of the person or companies opening the trench. The contractor must, if necessary, relay the pavement with entirely new materials and can make no claim for damages to the work or its maintenance.

The price to be paid for maintaining the pavement in the above-described condition is _____ cents per square yard, and will be payable quarterly during the contract period. Ten percentum of the amount payable quarterly will be retained and shall not be due or payable until the expiration of the contract period.

The price to be paid per square yard for the renewal of the pavement over trenches is _____ dollars.

215. Specifications for Laying Cedar Pavement in Chicago.—

Before paving the street shall be graded to conform to stakes or profiles to be given by the engineer in charge, and thoroughly flooded, rammed, and rolled to give it a solid bed.

Paving.—1st. The pavement shall not be laid on any street until the material thereof shall have been made firm and unyielding, and the contractor shall assume all the responsibility therefor.

2d. A bed of clean lake-shore sand, not less than three (3) inches in depth, shall be smoothly and evenly spread over the surface of the street, and compactly rammed and rolled down.

3d. A foundation of two- (2-) inch sound common hemlock plank, to be laid lengthwise of the street, close together upon one- (1-) inch by eight- (8-) inch pine stringers under the ends and centres. Stringers to be firmly bedded in the sand.

4th. Upon said foundation live cedar blocks, free from bark and perfectly sound, not less than four (4) inches nor more than eight

(8) inches in diameter, and six (6) inches in length, shall be placed on end, close-laid, resting properly on their bases and well driven together. All blocks more than eight (8) inches in diameter shall be split and the corners cut sufficiently to make good joints with adjacent blocks.

No split blocks of less than three (3) inches in thickness will be allowed.

All knots or excrescences must be cut off to make the blocks practically uniform in diameter throughout their length.

No interstice between the blocks to be more than one and one-half ($1\frac{1}{2}$) inches nor less than three quarters ($\frac{3}{4}$) of an inch.

No square holes will be allowed, nor must two split sides come together.

The surface of the pavement must be true and uniform.

In case any loose or defective blocks shall be found in the pavement, they shall be removed and replaced by perfect blocks of proper size, and so much of the pavement as may be necessary to make the work perfect shall be taken up and relaid at the expense of the contractor.

The blocks will be carefully inspected after they are brought on the line of the work, and all blocks or other material which, in quality or dimensions, do not strictly conform with these specifications, or which may be otherwise defective, shall be rejected, and must be immediately removed from the line of the work by the contractor. The contractor will be required to furnish such laborers as may be necessary to aid the inspector in the examination and culling of the blocks and other material; and in case the contractor shall neglect or refuse so to do, such laborers as in the opinion of the Commissioner of Public Works may be necessary will be employed, and the expense incurred shall be deducted from any money then due or which thereafter may become due the contractor.

5th. The spaces between the blocks to be filled with clean, dry lake-shore gravel, of one fourth ($\frac{1}{4}$) to one (1) inch in size, the proportion of said gravel to be such as to completely fill the interstices, and shall be thoroughly rammed with proper tools and by competent and experienced help, and again filled with the same kind of gravel and again thoroughly rammed.

In the above-described ramming the filling in each interstice must be struck three full blows and driven down well. Two com-

petent rammers must be constantly employed after each paver. No teams will be allowed on the pavement before it is properly rammed. After ramming the pavement will be flooded with hot composition, not less than one and one half ($1\frac{1}{2}$) gallons per square yard being used. The tar will be distributed with a three- (3-) gallon kettle, the work to be done in sections as the Commissioner of Public Works, or his representative, may direct.

6th. After which clean, dry lake-shore gravel, about one fourth ($\frac{1}{4}$) inch in size, shall be spread over the street in such quantity that when swept all the interstices between the blocks will be thoroughly filled. When the gravel is put on the second and third time there must be enough space left between the portions rammed once and twice for the other portions to enable the inspector to see that every part of the street is thoroughly rammed.

7th. The whole surface will be swept over and covered with hot composition not less than one half ($\frac{1}{2}$) gallon per square yard, and immediately covered with dry roofing-gravel, or gravel screened from that used to fill the spaces between the blocks, said covering to be not less than one (1) inch thick. All gravel used here must be lake-shore gravel, entirely free from sand or pebbles, over one half ($\frac{1}{2}$) inch in size, and dried and heated enough to prevent the chilling of the composition. The gravelling and tarring must be completed each day to within fifteen (15) feet of the end of the paving, and the top dressing to within fifty (50) feet. If the gravel and pavement becomes wet before the tarring is completed, the same may be ordered taken by the Commissioner of Public Works.

The composition used will be furnished by the city in the ordinary portable tanks at some point within the city limits; the same to be transferred by the contractor from the receiving point to the work, and the empty tanks returned to the place of reception; the contractor to furnish the necessary fuel and labor to keep the composition at a temperature of not less than 300 degrees Fahrenheit, and be at all times responsible for the tanks and their contents while in his care. The Department reserves the right to increase or diminish the quantity of the composition used.

216. Extracts from the Specifications for Laying Cedar-block Pavements in Minneapolis.—*Street Railway.*—Upon such streets as the street-railway company has tracks, it shall be the duty of the street-railway company to lower its tracks to the grade of the pavement to be laid. The said street-railway company in lowering its

tracks shall deposit the material excavated on the outside of its tracks, and the contractor will be required to remove the same at the same price per cubic yard as for extra excavation. It is, however, expressly understood that when the street-railway company has double tracks the contractor will be required to excavate and pave the spaces between said double tracks in the same manner as the remainder of the roadway, and shall receive the same price per square yard for said paving as he shall receive per square yard for the remainder of the paving of said roadway.

Blocks.—The blocks must be of the best quality of cedar, live and perfectly sound, and when in place be free from projecting knots and bark. They must be of a uniform length of six (6) inches, and have a diameter of not less than four (4) inches nor more than (10) ten inches. No blocks exceeding ten (10) inches in diameter will be allowed in the work either whole or split, and it is hereby expressly understood that the contractor will not be allowed to deposit upon the line of the work any blocks having the diameter greater than ten (10) inches, or any blocks turned from a post of a greater diameter than ten (10) inches.

It is expressly understood that the contractor will be required to repair in a satisfactory manner any paving that may settle or become defective on account of improper workmanship or material, or on account of the laying or construction of water-mains, sewers, gas-pipes, or making sewer, water, or gas connections, or conduit-laying, or any excavations allowed to be made in the street by the city council, which may have been done previous to the laying of said pavements, without cost to the city of Minneapolis.

Flooring.—Upon the finished sub-grade must be laid a floor of sound white-pine plank, of the quality equal to the grade known as first common lumber, as the city engineer and the city council may determine. These plank must be laid lengthwise of the street with close joints, and be two (2) inches thick, from eight (8) to twelve (12) inches wide, and from fourteen (14) to sixteen (16) feet long. They must have a bearing at each end and in the centre upon a one- (1-) inch by eight- (8-) inch stringer firmly bedded in the sand. Planks not less than six (6) inches wide may, however, be used in order to form the crown of crossings.

Laying.—The blocks must be placed upon their ends in close contact with each other, on a clean floor. The joints between the

blocks must not exceed two inches in their longest direction. Blocks of less diameter than six inches must not be split, nor must a piece of less size than half the block be used. The corners of split blocks must be trimmed so as to make proper joints. Unnecessary splitting of blocks will not be allowed.

Joints to be Filled.—The joints or spaces between the blocks must be filled in the following manner: First, fill the joints by sweeping clean, screened gravel, the pebbles of which shall be of a size not exceeding one inch in their largest diameter, into them. After sweeping, the surface of the pavement must be clean and free from gravel, then the gravel must be thoroughly tamped. This process must be repeated a second time. Gravel of the same kind as before used must be spread over the surface to a depth of not less than one inch above the top of the blocks.

Gutters and Corners of Crossings must be made as follows: The outside plank shall be 3 inches thick, 16 inches high, and 20 feet long on 80-foot streets, and 3 inches by 16 inches by 16 feet on 60-foot streets, and held in place by not less than six posts of 3 by 6 by 30 inches, driven to a depth of three inches below the top and equidistant along the length of the plank. There shall be a plank 2 inches thick, 10 feet long, for 80-foot streets, and 2 inches by 8 feet on 60-foot streets, and of a width of 3 inches less than the depth of the gutter, placed against the curb to support the gutter-cover, which shall be made of two pieces of 3 by 12 inches by 10 feet on 80-foot streets, and of 3 by 12 inches by 8 feet on 60-foot streets, fastened together with four pieces, 2 by 19 inches, well nailed with six 30d. spikes to each piece. The top of the outside gutter-plank on the slope of the crossing shall be trimmed to conform to the top of the paving. In making proposals the contractor will state a price which shall include cost of excavating eight (8) inches below the top of the finished paving; also the furnishing and putting in place complete of all lumber required in the gutter crossings and covers. The contractor will state a price per cubic yard for extra excavation.

216a. Microbes in Wood Pavements.—Recent investigations made in Europe regarding the sanitary qualities of wood pavements are reported in "Le Lyon Medical" as follows:

In the superficial layers of a wood pavement, after it had been thoroughly swept and washed with water, there were found in one

case 50,000,000 and in another 79,360,000 microbes to the gram; at a depth of five centimeters in one case 51,000, at a depth of six centimeters in another case 423,600 to the gram. Only a few of the microbes found were liquefying organisms, and in no case did they seem noxious when introduced by inoculation into the circulation of guinea-pigs.

216b. Cedar-block Pavements.—INDIANAPOLIS, IND.—Washington red cedar *untreated*; rectangular blocks; sand foundation unsatisfactory; concrete foundation, 1-inch sand cushion coat; blocks laid close together. After five years shows considerable wear, while here and there rotted blocks are visible.

Red cedar *treated* with 3 pounds of creosote per cubic foot; rectangular blocks 4 inches wide and 5 inches with the grain of the wood; concrete foundation, 1-inch sand cushion; blocks laid at an angle of 45° with the axis of the street; no provision for expansion; blocks driven close together with a sledge; joints filled as far as possible with paving-pitch.

Extent of wood-block pavement in 1899, 209,094 square yards.

TORONTO, CAN.—In 1898, 41.1 per cent of all the pavements in the city was cedar block. Mr. Rust, City Engineer, explains the preference for this pavement as follows:

"A cedar-block pavement is cheap, easily laid and repaired, noiseless, and—dependent upon the extent of the traffic—will remain in good repair for from six to eight years, and at the end of that period it can be renewed at a cost of from 45 to 50 cents per square yard, making it the cheapest pavement that can be laid."

216c. Karri (Australian) Block Pavement.—NEW YORK, N. Y.—The experimental block of Karri or Australian redwood pavement laid in 1895 on Twentieth Street is not considered a success, on account of its excessive slipperiness in wet weather.

LONDON, ENG.—The Australian hard-wood blocks laid in 1896 or earlier are reported as either in "fair condition" or "showing signs of wear." "Outside the city proper hard-wood blocks laid in Tottenham Court Road in December, 1892, had worn very unevenly by June, 1899, besides which the noise caused by the traffic was very great, and the pavement was being extensively repaired." (Mr. J. D. Ross, Engineer to the City of London.)

216d. Creosoted Pine Blocks.—INDIANAPOLIS, IND.—*Material:* Long-leaf Southern pine treated with 10 pounds of creosote per cubic foot.

Size of blocks: 4 inches by 4 inches, and from 6 to 10 inches long.

Foundation: Concrete.

Cushion coat: 1 inch of sand.

Width of joints: Blocks laid close.

Joint-filling: Fine sand or paving-pitch.

Ramming: Blocks compacted by rolling.

Expansion-joint: 1 to 2 inches at curb (according to width of street), filled with sand and covered with paving-pitch.

Surface of blocks covered with $\frac{1}{2}$ inch of clean coarse sand or granite screenings.

Composition of paving-pitch: 10% of refined Trinidad asphalt and 90% of coal-tar distillate.

Cost of construction: \$2.10 to \$2.50, with guaranty for five to nine years.

GALVESTON, TEX.—*Material:* Yellow pine impregnated by the vacuum process with 12 pounds creosote per cubic foot.

Size of blocks: 5 inches wide, 5 inches deep, 10 inches long.

Foundation: The natural sandy soil, compacted by saturating with water and shaped to the required form.

Joint-filling: Sand.

Width of joints: Close.

Ramming: By hand-rammers.

Surface is flooded with coal-tar sufficiently fluid to permeate the joints, followed by a coating composed of asphaltic paving-cement or asphaltum and dead-oil, after which the surface is covered with a thin layer of sand.

216e. Cottonwood and Gum Blocks.—ST. LOUIS, MO.—Gum and cottonwood blocks impregnated with chloride of zinc; concrete foundation 6 inches thick; joints filled with bituminous paving-cement. Burnettized cottonwood used on Broadway developed decay in the third year.

216f. Redwood Block Pavement.—OAKLAND, CAL.—Rectangular blocks 4 inches by 6 inches by 6 inches cut from seasoned butt-cut redwood and boiled in asphalt; foundation 6 inches concrete,

surface of which is painted with hot asphalt; blocks laid close in rows at right angles to axis of street; joints filled with asphalt, and surface covered with a coat of asphalt $\frac{1}{8}$ inch thick. The asphalt coat is designed to be the wearing surface and to be renewed as often as necessary.

It is said that this pavement has given satisfaction during three years' service in San Francisco.

216g. Jetley's Patent.*—The wood blocks are compressed together by machinery in slabs 4 feet 6 inches long and 12 inches wide. These slabs are laid directly upon the compacted earth surface, and when the surface exposed to traffic becomes worn they can be turned over, presenting a new surface to the traffic.

The Jetley system is the most recent contribution to the numerous inventions for the improvement of wood pavements; it has been tried in London with, it is said, satisfactory results; but it seems strange, in view of past experiences, to hear any one advocating the laying of a pavement directly upon the earth.

216h. Creco-resinate Wood Paving-blocks—BOSTON, MASS., 1901.—The specifications for preparing the blocks and forming the pavement are as follows :

(1) All lumber is to be of long-leaf Georgia or Florida yellow pine, free from sap, loose or rotten knots or other defects which would be detrimental to the life of the wood. No second-growth timber is to be used. (2) Blocks, except as otherwise ordered, are to be not less than 4 inches deep, 4 inches wide, and 8 inches long, uniform in depth, width, and length, with grain vertical. (3) Blocks are to be treated as follows: The blocks are to be placed in an airtight cylinder, and when the doors are closed the dry heat is to be raised to 215 degrees Fahrenheit, without pressure, for one hour, for the purpose of getting rid of the moisture. Then the heat is to be increased, pressure is to be applied, and both are to be raised gradually, to avoid injury to the fibre, for two hours, until the heat has reached about 285 degrees and the pressure about 90 pounds, and both are to be held there for one hour. The heat is then to be shut off and the tanks are to be allowed to cool gradually for one hour. At the end of this time the heat is to be reduced to

* *Engineering News*, vol. xliii. p. 409.

250 degrees and the pressure to about 40 pounds. The pressure is then to be blown off and the heat still further reduced. Vacuum is then to be applied until about 26 inches is reached, and while under vacuum the creo-resinate mixture (creosote and rosin) is to be run into the cylinders at a temperature of 175 to 200 degrees, and hydraulic pressure is to be applied, reaching 200 pounds per square inch, and kept at this point until 21 to 22 pounds of mixture per cubic foot has been absorbed. The liquid is then to be run off and the wood is to be placed in another cylinder, and milk of lime at a temperature of about 150 degrees is to be run in, and hydraulic pressure of about 200 pounds is to be applied for from one-half to one hour. (4) The blocks are to be laid close on a cement concrete foundation six inches in depth, as hereinbefore provided, and at such an angle to the curb as directed by the superintendent on a 1-inch cushion of clean-screened sand, and are to be driven as tightly together as possible at every sixth row. (5) The joints are to be filled with dry-screened sand and the pavement rolled with a steam roller weighing not less than five tons, until the blocks present a firm, uniform and unyielding surface. The joints are then to be filled with paving pitch, creo-resinate mixture heated to 300 degrees Fahrenheit, or Portland cement grout, as required. (6) The surface of the paving when completed is to be covered with $\frac{1}{4}$ -inch deep dressing of clean-screened, sharp sand or crushed-stone screenings.



CHAPTER V.

ASPHALTUM AND COAL-TAR PAVEMENTS.

217. Asphalt was first employed for street-paving in Paris in 1838, but it was not employed to any great extent until 1854. In 1869 it was introduced into London, and since then has been extensively used throughout Europe.

The success which attended this pavement led to its introduction into America. The great cost of importing the materials from Europe made the pavement so expensive as to induce American inventors to seek to manufacture a material which should have similar qualities. The result was the introduction of many substitutes and imitations, the majority of which proved defective.

The great cost of the imported material and the failure of the substitutes directed attention to the deposits of natural bitumen on the island of Trinidad, which could be brought here very cheaply. Experiments were made which demonstrated the possibility of making a mastic with Trinidad bitumen as its cementing material, as strong, elastic, and durable as that imported from Europe; but it was only after some years that this process was introduced and made a commercial success.

218. The difference between the asphalt pavements of Europe and those of America is due to the character of the materials. The former are composed of limestone rock naturally impregnated with bitumen, while the latter are composed of an artificial mixture of bitumen, limestone, and sand. The limestone in the European pavements becomes hard, smooth, and slippery under traffic, and is thus objectionable for general use in frosty latitudes. The granular nature of the sand used in preparing the Trinidad asphaltum diminishes the tendency to wear smooth and materially lessens the slipping of horses.

219. Although many deposits of bituminous rock are found in the United States, they have been used only to a limited extent,

and the island of Trinidad continues to be the main source of supply for the United States. This is due entirely to its advantage in cost of transportation. The railroad freight rates from the place of the deposits practically shut out the bituminous rock of California and Kentucky from competition in the Eastern States, and a similar condition may be said to affect the sale of Trinidad asphaltum in the cities of Europe, since the bituminous limestones of Val de Travers and Seyssel, having the advantage in freights, control the markets.

220. The cost of preparing the different varieties of asphaltum for street pavement is nearly the same; and as all appear to be about equally durable, the exclusive use of any one of them is due merely to the advantage in freights.

TYPE-SECTIONS OF ASPHALT PAVEMENTS.




FIG. 14. HEAVY-TRAFFIC PAVEMENT.




FIG. 15. LIGHT-TRAFFIC PAVEMENT.




FIG. 15A. ASPHALT ON STONE BLOCKS.




FIG. 15B. ASPHALT ON MACADAM.

221. The Advantages of Asphalt may be summed up as follows:

- (1) Ease of traction.
- (2) It is comparatively noiseless under traffic.
- (3) It is impervious.
- (4) It is easily cleansed.
- (5) It produces neither mud nor dust.
- (6) It is pleasing to the eye.
- (7) It suits all classes of traffic.
- (8) There is neither vibration nor concussion in travelling over it.
- (9) It is expeditiously laid, thereby causing little inconvenience to traffic.
- (10) Openings to gain access to underground pipes are easily made.

(11) It is durable.

(12) It is easily repaired.

222. Defects of Asphalt Pavement.

- (1) It is slippery under certain conditions of the atmosphere.

The American asphalts are much less so than the European on account of their granular texture, derived from the sand. The difference is very noticeable: the European are as smooth as glass, while the American resemble fine sand-paper.

(2) It will not stand constant moisture, and will disintegrate if excessively sprinkled.

(3) Under extreme heat it is liable to become so soft that it will roll or creep under traffic and present a wavy surface, and under extreme cold there is a danger that the surface will crack and become friable. (In Washington, D. C., with a range of temperature from 5 to 150 degrees Fahr., no serious trouble has been experienced with the Trinidad asphalts.)

(4) It is not adapted to grades steeper than $2\frac{1}{2}$ per cent. In the city of New York there are streets paved with asphalt on which the grade varies from 2 to 6 per cent, and Mr. North, C.E., states that the traffic has deserted Ninety-third Street, which is paved with granite on a grade of 5.15 per cent, for Ninety-fourth Street, which is paved with asphalt on a 6 per cent grade. (See also Art. 261.)*

(5) Repairs must be quickly made, for the material has little coherence, and if, from irregular settlement of the foundation or local violence, a break occurs, the passing wheels rapidly shear off the sides of the hole, and it soon assumes formidable dimensions. In London this is prevented by constant watchfulness. Workmen are employed to traverse the street with a light repairing outfit, and whenever a defect is observed it is patched at once, and so effectually that the spot cannot be distinguished.

223. The strewing of sand upon asphalt renders it less slippery; but in addition to the interference of the traffic whilst this is being done, there are further objections, viz., the possible injury by the sand cutting into the asphalt, the expense of labor and materials, and the mud caused thereby which has afterwards to be removed.

224. Although pure asphaltum is absolutely impervious and insoluble in either fresh or salt water, yet asphalt pavements in the continued presence of water are quickly disintegrated. Ordinary rain or daily sprinkling does not injure them when they are allowed

* James Street, Syracuse, N. Y., is paved with asphalt on a 7.80 per cent grade.

to become perfectly dry again. The damage is most apparent in the gutters and adjacent to overflowing drinking-fountains. This defect has long been recognized, and various measures have been taken to overcome it, or at least to reduce it to the minimum. In some cities ordinances have been passed seeking to regulate the sprinkling of the streets, and in many places the gutters are laid with stone, while in others the asphalt is laid to the curb and a space of 12 to 15 inches along the curb is covered with a thin coating of asphalt cement. Vitrified brick has been used for the gutters of streets paved with sheet asphalt. Regarding the use of this material in Washington, D. C., the Report of the Engineers' Department for 1899 says:

"The use of brick gutters for sheet-asphalt pavements has been continued, and the experience of the office leads to the conclusion that this form of construction is decidedly better than laying asphalt to the curb. The first gutters of this material were laid with the brick toothed into the asphalt. This practice, however, was discontinued, and the gutters have been laid since with continuous joints. The latter construction has been found to be much better than the toothed method, as it has been demonstrated by several years' experience that it is impossible to sufficiently compact the asphalt between the teeth to prevent water entering, thus producing early decay or breaking up of the asphalt. With continuous joints it is possible to run the roller up to and along the very edge of the brick, producing as much compaction at this point as on other portions of the street. It has been observed in the cases of gutters of the two classes laid about the same time that in the toothed gutter the asphalt between the teeth and immediately adjacent thereto is, in a number of cases, already beginning to show signs of breaking up, while the asphalt adjacent to the continuous-joint gutter is apparently as good as ever."

It is said that the pavements formed of asphalt cement in which "maltha," or liquid asphalt, is used, instead of the residuum of petroleum, as the fluxing agent, are not affected by moisture.

Investigations* made to ascertain the action of water on asphalts

* By Messrs. G. C. Whipple and D. D. Jackson at Mt. Prospect Laboratory, Brooklyn, N. Y. Paper read before Brooklyn Engineers' Club, March 8, 1900.

show that some asphalts are acted upon to a considerable extent, while others are apparently unaffected; that the action varies with the character of the water. Distilled water and waters containing the smallest amounts of mineral matter produced the greatest action. Sea-water gave but little action, and a concentrated solution of brine showed no action.

The action of the water was exhibited by a change in color from black to brown, and in condition from hard to soft and punky, with the surface covered with cracks and pits.

The softening action penetrated to depths ranging from 00 to 1.3 millimeters with distilled water and 00 to 1.1 millimeters with surface and ground water.

The amount of soluble matter extracted from the asphalt corresponded with the intensity of the action of the water; distilled water showed the greatest action and took up the largest amount of soluble matter. The amount ranged from 2.83 to 21.42 per cent. The mineral constituents given up were sodium chloride, carbonates and sulphates of calcium and magnesium, and oxide of iron. Some of the samples yielded both mineral and organic soluble matter.

All the samples showed an increase in weight which varied with the condition of exposure.

The greatest increase was observed in the case of Trinidad asphalt. The sample exposed in Mt. Prospect reservoir gained 3.92 grams per square metre in one day; after two months it had gained 31.24 grams; in the conduit at Freeport the gain during two months was 84.41 grams; in Mt. Prospect stand-pipe, where the pressure was great, the gain was 137.09 grams, equivalent to 4028 per square yard of exposed surface. The gain in weight of the other samples was less, but corresponded in a general way with the amount of action observed.

"The cause of the action of water upon asphalt appears to be in part chemical and in part physical.

"The action of water upon asphalt is due to the unsaturated nature of the hydrocarbons present, and is attended by a partial solution of the asphalt in the water. There is also a loss of sulphur as hydrogen sulphide, and an increase in weight of the asphalt itself, due to oxidation and to the mechanical admixture of water. By

far the most important action which occurs is that produced by this oxidation of the asphalt by means of the dissolved oxygen in the water."

"The following asphalts and fluxes are arranged in the order of least to greatest action by water: Petroleum residuum; Assyrian asphalt; Asphaltina; Cuban asphalt; Alcatraz maltha No. 2; Alcatraz maltha No. 1; Alcatraz asphalt D; Alcatraz asphalt XX; Bermuda asphalt; Trinidad asphalt.




FIG. 15c.




FIG. 15D.—ASPHALT WITH BRICK GUTTER.

225. Asphalt laid adjoining centre-bearing street-car rails is quickly broken down and destroyed. This defect is not peculiar to asphalt. All other materials when placed in similar positions are quickly worn. Granite blocks laid along such tracks have been cut into at a rate of more than half an inch a year. The frequent entering and turning off of vehicles from car-tracks is one of the severest tests that can be applied to any paving material; moreover, the gauge of trucks and vehicles is frequently greater than that of

the rails, so one wheel runs on the rail and the other outside. The number of wheels thus travelling in one line must quickly wear a rut in any material adjoining the centre-bearing rail.

To obviate the destruction of asphalt in such situations it is usual to lay a strip of granite block or brick paving alongside the rail. This pavement should be of sufficient width to support the wheels of the widest gauge using the street.

The burning of leaves or making of fires on asphalt pavements should not be permitted, as it injures the asphalt, and the paving companies cannot be compelled to repair the damaged places without compensation.

226. Asphalt Pavement Injured by Illuminating-gas.—The asphalt pavements on some of the streets of Frankfort, Germany, became friable and porous. City Engineer Dehnhardt attributed this to the escape of illuminating-gas. This view was ridiculed by several German authorities on this material. The pavements were taken up, and it was found that the gas-pipes had several leaks under the worst parts of the street. Some of the injured pavement and pieces of sound pavement were tested. The sound fragments were placed in a tube through which gas was allowed to flow. After a week the samples were reduced to the same friable condition in which parts of the pavement had been found. The samples after several weeks' exposure to the atmosphere regained their original good condition. The explanation offered is that a portion of the carburetted hydrogen of the gas is absorbed by the asphalt, thus destroying its cohesion.

Regarding the destruction of asphalt pavements by illuminating-gas, Mr. A. W. Dow, Inspector of Asphalts and Cements, District of Columbia, in his report for 1898, says:

"As it has been doubted by some that this disintegration is really due to illuminating-gas, I have made a most thorough investigation of the subject, and believe have positively proven that gas is the cause. Samples of pavements were obtained from several affected spots, and in all cases I have been able to obtain from them a gas that exploded by passing an electric spark after mixing with air. The method employed to obtain the gas from samples of the surface mixture was by heating them under boiling water and collecting the gas given off in an inverted funnel. . . . Two sam-

ples of a pavement were taken, one from an affected spot, and the other from a good portion of the pavement about ten feet away. These samples were treated under boiling water until they ceased to evolve gas. The affected sample gave several times more gas than did the other. On testing, the gas from the good sample was found to consist of oxygen and nitrogen, which was evidently just the air from the voids in the pavement. The gas from the affected piece gave on analysis the results shown in column I of the following table." For comparison the composition of illuminating-gas is given in column II.

	I. Gas from Pavement. Per Cent.	II. Illuminating-gas. Per Cent.
Carbon dioxide.....	8.4	0.2
Oxygen.....	10.8	0.0
Heavy hydrocarbons.....	13.4	12.1
Carbon monoxide.....	0.7	25.5
Hydrogen.....	6.6	39.2
Methane.....	2.0	23.0
Nitrogen.....	58.1	0.0

The composition of the gas obtained from the disintegrating pavement does not correspond to that of a natural or marsh gas, sewer-gas, or air; hence the only gas it can be compared with is illuminating-gas, the analysis of which is given in column II of the preceding table.

"On comparing the composition of the gas given off from the disintegrating pavement with the illuminating-gas, it is seen that they are not at all similar in composition. At first glance it would not seem possible that the former gas could originate from the latter, but when the properties of asphalt are considered it is easily explained.

"Heavy hydrocarbons, to which class asphalts belong, are known to absorb other gaseous hydrocarbons: the heavier the gas the more affinity between it and the heavy hydrocarbons. Knowing this, the ingredients of the illuminating-gas that asphalt would have the greatest affinity for would be the heavy hydrocarbon gases, a slight affinity for the marsh-gas or methane, and no affinity for any of the other ingredients. If we examine the ingredients of the gas from the affected pavement, it will be found to consist of some carbon

dioxide, air that was in the voids and cracks of the pavement, and the constituents of illuminating-gas with the heavy hydrocarbon gases very much in excess, which is what we would expect. To practically demonstrate that the above takes place when asphalt is in contact with illuminating-gas, I took two samples of gas from a tap in the laboratory. One was analyzed, while the other was kept for several weeks in a tube the interior of which was coated with asphalt cement, such as is used in pavements, after which it was analyzed. The results of the two analyses are given in the following table:

	Original Gas. Per Cent.	Gas after Asphalt Absorption. Per Cent.
Carbon dioxide.....	0.2	0.1
Oxygen.....	0.0	0.0
Heavy hydrocarbons.....	12.1	7.2
Carbon monoxide.....	25.5	27.3
Hydrogen.....	39.2	42.2
Methane.....	23.0	23.2
Nitrogen.....	0.0	0.0

"It is evident from this that the asphalt cement has absorbed over 5 per cent of the heavy hydrocarbon gases, a little methane, and practically nothing else.

"I have ascertained by experiment that one part by volume of asphalt cement will absorb forty-two parts of illuminating-gas in somewhat over a month. I have also practically shown that asphalt is much softened by absorbing gas, the ordinary asphalt cement becoming as soft as a thick maltha after being in an atmosphere of illuminating-gas for several months. As to the quantity of gas contained in the affected pavements, this of course varies, but in one instance 1000 c.c. of pavement gave off 500 c.c. of gas."

There is but one remedy for the disintegration caused by gas and that is to stop the leak of gas.

227. Durability.—The systems adopted for the maintenance of asphalt pavements render it difficult to ascertain their actual life under traffic. They are repaired immediately they need it, and as each repair is so much new material laid, the whole surface is really relaid in the course of years. Col. Haywood states that in his opinion asphalt will last without extensive repairs from four

to six years, and that in the course of ten years the entire surface will have been renewed.

228. That asphalt successfully sustains an enormous traffic is shown by the following figures: From London, Cheapside has a traffic of 13,772 vehicles in 24 hours; Mansion House Street, 23,332 vehicles in 24 hours. Cornhill, Holborn Viaduct, and many others have a daily traffic of upwards of 12,000 vehicles. These streets are paved with asphalt.

229. There are no streets in America or elsewhere in the world that have so much traffic as the above-mentioned London streets. Among the vehicles that travel on them are omnibuses loaded with passengers inside and out, light vehicles of all descriptions, carts, carriages, and brewery trucks loaded with tons of ale and porter.

The first asphalt pavement was laid in the city of London in 1869, on Threadneedle Street, adjacent to the Bank of England, and was renewed at the end of 17 years. Asphalt has lasted on Holborn Viaduct 17 years, on London Wall 20 years, in Lothbury 23 years, and in Princess Street 22 years; in many of the minor streets it has lasted 30 years.

Cheapside was paved in 1870, and the pavement remained in constant use for 19 years, with of course extensive repairs; but up to 1889 the carriageway was never closed entirely for a general relaying of the pavement. In 1889, the contract for maintenance of the asphalt having expired, a new contract was made and a new surface of asphalt was laid.

Most of the main thoroughfares of the old city of London are paved with asphalt, under 17-year maintenance contracts.

230. St. Louis, Mo.—"The asphalt laid on Pine Street in 1883 is now in good condition after a test of eight years under a mixed traffic of 3000 vehicles in 12 hours from 7 A.M. to 7 P.M. The work was carefully executed, and consists of a 6-inch hydraulic-cement concrete base, $\frac{1}{2}$ -inch cushion-coat and 2-inch surface or wearing coat; cross-section camber 0.50; width between curbs 36 feet. Traffic is what may be termed building materials, residence supplies, and suburban. While it has been subjected to the heaviest loads hauled in the city with fair results, it must stand below granite for wear." (Report of Mr. T. H. Macklind, District Engineer.)

231. Wear.—Asphalt is to a certain extent elastic and does not begin to wear until this elasticity is overcome by thorough compression. This is the case with no other paving material. Stone and wood begin wearing from the day traffic commences. Under ordinary traffic it may be estimated that it will take two years to complete the compression of asphalt, and the weight of a square foot of this pavement will at the expiration of that time be nearly the same as on the day it was laid, though the thickness is reduced during the first two years as much as it will be in the following eight. The extent to which the thickness has been reduced is said to be as much as one fourth the original thickness.

A pavement in Paris which had lost more than one fourth of its thickness was found to have lost only 5% of its weight after 16 years' use.

The pavement in Cheapside, London, after fourteen years' use, shows a reduction, where not repaired, from its original thickness of $2\frac{1}{4}$ to $1\frac{3}{8}$ inches.

232. Cost of Construction.—The cost of construction varies with the locality, thickness of wearing surface, and kind of foundation.

Table XXXV shows the extent and cost in several cities in America.

In London the first cost is from \$3.75 to \$4.50 per square yard, including maintenance. The total annual expense varies from 33 to 57 cents per square yard.

In Omaha, Neb., the first cost per square yard, including maintenance for five years, is about \$2.98.

The prices per square yard given in Table XXXV for American cities includes in nearly all cases the maintenance of the pavement for a period of five years.

The extent of the asphalt pavement in use in 1890 was: United States, 6,803,054 square yards, equal to 446 miles of roadway 26 feet wide; Europe, 1,698,846, equal to 111.3 miles.

233. Cost of Maintenance.—Asphalt pavements are generally maintained by the companies that construct them. The systems adopted are as follows:

The company constructing the pavement undertake to maintain

TABLE XXXV.

EXTENT AND COST OF ASPHALT PAVEMENT IN THE PRINCIPAL CITIES OF THE UNITED STATES, 1898-99.

	Square Yards.	Cost of Con- struction per Sq. Yd.	Kind of Asphalt.	Guaranty Period. Years.
Akron, O.....	8,800			
Albany, N. Y.....	164,138	\$3.08	T *	5 and 7
Allegheny, Pa.....	555,559	{ 2.75 } 1.67	T, B, & S	
Altoona, Pa.....	105,842	2.58	T	
Atlanta, Ga.....	85,728	2.08	T	10
Auburn, N. Y.....	1,000			
Augusta, Ga.....	51,398	{ 2.63 } 2.58	T	
Baltimore, Md.....	538,135	{ 2.70 } 2.25	T & A	
Binghamton, N. Y.....	117,290	{ 2.69 } 1.69	T & A	5
Boston, Mass.....	210,388	3.00	T & S	5 and 10
Bridgeport, Conn.....	35,000	2.18		5
Buffalo, N. Y.....	3,900,631	{ 2.67 } 2.18	T, K, G, & S	5 and 10
Cambridge, Mass.....	16,424	3.00	T	
Camden, N. J.....	96,546	1.95	Block	
Charleston, S. C.....	17,130	2.56	T	5
Chattanooga, Tenn.....	78,890			
Chicago, Ill.....	1,835,000			
Cincinnati, O.....	406,700	{ 2.78 } 2.89	T, T', B & A	
Cleveland, O.....	130,240	{ 2.95 } 1.66	T	
Columbus, O.....	385,577	2.25	T, K, & U	5
Covington, Ky.....	74,567	3.09	T	
Dayton, O.....	849,106	{ 2.07 } 2.30	T	5
Denver, Colo.....	371,684	{ 2.62 } 2.30	T, T', & A	
Detroit, Mich.....	470,925	{ 2.48 } 1.90	T, A, B	5 and 10
Dubuque, Iowa.....	100			
Elmira, N. Y.....	17,596	{ 2.69 } 2.29	T	10
Erie, Pa.....	199,974	{ 2.45 } 1.80		
Evansville, Ind.....	46,933			
Fall River, Mass.....	2,142			
Fort Wayne, Ind.....	117,201	{ 1.60 } 1.40	T, A	10
Grand Rapids, Mich.....	89,566	{ 2.40 } 1.77	T, C, U	
Harrisburg, Pa.....	90,516	{ 2.65 } 2.35	T, Block	5

* For explanation of symbols, see p. 172.

TABLE XXXV.—Continued.

EXTENT AND COST OF ASPHALT PAVEMENT IN THE PRINCIPAL CITIES OF THE UNITED STATES, 1898-99.

	Square Yards.	Cost of Con- struction per Sq. Yd.	Kind of Asphalt.	Guaranty Period. Years.
Hartford, Conn	122,577	{ \$2.55 2.70 }	T, A	5
Hoboken, N. J.....	95,000	1.51	T, M, A	
Holyoke, Mass.....	19,866	2.75	Block	
Houston, Tex.....	19,910			
Indianapolis, Ind.....	826,725	{ 1.75 8.0 }	T, B	9
Jersey City, N. J.....	179,520	{ 2.73 1.65 }	T, T', C	
Joliet, Ill.....	9,695			
Kansas City, Kans.....	64,000			
Kansas City, Mo.....	1,129,427	{ 2.54 2.06 }	T, A R	10
Lancaster, Pa.....	21,728	2.50	2
Lincoln, Neb.....	5,884			
Los Angeles, Cal.....	142,850	1.80	C	
Louisville, Ky.....	175,340	2.00	T, K, G, IT	5 and 10
Lowell, Mass.....	18,442	2.65	Asphaltina	
Manchester, N. H.....	50,356			
Milwaukee, Wis.....	153,856	{ 2.30 2.12 }	T	5
Minneapolis, Minn.....	199,978	{ 2.49 2.18 }	T, U, C	10
Newark, N. J.....	593,683	{ 2.68 2.35 }		
New Bedford, Mass.....	1,088			
New Haven, Conn.....	75,018	{ 3.80 3.36 }	S	10
New Orleans, La.....	290,348	2.85	T, Block	
Newport, Ky.....	3,150		T	
New York, N. Y.....	3,990,448	{ 2.95 2.72 }		
Norfolk, Va.....	20,000	2.00	Block	
Oakland, Cal.....	1,500			
Omaha, Neb.....	680,836	{ 2.17 1.45 }	T, A	5
Paterson, N. J.....	26,400			
Pawtucket, R. I.....	2,576	3.15	S	
Peoria, Ill.....	160,233	{ 1.97 1.85 }	T, T'	5
Philadelphia, Pa.....	3,298,902	{ 2.30 2.05 }	T, B, A, S	
Pittsburg, Pa.....	1,570,061			
Portland, Oregon.....	106,928			
Providence, R. I.....	57,232	2.25	T	
Reading, Pa.....	100,299			
Richmond, Va.....	6,400			

TABLE XXXV.—Continued.

 EXTENT AND COST OF ASPHALT PAVEMENT IN THE PRINCIPAL CITIES OF
THE UNITED STATES, 1898-99.

	Square Yards.	Cost of Con- struction per Sq. Yd.	Kind of Asphalt.	Guaranty Period. Years.
Rochester, N. Y.....	579,480	{ \$2.77 } 2.33 }	T, S, G	
Rockford, Ill.....	26,268	1.65	T	
Sacramento, Cal.	6,872			
Saginaw, Mich.....	54,726	{ 2.89 } 1.54 }	T, A	
St. Joseph, Mo.....	148,064	2.15	T	
St. Louis, Mo.....	232,108	2.25	T, A, R	1 and 3
St. Paul, Minn.....	279,516	{ 2.46 } 2.08 }	T, B	10
Salem, Mass.....	3,042			
Salt Lake City, Utah.....	64,144	2.74	U, C	
San Francisco, Cal.....	3,000,000 ±	C, R	
Savannah, Ga.....	140,813			
Scranton, Pa.....	234,756	{ 2.47 } 2.26 }	T	
Sioux City, Iowa.....	68,570	2.38	T	
South Bend, Ind.....	47,245			
Spokane, Wash.....	33,975			
Springfield, Mass.....	4,976	{ 2.50 } 3.07 }	T, E, R	10
Springfield, Mo.....	3,200			
Syracuse, N. Y.....	430,944	{ 2.00 } 2.20 }	5 and 10
Tacoma, Wash.....	58,000	2.00	C	
Terre Haute, Ind.....	66,000	{ 2.14 } 1.95 }	T	5
Toledo, O.....	316,204	{ 2.50 } 1.97 }	T, T'	5
Topeka, Kans.....	194,000	T	
Trenton, N. J.....	46,659			
Troy, N. Y.....	105,600	2.50	T, S	
Utica, N. Y.....	503,236	2.26	T, B, A	
Washington, D. C.....	3,027,788	{ 2.19 } 1.78 }	T, B	
Waterbury, Conn.....	2,600			
Wilkesbarre, Pa.....	206,114			
Williamsport, Pa.....	44,464			
Wilmington, Del.....	844	Block Asphaltina	5
Worcester, Mass.....	9,124	2.50		
Yonkers, N. Y.....	129,182	2.89	T	
Youngstown, O.....	60,336	2.48	T	

TABLE XXXV.—*Continued.*

EXTENT AND COST OF ASPHALT PAVEMENTS IN SOME FOREIGN CITIES.

	Square Yards.	Cost of Con- struction per Sq. Yd.	Kind of Asphalt.	Guaranty Period. Years.
Ottawa, Canada.....	60,000	{ 8.60 8.10 }	S	10
Toronto, "	400,000	{ 2.20 1.80 }	T	
Berlin, Germany.....	1,000,000	{ 8.50 4.50 }	E R	
London, England.....	500,000	{ 8.75 4.00 }	E R	
Paris, France.....	2,000,000		E R	

T = Trinidad Lake.

M = Mexican.

T' = " Land.

A R = American Rock.

A = Alcatraz.

I T = Indian Territory.

B = Bermudez.

U = Utah.

C = California.

S = Sicilian.

G = German.

E R = European Rock.

K = Kentucky.

it in good condition for a fixed number of years. In America the cost of maintenance is included in the price paid for the construction, and the period varies from five to fifteen years.

In Europe a fixed price is paid for construction, and the company maintain the surface free for two years, after which period they are paid a certain amount annually per square yard, depending upon the amount of the traffic over the pavement, for maintaining it in good condition (usually fifteen years); in case of any disturbance of the pavement by a corporation or by a private citizen, the company replaces the pavement at the expense of such corporation or citizen, and is responsible for the maintenance thereafter.

A force of men is kept constantly at work making repairs, and any defect, however slight, is repaired immediately.

It is not considered that the necessity for continual repairs is an evidence of poor workmanship in the original construction or of defective materials used, but rather that an earnest endeavor is being made to keep the pavement, even under heavy traffic, at all times in perfect order. This prompt and constant repairing explains the superior condition of the pavements in the cities of Europe.

234. In Table XXXVa is given the cost of maintaining asphalt pavements per square yard per annum in several American cities and London, Paris, and Berlin.

TABLE XXXV*a*.
COST OF MAINTAINING ASPHALT PAVEMENTS.

Locality.	Cost per Square Yard per Annum.	Remarks.
St. Louis, Mo.	Cents. $4\frac{1}{2}$ to 9	10-year contract.
Buffalo, N. Y.: Residence streets.047	With railroad tracks.
" "048	Without " "
Business "148	With " "
" "113	Without " "
Resurfacing.....	\$1.05	1898.
Skimming.....	.64	
Painting gutters.....	.02	Per lineal foot.
Cleaning and pouring cracks	.01	" " "
Omaha, Neb.08	10-year contract.
Baltimore, Md.	1897.
Highest.....	.7620	
Lowest.....	.0017	
Average.....	.1297	
Washington, D. C.	$1\frac{1}{2}$ to 2	
Cincinnati.....	.075	By contract for the second 5 years, the first 5 years being 0.
London: Val de Travers.....	.24	Average of 15 years.
Limner.....	.19	" " "
Société Française.....	.22	" " "
Paris.....	.40	Including renewal of $\frac{1}{4}$ part of the surface every year.
Berlin.....	\$1.50	For 20 years by contract.

238. Mr. Elliot C. Clarke gives the following as the cost per square yard per annum of Val de Travers compressed asphalt under an annual traffic tonnage of 100,000 tons per yard of width:

Interest on original cost.....	19.4 cents
Maintenance per square yard.....	7.2 "
Scavenging per square yard.....	0.8 "

Total..... 27.4 cents

Nothing is charged for renewal, as the annual sum for maintenance provides for the asphalt in perpetuity.

239. *The items composing the cost of an asphalt pavement are:*

	Cost per sq. yd.
Removal of old pavement and grading.....	\$0.10
6" concrete foundation (1 : 2 : 5).....	.48
400 lbs. asphalt cement.....	\$8.00
200 lbs. stone-dust.....	20
1 cubic yard sand.....	1.25
	<u>\$9.45</u>
This will lay 13 yards =73
Labor mixing.....	04
Hauling....	10
Labor laying.....	06
Superintendence.....	025—
	<u>.325</u>
	<u>\$1.535</u>

To which are to be added profits, risks, etc.

240. **Foundation.**—A solid unyielding foundation is indispensable with all asphaltic pavements, because asphalt of itself has no power of offering resistance to traffic; consequently, if the foundation is not thoroughly solid and unyielding the weight of the traffic will crush it, and the asphalt will give way in all directions and go to pieces. Two classes of foundation are used: (1) Hydraulic-cement concrete; (2) Bituminous concrete.

Recently, with the object of reducing the cost of construction, the asphaltic paving composition has been laid upon the surface of old macadam, cobble, and stone-block pavements, and the results seem to be equally as satisfactory as with the concrete foundations.

Old brick pavements have been used at Youngstown, Ohio, as a foundation for asphalt. The brick pavement is thoroughly

swept and washed clean, and, after it is dry, it is heated with surface heaters, which destroys all combustible matter and completely dries the brick. While they are still warm the surface of the bricks is painted with a thin coat of asphalt applied with brushes; If the holes and depressions are deep, they are filled with broken stone mixed with asphaltic cement; and if shallow, they are filled with the same material as the surface coat and thoroughly tamped. On this the surface coat is placed in the usual manner.

241. Each class of concrete has its advantages and disadvantages: with cement concrete, the bond between the foundation and the wearing surface is not very great, hence it is very easy to strip off the surface in case repairs are necessary; but, on the other hand, the surface sometimes slips on the foundation, and under traffic rolls into waves and irregular surfaces, and sometimes cracks with sudden and great changes of temperature. A cement concrete foundation must be set and thoroughly dry before the asphalt is laid; the best asphalt laid in the most skilful manner on first-class but damp concrete will rapidly go to pieces. When the hot asphalt is applied to a damp surface the water is immediately sucked up and turned into steam, which tries to escape through the heated material; the result is that coherence is prevented, and, although the surface of the asphalt is smooth, the mass is really disintegrated from underneath by its bitter enemy, "water." As soon as the pavement is subjected to the action of traffic, the fissures formed by the steam appear on the surface, and the whole pavement quickly falls to pieces. For the same reason asphalt should be laid only in dry weather.

242. With bituminous concrete the foundation and wearing surface are united into one mass and cannot be easily separated. Repairs are difficult, but waving and cracking are less frequent, and the bituminous concrete is less expensive.

243. **Asphalt Cement Pavements** are composed of two essential parts, the matrix and the aggregate, and the success or failure of the pavement will depend upon the care exercised in selecting the materials and the skill displayed in combining them and laying the pavement.

244. The matrix consists of cement prepared from some selected asphaltum in the manner described in Art. 96. Its propor-

tion varies from 10 to 15 per cent, according to the character of the aggregate, climate of the locality where used, amount and character of the traffic. In cold climates more cement is required than in warm ones; pavements subject to constant and heavy traffic require less cement than those used by light traffic.

245. The aggregate consists of sand and stone-dust.

246. In quality the sand should be equal to that used for the best quality of hydraulic cement mortar; it must be free from loam and vegetable impurities; its character should be angular grains ranging from coarse to fine. (See also Art. 252.) All of it should pass a 10-mesh screen; 20 per cent an 80-mesh screen; and 10 per cent, a 100-mesh screen.

247. The stone-dust is used to aid in filling the voids in the sand and thus reduce the amount of cement required for this purpose (the voids in sand range from 0.30 to 0.50 per cent). The amount used will vary with the coarseness of the sand and quality of the cement. The proportion used ranges from 5 to 15 per cent. All of it should pass through a 30-mesh screen, and 75 per cent should pass a 100-mesh screen.

248. As to the quality of the stone-dust; that from any durable stone is equally suitable. Limestone-dust was originally used and has never been entirely discarded, although it may be one of the weak elements in the composition; for carbonate of lime, though practically insoluble in pure water, is decidedly soluble in water containing carbonic acid gas. As rain-water contains this gas in absorption, its action upon the lime in the pavement is to slowly dissolve it, and thus expose the cement to the oxidizing action of the atmosphere. Organic and weak acids such as are found on streets also decompose the lime.

249. The paving composition is prepared by heating the mixed sand and stone-dust and the asphalt cement separately to a temperature of about 300° F. The heated ingredients are measured into a pug-mill and thoroughly incorporated; when this is accomplished, the mixture is ready for use. It is hauled to the street in iron carts, the interior surface of which is previously painted with petroleum oil to prevent it from sticking; it is spread with iron rakes to such depth as will give the required thickness when compacted (the finished thickness varies from 1½ to 2½ inches; the reduction of thickness by compression is generally about 40 per cent).

250. The compression is accomplished by means of rollers and tamping-irons, the latter being heated in a fire contained in an iron basket mounted on wheels; these irons are used for tamping such portions as are inaccessible to the roller, viz., gutters and around manhole heads, etc. Two rollers are generally employed—one a hand-roller weighing about 800 pounds, the other a steam-roller of the form shown in Chap. XXIII, ranging in weight from 5 to 10 tons. The surface of the hand-roller is painted with kerosene to prevent the mixture from sticking to it, and is generally propelled by four or more men walking on the surface of the heated paving mixture. The hand-roller is being superseded by heating the front roll of the steam-roller; the heating is effected either by fire carried in an iron basket suspended from the axle inside the roller, or by an attachment for using steam from the boiler. Two steam-rollers are sometimes employed, one weighing from 5 to 6 tons and of narrow tread—this is used to give the first compression; and the other, weighing about 10 tons and of broad tread, is used for finishing. The amount of rolling varies; the average appears to be about one hour per one thousand square yards of pavement. After the primary compression by either the hand or heated roller natural hydraulic cement or any impalpable mineral matter is sprinkled over the surface to prevent the adhesion of the material to the cold roller and to give the surface a more pleasing color. To prevent rotting of the paving material in the gutters they are formed of either hydraulic cement, granite blocks, vitrified brick, etc., or when the asphaltic material is laid up to the curb the surface of the portion forming the gutter is painted with a coat of hot asphaltic cement.

251. The paving composition is usually spread upon the foundation in two layers; the first is called the "binder" or "cushion coat"; it contains from 2 to 5 per cent more cement than the surface layer; its finished thickness varies from one half to one and one-half inches. The object of the binder is to unite the surface mixture with the foundation, which it does through the larger percentage of cement that it contains, and which if put in the surface mixture would render it too soft. When the "binder" has been compressed, it is ready to receive the surface coat, which is laid and compressed as above described. When bituminous concrete is used as the foundation, the "binder" is omitted. When the pavement is to be laid

upon the surface of an old pavement, the binder or cushion coat is used to fill up the inequalities and bring its surface to the uniform grade and contour.

252. Failure of Asphaltic Cement Pavements.—The failure of this class of pavement may be attributed to any one or all of the following causes:

(1) *Unsuitable asphaltum.* (That is, asphaltum which has been so changed by natural causes as to possess little or no cementing power.)

(2) *Too high temperature in refining the crude asphaltum.* (That is, a temperature which converts the petroleum or cementing medium of the asphaltum into asphaltene and thus reduces or entirely destroys its cementing qualities.)

(3) *Too low a temperature continued for a considerable length of time.* (This has the same effect as a high temperature for a short time, and is analogous to the action of solar heat, which through ages has been changing the liquid bitumen wherever exposed into asphaltum.)

(4) *Unsuitable fluxing agents.* (Such as those which are not solvents of the asphaltene and thus form a mechanical instead of a chemical union, or fluxes which contain volatile oils, which under the action of solar heat evaporate from the pavement and leave it porous and in a condition to absorb rain-water, the oxidizing action of which is to gradually convert the petroleum or cementing agent of the bitumen into asphaltene, thus rendering the pavement brittle, in which condition it is easily broken up under the action of the traffic.)

(5) *Unsuitable temperature employed during the process of fluxing.* (That is, either a high temperature for a short time or a low one for a long time, the effects of which are similar to those stated under 2 and 3.)

(6) *Unsuitable sand.* (That is, sand either too coarse or too fine, or a sand of suitable fineness, but containing loam, vegetable matter or clay. The sand should be clean, sharp, large-grained, and not too uniform in size, well screened and if necessary washed. The presence of clay prevents that intimate contact between the cement and the grains of sand so essential to a homogeneous body, because the particles of clay adhere to the grains of sand and form diaphragms between it and the cement. The sand imparts crushing strength

and fulfils practically the same offices as in hydraulic cement mortar, therefore its quality should be in all respects equal to that used in the best mortar for important structures.)

(7) *Use of limestone-dust.* (This material is speedily dissolved by rain-water and some of the organic acids found in streets; its dissolution leaves the pavement in the same condition and exposed to the same agent of destruction as described under cause 4.)*

(8) *Insufficient mixing of the ingredients.* (Whereby the cement and the particles of sand are not brought into intimate contact; to secure a strong mortar or concrete it is essential that each piece of the aggregate shall be entirely surrounded by the cementing material, so that no two pieces are in actual contact.)

(9) *Insufficient quantity of cement.* (The quantity of cement required to coat each particle of the sand will vary with the character of the sand; if the grains in a given volume are small, the magnitude of the total surface to be covered is greater than when the grains are large; hence a fine sand requires more cement than a coarse one; therefore the proportion of the cement must be varied to suit the character of the sand to be used, or else the quality of the pavement will be impaired.)

(10) *Laying the paving composition on a wet foundation.* (When hydraulic concrete is used as the foundation, it must be set and thoroughly dry before the asphalt is laid upon it; if not, the contained water will be sucked up and converted into steam, which tries to escape through the heated material; the result is that coherence of the asphaltic mixture is prevented, and, although its surface may be smooth, the mass is really honeycombed, and as soon as the pavement is subjected to the action of traffic the voids or fissures formed by the steam appear on the surface, and the whole pavement is quickly broken up.)†

* The results obtained from several experiments indicate that the presence of finely divided amorphous calcium carbonate, calcium oxide, silicic oxide, or free or fixed carbon is detrimental to asphaltum. The action of these substances is to take up the oily constituent and pass it from one particle to another until the surface of the mass is reached, where it is expelled in such a metamorphosed condition that the oil is changed from a partial non-volatile to a slowly or even a rapidly volatile state at ordinary temperatures, and in some cases a portion at least in gaseous form. The effect of this action is to produce a porous mass easily disintegrated.

† The length of time which should elapse before the asphalt is laid upon

(11) *Weak or insufficient foundation.* (A weak or improperly prepared foundation will, by unequal settlement and settlement in spots, cause cracks and depressions in the asphalt surface which under traffic will be speedily enlarged, and the pavement will therefore be broken up.)

(12) *Use of paving mixture which has become chilled.* (Although asphaltum is a bad conductor of heat, and the cement retains its plasticity for several hours, occasions may and do arise through which the composition before it is spread or rolled has cooled; its condition when this happens is analogous to hydraulic cement which has taken a "set," and the same rules which apply to hydraulic cement in this condition should be respected in regard to asphaltic cement.)

(13) *Insufficient compression.* (To prevent the admission of the rain and other water falling upon the surface of the pavement, and its destroying effects, it is necessary that the paving composition be compacted into a solid homogeneous mass; if not, the oxygen contained in the water will have the effect described under cause 4.)

(14) *Lack of water-tight connection* with street furniture, curbs, and crossings, which permits the entrance of water under the asphaltic surface.

(15) *Destruction by natural causes.* (All materials in nature are undergoing changes due to the action of the elements, and asphaltum is no exception. Under the action of solar heat and water all the bitumens undergo a change; this change is due to evaporation, volatilization, and oxidation, and tends at first to greater solidification or hardness. When the maximum degree of hardness is attained, natural decay apparently commences, and under the combined action of organic acids, rain-water, and frost the material seems, so to speak, to rot and finally disintegrate. At any stage of the change the substance is still asphaltum and the process is termed "ageing," and a great deal of the controversy regarding the relative qualities of different asphaltums is due to ignoring the changes wrought by nature. While these changes are slow in

the concrete depends upon two conditions; the character of the cement and atmospheric conditions. It is desirable that ten days at least should elapse before surfacing, accompanied in warm weather by frequent sprinkling. There is no objection to lay surface in cold weather if proper attention is paid to the temperature of the mixture.

nature, some or all of them may be hastened by the unskilful application of artificial heat in preparing the material, and by the action of the organic acids and rain-water falling upon the pavement.

The failure or disintegration of an asphalt pavement manifests itself in different ways according to the cause and character of the pavement.

Disintegration caused by water entering the pavement either from the surface or through the base manifests itself differently, depending upon the character of the pavement. If the asphalt surface is soft, or the surface of the concrete smooth, the first defect noticed will be the tendency of the pavement to become wavy in warm weather. This is due to the under portion of the surface mixture rotting, so to speak, thus destroying the cementing properties of the asphalt. The upper portion, although good, being deprived of the support of the affected mixture under it, will be crowded out by the traffic. This crowding is assisted by the surface of the base being smooth, and also by the bond between the base and binder being destroyed by the moisture.

In cases where the surface of the base is rough and the surface mixture hard the principal disintegration will take place in cold weather, nothing abnormal being noticed until the pavement begins a rapid crumbling away in the affected spot under traffic.

On examining a section of asphalt surface disintegrating from this cause, especially where it has not been going on for too long a time, there will be found a layer of perfectly sound and good material at the surface of the pavement, while underneath the mixture will show evidence of being disintegrated by water; that is, the sand will appear clean and white in spots, as though there had been a deficiency of asphalt cement to cover it. The base under the affected pavement will generally be found damp or even wet. In Washington, D. C., the destruction of several pavements from this cause has been prevented by the use of blind drains put in under the gutter next to the lawn or terrace, and in some cases having bone drains placed under the pavement.

Disintegration caused by unsuitable oils or coal-tar in the binder is manifested by a slight depression over the affected spots. In time numbers of small cracks appear, running parallel with the

street; these gradually increase in importance, accompanied with transverse cracks, until the pavement has the appearance of an alligator-skin. On examining a section of the surface mixture cut from the affected spot it will be found to be quite soft near the binder, if the disintegration has not proceeded for a length of time; if older, the soft zone will be nearer the surface, while the bottom of the mixture will show the disintegrating effect of the water that has likely entered the pavement through the crack. The affected piece of mixture will smell strongly of coal-tar (if coal-tar was used in the binder), and will, in all cases, give a greenish fluorescence to a solution in carbon disulphide. The portion of the pavement thus acted on will be crowded or worn out by the traffic until nothing is left of it. If the surface mixture is soft, the pavement will roll at this place, the soft affected material crowding before the traffic. Binder made with asphalt cement, in some few cases, affects the surface mixture in the same way, due probably to the presence of some free oil, which may not have been properly incorporated with the asphalt in making the binder cement.

Disintegration caused by the absorption of illuminating-gas becomes apparent in very much the same way as when coal-tar is the cause, except that the fine cracks, running parallel with the street, make their appearance some time before the pavement begins to roll. Pieces of the surface mixture taken up smell very strongly of illuminating-gas, and in some cases the gas can be ignited by applying a match to the under surface when it has just been taken up. In nearly every case enough gas will be given off by heating a small piece of the affected pavement in a tube to have it flash by igniting. (See Art. 226.)

Disintegration caused by a deficiency of asphalt cement will be made apparent by cracking and crumbling during cold weather.

Defective bond between base and binder, or between binder and wearing surface, is shown by rolls and waves. (See also Art. 303*b*.)

253. Trinidad Asphalt Pavements.—The source of the asphaltum used in this class of pavement is described in Art. 100. The characteristics of the crude asphaltum are given in Art. 100*d*.

The method of refining is described in Art. 100*e*.

The characteristics of the refined asphaltum are given in Art.

100*n*, and the relative qualities of "lake" and "land" asphaltum are discussed in Art. 100*p*.

The paving material consists of silicious sand and stone-dust (usually limestone) cemented together with asphaltic cement, manufactured as described in Art. 96. The proportions of the ingredients are not constant, but vary with the climate of the place where the pavement is to be used, the character of the sand, and the amount and character of the traffic that will use the pavement; the range in the proportions is as follows :

Asphalt cement.....	12 to 15 per cent.
Sand.....	88 to 70 " "
Stone-dust.....	5 to 15 " "
100—100	

The sand and asphaltic cement are heated separately to about 300° F. The stone-dust (pulverized carbonate of lime) is added to the hot sand in the required proportions, and is then mixed with the hot asphaltic cement in a suitable mixing machine and thoroughly incorporated; when this is accomplished, the mixture is ready to be laid on the street.

Specifications for Trinidad asphalt pavements are given in Articles 262, 263, and 264.

254. The proportions of the materials for the Trinidad asphalt pavements at Washington, D. C., average as follows:

Weight of—	Cranford.		Barber.	
	Pounds.	Per cent.	Pounds.	Per cent.
Sand.....	584	75.0	637	74.8
Stone dust.....	54	6.9	60	7.0
Limestone dust.....	30	3.8	35	4.1
Asphalt cement.....	111	14.3	125	14.6

COMPOSITION OF PAVING MIXTURES.

255. The following table shows the maximum, minimum, and average per cent of the bitumen, and the mesh composition of the sand, in the paving mixtures used at Washington, D. C., during 1899:

	Eastern Bermudez Paving Co.	Cranford Paving Co.
Number of samples.....	29	62
Average per cent bitumen.....	10.7	10.7
Lowest " " "	9.1	9.8
Highest " " "	12.0	12.8
Sand—Per cent retained on sieve having		
20 mesh per inch.....	2.5	8.0
40 " " "	20.0	25.5
60 " " "	31.9	38.3
80 " " "	8.3	7.0
100 " " "	10.8	6.5
Passed 100 mesh.....	26.0	18.5

256. Memoranda.—One ton of refined asphaltum mixed with the flux makes about 2300 pounds of asphaltic cement, equal to about 3.4 cubic yards of paving material.

One cubic yard of paving mixture contains one cubic yard of sand, 675 lbs. \pm of asphaltic cement, and 490 lbs. \pm stone-dust; weighs about 4500 lbs., depending upon the character of the sand; and will lay the following amount of surface:

2 $\frac{1}{2}$ inches thick.....	12 square yards
2 " "	18 " "
1 $\frac{1}{2}$ " "	27 " "

257. Temperatures.

Refining, not over.....	400° F.
Fluxing, " "	325° F.
Sand—Lowest.....	250° F.
Highest	300° F.
In cold weather not lower than.....	280° F.
Mixing ingredients.....	275° F.
When spreading.....not lower than 250° in summer or 275° F.	
in winter. Never over.....	300° F.

Cold or chilled mixture should not be used. No compaction can be secured with such material.

It is doubtful if surface mixture can be successfully reheated.

258. Extracts from the Reports of City Civil Engineers.—**Washington, D. C.** (Capt. Greene, 1885).—The Trinidad asphalt has been the standard pavement for the last seven years, about 600,000 square yards having been laid on a foundation of hydraulic concrete, and about 160,000 yards more on the stone foundations of the worn-out tar pavements. Its cost for the last three years has been about \$2.25 per square yard. When made with skilled

labor and laid under proper supervision it seems to answer all the requirements of a first-class pavement in this city. It is almost noiseless, not slippery, under ordinary conditions offers little resistance to traction, is easily repaired and cleaned, and is very durable. Large numbers of streets have been laid five, six, and seven years, and are in perfect order, although not a cent has been expended on them for repairs. On other streets mistakes have occasionally been made in the mixture, and defects have appeared which needed repairs. Nearly all these repairs have been made at the contractor's expense during his guarantee period; but as nearly as it can be ascertained the total expense both to contractors and the District for repairing asphalt pavements during the eight years since they were first laid has been about \$30,000, or \$3750 per year, so that the average annual expense for maintenance up to date has been $\frac{1}{16}$ of one cent per yard per year. This is certainly a small expense for the luxury of smooth pavements, and much less than for any other pavement having the combined durability and smoothness of the asphalt.

259. *The French Asphalt Pavement*, made from the natural bituminous limestone of Switzerland, and similar in every respect to the asphalt pavements as laid in Paris, was tried here in 1873 and 1876, 31,388 yards having been laid on the following streets, viz.: Pennsylvania Avenue, between First and Sixth streets; I Street, between Thirteenth and Fifteenth streets; and Grant Place, between Ninth and Tenth streets. Experience has shown that this pavement is more slippery than the pavement of sand and Trinidad asphalt, and that it is not quite as durable. Its cost is nearly fifty per cent greater; for these reasons no more of it has been laid.

260. Buffalo, N. Y.—The streets paved with asphalt have stood the extreme changes of this climate without any serious defect, are giving satisfaction to our people, being healthful, easily kept clean, smooth, yet not slippery.

261. Omaha, Neb.—"Our temperature varies as much as 150 degrees Fahr., between the extremes of summer and winter. We are subject to rapid changes of temperature, which in the winter season occasionally are as high as 60 degrees in twenty-four hours. Douglas Street, which was paved in the fall of 1882 and spring of 1883, has experienced a range of temperature of from 120 degrees in the summer to 34 degrees below zero in the winter. . . . Our experience

is very favorable to asphalt pavements on all grades ranging from 6 inches to 4 feet rise per 100 feet, and I am not sure but that as high as 5 or 6 feet per 100 feet may be favorably overcome. The asphalt pavement is not as cheap as wood, but, in my opinion, a preferable pavement upon permanently established and well-improved streets. It is not quite as easy for horses as wood, but more comfortable for those who ride, is more cleanly, and from a sanitary standpoint far superior."

262. Heads of Specifications for Standard Trinidad Asphaltum Pavements.

(1) *Preparation of Roadbed.*

(2) *Foundation.* (Hydraulic-cement or bituminous concrete.)

(3) *The Wearing Surface* will be composed of

(a) Refined Trinidad asphaltum.

(b) Heavy petroleum oil.

(c) Fine sand containing not more than one per centum of hydrosilicate of alumina.

(d) Fine stone-dust.

(e) Fine powder of carbonate of lime.

(4) *Preparation of the Asphalt.*—The Trinidad asphaltum shall be refined, and as far as possible freed from foreign organic and animal matter and volatile oil, and brought to uniform standard of purity and gravity, containing not less than 60 per cent of bituminous matter soluble in bisulphide of carbon. The asphaltum must be refined under the direction and to the satisfaction of the engineer, and kettles will not be drawn lower than may be ordered by him.

The heavy petroleum oil shall be freed from all impurities and brought to a specific gravity of from 18 to 22 degrees Beaumé and a fire test of 250 degrees Fahrenheit.

From these two hydro carbons shall be manufactured an asphalt cement which shall have a fire test of 250 degrees Fahr., and at a temperature of 60 degrees Fahr. shall have a specific gravity of 1.19, said cement to be composed of 100 parts of pure asphalt and from 15 to 20 parts of heavy petroleum oil.

(5) *Manufacture of the Paving Material.*—The asphalt being prepared in the manner above described, the pavement mixture will be formed of the following materials, and in the proportions stated.

Asphaltic cement.....	from 12 to 15
Sand.....	" 88 " 70
Pulverized carbonate of lime.....	" 5 " 15

or

Asphaltic cement.....	from 18 to 16
Sand.....	" 63 " 58
Stone-dust.....	" 28 " 23
Pulverized carbonate of lime.....	" 8 " 5

The proportion of the materials will depend upon their character and the traffic on the street, and will be determined by the engineer. If the proportions of the mixture are varied in any manner from those directed to be used, the mixture will be condemned; and if already placed on the street, it will be removed and replaced by proper material, at the expense of the contractor.

The sand, stone-dust and asphaltic cement are to be heated separately to about 300 degrees Fahr. The pulverized carbonate of lime while cold shall be mixed with the hot sand and stone-dust in the required proportions, and then mixed with the asphaltic cement at the required temperature, and in the proper proportion, in a suitable apparatus, which will effect a perfect mixture. The proportions will be gauged daily in the presence of the inspectors.

(6) *Quality of the Materials.*—All the materials used, as well as the plant and method of manufacture, will be subject to the inspection and approval of the engineer. The degree of fineness, both of the sand, stone-dust, and powdered limestone, will be determined by testing with screens, as follows: The powdered carbonate of lime will be of such degree of fineness that 15 per cent by weight shall be an impalpable powder of limestone, and the whole of it shall pass a No. 26 screen. The sand will be of such size that more than 50 per cent of it will pass a No. 80 screen, and the whole of it shall pass a No. 20 screen. The stone-dust shall be the residue of granite or other approved stone, and shall pass a sieve of not more than 6 meshes to the inch.

(7) *Laying the Asphalt.* (Two-coat Pavements.)—The pavement mixture, prepared in the manner thus indicated, shall be laid on the foundation in two coats. The first coat, called cushion-coat, shall contain from 2 to 4 per cent more asphaltic cement than given above; it will be laid to such depth as will give a thickness of $\frac{1}{4}$ inch after being consolidated by a roller. The second coat,

called surface-coat, prepared as above specified, shall be laid on the cushion-coat; it shall be brought to the ground in carts at a temperature of about 250 degrees Fahr., and if the temperature of the air is less than 50 degrees iron carts with heating apparatus shall be used in order to maintain the proper temperature of the mixture; it shall then be carefully spread by means of hot iron rakes, in such manner as to give a uniform and regular grade, and to such depth that after having received its ultimate compression it will have a thickness of 2 inches. The surface then shall be compressed by hand rollers, after which a small amount of hydraulic cement shall be swept over it, and it then shall be thoroughly compressed by a steam roller weighing not less than 250 pounds to the inch run; the rolling to be continued for not less than five hours for every 1000 yards of surface.

(8) *Laying the Asphalt.* (One-coat Pavement.)—The pavement mixture, prepared in a manner thus indicated, will be laid on the foundation; it will be laid to such depth as will give a thickness of 2½ inches after being consolidated by rollers. It will be brought to the ground in carts, at a temperature of not less than 250 degrees Fahr. nor more than 310 degrees Fahr., and if the temperature of the air is less than 50 degrees the contractor must provide canvas covers for use in transit. It will then be carefully spread by means of hot iron rakes, in such manner as to give uniform and regular grade and to such depth that, after having received its ultimate compression of two fifths, it will have a net thickness of 2½ inches. This depth will be constantly tested by means of gauges furnished by the engineer. The surface will then be compressed by hand rollers, after which a small amount of hydraulic cement will be swept over it, and it will then be compressed by a steam roller weighing not less than 5 tons, to be followed by another steam roller weighing not less than 10 tons, the rolling being continued for not less than 10 hours for every 1000 yards of surface.

(9) In order to make the gutters entirely impervious to water, a width of 12 inches next the curb will be coated with hot pure asphalt and smoothed with hot smoothing-irons in order to saturate the pavement to a certain depth with an excess of asphalt; or if so directed by the engineer, the gutters will be formed with gutter-stones, granite blocks, or bricks, in accordance with the specifications for such work.

(10) *Laying Granite Blocks adjoining Railway Tracks.*—

When asphalt pavement is laid in a street containing the tracks of a street railroad one row of selected granite paving-blocks will be laid next to the track, alternating as headers and stretchers tooth-ing into the pavement. The foundation will extend to the depth of the bottom of the cross-ties, and will be similar in all respects to the foundation of the carriageway pavement, except as to the thickness of the base. If the foundation consists of bituminous concrete, the blocks will be laid directly upon and embedded in the binder while it is still in a hot and plastic condition. If the foundation consists of hydraulic-cement concrete, the base will be covered with a layer of fine sharp sand, washed and dried, 2 inches in thickness, and the blocks will be laid directly upon and embedded in the sand with close joints.

The top of the blocks will be even with the surface of the tread of the rail, which shall conform with the grade of the street. The blocks will be laid before the asphaltic wearing surface is laid upon the carriageway, and carefully rammed to a firm bed. Care will be taken to fit them well up against the stringers or web of the rail of the railroad. The space back of the blocks will be filled to the surface of the base for the carriageway pavement with the same material as is used for said base, well rammed.

Immediately after the wearing surface shall have been laid, clean, fine, hot gravel, not larger than one-half inch in any direction, will be poured into the joints of the blocks until they become nearly filled. There will then be poured into the joints, at a temperature of 300 degrees Fahr., paving cement made of No. 6 coal-tar distillate, until the joints are completely filled flush with the surface of the pavement. Additional fine hot gravel will then be poured along the joints, and will be consolidated by tapping with a light rammer. If found necessary additional paving cement will be poured between the blocks until the joints are thoroughly filled.

In measuring this work for payment, when standard size granite blocks are used, the area included between the outer edge of the rail and a line parallel to and six inches from rail will be taken as the area of granite-block pavement laid. Bids will be based on this rule. When so ordered, the block pavements will be extended to cover the entire area included between the rail and parallel to

and 2 feet distant from said rail. In case the tracks are laid with a grooved girder rail, these headers and stretchers may be omitted if so ordered by the engineer, and the asphalt pavement laid close to the rail.

(11) The work of laying the asphalt shall not begin until the curbstones, crosswalks, catch-basins, manhole heads, etc., have been properly adjusted to the finished grade of the street, and permission to proceed has been received from the engineer.

- (12) Interpretation of specifications.
- (13) Omissions in specifications.
- (14) Engineer defined.
- (15) Contractor defined.
- (16) Notice to contractors, how served.
- (17) Preservation of engineer's marks, etc.
- (18) Dismissal of incompetent persons.
- (19) Quality of materials.
- (20) Samples.
- (21) Inspectors.*
- (22) Defective work, responsibility for.
- (23) Measurements.
- (24) Partial payments.
- (25) Commencement of work.
- (26) Time of completion.
- (27) Forfeiture of contract.
- (28) Damages for non-completion.
- (29) Evidence of the payment of claims.
- (30) Protection of persons and property.
- (31) Indemnification for patent claims.
- (32) Indemnity bond.
- (33) Bond for faithful performance of work.
- (34) Power to suspend work.
- (35) Right to construct sewers, etc.
- (36) Loss and damage.
- (37) Old materials, disposal of.
- (38) Cleaning up.
- (39) Personal attention of contractor.
- (40) Payment of workmen.

* An inspector should be placed at the plant of the contractor, to know what course is pursued; otherwise the municipality has no data for studying the various mixtures nor does it know that the contractor is carrying out the specifications.

- (41) Prices.
- (42) Security retained for repairs.
- (43) Payment when made, final acceptance.

263. Specifications for Asphalt Pavement on Bituminous Base.—

Combination asphalt pavement on bituminous base will consist of a base 4 inches, a binder of $1\frac{1}{2}$ inches, and a wearing surface of $1\frac{1}{2}$ inches in thickness, when compacted.

The space over which the pavement is to be laid will be excavated to the depth of 7 inches below the top of the surface of the pavement when completed. Any objectionable or unsuitable material below the bed must be removed, and the space filled exactly parallel to the surface of the new pavement when completed; and the entire roadbed will be thoroughly rolled with a heavy steam-roller weighing not less than 5 tons. Upon the foundation will be laid the base and binder, $5\frac{1}{2}$ inches in thickness, in the following manner:

Base.—The base will be composed of clean broken stone that will pass through a 3-inch ring, well rammed and rolled with a steam-roller weighing not less than 5 tons, to a depth of 4 inches. The rolling will be continued until the stone ceases to creep before the roller, and until it is evident that the final compression has been reached. It will be thoroughly coated with No. 4 $\frac{1}{2}$ coal-tar paving cement in the proportion of about one gallon to the square yard of base.

Binder.—The second or binder course will be composed of clean broken stone, thoroughly screened, not exceeding 1 inch in the largest dimension, and No. 4 coal-tar paving-cement. The stone will be heated to a temperature between 230 and 250 degrees Fahr., by passing through revolving heaters, and thoroughly mixed by machinery with the paving-cement in about the proportion of one gallon of No. 4 tar to one cubic foot of stone. It will be hauled upon the work, spread upon the base course to such thickness that when compacted it will be $1\frac{1}{2}$ inches thick, and immediately rammed and rolled with hand and steam rollers while in a hot plastic condition.

Wearing Surface.—The wearing surface will be $1\frac{1}{2}$ inches thick when compacted, and will conform in all other respects to the wearing surfaces as prescribed for the standard asphalt pavement, as described in these specifications.

The pavement so constructed must be a solid mass, 7 inches thick, and must be thoroughly rolled and cross-rolled until it has become hard and solid.

Gutters, wherever directed, will be formed of granite-block or brick, of such width as may be directed, laid upon a hydraulic base of not less than 4 inches in thickness, in accordance with the specifications for granite-block pavement and for brick gutters.

264. Specifications for Asphalt Pavement on Hydraulic Base.—The asphalt pavement on hydraulic base will be 7 inches in thickness, consisting of a base composed of 4 inches of hydraulic concrete and 2 inches of binder, $1\frac{1}{2}$ inches when compacted, and a wearing surface of standard asphalt, $2\frac{1}{2}$ inches in thickness, or $1\frac{1}{2}$ inches when compacted.

Binder Course.—The binder course will conform in all respects to the binder course for the asphalt pavement on bituminous base, and will be $1\frac{1}{2}$ inches in thickness when compacted.

Wearing Surface.—The wearing surface will be $1\frac{1}{2}$ inches thick when compacted, and will conform in all other respects to the wearing surfaces as prescribed for the standard asphalt-pavement.

264a. Specifications for Asphalt Pavement on the Surface of an Old Pavement.—The surface of the old pavement shall be thoroughly cleansed by sweeping with stiff brooms until all the dirt, etc., has been removed from the surface and from the joints to a depth of about one inch.

The surface shall then be brought to a uniform grade and cross-section by excavating where necessary, and by filling and repairing all depressions with bituminous concrete or binder, this binder to be composed of clean broken stone, the fragments of which shall not exceed one and one quarter inches in their largest dimensions, and asphaltic pavement cement (or coal-tar paving-pitch).

The stone shall be heated in suitable heating apparatus, and shall be thoroughly mixed with the paving cement in the proportion of 12 to 15 per cent of asphalt paving cement (or one gallon of paving-pitch) to one cubic foot of stone.

This binder shall be spread to such thickness that, after being thoroughly compacted by tamping and rolling, its thickness shall be not less than one inch, and its surface shall be exactly parallel with the surface of the pavement to be laid upon it.

Upon this foundation the wearing surface or pavement proper of asphaltic cement shall be laid. (See also Articles 262, 263, 264.)

264b. Specifications for Asphalt Pavement, Washington, U. C., 1899.—Binder.—The binder course shall be composed of clean, sound stone broken into fragments of such size that 85 per cent of the whole amount will pass through a screen having 1½-inch meshes, and of the remaining 15 per cent no piece shall have a larger dimension than 2 inches, and the stone after passing the heating-drums shall not contain less than 5 nor more than 10 per cent of material passing a No. 10 screen.

The stone shall be heated not higher than 350° F. in suitable apparatus. It shall then be mixed thoroughly by machinery with the asphaltic cement, which shall be of the same quality as that used for the wearing surface, and having a penetration on Bowen's scale of 100° to 200°, in such proportions that the mixture will have life and gloss without an excess of cement. Should it appear dull from overheating or lack of cement, it will be rejected. While hot it will be hauled upon the work, spread upon the base to such depth that when compacted it will be at least 1½ inches in thickness, and immediately rammed and rolled until it is cold. Should the resulting course not show a proper bond, it shall be immediately removed and replaced by the contractor.

Asphaltum.—The crude asphaltum shall be refined to the satisfaction of the engineer.

Flux.—Petroleum residuum, Pittsburg flux, maltha, or any other softening agent complying with the required tests may be used. (See Art. 97*d* for specifications of petroleum residuum.)

Asphaltic Cement.—When the refined asphaltum is not already of the proper consistency the cement shall be prepared by tempering refined asphaltum with petroleum residuum or other approved softening agent, at a temperature between 250° and 350° F. The asphalt cement must not be inferior in quality to a cement made of the best quality Trinidad asphalt and petroleum residuum. Its penetration must be within the range of 60° and 120° on Bowen's scale, and will be fixed by the engineer. A variation of 10° from the degree decided upon will be sufficient for rejecting the mixture.

Samples of the asphalt, flux, and asphaltic cement must be furnished the engineer as required.

Sand.—The sand used shall be hard and moderately sharp.

On sifting, at least 15 per cent should be retained in a 40-mesh-per-inch sieve, 25 per cent that will pass 80-mesh-to-the-inch sieve, 10 per cent of which at least must pass a 100-mesh-to-the-inch sieve. If the sand does not contain the desired fine material, limestone dust or other suitable material can be added to make up the deficiency.

Inorganic Dust.—This shall be any inorganic dust not acted upon by water, the whole of which shall pass a 30-mesh screen and at least 75 per cent pass a 100-mesh screen.

Manufacture of the Paving Mixture.—The materials complying with the above specifications shall be mixed in proportions by weight, depending upon their character and the traffic on the street and upon the character of the asphalt, determined by the engineer, but the percentage of bitumen in any mixture soluble in carbon bisulphide shall not exceed the limits, 9 to 13 per cent. If the proportions of the mixtures are varied in any manner from those decided upon, the mixture will be condemned, its use will not be permitted, and if already placed on the street it will be removed and replaced by proper materials at the expense of the contractor.

The sand or the mixture of sand and stone dust and the asphaltic cement will be heated separately to about 300° F. The dust, while cold, will be mixed with the hot sand in the required proportion and then mixed with the asphaltic cement at the required temperature and in the proper proportion, in a suitable apparatus, so as to effect a thoroughly homogeneous mixture. Sand-boxes and asphalt-gauges will be weighed in presence of inspectors as often as may be desired.

Samples as desired shall be furnished the inspector in suitable boxes, and he shall have access to all branches of the works at all times.

265. Maintenance of Asphalt Pavements under Contract.—The contractors will furnish all the labor and materials necessary to make repairs and renewals required to preserve the surface in a perfect state, true to the profile, without humps or depressions, even if the dilapidations are the result of accidental causes, as sinking of the subsoil, etc., except only the digging of trenches. The contractor must renew all places where the surface is cracked, split,

depressed, swelled, or in any way perforated, where it matches unevenly with manhole heads and other street fixtures, etc., and especially where sunken near trenches.

Where the foundation is defective, it shall be removed and replaced with good material. Defective spots must be carefully cut out with a sharp tool, and at least 2 feet larger in every direction than the defective place; the sides must be cut on straight lines; there must be a perfect union of the old and new material, and the surface must show no irregularities.

On September 1st, or sooner in case of bad weather, a general examination will be made with the contractor, who must immediately begin repairs on doubtful surfaces, not likely to endure through the winter. In rainy weather the bottoms of patches must be sponged and dried as carefully as possible with fine hot ashes, and then be well brushed. Special care must be taken to clean all sand, powder, etc., from the bottom of patches.

During bad weather no repairs shall be made to the asphalt, unless expressly authorized by the engineer. Patches made during winter are to be considered as only temporary, and must be replaced by the 15th of May.

The contractor is absolutely forbidden to use pebbles for filling holes in the asphalt. When the contractor fails to make the necessary repairs, and the administration, exceptionally and in default of other available means, fills the holes with broken stone or other material, the contractor must pay for the work and materials, and cannot claim damages for injury to the pavement caused by such materials.

In winter, holes in the foundation may be filled with a mixture of 3 parts by volume of pebbles to 1 part of hot asphalt; but this provisional filling must be removed as soon as possible and replaced in the standard manner.

The contractor will be paid for repairs to all trenches opened in the street. He can, however, make no claim for settlement or any other injury at these places, and must maintain the pavement there in the same condition as elsewhere.

To secure a perfect welding at the edges of the asphalt, a width of 2 inches greater in every direction than the trench will be paid for.

To provide for settlement of the earth in the trenches, the contractor may maintain the area occupied by the trench, during a

period of eight days, with broken stone or gravel, well rammed, sprinkled, swept, and maintained, so as to prevent injury to horses. If after eight days final repairs are still impossible, the contractor must at his own expense make a provisional surface of bituminous concrete, which will be removed for final repairs.

If for any reason it becomes necessary to tear up asphalt pavements, it shall be done as follows: It will be cut in as straight lines as possible with sharp chisels, and when torn up must on no account pull up with it any of the adjacent material.

Then the concrete is to be cut by sharp chisels in lines about 3 inches from the edge of the asphalt, which may be broken into pieces and laid aside.

In removing the earth from the excavation, care must be taken that no portion of the concrete is undermined.

285a. The "Bermudez" Asphalt, recently introduced for paving purposes, is obtained from a lake or deposit which covers an area of several hundred acres in the state of Bermudez, Venezuela, S. A. (See also Art. 101.)

The purity and quality are said to be exceedingly high; the following analysis is given by Prof. E. J. De Smedt:

Bitumen soluble in CS ₂	97.86 per cent
Organic and inorganic matter (impurities).....	2.14 "
	<hr/> 100.00 per cent

The following are some of the characteristics of this asphalt:

At 60° F. compressible; at 70° F. viscous and malleable; at 100° F. flowing, and can be stretched in hair-like threads; at 189° F. melts; at 400° F. gives no flash.

The paving-cement is manufactured by adding 15 lbs. of residuum oil, 20 Baumé at 60° F., to each 100 lbs. of refined asphalt. This 100 lbs. of refined asphalt yields 97.86 lbs. of pure bitumen; consequently $13\frac{3}{8}$ per cent of oil is added to the pure bitumen.

The asphalt is melted at from 250° to 300° F. The oil is then added and thoroughly mixed with the melted asphalt.

The pavement mixture is composed of the following materials and in the proportions stated:

Asphaltic cement.....	9 to 10 parts
Pulverized carbonate of lime.....	20 " 30 "
Fine clean sand.....	71 " 60 "
	<hr/> 100 100

The sand and carbonate of lime are mixed and heated to from 250° to 300° F. The asphaltic cement is heated separately to from 225° to 250° F. The materials so heated are mixed in a suitable mixing apparatus, and the mixture while at a temperature not below 200° F. is spread upon the foundation in two coats, the lower or cushion coat being one-half inch thick after compression, and the second or wearing coat being two inches thick after final compression with a roller weighing not less than 250 lbs. per inch run. A small amount of hydraulic cement is swept over the surface before the application of the roller.

It is claimed that pavements made from this asphalt do not rot in contact with water.

One square yard of pavement 2½ inches thick weighs 250 lbs.

266. European Asphalt Pavements.—In Paris two kinds of asphalt pavement are employed. First, *asphalt coulé*, made from natural rock asphalt to which is added sufficient bitumen to make the total 15 to 18 per cent of bitumen. The mass is heated for about six hours so as to make a thorough mixture. The ground having been graded, sprinkled and thoroughly rammed or rolled, a bed of hydraulic-cement concrete from 4 to 6 inches thick is laid, and after this is set and well dried the asphalt mixture is spread and surfaced by a wooden float. The thickness of the asphalt is about 1½ inches, and it is usually applied in two layers. This covering will not soften at a temperature of 140 degrees Fahr.

267. The second kind of asphalt covering is *asphalt comprimé*, or compressed asphalt. In this the natural rock alone is used. It comes from Val de Travers in Switzerland, Seyssel in France, and other localities, and consists of carbonate of lime impregnated with bitumen. The color is a dark (almost black) chocolate-brown. When cold the rock breaks easily, with an irregular fracture and without definite cleavage. Its grain should be regular and homogeneous; the finer the grain the better. When exposed to the atmosphere the bituminous rock gradually assumes a gray tint, by reason of the bitumen evaporating from the surface, leaving a thin film of limestone behind.

268. The following is a test for bituminous rock given by Mr. Delano in a paper he read before the Institution of Civil Engineers in the year 1880. "A specimen of the rock, freed from all

extraneous matter, having been pulverized as finely as possible, should be dissolved in sulphurate of carbon, turpentine, ether, or benzine, placed in a glass vessel and stirred with a glass rod. A dark solution will result from which will be precipitated the limestone. The solution of bitumen should then be poured off. The dissolvent speedily evaporates, leaving the constituent parts of the bitumen, each of which should be weighed so as to determine the exact proportion. The bitumen should be heated in a lead bath and tested with a porcelain or Baumé thermometer to 428 degrees Fahr. There will be little loss by evaporation if the bitumen is good, but if bituminous oil is present the loss will be considerable. Gritted mastic should be heated to 450 degrees Fahr. The limestone should be next examined. If the powder is white and soft to the touch, it is a good component part of asphalt; but if rough and dirty, on being tested with reagents it will be found to contain iron pyrites, silicates, clay, etc. Some bituminous rocks are of a spongy or hygrometrical nature; thus, as an analysis which merely gives so much bitumen and so much limestone may mislead, it is necessary to know the quality of the limestone and of the bitumen."

The European bituminous limestone appears like a fine-grained rock, friable in summer, hard in winter. When heated to 50 or 60 degrees (centigrade) it can be crushed between the fingers, and if exposed for several hours to a fierce sun it crumbles into unctuous brown powder. Examined under the microscope it is found to consist of minute calcareous grains, each covered with a thin film of bitumen which causes them to adhere together. If a small portion is heated, the cementing bitumen is melted and releases the solid particles from a loose heap of a deep chocolate color. If this powder is raised to 175 or 212 degrees Fahr. and rapidly compressed in a mould, it will regain, in cooling, its original consistency in the new form. And the process may be indefinitely repeated, no change being produced by melting, followed by compression and cooling.

269. The best material used by the "Compagnie Generale des Asphaltes de France" comes from the Pyrimont mines of the Seyssel region in the Department of Haute Savoie and Litin, France. The workings are in great part subterranean and the deposit lies in eight superimposed beds separated by beds of white limestone. One of these bituminous beds lies about 100 feet above

the level of the Rhone and has a thickness of 23 feet; it is the largest of all known beds of this material. The galleries now driven aggregate about seven miles in length.

270. The rock is extracted in a temperature ranging from 53 to 55 degrees Fahr., and it is relatively hard. This desirable quality can be increased by taking it outside during the winter, but it should not even then be exposed to the sun. Dynamite or gunpowder is used in extracting it, the latter being used when the mass is compact, dry, and without fissures. As the rock is to a certain degree plastic, it compresses easily and does not work well with the more violent and quick explosives. On the other hand, dynamite is effectively used in the wetter parts of the mine and in places where fissures would permit the slower-acting gases from gunpowder to escape without efficient work.

The blocks of bituminous rock are removed outside by rail and as few blocks as possible are piled upon one car, to avoid crushing under the effect of the heat of the sun. This crushing is undesirable for two reasons: first, there is more waste in the transport and handling; and secondly, if rain falls upon a pulverized mass, it absorbs water rapidly and becomes exceedingly difficult to treat.

271. The operations preliminary to the application of the bituminous rock to the street surface are: (1) The extraction and (2) the crushing of the rock. (3) The heating of the powder. (4) Transporting the heated powder to the street. (5) Spreading it while warm. (6) Ramming. (7) Rolling.

272. The quarried blocks of mineral are crushed between toothed cylinders, revolving at unequal speeds, which reduce it to pieces of the average size of eggs. These are pulverized in "Carr" machines, which run about 600 revolutions per minute, and deliver it as powder, which is sifted to uniform extreme fineness. This powder is heated in an apparatus resembling a "coffee-roaster;" the revolving cylinder is about $6\frac{1}{2}$ feet in diameter and the same in length; the exterior envelope carries a chimney, disposed in such fashion that the heated air from the furnace passes all around the cylinder. The furnace itself is movable and placed immediately below the cylinder, and rests on a railway so that it may be run out of the way. The moving cylinder is mounted upon an axle and supported on journals in the enveloping cylinder, which rests upon four stout legs.

273. The powder is put into the roaster by means of a hopper placed opposite a central hole forming an annular space around the axle. The powder falls into the cylinder, which is moving very slowly; the cylinder is provided with interior blades arranged in a spiral, by which the contents are lifted up to the top and fall in a shower through the hot air in the cylinder, until it is thoroughly warmed both by this action and by contact with the hot sides of the cylinder. As the movement of the cylinder is perfectly regular, the powder remains on the blades only a determinable time, and the entire mass has imparted to it a uniform temperature. The apparatus used on the work of the city of Paris heat, to a temperature of about 300 degrees Fahr., about 3960 pounds of powder in 15 minutes.

When the powder is sufficiently heated the furnace is run out from under it, and is replaced by the special wagon used for transporting the warm powder to the place of use, into which the powder falls after opening a gate in the side of the cylinder.

274. Asphaltum is a bad conductor of heat, and this negative quality much simplifies the difficulties of its preparation, and permits the material to be heated at central stations and conveyed a considerable distance before it will fall appreciably in temperature; in fact, the powder loaded into sheet-iron carts with double sides and cover may be carried from $1\frac{1}{2}$ to $9\frac{1}{2}$ miles from the place of heating to the place of use without losing on the way more than 35 or 40 degrees Fahr. of its mean temperature.

275. The hot material is emptied out on the concrete foundation, spread by hot rakes in a layer of sufficient thickness to allow for compression to the exact finished surface and required thickness, viz., about 3 inches for a 2-inch coat.

The surface, and consequently the thickness, is regulated by a wooden straight-edge bearing on parallel guides set at the required height in the surface of the concrete.

276. The ramming is done by round cast-iron rams, 6 to 8 inches in diameter, which are used by fifteen or twenty men, marching side by side and vigorously ramming the asphalt while it is yet hot. After a few minutes a roller drawn by two men and heated by an internal furnace gives what is called the "primary compression," the normal compression being effected under the traffic by the carriage-wheels. During the rolling a small quantity

of hydraulic cement is strewn over the surface. The rolling is continued until the asphalt is cold.

The bituminous limestone to form a good roadway pavement should contain from 9 to 10 per cent of bitumen, and be non-evaporative at 428° Fahr. Limestones containing much more than 10 per cent of bitumen become soft and wavy in summer; those containing much less have not sufficient binding power to sustain heavy traffic.

277. Bituminous Limestone Pavements in the United States.

—About 55,000 square yards of bituminous limestone pavement were laid in Washington, D. C., during 1876 and 1887, and about 3000 square yards in New York in 1883 or 1884; nearly all of this was subsequently taken up and replaced by Trinidad asphalt. In 1887 about 10,000 square yards were laid in Rochester, N. Y.; in 1888 about 20,000 square yards in St. Augustine, Florida; and in 1890 40,000 square yards in New York City. The total amount of bituminous limestone pavements now in use in the United States is estimated at 75,000 square yards.

These pavements are composed of a mixture of about three parts of bituminous limestone rock from Ragusa, Sicily, and one part of a similar rock from Vorwohle, Germany; the latter is a harder rock and contains less bitumen than the Sicilian.

The paving mixture contains from 10 to 12 per cent of bitumen, and is prepared by pulverizing the mixed rock and heating it to a temperature of about 160° Fahr. The heated powder is laid and compressed in the manner described under European Asphalt Pavements.

278. Coal-tar Pavements.*—The wearing surface of the earlier pavements was made in various ways, according to the patent, but consisted essentially of small gravel, sand, and stone-dust, cemented by a product of coal-tar. In the later pavements of this variety a certain proportion of bitumen is mixed with the tar, and with beneficial results.

*The Report of the Engineer Department of the District of Columbia for 1896 says regarding tar pavements: "This pavement answers the purpose well during hot weather, but as soon as the temperature becomes low enough to cause the tar to become brittle, it goes to pieces with but little more cohesion than so much loose gravel or broken stone."

Wherever laid in the United States, coal-tar pavements, as a rule, have given little satisfaction, their failure being due to the presence of volatile oils in the tar, which on exposure to atmospheric influence slowly oxidize and become inert, thus destroying the cementing qualities of the tar. If these oils are removed before the tar is used the resulting material is brittle, and soon crumbles to pieces after being laid. Coal-tar is also very sensitive to heat: in summer it is soft, in winter brittle. On account of these defects, the use of coal-tar alone, as a cementing material for pavements, has been almost entirely abandoned.

279. Coal-tar and Asphalt.—To overcome the defects of coal-tar when used alone, the practice has arisen of mixing the gas tars with bitumen, and this has been successful in proportion to the amount of the bitumen used. The most successful pavement of this character is that known as the "Vulcanite." This pavement is prepared as follows:

280. Filbert Vulcanite Asphalt Pavement as laid by the National Vulcanite Company of New Jersey.—The pavement is $8\frac{1}{2}$ inches in thickness, formed as follows: The wearing surface $1\frac{1}{2}$ inches when compacted, and a bituminous base and binder 7 inches in depth.

The base is composed of stone broken to pass through a 3-inch ring. It is spread on the earth surface, previously graded to receive it, to a depth of 5 inches, these consolidated with a steam roller, after which it is covered with a hot paving-cement composed of No. 4 tar distillate in the proportion of about one gallon to the square yard of pavement.

The second or binder course is composed of stone broken to pass through a $1\frac{1}{4}$ -inch ring,—the stone being thoroughly cleansed and screened,—and No. 4 tar distillate. The stone is heated by passing through revolving heaters, and is thoroughly mixed by machinery with the distillate in the proportion of one gallon of distillate to one cubic foot of stone.

The binder is spread upon the base to a depth of two inches, and is immediately rammed and rolled with hand and steam rollers while hot and in a plastic condition.

The wearing surface, $1\frac{1}{2}$ inches thick, is made of paving-cement, composed of 25 per cent of asphalt and 75 per cent of tar distillate,

and clean sharp sand and stone pulverized to pass through a $\frac{1}{4}$ -inch ring in the proportion of two parts of sand to one part of stone.

To 21 cubic feet of the above ingredients are added one peck of hydraulic cement, one quart of flour of sulphur, and two quarts of air-slaked lime. To this mixture is added 320 pounds of paving-cement.

The materials above described are heated to about 250 degrees Fahr.—the paving cement in kettles, the sand, stone, etc., in revolving heaters—then thoroughly mixed by machinery, carried to the street, and spread on the binder course to a depth of two inches. While hot and plastic it is rolled with a steam roller, hydraulic cement being dusted over the surface. The rolling is continued until the roller ceases to leave an impression on the surface.

281. Advantages of Coal-tar and Asphalt or Distillate Pavement.

- (1) It is cheap.
- (2) Its surface is more granular and less slippery than asphalt.
- (3) The binder binds the base and wearing surface firmly together and eliminates to a great extent the faults of weather cracks and wave-surfaces.
- (4) It can be laid from curb to curb, as it will not "rot" in the gutters as does the asphalt.
- (5) Pavements constructed of carefully selected and combined materials and properly laid will cost but little, if any, more than the asphalt for maintenance.

282. Defects of Coal-tar and Asphalt Pavement.

- (1) The wearing surface consists of 75 per cent of coal-tar, which material can rarely be obtained of uniform quality.
- (2) The wearing surface, being only $1\frac{1}{4}$ inches thick, requires renewal at frequent intervals.
- (3) The pavement is not so pleasing to the eye as asphalt in color.
- (4) The use of the bituminous base gives rise to many perplexing problems in the grade of the streets on which it is used, due to the fact that the base, the binder, and the wearing surface coalesce so as to form a solid mass. The wear on the surface is never quite uniform; and when the binder or base becomes exposed on the most travelled part of the street, the pavement near the gutter may be worn but slightly. To resurface properly, the remnants of the old surface should be removed, and the new surface laid directly

upon the binder. It is, however, impracticable to strip a coal-tar surface. It may be broken by the pick and bar, but it breaks as readily in the base or binder as at the original line of demarcation. In fact, there is no such line. The practice is to cut out what may be necessary near the curb and put a new surface on the roadway as it stands. The result is to raise the level of the roadway at every resurfacing, or, if the original level at the curb be maintained by the method of cutting out as stated, to increase the crown of the street; but as such pavements will not, as a rule, require resurfacing at more frequent intervals than every fifteen years, and as the surfacing should not raise the level more than one-half inch, the upward growth will not exceed $3\frac{1}{4}$ inches per century.

If the surface is tarred over every year with a brush and sprinkled with sand, the life is lengthened.

283. Asphalt and Coal-tar or Distillate Pavements in Washington, D. C. (Extract from the Report of Capt. E. Griffin, United States Engineers, Assistant to the Engineer Commissioners, for the year ending June 30, 1887.)—During the year 1886–1887 six per cent of the new pavements laid was sheet coal-tar distillate. As this is the first year since the organization of the present form of District government that coal-tar distillate pavements have been laid in the streets of Washington, a few words in this connection will not be inappropriate. Previous to 1878, 745,305 square yards of coal-tar pavements of various kinds were laid at prices ranging from \$1.74 to \$3.70 per square yard. Many of these pavements proved unreliable, either through inherent defects in the materials used or faulty methods of mixing and laying. Some went to pieces in a few years, and others deteriorated so rapidly as to soon place the annual cost of maintenance at excessively high figures. Of the so-called Evans pavement 190,663 square yards were laid, mostly in 1873. When only two years old nearly all these pavements were resurfaced at an average cost of \$1.09 per square yard.

284. As late as 1877 Lieutenant Hoxie estimated twenty cents per yard per annum as the cost of maintaining coal-tar pavements.

285. The average annual expenditure for maintenance of coal-tar pavements for the fifteen years ending June 1, 1886, has been $7\frac{2}{3}$ cents per square yard. Of the Evans pavement, 157,324 square yards were resurfaced by Scharf within two years after being laid, and virtually became Scharf pavements. Considering them as such,

the mean average annual expenditure for maintenance was $5\frac{1}{2}$ cents per square yard. For the first five years the annual average was $3\frac{1}{10}$ cents; for the second five years, 6 cents; for the last five years, $6\frac{4}{10}$ cents.

286. "That a durable coal-tar pavement can be laid is proven by the fact that the 158,595 square yards of vulcanite pavements have only averaged $2\frac{3}{10}$ cents per square yard per annum for fourteen years' maintenance, the average being $\frac{3}{10}$ cents per yard for the first five years, $4\frac{2}{10}$ cents for the second five years, and 4 cents for the last four years.

287. The return to the coal-tar distillate pavements was virtually forced upon the commissioners by the clause in the appropriation act for 1886-7 which "provided" that under this act no contract shall be made for making or repairing concrete or asphalt pavements at a higher price than \$2.00 per square yard for a quality equal to the best laid in the District prior to July 1, 1886, and with same depth of base.

288. No bids were received for asphalt pavements in response to proposals advertised for under this act, so a return to distillate pavements was made.

289. In 1888 bids for a modified asphalt pavement were received, and contracts have been made to lay a large proportion of the streets with it during the present year. This modified asphalt pavement consists of a 4-inch bituminous base, $1\frac{1}{2}$ inch binder course, with a wearing surface of $1\frac{1}{2}$ inches of Trinidad asphalt instead of $1\frac{1}{2}$ inches of coal-tar distillate composition.

290. "Another modification of the standard asphalt pavement was laid in Washington last year. This consists of a base of 4 inches of hydraulic concrete, $1\frac{1}{2}$ inches of bituminous binder, and $1\frac{1}{2}$ inches of asphalt wearing surface-coat. This is in every respect a most excellent pavement, and more of it would be laid, only the contractors refuse to lay it for less than \$2.10 per square yard, and as the law prohibits the payment of more than \$2.00 its use had to be discontinued." (Report of Capt. T. W. Symons, United States Engineers, Assistant to the Engineer Commissioners of the District of Columbia in 1889.)

291. Specifications for Coal-tar Distillate Pavement.—Coal-tar distillate pavement will consist of a base and binder of $4\frac{1}{2}$ inches in depth when compacted, and a wearing surface of $1\frac{1}{2}$ inches in

thickness when compacted. The space over which the pavement is to be laid will be excavated to the depth of 6 inches below the top of the surface of the pavement when completed. Any objectionable or unsuitable material below the bed must be removed and the spaces filled with clean gravel or sand well rammed. The bed will then be trimmed so as to be exactly parallel to the surface of the new pavement when completed, and the entire roadbed will be thoroughly rolled with a heavy steam roller. Upon this foundation will be laid the base and binder, $4\frac{1}{2}$ inches in thickness, in the following manner:

Base.—The base will be composed of clean broken stone that will pass through a 3-inch ring, well rammed and rolled with a steam roller to a depth of 4 inches, and thoroughly coated with No. 1 $\frac{1}{2}$ coal-tar paving-cement in the proportion of about 1 gallon to the square yard of base.

Binder.—The second or binder course will be composed of clean broken stone, thoroughly screened, not exceeding $1\frac{1}{2}$ inches in the largest dimension, and No. 4 coal-tar paving-cement. The stone will be heated to a temperature between 230 and 250 degrees Fahr., by passing through revolving heaters and thoroughly mixed by machinery, with the paving-cement in about the proportion of 1 gallon of No. 4 tar to 1 cubic foot of stone. It will be hauled upon the work, spread upon the base course at least 2 inches thick, and immediately rammed and rolled with hand and steam rollers while in a hot plastic condition.

Wearing Surface.—The wearing surface will be composed of the following materials in the given proportions:

	Per cent.
Clean sharp sand	63 to 68
Broken stone or rock-dust.....	28 to 23
Paving-cement.....	18 to 15
Hydraulic cement.....	0.9
Slaked lime.....	0.15
Flour of sulphur.....	0.1

The sand shall be clean, sharp river sand, free from clay, and of such size that not more than 20 per cent shall be retained upon a sieve of twenty meshes to the inch and not more than five per cent shall pass through a sieve of 70 meshes to the inch, about 60 per cent to be coarser than 40 meshes to the inch. The broken

stone or stone-dust shall be the residue from the crushing of stone from the base and binder which passes a sieve of not more than 6 meshes to the inch.

The paving-cement shall be composed of fine Trinidad asphalt, twenty-five to thirty parts; No. 4 coal-tar paving-cement, seventy-five to seventy parts. The refined asphalt must contain at least 60 per cent of pure bituminous matter, soluble in carbon bisulphide. The No. 4 coal-tar paving-cement must correspond to a standard to be furnished by the engineer, and be free from excess of sooty matter, naphthaline and creosote oils. The hydraulic cement, lime, and sulphur must be of the best commercial quality.

The materials for the wearing surface will be heated to not over 26 degrees Fahr., the paving-cement in kettles, the sand and stone-dust in revolving heaters. To the latter the hydraulic cement, lime, and sulphur will be added cold in the sand-box before going to the mixer. They will be thoroughly mixed by approved machinery, and the mixture carried upon the work, where it will be spread upon the binder course 2 inches thick with hot iron rakes and other suitable appliances, and immediately compacted with hot tamping-irons and hand and steam rollers, while in a hot and plastic state. In spreading the material the joints are to be diagonal to the line of the street. The surface will be finished with a dusting of dry hydraulic cement rolled in. In cool weather or when ordered the carts carrying the mixture are to be protected with canvas covers.

The pavement so constructed must be a solid mass 6 inches thick, and must be thoroughly rolled and cross-rolled until it has become hard and solid. The relative proportions of the component materials will be changed upon the order of the engineer, as occasion shall require.

All materials, as well as the plant and methods of manufacture, will be subject to the inspection and approval of the engineer.

The degree of fineness, both of sand, stone-dust, and powdered limestone, will be determined by testing with screens as follows: The powdered carbonate of lime will be of such degree of fineness that 16 per cent of weight shall be an impalpable powder of limestone, and the whole of it shall pass a No. 26 screen. The sand will be of such size that no more than 50 per cent of it will pass a No. 80 screen, and the whole of it shall pass a No. 20 screen. The broken stone or stone-dust shall be the residue from the crushing of stone

from the base and binder which passes a sieve of not more than 6 meshes to the inch.

Gutters, wherever directed, will be granite-block or brick, of such width as may be directed, laid upon a hydraulic base of not less than 4 inches in thickness, in accordance with the specifications for granite-block pavement or brick gutters.

292. Asphalt Block Pavements.—The manufacture of paving-blocks from crushed stone and asphaltic cement was begun in San Francisco in 1869, but, in consequence of imperfectly prepared materials and crude appliances, the blocks were weak and friable and the results were unsatisfactory; since that time to the present improvements have been made in the processes and machinery, resulting in the production of a tougher and more enduring block, a large amount of which has been laid, particularly in Washington and Baltimore.

Composition.—The blocks are composed of crushed stone and asphaltic cement in the proportion of 87 to 90 per cent of stone and 13 to 10 per cent of cement.

The stone employed is trap, gneiss, limestone, etc.; the stone is broken and partially pulverized under crushers and rollers; the asphaltic cement is prepared from any selected asphaltum (usually Trinidad and California) in the manner described in Art. 96.

The composition of the blocks now used in Washington, D. C., is:

Asphaltic cement.....	13 per cent.
Limestone-dust	10 " "
Crushed gneiss.....	77 " "
<hr/>	
100 per cent.	

(Sand is not used, because it has been found to cut the moulds.)

Manufacture.—The materials are heated to a temperature of 300° F., then thoroughly combined in mechanical mixers. As the mixture leaves the mixing apparatus it passes into a pressing machine very similar to that used for pressing bricks, and is moulded and compressed while hot into blocks measuring 4 × 5 × 12 inches; the blocks are then cooled under water and are ready for use. The blocks weigh from twenty-two and a half to twenty-four pounds each, according to the specific gravity of the

stone employed, and about twenty-six blocks are required per square yard. The dimensions of blocks from different factories vary slightly.

The blocks are laid on the street in close contact, in the same manner as stone paving-blocks, either with or without an artificial foundation; the foundation usually employed is gravel or gravel and sand or sand alone.

293. Advantages and Defects.—The advantages and defects stated under Asphalt Pavement in Articles 221 and 222 are equally applicable to asphalt block pavements. The special advantage which they possess over "Sheet" asphalt is that they can be made at a factory located near the materials, whence they can be transported to the place where they are to be used, and laid by ordinary pavers without the aid of skilled labor; whereas sheet pavements require special machinery and skilled labor in each city where they are laid.

Compared with stone blocks they are much smoother and less noisy, and they form a practically impervious pavement, because under the action of the sun and traffic the asphalt cements the blocks together.

For narrow well-travelled streets they do not make a suitable pavement, but where the traffic is of such a character (such as residence streets where the traffic is light) to warrant their use they make when laid upon a concrete foundation an excellent pavement, smooth, durable, and easily cleaned, healthy and pleasant to the eye.

294. Cost.—The blocks cost about \$60.00 per 1000 or \$1.56 per square yard f. o. b. at the factory.

The cost of construction will vary with the locality, cost of transportation, character of foundation, etc. Table XXXVI shows the extent and cost of construction in some of the principal cities in 1890.

In Washington, D. C., the contract price for 1900 was \$1.77 per square yard.

TABLE XXXVI.

EXTENT AND COST OF ASPHALT-BLOCK PAVEMENTS IN SOME OF THE
PRINCIPAL CITIES OF THE UNITED STATES IN 1890.

Cities.	Extent. Miles.	Cost of Construction per square yard.
Philadelphia, Pa.....	18.80	
Washington, D. C.....	10.10	\$2.00
Camden, N. J.....	5.86	2.00
Chicago, Ill.....	4.11	2.00
Trenton, N. J.....	2.50	2.50
Schenectady, N. Y.....	0.75	

295. Cost of Maintenance.—No statistics are available as to the cost of maintenance. Some of the cities using them report that no repairs have been made in five years, and that, as the traffic is very light, it does not appear likely that repairs will have to be made; others report that no repairs have been made and that the blocks are badly worn. (See also Art. 782, *et seq.*)*

296. Specifications for Laying Compressed-asphalt Blocks.—Upon the soil-bed, previously compacted by rolling and ramming, a layer of bank gravel, screened from all pebbles measuring more than one and one-half ($1\frac{1}{2}$) inches in their largest dimensions, will be laid of such depth as to give five (5) inches in thickness when compacted by rolling and ramming. Upon the gravel will be spread a layer of fine sharp sand two (2) inches in thickness, to serve as a bed for the blocks, which will be laid directly upon and embedded in it with close joints. Special care will be observed to make the surface of the sand exactly parallel to the surface of the pavement when completed. The blocks shall be laid by the pavers standing or kneeling upon the blocks already laid, and not upon the bed of sand.

The blocks shall be laid with their length at right angles to the axis of the street; each course will be formed with blocks of a uniform width and depth. The blocks shall be so laid that all longitudinal joints shall be broken by a lap of at least four (4) inches.

* Cost of maintaining asphalt-block pavements, Baltimore, Md., 1897 :

Cost per square yard: Highest.....	\$0.1633
Lowest.....	0.0018
Average.....	0.0711

Each course of blocks will be driven against the course preceding it by a heavy wooden maul, in order to make the lateral joints as tight as possible. The longitudinal joints will be closed by pressing on a lever inserted at the end of the course adjoining the curb, and keying with a block cut to the required size. When laid, the blocks will be immediately covered with clean, fine sand entirely free from loam or earthy matter, perfectly dry, and screened through a screen having 20 meshes to the inch. The blocks will then be rammed by placing an iron plate, 24 inches by 8 inches, and $\frac{5}{8}$ inch thick, over four blocks, and striking on the plate with a rammer weighing not less than 45 lbs. The ramming will be continued until the blocks reach a firm, unyielding bed and present a uniform surface, with the required grade and crown. Any lack of uniformity in the surface must be corrected by taking up the blocks, increasing the sand bedding, and relaying them. When the ramming is completed, a sufficient amount of fine, dry sand, as above described, will be spread over the surface and swept into the joints.

297. American Bituminous-rock Pavements.—Beds of sand-stone rock impregnated with bitumen are found in many places in the United States, but it is only within the last few years that it has come into use as a paving material. San Francisco, Los Angeles, and other cities now have several miles of this pavement.

298. The rock is quarried, broken into fragments, heated, and while hot taken to the street and compressed by rolling and tamping.

299. The reports concerning the durability of these pavements are conflicting. A claim is made that pavements made of this material 15 years ago and used under heavy traffic have recently been removed and found to have lost very little either in weight or thickness. On the other hand, it is claimed that these pavements are soft; that wheels and horses sink into them quite deeply, but these marks appear to be more or less obliterated by the next passing vehicle.

The granular nature of these pavements renders them less slippery than the ordinary asphalt pavements. They also possess the quality of resisting disintegration by moisture. It is also claimed that these pavements stand equally well the high tem-

perature of the interior cities and the cold, damp atmosphere of the coast.

300. Cost of Construction.—The cost of construction in the West is less than that of the standard asphalt, the average being about \$2.50 per square yard, including a 6-inch concrete base. In the Eastern cities there is but little difference in their cost.

301. Cost of Maintenance.—As none of these pavements has been laid on a large scale for a sufficient length of time, nothing can be said as to the cost of maintaining them.

302. One ton of the bituminous rock will form 10 square yards of pavement 2 inches thick.

303. Specifications for Bituminous-rock Pavements.—The manner of laying the bituminous rock is left to the contractor, except in the following particulars:

The bituminous rock used for the paving must contain not less than 7 nor more than 13 per cent of its weight of bitumen.

The powdered rock shall be prepared at a uniform temperature in suitable boilers.

Ten days before the award of contracts bidders must deposit in the office of the engineer samples of the bituminous rock which they propose to use. Each sample shall bear the bidder's name and the name of the place where obtained. All materials used must conform to the samples so deposited. If other material is wished to be used, samples of them must be deposited and accepted by the engineer.

The asphalt covering, when completed, is to have a thickness of at least 2 inches, everywhere equally firm and compact, and jointing closely to the curb of the sidewalks, gutter-covers, etc., and the surface must in every place conform to the prescribed longitudinal transverse profiles.

Laying the Asphalt.—The asphalt is to be laid in dry weather. Work must not be carried on during rains or snowstorms. Only on the special permission of the engineer may the asphalt be laid on the concrete, which is to be thoroughly cleaned of earth, dirt, and loose substances of all kinds. If the cleaning reveals any soft or injured places in the concrete, they are to be chiselled out and filled with new concrete containing a greater proportion of cement. This is not to be covered over until it has set.

All possible measures must be taken to prevent the cooling of the asphalt powder while being carried to the place where it is

to be laid. While the hot powder is being spread out and before the commencement of the tamping and rolling, the greatest care must be exercised in removing all, even the smallest, foreign bodies, such as stones, paper, wood, straw, leaves, cigar-stumps, etc., and no one shall be allowed to throw such bodies on the work. Moreover, the carts in which the asphalt is to be moved must be carefully cleaned after each use. The engineer has the right to require proofs of their cleanliness, and to require a second cleaning under supervision.

303a. Expansion of Asphalt.—The coefficient of expansion of asphalt paving material has not been definitely determined, but the investigations made so far indicate that it has about the same coefficient as steel, which, according to Kent, is .0000063811.

303b. Repairs to Asphalt Pavements.—The damages which have usually to be repaired in the surface of an asphalt pavement are: cracks, rolls or waves, and disintegration, breaking down or wearing away in patches.

Irregular Cracks.—These are generally attributed to contraction of the asphalt from cold; in some cases they are due to the settlement and cracking of the foundation. They usually start near the gutter, and gradually extend in an irregular course across the street. They are also found radiating from manhole-heads and other street furniture set in the pavement, and sometimes at the junction of a new with an old pavement, and at the joint between one day's work and another. They appear sooner and increase more rapidly on a street with little traffic. (With respect to this peculiarity, Mr. A. W. Dow, Inspector of Asphalts and Cements, Washington, D. C., says: "This appears on first thought paradoxical, but it is simply explained. When the pavement is subjected to a continuous traffic, the asphalt surface, which is more or less plastic at all temperatures, is kept from cracking by the constant kneading, so to speak, produced by the traffic. And again, when an asphalt surface has but little or no traffic, it becomes more porous, owing to the fact that, expanding and contracting from heat and cold without the compression due to traffic, it becomes spongy and, as a consequence, materially weakened. If such cracking occurs at all on a street with a fair amount of traffic, it is evident that the paving mixture used is at fault, either

in not being rich enough in bitumen, or the asphalt cement used was too hard.")

In order to lessen the tendency to crack, and, if possible, confine it within certain limits, expansion-joints have been used in several places. City Engineer Thompson of Peoria, Ill., has provided expansion spaces at intervals of 50 feet. These were made by cutting the asphalt surface (after it had been compacted with a hand-roller), with an ordinary trowel, down to the concrete; the crevice thus formed was filled with dry cement, and the compaction continued with a steam-roller.

The employment of expansion-joints seems to be of doubtful utility. The asphalt mixture being more or less plastic, the space will be closed under the action of the traffic. If the mixture be sufficiently hard to resist the spreading action of the traffic, and thus keep the joint open, its edges will be broken down and the pavement will be speedily disintegrated; they also afford an entrance to water, which, finding its way under the surface material, will quickly rot it; hence they are equally objectionable as the cracks which they are intended to avoid. The tendency to crack may be lessened, and in many cases eliminated, by the use of a cement as soft as is practicable to put into the mixture without having it mark too badly in the hottest weather to which the pavement will be subjected.

Cracks are repaired by first cleaning thoroughly, then filling, by pouring in asphaltic cement.

Rolls or Waves.—This condition may be produced by (a) unequal thickness; (b) sliding towards the gutter under the action of the traffic; (c) creeping in the direction of the heaviest traffic; (d) expansion of the asphalt or the concrete or both; (e) too soft a cement; (f) a defective bond between the base and binder (this occurs when the surface of the concrete is made smooth by bringing an excess of mortar to the surface through too much ramming, or by the use of an inappropriate aggregate); (g) a defective bond between the binder and the wearing surface (a proper union is prevented between binder and wearing surface when the binder contains an excess of cement, or its surface is dirty when the wearing coat is put on); (h) a combination of two or more of the foregoing.

The above causes are due to errors in the preparation of the different parts of the pavement, or defects in its laying, and their occurrence may be prevented by the exercise of proper care.

Disintegration.—This usually occurs in spots, and may be produced by any one or a combination of the following causes: (a) excessive traffic; (b) action of water; (c) unsuitable asphalt; (d) unsuitable flux; (e) Imperfect mixture and improper manipulation; (f) deficiency of asphalt cement; (g) soft spots due to an excess of cement; (h) improper binder; (i) action of illuminating-gas. The damage due to disintegration is repaired by cutting out the surface material down to the base and replacing with new material.

The repairing of an asphalt surface is now generally effected by the "skimming process," in which is used either a heater, such as the "Perkins" (Fig. 267), having a tank for fuel-oil and hooded burners, or an open grate on low wheels, in which coke is burned. Either of these appliances is placed immediately over that part of the pavement to be repaired, and sufficient heat is produced to soften the asphalt so that it can be scraped off to the required depth. To protect the adjoining pavement from injury, the portion to be removed is surrounded with asbestos boards.

It is claimed that by the "skimming process" a perfect union can be secured between the new material and the old pavement. It is not advisable to take this statement as an established fact. In many cases the patches have scaled or peeled off. This may have been due to careless manipulation, presence of moisture, or defective material.

The injury to gutters is usually repaired by cutting out and replacing the surface material and by painting with liquid cement.

303c. Specifications for the Repairs of Asphalt Pavements.

Extent of Repairs.—The repair of wearing surface, binder, and concrete base shall be made to such an extent as is directed by the city engineer.

In every case the defects, such as ruts, cracks, depressions, holes, etc., are to be remedied and repaired. Pavement taken up to give access to sewer-, water-, gas-, or other underground pipes or structures will be included under the head of repairs.

Concrete Base.—When it is necessary to replace the concrete base, the base thus replaced shall be six (6) inches in thickness,

and composed of one part of freshly burned hydraulic ^(Rosendale Portland) cement and two parts of clean, sharp, coarse sand, and five parts of clean broken stone, all by measure.

The material from the old concrete shall not be used in restoring the base.

Earth Foundation.—Should the earth under the concrete to be replaced be soft, spongy, or otherwise deficient in affording a firm foundation, it shall be dug out and replaced with sand, gravel, or broken stone well compacted by ramming.

Binder.—The binder course will be placed on the concrete base, and shall consist of a concrete made of clean broken stone not exceeding one and one-half ($1\frac{1}{2}$) inches in the largest dimension, and asphalt paving-cement (or coal-tar paving composition No. 4). The stone will be heated to the required temperature in revolving heaters, and shall be thoroughly mixed by machinery with the cement in the proportion of one gallon of cement to one cubic foot of stone. The binder will be hauled to the work while hot, carefully spread on the base with hot iron rakes to such a depth that the least thickness for the wearing surface will be $1\frac{1}{2}$ inches when the sum of the wearing surface and binder is not over 2 inches. As this sum increases the thickness of the wearing surface will be increased until it attains a depth of 2 inches. Beyond this the thickness of the binder may be increased when the wearing surface has slid on the concrete. The surface of the latter must be roughened by picks.

Wearing Surface.—Upon the binder the wearing surface shall be laid. This shall consist of the same kind of composition or kind of asphalt as the existing pavement, and laid so as to bring the surface even with the adjoining pavement, making a close, smooth joint therewith, without any cracks, depressions, or elevations. The edges of the old pavement shall be cut so as to form a bevelled joint, and will be painted with hot asphaltum before the new material is laid.

The repairs are to be so made that at the completion of each day's work no holes cut out for repair shall be left unfilled or unfinished. The holes must be perfectly dry before the material is laid, and no material shall be laid during a rain.

Old Material.—All old material, dirt, asphalt, concrete, etc.,

broken up is to be the property of the contractor, and must be removed promptly from the street by him.

303d. Specifications for the Condition of Asphalt Pavements at End of Guarantee Period.—1. The pavement shall not be reduced more than one-fourth ($\frac{1}{4}$) inch from the original thickness at the end of the first five years, nor more than one-half ($\frac{1}{2}$) inch from the original thickness at the end of the first ten years. (This requirement shall not apply to pavements constructed of rock asphalt, as this material does not receive its ultimate compression for a considerable period after being laid.)

2. Places which show a disintegration of the material shall be removed to the binder or concrete foundation, as found necessary, and replaced with new material having the same thickness and conforming to the adjacent pavement.

3. All elevations or depressions three-eighths ($\frac{3}{8}$) of an inch or more above or below the general surface of the street shall be brought to the same elevation as the general surface, these elevations and depressions to be determined by measuring from a straight-edge four (4) feet in length, placed on the surface of the pavement parallel to the line of curbing. (In making such repairs the process known as "skimming" may be employed.)

4. Where elevations or depressions are due to the failure of the concrete foundation from any cause, the asphalt and concrete shall both be removed a length and width to include the entire defect. If the failure is due to buckling of the concrete, the new foundation shall consist of broken stone thoroughly compacted, and of the same thickness as the original concrete. In all other cases a new foundation of concrete shall be placed of the same quality and thickness as the original construction. Upon the foundation shall be placed the pavement, of the same thickness as the adjacent surfaces.

5. Cracks which show any indication of disintegration, or which are three-eighths ($\frac{3}{8}$) of an inch or more in width, shall be cut out to the binder or concrete foundation, as found necessary, a length and width sufficient to include the entire portion affected; this portion to be replaced with new material of the same quality and thickness as shown in the pavement adjacent thereto.

6. Should it be found necessary to replace twenty-five per cent

or more of any section of the street with new material, the entire section shall be resurfaced.

The above specifications are recommended by the Committee on Street Paving of the American Society of Municipal Improvements, with the following comment :

“ Your committee does not consider it possible to give definite specifications for this work that will be applicable to all localities, but after a careful consideration of all the facts obtainable, and after due consideration of the opinions presented, we would recommend that the following [above] clauses, modified as found necessary for each locality, be included in the guarantee contracts of the cities belonging to the association.”

CHAPTER VI.

BRICK PAVEMENTS.

304. BRICK, although one of the oldest materials used for paving, was not employed for this purpose in the United States until about twenty years ago. The first brick pavement laid in the United States was in Charleston, W. Va., in 1872. Since then the use of brick as a paving material has extended over a wide section of country; and in localities with moderate traffic such pavements appear to give satisfaction.

305. The advantages of brick pavements may be stated as follows:

- (1) Ease of traction.
- (2) Good foothold for horses.
- (3) Not disagreeably noisy.
- (4) Yields but little dust and mud.
- (5) Adapted to all grades.
- (6) Easily repaired.
- (7) Easily cleaned.
- (8) But slightly absorbent.
- (9) Pleasing to the eye.
- (10) Expeditionously laid.
- (11) Durable under moderate traffic.

Brick pavements will be found in many localities to be superior to wood or broken stone, and in many cities and towns will be found superior to stone blocks.

306. The Defects of Brick Pavements.—The principal defects of brick pavements arise from lack of uniformity in the quality of the bricks and the liability of incorporating in the pavement bricks of too soft or porous structure, which crumble under the action of traffic or frost.

The employment of unsuitable brick is liable to be fostered by a popular desire to help a local industry without due regard to the

TYPES OF BRICK PAVEMENTS.




FIG. 16.—SECTION OF HALE PAVEMENT.




FIG. 17.—PLAN OF HALE PAVEMENT.



FIG. 18.—SECTION OF BRICK PAVEMENT ON CONCRETE.




FIG. 19.—PLAN SHOWING ARRANGEMENT OF JUNCTION.

quality of the local clays for the manufacture of good paving brick. This circumstance, together with the comparative ease with which contractors who have little experience can bid on this class of work, and the difficulty of rejecting the lowest bid by local authorities, will in many places result in the failure of the brick pavements. If cities, however, in making contracts for brick pavements, will keep these contingencies in mind, and as far as possible exercise discrimination in selecting bricks made especially for this purpose and contractors interested in making these pavements popular, then the development of a great industry may be anticipated.

307. Durability.—Brick has been used for upwards of a hundred years in the Netherlands, and pavements laid half a century ago are still in good condition. There are several brick pavements in the United States from ten to eighteen years old which are still in good condition.

308. The general experience with pavements formed of suitable brick, laid on an unyielding foundation, with the joints filled with bituminous or Portland-cement grout, is that they furnish a smooth and durable surface, well adapted to moderate traffic.

309. Failures of the earlier pavements are frequently reported. These pavements were generally constructed on defective foundations, and with the ordinary building bricks of the locality. Such failures are the result of overhaste in the selection of the material, and poor foundations.

310. The durability of the bricks seems to depend (1) on the clay from which they are made being practically free from lime; (2) on the thorough grinding and mixing of the clay, so as to have no lumps in the bricks; (3) upon the bricks being thoroughly annealed.

311. The brick pavements at The Hague, Holland, are made of a hard-burned brick 8.668 inches by 4.33 inches wide and 2.16 inches thick. They are laid on a sand foundation 7.88 inches deep, with very little clay. Joints are laid as close as possible.

The Hague is a city of residences, and street traffic is very light. Amsterdam is paved almost entirely with brick. The road from Utrecht to Connighem, twenty-seven miles, is paved with brick.

312. Bricks are successfully used in Rotterdam, which is a commercial city. Two classes of brick are used—one made from local clays, and the other a scoria brick, manufactured by the Tees Scoria

Brick Company, of England. The local bricks are preferred for light traffic, and for medium traffic the scoria bricks.

313. Size and Shape of Bricks.—Bricks are passing through an ordeal similar to that through which wood for paving passed many years ago, with practically the same results, viz., that with a proper foundation neither odd shapes, grooves, lugs, nor other devices are necessary or beneficial. Experience shows that the most economical and desirable size for paving bricks is that of the standard building brick. Bricks of this size can be made more cheaply, burned more uniformly, and those which are unsuitable for paving can be utilized for building purposes, which would be impracticable with odd shapes. The imperfect ones of said shapes or peculiar form are so much waste material, and the cost of their manufacture must be added to the price of the good ones in order to protect the manufacturer from loss. Moreover, with irregular sizes and odd shapes it would be necessary for the towns employing brick pavements to keep a large stock of the different bricks on hand to make repairs, which would be expensive and troublesome.*

314. Quality of Bricks.—The qualities essential to a good paving brick are the same as for any other paving material, viz., hardness, toughness, and ability to resist the disintegrating effects of water and frost. As with other materials, porous brick are unfit for paving.

These qualities are not obtained, as is commonly supposed, by vitrifying the bricks: in fact the application of the term vitrified to paving bricks is a misnomer. The process of vitrification is to convert into glass by fusion or the action of heat. Glass is a smooth, impermeable, brittle substance, easily fractured; therefore the edges of bricks that are vitrified or turned into glass will be quickly broken off, and their surface will be slippery. Vitrification adds nothing to the strength; in fact it defeats the object for which the bricks are made.

315. The required qualities are imparted to the brick by a process of annealing. The bricks should be burned just to the point of fusion, then the heat gradually reduced until the kiln is cold. This process will produce a brick thoroughly compact, hard, and

* Cleveland, Philadelphia, and other cities require that the bricks shall have projections of $\frac{1}{4}$ inch on the vertical sides, to insure open joints for receiving the filling material.

tough. If the cooling off is done quickly, it will produce a brittle brick, that will speedily go to pieces under traffic.

316. Foundation.—A solid unyielding foundation is as indispensable with bricks as with any other paving material: the failure of the earlier pavements was due, in many cases, more to defective foundations than to defective material. The use of plank laid on sand is objectionable for the same reasons stated under wood pavements, Articles 185, 186.

317. The foundation in all cases should be formed of cement concrete, the aggregate of which, in localities where stone or gravel are unobtainable, may be of broken bricks.

The usual proportions for the concrete are: hydraulic cement 1 part, clean, sharp sand 2 parts, broken stone 5 parts.

317a. Sand Cushion.—The sand cushion is a layer of sand placed on top of the concrete to form a bed for the brick. Practice regarding the depth of this layer of sand varies considerably. In some cases it is only half an inch deep, varying from this up to three inches. The sand cushion is very desirable, as it not only forms a perfectly true and even surface upon which to place the brick, but it also makes the pavement less hard and rigid than would be the case were the brick laid directly on the concrete.

The sand is spread evenly, sprinkled with water, smoothed and brought to the proper contour by screeds or wooden templets, properly trussed, mounted on wheels or shoes which bear upon the upper surface of the curb. Moving the templet forward levels and forms the sand to a uniform surface and proper shape.

The sand used for the cushion-coat should be clean and free from loam, moderately coarse, and free from pebbles exceeding one-quarter inch in size.

318. Manner of Laying.—The bricks should be laid on edge, as closely and compactly as possible, in straight courses across the street, with the length of the bricks at right angles to the axis of the street. Joints should be broken by at least 3 inches. None but whole bricks should be used except in starting a course or making a closure. To provide for the expansion of the pavement, both longitudinal and transverse expansion-joints are used; the first are formed by placing a board templet seven-eighths of an inch thick against the curb and abutting the brick thereto. The

transverse joints are formed at intervals varying between 25 and 50 feet, by placing a templet or building-lath three-eighths of an inch thick between two or three rows of brick. After the bricks are rammed and ready for grouting, these templates are removed, and the spaces so left are filled with coal-tar pitch or asphaltic paving-cement. The amount of pitch or cement required will vary between one and one and a half pounds per square yard of pavement, depending upon the width of the joints. After 25 or




FIG. 19A.—PLAN OF BRICK PAVING AT STREET INTERSECTIONS. 30 feet of the pavement is laid, every part of it should be rammed with a rammer weighing not less than 50 pounds, and the bricks which sink below the general level should be removed and replaced by a brick of greater depth. After the ramming and rectification Portland-cement grout should be poured into the joints until it appears on the surface ; then the whole surface should be covered with a layer of dry sand one-half inch deep. At street-intersec-

tions the course should be laid meeting at an angle, as shown in Fig. 19 or 19*a*, so that the courses may not run parallel to the traffic.

319. Joint-filling.—The character of the material used in filling the joints between the brick has considerable influence on the success and durability of the pavement. Various materials have been used, as sand, coal-tar pitch, asphalt, mixtures of coal-tar and asphalt, Portland cement, and various patented fillers, as "Murphy's grout," made from ground slag and cement; each material has its advocates, and there is much difference of opinion as to which gives the best results.

The office of a filler is to prevent water from reaching the foundation, and to protect the edges of the brick from spalling under traffic. In order to meet both of these requirements every joint must be filled to the top and remain so, wearing down with the brick. Sand does not meet these requirements, although at first making a good filler, being inexpensive, and reducing the liability of the pavement to be noisy; it soon washes out and leaves the edges of the brick unprotected and consequently much more liable to be chipped. Coal-tar and the mixtures of coal-tar and asphalt have an advantage in rendering the pavement less noisy and in cementing together any breaks that may occur by upheavals from frost or other causes; but unless made very hard they have the disadvantage of becoming very soft in hot weather and flowing to the gutters and low places in the pavement, there forming a black and unsightly scale, leaving the high parts unprotected. The joints thus deprived of their filling become the receptacle of water, mud, and ice in turn, and the edges of the brick are quickly broken down. Some of these mixtures become so brittle in winter that they crack and fly out of the joints under the action of the traffic.

The Murphy grout works well in places, being fairly hard and elastic, but is said to be uneven in its results.

The best results seem to be obtained by using a high grade of Portland cement containing the smallest amount of lime in its composition, the presence of the lime increasing the tendency of the filler to swell with age and the absorption of moisture, causing the pavement to rise or lift away from the foundation, and so producing the roaring or rumbling noise so frequently complained of.

The Portland-cement grout, when uniformly mixed and carefully placed, resists the impact of traffic and wears well with the brick. When a failure occurs the repairs can be quickly made; and if made early, the pavement will be restored to a good condition; but if neglected, the brick soon loosens and the pavement fails.

The Portland-cement filler is prepared by mixing two parts of cement and one part of fine sand with sufficient water to make a thin grout. The most convenient arrangement for preparing and distributing the grout is a water-tight wooden box carried on four wooden wheels about 12 inches in diameter. The box may be about 4 feet wide, 7 feet long, and 12 inches deep, furnished with a gate about 8 inches wide in the rear end. The box should be mounted on the wheels with an inclination, so that the rear end is about 4 inches lower than the front end.

The operation of placing the filler is as follows: The cement and sand are placed in the box and sufficient water is added to make a thin grout. The box is located about 12 feet from the gutter, the end gate opened and about 2 cubic feet of the grout allowed to flow out and run over the top of the brick (care being taken to stir the grout while it is discharging). If the brick are very dry, the entire surface of the pavement should be thoroughly wet with a hose before applying the grout; if not, the absorption of the water from the grout by the bricks will prevent adhesion between the bricks and the cement grout. The grout is swept into the joints by ordinary bass brooms. After about 100 feet in length of the pavement has been covered, the box is returned to the starting-point and the operation is repeated with a grout somewhat thicker than the first. If this second application is not sufficient to fill the joints, the operation is repeated as often as may be necessary to fill them. If the grout has been made too thin or the grade of the street is so great that the grout will not remain long enough in place to set, dry cement may be sprinkled over the joints and swept in. After the joints are completely filled and inspected, allowing three or four hours to intervene, the completed pavement should be covered with sand to a depth of about $\frac{1}{4}$ inch and the roadway barricaded and no traffic allowed on it for at least ten days.

If coarse sand is employed in the grout, it will separate from

the cement during the operation of filling the joints, with the result that many joints will be filled with sand and very little cement, while others will be filled with cement and little or no sand; thus there will be many spots in the pavement in which no bond is formed between the bricks, and under the action of traffic these portions will quickly become defective.

The object of covering the pavement with sand is to prevent the grout from drying or setting too rapidly; hence in dry and windy weather it should be sprinkled from time to time.

The coal-tar filler is best applied by pouring the material from buckets and brooming it into the joints with wire brooms. To effectually fill the joints it must be used only when very hot. To secure this condition a heating-tank on wheels is necessary. It should have a capacity of at least five barrels, and be kept at a uniform temperature all day. One man is necessary to feed the fire and draw the material into the buckets, another to carry the buckets from the heating-tank to a third, who pours the material over the street. The latter starts to pour in the centre of the street, working backward toward the curb, and pouring a strip about two feet in width. A fourth man with a wire broom follows immediately after him, sweeping the surplus material toward the pourer and in the direction of the curb. This method leaves the entire surface of the pavement covered with a thin coating of the pitch, which should be immediately covered with a light coating of sand; the sand becomes imbedded in the pitch. Under the action of the traffic this thin coating is quickly worn away, leaving the surface of the bricks clean and smooth.

320. Cost of Brick Pavements.—The cost of construction of these pavements depends largely upon the facilities for obtaining the requisite material and the character of the foundation.

The cost of a first-class brick pavement per square yard may be estimated as follows:

Excavation	\$.....
$\frac{1}{4}$ th of a cubic yard of concrete.....
$\frac{1}{2}$ th " " " sand.....
72 bricks of standard size.....
Labor laying, etc.....
Freight
24 gallons of asphaltic cement.....
Total.....	\$.....

321. Table XXXVII shows the cost in various localities in the United States.

TABLE XXXVII.

EXTENT AND COST OF BRICK PAVEMENT IN SEVERAL LOCALITIES IN THE UNITED STATES, 1898-99.

	Square Yards.	Cost of Construction.	Guaranty Period. Years.
Akron, O.....	252,267		
Albany, N. Y.....	228,777	\$1.79	5, 7, and 10
Allegheny, Pa.....	260,591	1.26	
Allentown, Pa.....	5,160		
Altoona, Pa.....	13,160	1.60	
Atlanta, Ga.....	28,336	1.85	5 and 10
Auburn, N. Y.....	30,000		
Baltimore, Md.....	14,628	2.50	
Bay City, Mich.....	36,243		
Binghamton, N. Y.....	6,043	{ 1.73 }	5 and 10
Birmingham, Ala.....	3,926	{ 2.40 }	
Boston, Mass.....	6,050		
Buffalo, N. Y.....	107,172	{ 1.87 }	5 and 10
Camden, N. J.....	3,666	2.05	
Canton, O.....	260,480	1.00	1
Chattanooga, Tenn.....	86,764		
Chelsea, Mass.....	44,000		
Chicago, Ill.....	330,000		
Cincinnati, O.....	432,300	1.70	
Cleveland, O.....	800,000	1.12	
Columbus, O.....	1,509,015	{ 1.25 }	5
Covington, Ky.....	11,600	{ 1.00 }	
Dallas, Tex.....	843	1.10	
Davenport, Iowa.....	467,684	1.18	
Dayton, O.....	278,618	{ 1.87 }	5
Des Moines, Iowa.....	1,509,195	{ 1.29 }	5
Detroit, Mich.....	501,750	1.40	5
Dubuque, Iowa.....	118,568	1.25	
Elmira, N. Y.....	46,675	1.34	
Erie, Pa.....	119,796	{ 2.17 }	5 and 7
Evansville, Ind.....	539,798	{ 1.78 }	
Fort Wayne, Ind.....	138,566	1.50	5
Galveston, Tex.....	8,437		
Grand Rapids, Mich.....	62,075	1.50	
Harrisburg, Pa.....	6,413		
Hartford, Conn.....	1,427		

TABLE XXXVII.—*Continued.*

EXTENT AND COST OF BRICK PAVEMENT IN SEVERAL LOCALITIES IN THE UNITED STATES, 1898-99.

	Square Yards.	Cost of Construction.	Guaranty Period. Years.
Holyoke, Mass.....	81,938	\$2.04	
Houston, Tex.....	133,430		
Indianapolis, Ind.....	392,326	{ 1.50 }	9
		{ 2.00 }	
Jersey City, N. J.....	8,800		
Johnstown, Pa.....	143,733		
Joliet, Ill.....	77,775		
Kansas City, Kans.....	220,000		
Kansas City, Mo.....	502,247	{ 1.37 }	5 and 7
		{ 1.50 }	
Knoxville, Tenn.....	96,000		
Lancaster, Pa.....	50,844	1.40	2
Lincoln, Neb.....	338,488		
Little Rock, Ark.....	39,100		
Los Angeles, Cal.....	10,975	2.52	
Louisville, Ky.....	659,733	1.85	
Lowell, Mass.....	2,000	2.10	
Lynn, Mass.....	3,667		
McKeesport, Pa.....	295,730		
Macon, Ga.....	19,180	2.08	
Memphis, Tenn.....	126,432	1.97	
Milwaukee, Wis.....	4,027	1.75	5
Minneapolis, Minn.....	60,198	1.60	10
Mobile, Ala.....	88,000		
Nashville, Tenn.....	24,023	1.78	
Newark, N. J.....	79,411	2.05	
New Haven, Conn.....	35,677	2.33	5
New Orleans, La.....	30,682	2.38	
Newport, Ky.....	81,000	1.52	
New York, N. Y.....	337,920		
Norfolk, Va.....	22,000	1.54	
Omaha, Neb.....	229,124	{ 1.40 }	1 and 10
		{ 1.78 }	
Pawtucket, R. I.....	1,965	2.50	
Peoria, Ill.....	473,194	{ 1.32 }	
		{ 1.45 }	
Philadelphia, Pa.....	1,777,123	1.49	
Pittsburg, Pa.....	10,378		
Portland, Oregon.....	16,405		
Providence, R. I.....	8,096		
Quincy, Ill.....	742,855		
Rochester, N. Y.....	112,180	1.50	
Rockford, Ill.....	45,830	1.33	
Saginaw, Mich.....	81,557	1.35	
St. Joseph, Mo.....	99,428	1.65	
St. Louis, Mo.....	222,605	1.46	1

TABLE XXXVII.—*Continued.*

EXTENT AND COST OF BRICK PAVEMENT IN SEVERAL LOCALITIES IN THE UNITED STATES, 1898-99.

	Square Yards.	Cost of Construction.	Guaranty Period. Years.
St. Paul, Minn.....	14,076	\$1.80	
Savannah, Ga.....	11,808		
Scranton, Pa.....	11,979	1.50	
Seattle, Wash.....	50,480	2.20	
Sioux City, Iowa.....	90,844	1.79	
South Bend, Ind.....	264,618		
Spokane, Wash.....	5,500		
Springfield, Ill.....	407,922	{ 1.05 }	1
Springfield, Mass.....	29,192	{ 1.24 }	
Springfield, Mo.....	93,573	2.25	
Springfield, Ohio.....	115,187	1.80	
Syracuse, N. Y.....	145,040	1.59	
Tacoma, Wash.....	2,000	{ 1.85 }	1 and 5
Terre Haute, Ind.....	92,400	{ 1.91 }	
Toledo, O.....	468,988	1.20	5
Topeka, Kans.....	94,000	1.25	5
Trenton, N. J.....	120,997	1.17	
Troy, N. Y.....	131,000	1.57	
Utica, N. Y.....	1,788	1.81	
Washington, D. C.....	13,903		
Waterbury, Conn.....	9,224		
Wheeling, W. Va.....	308,131	0.74	
Wilkesburre, Pa.....	72,183		
Williamsport, Pa.....	65,684		
Wilmington, Del.....	191,488	1.63	
Worcester, Mass.....	3,675	2.65	3
Youngstown, O.....	60,923		

322. Variety of Systems.—Many patented systems of forming brick pavements have been introduced, differing either in the shape and size of the bricks or in the method of laying them. The following are representative systems:

The Hayden Paving-block (Fig. 196).—The shape and manner of laying these blocks is patented. The blocks are square in plan, with deep hollows underneath to facilitate burning and save material; the top surface is flat, broken by indentations, and the edges of the top are bevelled. The blocks are made in two sizes, the smaller ones 5½ inches deep and 5¾ inches square.

The manner of laying these blocks is as follows: The surface of the street, being brought to the required grade, is covered with 8 inches of broken stone, which is compacted by rolling or ramming; on the broken stone a layer of 2 or 3 inches of sand is spread, on which the blocks are laid. The hollows in the bottom of the

blocks are filled with moist sand, then laid in position, rammed to grade, and the joints filled with hot pitch.




FIG. 19B.

The cost of this pavement is about \$1.92 per square yard.
The clay from which these blocks are made is composed of

Silica.....	76.24 per cent
Alumina.....	16.87 "
Iron.....	.16 "
Lime.....	.50 "
Magnesia.....	trace
Alkalies.....	1.09 "
Water.....	5.14 "

100.00 per cent

323. The Halwood Block.—These blocks are composed of a mixture of mica shale, clay, and sand. The blocks measure $3 \times 4 \times 9$ inches, taking 48 to a square yard. They are laid on a foundation of either 6 inches of concrete or 8 inches of broken stone, joints filled with coal-tar. The cost per square yard, including foundation, is from \$2.50 to \$2.10.

324. The McReynolds Patent Brick.—The patent consists in the bricks having lugs, and in one end of each brick a recess. The claim is that this arrangement permits the joint-filling to flow around the brick, and that these projections act as an obstruction to the cement running during hot weather to the gutter.

325. The Hale Pavement.—Introduced in 1873 is a patent process for laying any brick for paving purposes, the novelty being in the foundation, which consists of 3 inches of sand, on which are laid 1-inch oak boards dipped in coal-tar. The boards are laid either lengthwise or crosswise of the street. On the boards a layer of clean sand from an inch to an inch and a half thick spread, and the bricks laid on edge, "herring-bone" fashion, with the joints filled with tar or sand as may be desired. This costs in West Virginia \$1.35 per square yard, varying of course with the cost of the brick used. A royalty of 10 cents per square yard is charged by the Hale Company for the use of this method (see Figs. 16 and 17).

326. "Charleston Plan."—On the graded surface of the street spread 3 inches of clean coarse sand; on this place 1-inch oak boards dipped in hot coal-tar; on the boards spread a cushion-coat of clean sand $1\frac{1}{2}$ inches deep; on this lay the bricks (common red) on edge, "Herring-bone" fashion; cover the bricks with dry clean sand, and broom well to fill the joints.

327. "Wheeling Plan."—The roadbed is first graded and compacted by rolling with a 5-ton roller, then 3 to 7 inches of coarse gravel and sand is spread and rolled; on this the bricks are laid with their length at right angles to the axis of the street and then brought to a solid bearing by rolling; the joints are filled with sand and coal-tar, and the surface covered with dry sand. Both the common red and special bricks are used.

328. Paving-bricks are made at Kakos near Buda Pesth from carefully selected clay mixed with a little lime. The bricks when moulded are subjected to a pressure of about 3500 pounds per square inch, and then burned nearly to vitrification. The product is regular in form, homogeneous, of uniform density, and of great resistance to wear. According to the experiments of Prof. Ignaz, they have supported without deformation or fissuring a maximum load of over 45,000 pounds per square inch and a mean load of 31,426 pounds per square inch. A square meter (1.196 square yards) of this pavement costs \$3.80. In forming the paving, the soil is

first consolidated and a bed of ordinary brick masonry is laid upon it; the paving-bricks are set in mortar, leaving a joint of $\frac{1}{16}$ of an inch between them to be filled with cement. The dimensions of the bricks are $7.87 \times 7.87 \times 3.9$ inches and they weigh 24 pounds each. It takes 22 bricks to lay 1 square yard of paving. The brick foundation is 6 inches deep. The pavement made with these bricks is easy to clean, does not become slippery, and is pleasant to drive over. The only objection is that it is somewhat noisy in the narrow streets.

329. Iron Bricks, so called, are said to be used satisfactorily for paving in Germany. These bricks are made by mixing equal parts of finely ground red argillaceous slate and finely ground clay, with the addition of 95 per cent iron-ore. The ingredients thus mixed together are then moistened with a solution of 25 per cent of sulphate of iron to which fine iron-ore is added; after this the compound is shaped in a press, dried, dipped once more in a concentrated solution of finely ground iron-ore, and then baked in an oven for about 48 hours in a reducing-flame.

330. Bricks made from blast-furnace slag and scoria have been tried; they are durable, but soon wear slippery and afford little foothold for horses. Ordinary building-bricks saturated with gas-tar have been experimented with in Nashville, Tenn. The results were not satisfactory, and the pieces of experimental paving have been removed.

331. Heads of Specifications for Brick Pavement.

(1) Preparation of roadbed.

(2) Foundation. (Concrete.)

(3) *Quality of the Bricks*.—The bricks shall be manufactured from suitable clay containing not more than one per centum of lime.

They must be burned especially for paving purposes. They shall have a resistance to crushing of not less than 8000 pounds, per square inch on the flat, and must not absorb more than $\frac{1}{16}$ of their weight of water after 48 hours' immersion. They must possess such a degree of toughness that when struck a quick blow with a 4-lb. hand hammer on the edges, the edges shall not spall or chip.

(4) *Size and Shape*.—They shall be of a uniform size of $8\frac{1}{4} \times 4 \times 2\frac{1}{4}$ inches, shall be square on the edges, straight, and free from fire-cracks or checks; when broken, the fracture shall be smooth and

straight, not conchoidal; and the texture shall be uniform throughout and not granular.

(5) *Samples*.—Not less than three bricks of the quality, size, and shape proposed to be used shall be furnished with each proposal, each brick to be labelled with both the bidder's and maker's name and address; these samples shall be deposited in the office of three days before the time of opening the bids. They will be subjected to the required tests, and the characteristics of those deposited by the successful bidder will become the standard by which will be tested all the bricks to be furnished by him, and no deviation from this standard greater than one per cent in any particular will be permitted in the bricks placed in the work.

(6) *Inspection and Culling*.—The bricks will be inspected after they are brought upon the ground, and all bricks which are soft, cracked, checked, overburned, or otherwise defective in quality or dimensions will be rejected and must be immediately removed from the line of the work. The contractor must furnish such laborers as may be necessary to aid the inspector in the examination and the culling of the bricks; and in case the contractor neglect or refuse to furnish said laborers, such laborers as in the opinion of the _____ may be necessary will be employed by said _____, and the expense thus incurred by _____ will be deducted and paid out of any money then due or which may thereafter become due to said contractor under the contract to which these specifications refer.

(7) *Cushion-coat*.—On the concrete foundation a layer of clean, sharp sand, free from loam and pebbles exceeding $\frac{1}{4}$ inch in size, will be evenly spread to the depth of _____ inches. A template shall be used for striking the sand cushion to the exact shape of the crown of the street. This template shall be made in accordance with the plans and directions of the engineer; it shall be kept whole, true to shape, and in good condition; it shall rest on the curbs, and be drawn forward immediately before the bricks are laid. Particular care must be taken that the sand be wet at the time the bricks are laid.

(8) *Laying the Bricks*.—The bricks shall be set on the cushion-coat in close contact with each other, both on sides and ends; they will be laid in parallel courses across the street, with the length of the bricks at right angles to the axis of the street. The bricks of

adjoining courses shall break joints by at least 3 inches. At street-intersections the bricks will be laid on the diagonal, as shown on the plans. . . . Whole bricks only shall be used, except in starting a course or making a closure and in paving around manhole-heads, etc.

The bricks shall be laid by skilled workmen, who shall stand on the bricks already laid, and in no case shall the sand bed in front of the pavement be disturbed or walked on after having been smoothed over and brought to the required crown.

(9) *Ramming*.—The bricks shall be rammed to a solid bearing, with hand-rammers weighing not less than 50 pounds, and all bricks which sink below the general level must be removed and the sand bedding increased until the level is uniform.

As soon as practicable after the ramming and rectification, and not to exceed three days after the bricks are laid, they are to be rolled with a roller weighing not less than three and not more than five tons, the surface of the bricks to be swept clean before the rolling.

(10) *Jointing*.—After the bricks have been satisfactorily rolled, the joints will be filled with (Portland-cement grout made from two parts cement and one part fine, sharp sand) or (paving-cement of straight-run coal-tar pitch of standard quality, such as is ordinarily numbered 6 at the factory).

After the jointing is completed and inspected, the entire surface of the pavement shall be covered with a layer of clean, sharp sand to a depth of about $\frac{1}{2}$ inch and the roadway barricaded and no traffic allowed on it for ten days. At the end of this period the contractor shall thoroughly sweep the street and remove the sweepings.

- (11) Interpretation of specifications.
- (12) Omissions in specifications.
- (13) Engineer defined.
- (14) Contractor defined.
- (15) Notice to contractors, how served.
- (16) Preservation of engineer's marks, etc.
- (17) Dismissal of incompetent persons.
- (18) Quality of materials.
- (19) Samples.
- (20) Inspectors.

- (21) Defective work, responsibility for.
- (22) Measurements.
- (23) Partial payments.
- (24) Commencement of work.
- (25) Time of completion.
- (26) Forfeiture of contract.
- (27) Damages for non-completion.
- (28) Evidence of the payment of claims.
- (29) Protection of persons and property.
- (30) Indemnification for patent claims.
- (31) Indemnity bond.
- (32) Bond for faithful performance of work.
- (33) Power to suspend work.
- (34) Right to construct sewers, etc.
- (35) Loss and damage.
- (36) Old materials, disposal of.
- (37) Cleaning up.
- (38) Personal attention of contractor.
- (39) Payment of workmen.
- (40) Prices.
- (41) Security retained for repairs.
- (42) Payment, when made. Final acceptance.

332. Specifications for Brick Pavements in Memphis, Tenn.—The roadway between curb lines shall be taken down to sub-grade, care being taken not to plough within three inches (3) of the sub-grade stakes, which last shall be carefully removed with pick and shovel, in such manner as to leave a true and perfect surface, which shall be rolled down with a 5-ton roller three times before the concrete foundation is laid. Before the sub-grade foundation is finally fixed, all water and gas pipes must be put in and adjusted; water-pipes must be of lead, double strength, and the gas of the best galvanized pipe; the trenches shall be filled in layers of three inches, and carefully rammed to within six inches of sub-grade and the balance of trench concreted.

Concrete.—Upon the sub-grade thus formed shall be spread the concrete foundation, composed of hard limestone, broken or crushed to pass a two-inch ring,—the same to be free of all dirt, trash, etc.,—clean, sharp sand mixed with fine gravel, and the best fresh Louisville cement, in the following proportions, viz., one

measure of cement and two of sand, thoroughly mixed, and then made into mortar, with the least possible amount of water; into this will be put the macadam, which shall first be well wet, and the whole worked into a concrete in such quantities as will produce a surplus of free mortar when well rammed. This proportion, when ascertained, will be regulated by measure. Each total of concrete will be thoroughly mixed, in suitable boxes, with hoes and shovels, the mortar always to be mixed fresh before being applied to the broken stone. It will then be spread and at once thoroughly compacted by ramming with heavy cast-iron rammers, until free mortar appears on the surface: the whole operation shall be done as expeditiously as possible. The upper surface will be made exactly parallel with the surface of the pavement to be laid, by floating over the surface with cement and the straight edge. The depth of concrete consolidated shall not be less than nine (9) inches. No walking or driving shall be permitted on the concrete when it is setting, and it shall be allowed to set for three (3) days before any pavement is laid on it.

Pavement.—On the concrete foundation thus prepared a bed of clean, sharp sand, free from moisture, two (2) inches deep, shall be laid. The paving bricks to be used shall be such as shall be satisfactory and acceptable to the Engineer, and shall conform strictly to the samples offered by the contractor, and accepted by the Engineer and the Council. The sand must be brought to a true and perfect surface, and made to conform strictly to the grade pegs set by the Engineer, by means of a drag straight-edge, seven (7) feet long, drawn over the surface, and resting on two pieces of scantling $2 \times 4 \times 16$ feet long, having planed surfaces, the top of the sand bed being flush with the grade pegs. Upon this bed of sand the paving bricks are to be laid on edge, at right angles to the line of curbs, in parallel lines, in as close contact as possible on sides and ends; the joints broken one with another, by starting at curb-lines with half-bricks, in alternate rows, so as to break the joints. No half or broken brick shall be laid except at the curb-lines, in order to make closures, but the brick must be laid whole throughout, except as above named.

As the pavement is laid over thirty or more feet at a time, it shall be thoroughly rammed over three times with a flat iron rammer, about one foot in diameter, weighing thirty or forty pounds,

which must be done by lifting and dropping the rammer vertically. When the bricks have been rammed to a solid bearing and brought to a perfect surface, the interstices shall then be thoroughly and completely filled, from bottom to top, with distilled coal-tar pitch (known as No. 6) heated up to 300 degrees. All crevices must be filled, and the entire top surface covered to a depth of not less than one fourth inch, and upon this must be spread one fourth inch of clean, sharp sand, which must be comparatively dry and free from moisture. This sand must be thrown evenly over the boiling pitch as rapidly as the pavement is filled in, and the pitch spread over the surface of pavement, the aim and object being to make the pavement one solid mass, which, when completed, shall be practically a fixture and water-tight. The bricks shall be rigidly inspected before being laid in the pavement, and all objectionable ones removed. The sand and pitch shall be acceptable, and shall also be applied as directed by the Engineer, or his assistant, and to his entire satisfaction and acceptance. The pavement, when completed, must be smooth, and conform to the grades given by the Engineer.

Dimensions of Brick.—Square-edged, to wit: Length, $8\frac{1}{4}$ inches; thickness, $2\frac{1}{4}$ inches; width, 4 inches. Halwood block, patent length, 9 inches; width, 4 inches; thickness, 3 inches.

Bricks thoroughly burned throughout to vitrification.

333. Extracts from Specifications for Laying Brick Pavements in the City of Bloomington, Ill.

Roadbed.—The roadbed shall be carefully graded and shaped to an elevation of at least eleven inches below the established grade line given by the City Engineer, and intended for the surface of the pavement when completed. The City Engineer, or his assistant, shall set all grade stakes, and thereafter the same must be protected and maintained by the contractor and his employees until the services of the same are no longer needed. The contractor shall do all necessary grading and shall provide all earth necessary for filling, and dispose of all surplus excavation by removing the same to the lawns or other dirt streets as the City Engineer may direct. In order to bring the roadbed to the proper shape and grade, a pattern made under the direction of the City Engineer, giving the street proper convexity, shall be continuously used as a guide to the graders. After said roadbed is properly graded and

shaped it shall be thoroughly rolled and compacted by the steam roller, wherever it is practicable to use said roller; and wherever the use of the steam roller is impracticable the foundation shall be compacted either by the use of the smaller roller or by tamping. The roadbed, being properly rolled, shall then be covered with cinders of a uniform depth of at least three inches, and the same shall be rolled and compacted as before; and there shall then be spread a covering of sand of sufficient thickness to grade the surface of said roadbed to a uniform shape, regular and smooth surface for receiving the bottom course of brick. Should any depressions appear during the process of rolling, such as the settlement of sewer branches or otherwise, the same must at once be filled up and again rolled, so that, when the process of rolling shall cease, the entire roadbed shall be uniform and complete in its settlement.

Brick Work.—There shall then be placed a course of brick upon their flat surface, long dimensions parallel with the street, laid as closely together as practicable and all joints broken. Dry sand, screened, will then be spread over the entire course of brick, and well brushed in so as to completely fill all crevices. Sufficient screened sand will then be placed on the bottom course of brick to make a bed of one inch depth upon which to place the top course of brick. The top course of brick will then be laid on their longest two-inch surface across the street, breaking joints and laying the brick as closely together as possible. Nothing less than whole bricks to be used in the top course except where necessary to break joints. The courses of brick in the top course must be kept straight across the street, at right angles to the curbing as near as practicable. Brick that are badly swelled and irregular will not be permitted in the top course. They must constitute a good quality of "paving-brick," maintaining uniformity and regularity in shape to such a degree as will be consistent with a first-class pavement, and render satisfaction to the Engineer in charge. The bottom course of brick must be composed of a good quality of such as are known as "sidewalk brick." The top course of brick, having been laid as above provided, must then be covered with screened sand and rolled with a roller weighing at least two tons. During this final process of rolling the sand must continually be brushed into the pavement so as to effectually fill all crevices. All such work shall be under the supervision and subject to the approval of the Engineer.

334. Specifications for brick pavements differ widely in their requirements. As yet no standard method of construction or of testing the quality of the brick has been arrived at.

A variety of methods of construction are in vogue, and each one has its advocates and opponents. Thus we find in one place a foundation of sand, in another sand and boards, in another gravel, in others broken stone laid in the form of a Telford foundation, in others broken-stone concrete, and so on.

As to the quality of the brick no definite requirements have been determined. In the absence of determined qualities it has of course been impossible to adopt a uniform system of tests, and the majority of tests published are of little value from this want of uniformity.

The specifications relating to the quality of the brick to be used are generally vague; the majority recite that "the brick used shall be hard, free from defects of any kind, manufactured and burned especially for street-paving purposes, be equal in all respects to the sample filed with the proposal, and subject to inspection and acceptance or rejection by the engineer or inspector." This statement of the qualities required defines in reality but very little. The term *hard* is an indefinite one; a hard brick in one locality may be known as a soft one in another. Without a definite statement as to what constitutes defects there may be differences of opinion as to whether or not they exist in a given article, as well as to the *equality* of goods furnished with the sample deposited.

The characteristic qualities and strength of the material are not clearly defined, or in such manner as will enable the bidder to correctly interpret the meaning. The power to accept or reject, although nominally in the hands of the engineer, is indefinite and unsupportable, because the acceptance or rejection cannot be made in accordance with known provisions and fixed rules. In the absence of recognized standards two courses are open in order to secure the desired qualities, avoid indefiniteness and controversy; namely, (1) to reserve the right to make, before awarding the contract, any test that the engineer may see fit to make, and award the contract in accordance with the results of such tests; or (2) prescribe in the specifications the definite tests to which the material will be subjected, with such reservations as to time and place as the exigencies of each particular place seem to demand.

334a. Extract from Paving-brick Specifications.—ST. LOUIS, Mo.—"The bricks shall not be less than eight inches nor more than nine inches long, not less than two and one-half inches nor more than three and one-half inches wide, not less than four inches nor more than four and one-half inches deep, with rounded edges with a radius of three-eighths of an inch. Said brick shall be of the kind known as 'repressed' brick, and shall be repressed to produce a mass free from internal flaws, cracks, or laminations.

"The bricks shall be uniform in size and quality, and thoroughly burned and annealed.

"All bricks so distorted in burning or with such prominent kiln-marks as to produce an uneven pavement shall be rejected.

"Each bidder shall submit one hundred bricks, which shall be subjected to such physical tests as may, in the opinion of the Street Commissioner, be necessary to determine their quality and suitability for the work.

"To secure uniformity in bricks of approved manufacture, delivered for use, the following tests shall be made:

"1. They shall show a modulus of rupture in cross-breaking of not less than twenty-five hundred pounds per square inch.

"2. Specimen bricks shall be placed in the machine known as the "rattler," twenty-eight inches in diameter, making thirty revolutions per minute. The number of revolutions for a standard test shall be eighteen hundred, and if the loss of weight by abrasion or impact during such test shall exceed thirty per cent of the original weight of the bricks tested, then the bricks shall be rejected. An official test to be the average of two of the above tests.

"No bid contemplating the use of rejected brick shall be entertained.

"Samples may be submitted by manufacturers, in which case the bidders proposing to use brick of such manufacture will not be required to submit samples. The quality of the brick furnished must conform to the samples presented by the manufacturers and kept in the office of the Street Commissioner.

"The Street Commissioner reserves the right to reject any and all bricks which, in his opinion, do not conform to the above specifications."

The specifications for vitrified block differ from the above only in the following particulars:

Dimensions.—The blocks shall not be less than nine inches nor more than twelve inches long, not less than three and one-half inches nor more than four and one-half inches wide, not less than five inches nor more than six inches deep.

Rattler Test.—When tested in the rattler, under the above conditions, if the loss exceeds twenty-five per cent of the original weight, then the blocks shall be rejected.

334b. Rumbling in Brick Pavements.—The rumbling is caused by vacant spaces between the brick and the foundation. These spaces may be formed in a number of ways. If the sand bed is carelessly made or not properly compacted, the settlement will leave a space between the bed and the brick; if the rows of brick are keyed up too tightly, they are forced off the sand bed a slight distance, which is sufficient to transmit a rumbling sound; or the same result is obtained if the brick are not rolled sufficiently to force them solidly into the sand bed. Lime in the material used for joint-filler will, by swelling, cause the brick to rise from the foundation.

It is now thought that the tendency to lift may be remedied by introducing at intervals of 25 or 30 feet across the street, and on both sides of the street at the curb, an expansion-joint of pitch, so that any movement of the pavement due to swelling of the filler or to change in temperature will be taken up by the elasticity of the pitch-joints.

334c. Number of Brick and Block Required per Square Yard.

Trade Name.	Number per Yd.	Weight of 1 brick, lbs.
Mack repressed brick.....	60	6.88
Mack (Lug) repressed brick.....	58	7.06
Corning repressed brick.....	60	6.40
Johnsonburg repressed brick.....	63	6.81
Preston repressed brick.....	62	6.04
McMahon-Porter repressed brick....	56	7.07
Park repressed brick.....	59	6.81
Park (wire-cut) brick.....	58	6.35
Metropolitan (repressed) block.....	42	9.98
Nelsonville repressed block.....	42	9.50
Mack (Lug) repressed block.....	44	9.11

Trade Name.	Number per Yd.	Weight of 1 brick, lbs.
Townsend repressed block.....	46	8.60
Athens repressed block.....	42	9.50
Harris repressed block.....	43	9.00
Bollivar repressed block.....	44	8.25
Guise repressed block.....	46	9.25
Park repressed block.....	40	9.80
Eastern repressed block.....	46	9.25
McMahon-Porter repressed block.....	43	9.14
Clearfield repressed block.....	48	8.20
Clearfield (wire-cut) block.....	47	8.56

334d. Brick Paving for Country Roads.—Brick is being successfully used for paving country roads, both as a substitute for broken stone and in localities where good stone is not obtainable, and also in combination with broken stone. The first experiment with brick for this purpose was made at Monmouth, Ill., where a strip of pavement 3000 feet long and 7 feet wide was constructed, at a cost of \$2650. The method of construction was as follows: The earth road-bed was graded and formed to the proper contour. The curbing to hold the brick in place was made of 2 × 6-inch oak plank set 7 feet apart, and held in place by oak stakes 18 inches long, driven 4 feet apart; in the space inclosed by the curbs a sand bed 5 inches thick was formed and shaped to the required contour; on this was placed a single course of No. 1 paving-brick set on edge, and the joints were filled with sand. Outside the curbing broken stone was placed for a width of 2 feet, thus making the width of the improvement 11 feet. The earth road on each side of the paved strip was graded and formed to afford trackways for use in dry weather. The total width of the road being 40 feet.

The use of brick for the construction of trackways has been suggested by *Engineering News*. The advantages of such trackways would be the same as stated in Art. 439 under Stone Trackways.

The details of construction, such as the foundation, under the bricks, the construction of the broken-stone pavement at their sides and between them, the material for filling the joints between the bricks, drainage, etc., will have to vary with local circumstances. The method of construction adopted must make provision against the tilting of the brick under loads crossing them, and

also against their displacement by frost. To provide against the first, a rough stone curb may be used, as shown in Fig. 19c. If




FIG. 19C.—CROSS-SECTION MACADAM ROAD WITH BRICK TRACKWAY.

stone is not available, brick set on edge, artificial stone, or fire-clay curbing may be used.

Where provision has to be made for drainage, the construction may be as shown in Fig. 19d.



FIG. 19D.—CROSS-SECTION BRICK TRACKWAY UNDERDRAINED.

The ditch above the drain-tile may be filled with any coarse materials—field-stone or quarry-spalls too soft or gravel too large for road-covering—or with lumps of burnt clay. The filling to be thoroughly compacted by ramming. The space between the brick strips and outside them to be covered with gravel, and the joints between the bricks filled with sand.

334e. Average Price of Paving-brick per Thousand in 1898.

State.	Price.	State.	Price.
New Jersey.....	\$14.00	Massachusetts.....	\$9.00
Washington.....	12.78	Illinois.....	8.88
Connecticut and Rhode Island.....	12.58	Pennsylvania.....	8.70
Maryland.....	12.00	West Virginia.....	8.69
Alabama.....	11.50	Arkansas.....	8.40
New York.....	10.99	Iowa.....	8.20
Michigan.....	10.76	Nebraska.....	8.09
Virginia.....	10.00	District of Columbia.....	8.02
Wisconsin.....	10.00	Georgia.....	8.02
North Carolina.....	9.98	Montana.....	8.00
Missouri.....	9.42	Kansas.....	7.24
Indiana.....	9.38	Tennessee.....	7.11
Texas.....	9.38	Ohio.....	6.92
Colorado.....	9.11	Utah.....	5.45
Kentucky.....	9.00	Average for United States	\$8.48
In 1897 the general average was.....			\$8.22

CHAPTER VII.

BROKEN-STONE PAVEMENTS.

335. As near as can be ascertained, the first broken-stone pavements were constructed in France in 1764 by one M. Tresaguet, who built many miles of such pavements in the latter part of the last century. In the early part of the present century two systems were introduced into England, the first by Telford, the second by Macadam.

336. The name of Telford is associated with a rough stone foundation, which he did not always use, but which closely resembled that which had been previously used in France. Macadam disregarded this foundation, contending that the subsoil, however bad, would carry any weight if made dry by drainage and kept dry by an impervious covering. The names of both have ever since been associated with the class of road which each favored, as well as with roads on which all their precepts have been disregarded.

337. The following specifications show the difference in the methods of the inventors.

338. Tresaguet's Method, 1764 (Fig. 21).—"The bottom of the foundation is to be parallel to the surface of the road. The first bed or foundation is to be placed on edge and not on the flat, in the form of a rough pavement, and consolidated by beating with a large hammer; but it is unnecessary that the stones should be even one with the other. The second bed is to be equally placed by hand, layer by layer, and beaten and broken coarsely with a large hammer, so that the stones may wedge together and no empty spaces remain. The last bed, three inches in thickness, is to be broken to about the size of a nut with a small hammer, on a sort of anvil, and thrown upon the road without a shovel to form the curved surface. Great attention must be given to choose the hardest stone for the last bed, even if one is obliged to go to more

distant quarries than those which furnish the stone for the body of the road. The solidity of the road depending on this latter bed, one cannot be too scrupulous as to the quality of the materials which are to be used for it."



Fig. 20. FRENCH. PREVIOUS TO 1775.



Fig. 21. TRESAGUET.



Fig. 22. TELFORD.




Fig. 23. MACADAM.

339. Telford's Method, 1824 (Fig. 22).—"Upon the level bed prepared for the road materials a bottom course or layer of stones is to be set by hand in the form of a close firm pavement. The stones set in the middle of the road are to be seven inches in depth; at nine feet from the centre, five inches; at twelve feet

from the centre, four inches; and at fifteen feet from the centre, three inches. They are to be set on their broadest edges lengthwise across the road, and the breadth of the upper edge is not to exceed four inches in any case. All the irregularities of the upper part of the said pavement are to be broken off by the hammer, and all the interstices to be filled with stone chips firmly wedged or packed by hand with a light hammer, so that when the whole pavement is finished there shall be a convexity of four inches in the breadth of fifteen feet from the centre.

"The middle eighteen feet of pavement is to be coated with hard stones to the depth of six inches. Four of these six inches to be first put on and worked in by carriages and horses; care being taken to rake in the ruts until the surface becomes firm and consolidated, after which the remaining two inches are to be put on.

"The whole of this stone is to be broken into pieces, as nearly cubical as possible, so that the largest piece in its largest dimensions may pass through a ring of two and one half inches inside diameter.

"The paved spaces on each side of the middle eighteen feet are to be coated with broken stones or well-cleaned gravel up to the footpath or other boundary of the road, so as to make the whole convexity of the road six inches from the centre to the sides of it, and the whole of the materials are to be covered with a binding of an inch and a half of good gravel free from clay or earth."

340. Macadam's Method (Fig. 23).—Macadam omitted the foundation of large stones, claiming that it was not only useless but injurious; he placed on the natural soil a layer of stone broken equally into cubes of about one and a half inches in their greatest dimensions, and spread equally over the surface of the road to a depth of ten or twelve inches. Binding material was not used, the stone being left to work in and unite by its own angles under the traffic. Macadam preferred the test of weight to that of measurement, and insisted that no stone should weigh more than six ounces, which is the weight of a cube of one and a half inches of hard compact limestone; his overseers were provided with small scales and a six-ounce weight to test the larger stones.

Although Macadam was the pioneer of good road construction in England, and from whose name the word *macadamized* is derived; it may be observed that he had been anticipated in the pro-

mulgation of the system of a regularly-broken stone covering by Mr. Edgeworth, an Irish proprietor, whose treatise on roads, of which the second edition was published in 1817, contains the results of his experiments on the construction of roads, with some useful rules. He advocated the breaking of the stones to a small size, and their equal distribution over the surface. He also recommended that the interstices should be filled with small gravel or sharp sand—a practice which, though condemned by Macadam, is now adopted by the best roadmakers.*

341. Since Telford and Macadam's time the practice of road-making has been greatly improved by the introduction of rollers and stone-crushing machinery.

342. Modern Telford.—On the natural-soil bed, properly graded, a layer of stones eight inches thick is set by hand, arranged and wedged as described by Telford. On the stone foundation so prepared a layer of broken stone of a size not exceeding three inches is evenly spread and rolled; the surface so rolled is covered with a layer of sand one-half inch thick, and the rolling continued; then a layer of stones not larger in any dimension than two inches is spread to a depth of four inches and rolled, followed as before with a layer of sand and also rolled. Finally a coating of clean sharp sand is applied, well watered, and the rolling continued until the surface becomes smooth. The surplus sand is then swept off and removed.

343. Modern Macadam pavements are constructed in the manner above described, only omitting the stone foundation, and the depth of the stone varies from four to twelve inches.

344. Defects of the Telford System.—(1) No matter how carefully the interstices between the foundation-stones are filled with chips, a large percentage of voids is left giving free access to water, thus defeating the object of the covering, which is to preserve the natural soil from contact with water. The pavement acts as a drain; the natural soil becomes saturated with water, and a slow but constant sinking of the bottom stone into the sub-soil and a slow but gradual rising of the natural soil takes place,

* Rennie also brought into use, eight or ten years before Macadam, the system of broken-stone road construction in connection with the formation of the road-surface upon many of the bridges built by him, notably the bridge commenced in 1809, afterwards known as Waterloo Bridge, where upon a compacted clay foundation a layer of fine gravel was rolled in to receive a coating of flints broken to the size of an egg.

the cohesion of the superstructure is destroyed, and it finally becomes a mass of mud and stones.

(2) If the foundation be of a harder rock than the covering, it becomes an anvil on which the softer stones are pounded to pieces by the passing loads.

(3) The stone foundation unnecessarily increases the cost of construction. The roads of Central Park, N. Y., are excellent examples of the Telford system. They are of indefinite thickness, reposing on a bed of thoroughly drained earth; they were constructed and are maintained at a cost that is prohibitory to an extensive use of such pavements.

345. Defects of the Macadam System.—The broken stone laid as directed by Macadam cannot be impervious, because the interstices compose one half of the bulk of loosely spread stones, and no amount of rolling will reduce the voids more than one fourth; and as nature abhors a vacuum, the subsoil when moistened will rise up and fill the vacant space, and the weight of the traffic will force the lower stones down until the whole becomes a mass of mud and stones, as shown by the following analysis of a portion of the crust of the macadamized roads in the Mall, St. James Park, London:

ANALYSIS OF MACADAMIZED ROAD CRUST.

Mud.....	11.00	cu. ft. or	41.00	per cent
Sand with pebbles not exceeding $\frac{1}{8}$ of an inch...	2.40	" "	9	"
Stones from $\frac{1}{8}$ to $\frac{1}{2}$ inch.....	6.56	" "	24	"
" " $\frac{1}{2}$ to 1 inch.....	4.48	" "	16 $\frac{1}{2}$	"
" " 1 to 2 $\frac{1}{2}$ inches.....	2.56	" "	9 $\frac{1}{2}$	"

Total volume.....27.00 cu. ft. or 100.00 per cent

From this analysis it appears that less than 9 $\frac{1}{2}$ per cent, say one tenth of the original stone, escaped underground, whilst 40 per cent of it was reduced to the state of mud.

346. Advantages of Broken-stone Pavements.

- (1) Good foothold.
- (2) Reasonably easy traction when in good condition.
- (3) Moderate first cost.
- (4) Comparatively noiseless.

347. Defects Common to all Broken-stone Pavements.

- (1) Mud when wet.

- (2) Dust when dry.
- (3) Excessive cost of maintenance under heavy traffic.
- (4) Impossibility of keeping them clean.

348. The foregoing defects condemn the use of broken stone for city streets, yet when properly built and maintained broken stone forms the pleasantest, safest, and most economical road-surface known for city suburbs and country highways.

Ideally perfect broken-stone road construction has never been attained, and never will be until our road constructors abandon obsolete precedents and construct road-coverings that will be adapted to the requirements of the traffic and impervious to water and frost.

349. Essentials Requisite to Successful Construction.—The essentials requisite to the successful construction of broken-stone pavements may be summed up as follows:

- (1) The entire removal from the roadbed of all vegetable or perishable matter.
- (2) The removal of the natural soil to such depth as may be determined by its character, and by the thickness of the intended covering.
- (3) Sub-surface drainage wherever required.
- (4) The thorough compacting of the natural-soil bed.
- (5) The employment of sand or gravel for the foundation.
- (6) The employment of the best materials afforded by the locality.
- (7) The employment of unscreened stones.
- (8) The complete exclusion of clay or loam from the broken stone.
- (9) The employment of sand or gravel for binding, in sufficient quantity to fill the voids.
- (10) The thorough compacting of the broken stone with a roller of competent weight and suitable form.

350. Erroneous Methods of Construction.—Broken-stone pavements can be made very unsatisfactory and defective by:

- (1) A permeable foundation.
- (2) By the use of excessively hard stones which no amount of rolling will consolidate.
- (3) By the use of improper binding material, such as loam and clay.

(4) By an undue proportion of soft among hard stones. A small quantity (about one fourth) of soft stones judiciously mixed with the harder will be an undoubted advantage.

(5) By employing stones of too large a size.

(6) By screening the broken stone, thus removing the chips and dust which otherwise would assist in filling the voids. Screening should not be practised, except when an injurious amount of clay or loam has become mixed with the stone.

(7) By assorting the stone and laying it in layers according to the size of the stone. The practice of forming a road with strata of screened stone assorted in different sizes and growing smaller and smaller towards the top is erroneous; the smaller stone will find its way to the bottom, and the larger stone will work to the surface and ruts will be quickly formed. It will be porous, and no matter how heavily rolled it will be continually crumbling.

(8) By covering the surface of the compacted stone with a layer of stone-dust.

(9) By the use of an excessive quantity of binding material.

(10) By the use of an excessive quantity of water when rolling.

351. Quality of the Stones.—The materials used for broken-stone pavements must of necessity vary very much according to the locality. Owing to the cost of haulage, local stone must generally be used especially if the traffic be only moderate. If, however, the traffic is heavy, it will sometimes be found better and more economical to obtain a superior material, even at a higher cost, than the local stone; and in cases where the traffic is very great, the best material that can be obtained is the most economical.

352. The qualities required in a good road stone are hardness and toughness and ability to resist the disintegrating action of the weather. These qualities are seldom found together in the same stone. Igneous and silicious rocks, although frequently hard and tough, do not consolidate so well nor so quickly as limestone, owing to the sandy detritus formed by the two first having no cohesion, whilst the limestone has a detritus which acts like mortar in binding the stones together.

353. A stone of good binding nature will frequently wear much better than one without although it is not so hard. A limestone road well made and of good cross-section will be more impervious to wet than any other, owing to this cause, and will not disintegrate

so soon in dry weather, owing partly to this and partly to the well-known quality which all limestone has of absorbing moisture from the atmosphere. Mere hardness without toughness is not of much use, as a stone may be very hard but so brittle as to be crushed to powder under a heavy load, when a stone not so hard but having a greater degree of toughness will be uninjured.

By a stone of good binding quality is meant one that, when moistened by water and subjected to the pressure of loaded wheels or rollers, will bind or cement together. This quality is possessed to a greater or less extent by nearly all rocks when in a state of disintegration. The binding is caused by the action of water upon the chemical constituents of the stone contained in the detritus produced by crushing the stone, and by the friction of the fragments on each other while being compacted; its strength varies with the different species of rock, but it exists in some measure with them all, being greatest with limestone and least with gneiss.

The essential condition of the stone to produce this binding effect is that it be sound. No decayed stone retains the property of binding, though in some few cases, where the material contains iron oxides, it may, by the cementing property of the oxide, undergo a certain binding.

The first attempt to ascertain the cementing property of rocks was made by the Massachusetts Highway Commission. The method followed is described in Art. 356a.

These tests show in general that quartzites, sandstones, granites, gneisses, and marble possess very little cementing power, some of them breaking down with two or three blows; whereas limestones and some trap-rocks show a high power of cementation and stand thirty or forty blows before giving way. Other trap-rocks have not proved so good.

354. *The durability of stones used for roads depends partly upon resistance to chemical decomposition and partly upon resistance to mechanical abrasion. The former character is influenced mainly by the chemical composition of the constituent materials, while the latter depends upon the manner in which and the material by which these component minerals are aggregated into a compact mass. To know thoroughly the qualifications of any rock as a road-stone, therefore, involves an intimate knowledge of both*

its mineralogical composition and its structure. Some of the apparently hard and durable rocks, such as certain granites and basalts, which remain comparatively unaltered when in the solid crust of the earth and removed from the disintegrating influence of air and water, when broken up and exposed to the chemical influences prevailing on the surface of a road rapidly decompose into clayey mud. Other rocks, such as many of the sandstones, are chemically almost indestructible, but are so loosely aggregated together that under the action of traffic they crumble into powder. As regards the structure, its character is influenced by the size of the grains (within certain limits the coarser the grain the weaker the crushing-strength of the stone), the orientation of the crystals, and the nature of the base or matrix in which these crystals are imbedded. Many of the crystalline rocks are merely an aggregate of crystal grains wedged together into a tight-fitting mosaic. The breaking down or decomposition of one of the component minerals seriously diminishes the cohesion of such rocks. In other cases there is much more intimate union of the crystals, which are interlocked in such a manner that the cohesion is increased. In others the crystalline particles are firmly set in a more or less compact siliceous paste or cement of considerable hardness and durability, and forming a continuous matrix, which would hold together even if the crystals themselves decayed. As regards the mineralogical constituents, a vast difference exists in the chemical durability of different minerals. Feldspar, which forms a considerable proportion of the composition of the great majority of rocks used for roads, occurs in many different varieties, some of which—the potash feldspars—are much more durable than those which contain a large proportion of soda or lime. With regard to the durability of minerals a distinction must be drawn between chemical disintegration or decomposition and alteration. Many minerals are liable to alteration without any loss of cohesive power. In some cases there is often a distinct gain in the chemical durability of such altered minerals. Among minerals of this kind may be mentioned the ferro-magnesian silicates, which readily alter into serpentinous products of great stability. The mere presence, therefore, of an unstable element in a rock is not necessarily of itself unfavorable, unless the result of its alteration is such that disinte-

gration ensues, as when feldspar breaks down into a powdery clay. Hardness, though important when combined with other qualities, is singly not of great consequence. Quartz, the hardest of the common minerals, used alone does not make a desirable road-stone, as its dust is lacking in cementing power; it has a low specific gravity and is very brittle. Brittleness promotes crumbling under the impact of traffic. Soft rocks, as limestones and slates, are quickly ground to powder and are rapidly carried away by water and wind action.

The most efficient road-stones are obtained from the class of rocks called traps, or dike-stones, and technically known as diabases and diorites. These rocks are not uniformly desirable, but nearly all of them are better than the best of other rocks. The normal composition of the diabase rocks is feldspar and pyroxene, with or without black mica. The diorites may be considered as the same rock with the mineral hornblende replacing the pyroxene. The structure of these rocks is such that the minerals composing them are interlocked with one another in the most perfect manner, thus producing great toughness. To the effect of this structure must be added the uniform toughness of the individual minerals pyroxene and hornblende. The feldspars present in the diabases and diorites are essentially aluminosilicates of calcium and sodium, and they form one of the unstable compounds, under the influences of their environment, on which depends so largely the rapid disintegration of these rocks. When these rocks are fresh, little loss from this cause is to be apprehended during the life of the road; but where the weathered portion of the rock, the sap, is used, the loss sustained by chemical and mechanical means is considerable. The alteration of feldspar to clay, quartz, and calcite in many cases so weakens the coherency of the rocks that they readily crumble to powder under pressure and are converted into fine sand. The calcite derived from the alteration of the feldspar, when deposited from solution during dry periods, acts to a limited extent as a binding material, tending to strengthen the rock-dust and increase its attachment to the broken stone. The experiments of the Massachusetts Highway Commission shows that the maximum cementing value of powdered rock was obtained from an olivine diabase which was much weathered. Some diabases carry a considerable percent-

age of black mica, which, owing to its tabular form and the readiness with which it cleaves into thin plates, is quickly and easily transported by the winds. The essential mineral pyroxene and the occasional mineral pyrite in diabases, and the hornblende in diorite, are also prone to decomposition, a change which is aided by the presence of acids.

The granite rocks are undesirable for use as road-stones. Many of them contain more or less of the soda and lime-bearing feldspars, in addition to the potash variety, and their durability is in consequence adversely affected. No granite can be found whose feldspar is free from some secondary alteration to clay, and when this change has gone on to a degree sufficiently great to affect the strength of the stone it should be discarded as unfit for broken-stone roads. Granites in this condition quickly crumble to sand and clay, and the winds sweep away the fine material in dry weather, while in rainy times the road is in a muddy state. There are several kinds of mica present in granite rocks. Of these muscovite or white potash mica is much more durable than the black ferro-magnesian mica, biotite. This circumstance is proved by the fact that white mica is a much more frequent constituent of the sedimentary sands and clays derived from the breaking up of granite rocks than is biotite or black mica. The mica is very easily transported both by wind and water action, owing to its tabular character, and this mineral under all circumstances is undesirable in road-stone. Other constituents of granite, such as pyrites and iron oxides, are also notably unstable. A true granite is composed of quartz, orthoclase, feldspar, and two micas—biotite and muscovite. The micas are not always present, their place being wholly or in part taken by hornblende or pyroxene. When a granite is free from mica it offers great resistance to wear, but its brittleness and its granular structure operate to increase the rate of abrasion. Granite differs from the trap-rocks not only in mineral composition, but also in an entire difference in the form and arrangement of the constituent minerals; in the granites the structure is granular, with little tendency toward an interlocking arrangement. The brittleness of granite is due principally to the quartz, one of the hardest as well as most brittle minerals of common occurrence. When the necessities of the case force the use of

granite rocks it is well to select those, such as syenites or granites, containing as small a percentage of mica and quartz as possible. Syenite if badly weathered is considered even more objectionable than granite. Although granite and syenite contain a great amount of feldspar, the cementing value of these rocks is much less than that possessed by the diabases and diorites.

Gneiss and mica schists are either too soft or too brittle to withstand the action of traffic. The micaceous element causes the stones to break up and grind away quickly. The hornblende schists, although rather soft and easily ground up, have considerable toughness, and in the absence of better material will make tolerable roads.

Limestone rocks, though they vary considerably in hardness, are in general much too soft for economical use in road-making, provided any other more suitable material can be obtained. The variety of such stone which is known as dolomite commonly affords a better rock than calcite, or ordinary limestone. Where the lime is commingled with clay the effect is generally to improve its value as a road material; where the mixture is of sand and the mass is an arenaceous limestone, it is generally poor road-stone. Where the surface of a limestone road can be covered with iron ore the firmness of the mass is much increased.

Crystalline limestone or marble is unsuitable, for, while the material binds well together, it is brittle, and consequently quickly passes into a condition of dust under the action of the traffic. Its granular or crystalline structure has a very pronounced tendency to break up into rhombic grains, a tendency which serves further to increase the weakness of the stone. The white powdery dust produced is very offensive. The limestones suffer a considerable loss from the ready solubility of the calcite in rain-water and water impregnated with acids. Rain-water charged with carbonic acid will dissolve when cold one part of lime carbonate in 10,800 parts of water. In the magnesian or dolomitic limestones the loss from this cause is somewhat less, but still important. The carboniferous and transition limestones are fairly durable and make smooth and pleasant roads for light traffic and pleasure-drives.

Quartz, when it is found, as is sometimes the case, in large veins in which it has been deposited from water at depths below

the original surface, often affords a tolerable material for macadam purposes. Owing to the very angular forms which the material assumes when crushed, it mats well together. The bits, however, are not really cemented into a mass, for the dust, unlike that from most other rocks, does not form a binding cement. Moreover, under the pressure of wheels and the beating of horses' feet, the material passes rapidly into the state of fine sand, which is blown or washed away. Roads of this material rarely attain a very smooth state, and they wear out rapidly.

Quartzites are rocks which were originally sandstone the fragments of which have to a greater or less extent been dissolved and recemented into a firm mass. The nature of quartzites varies greatly. They are generally hard, but brittle, and break up rapidly under the action of traffic, forming a fine sand much like powdered glass. The smooth surface of the fragments prevents their forming a bond. Mixed with limestone they form fair roads.

Chert consists of quartzose material which has been segregated in beds of limestone rock. When the limestone decays and is washed away, the cherty matter is often left in a rubble-like mass. In many cases the material verges into quartzite and is indistinguishable from it. The cherty residuum arising from the decay of limestone is of value in road-making in the southern portion of the Appalachians and in other portions of this country beyond the glaciated field, and also in some of the States of the Northwest.

Field-stone and river-stone have been much used in some districts of England; they generally make a rough road, as they are composed of the hardest parts of those stones which have resisted the action of the weather, and are, though frequently very hard, of unequal hardness, so that they wear very irregularly.

From the results obtained on experimental paving-strips and in the laboratory the following conclusions have been deduced as to the relative wearing value of different rocks:

One cubic yard of basalt having a resistance to crushing of 24,040 pounds per square inch is equal to—

	Pounds per square inch.
1.10 cubic yards of basalt with a crushing strength of	21,015
1.34 " " " " " " " "	19,200
1.70 " " " " " " " "	16,780

				Pounds per square inch.
3.00	cubic	yards	of coral limestone with a crushing strength of.....	11,750
3.80	"	"	" coral limestone with a crushing strength of	10,810
5.80	"	"	" Triassic with a crushing strength of	9,670
7 to 8	"	"	" sandstone " " " "	8,390
9 to 11	"	"	" cretaceous " " " "	7,260

355. Coefficients of quality for various road materials have been obtained by the engineers of the French "Administration des Ponts et Chaussées." The quality was assumed to be in inverse proportion to the quantity consumed on a length of road with the same traffic, and measurements were systematically made of the traffic and wear to arrive at correct results, these processes requiring great care and considerable time. Direct experiments on resistance to crushing and to abrasion and collision were made on 673 samples of road materials of all kinds. The coefficients obtained by these experiments were found to agree fairly well with those arrived at by actual observation of the wear in the roads, and are summarized in Table XXXVIII. The coefficient 20 is equivalent to "excellent," 10 to "sufficiently good," and 5 to "bad."

356. The experiments were conducted as follows: The apparatus employed to determine the resistance to wear consisted of cylindrical boxes of iron about 8 inches in diameter and 13 inches long, mounted on an axle revolving horizontally, and so cranked as to hold the axes of the boxes at an angle of 30 degrees with the axis of revolution. In each box was placed 5 kilograms of the broken materials to be tested, carefully cleansed from dust by washing, and the boxes put in motion at a rate of 2000 revolutions per hour. The stones rolled against one another, and were thrown from one end of the box to the other at each revolution. After 5 hours or 10,000 revolutions the boxes were opened, the detritus resulting from the rubbing and collision was carefully collected and sorted, and the weight of all of less diameter than $\frac{1}{8}$ inch, compared with that of the original samples, gave the degree of wear. It was found that the best materials seldom gave less than 20 grams of detritus per kilogram, and the coefficient of 20 was therefore, adopted,

for materials having that proportion of wear. For other materials the coefficient was deriyed from the proportion

Grams of detritus : 20 :: 20 : coefficient.

Resistance to crushing was determined by means of an hydraulic press. Experience having shown that cubes of the hardest materials rarely resisted more than 3000 kilograms per square centimeter (equal to about 19 tons per square inch) the coefficient of 20 was given to materials presenting that degree of resistance, and other coefficients were derived from the proportion

3000 : crushing weight per square centimeter :: 20 : coefficient.

In the experiments every precaution to insure accurate results was taken. When the materials were already rounded, as pebbles, they did not wear much in the machine, and obtained a coefficient far above their value; and there were anomalies with a few other materials, such as chalk flints with a softer coating, and stones with cavities. The size to which the stones were broken did not seem to have much influence on the wear.

TABLE XXXVIII.
COEFFICIENTS OF QUALITY.

Materials.	Coefficient of Wear.	Coefficient of Crushing.
Basalt.....	12.5 to 24.2	12.1 to 16
Porphyry.....	14.1 " 22.9	8.3 " 16.8
Gneiss.....	10.3 " 19.0	13.4 " 14.8
Granite.....	7.3 " 18.0	7.7 " 15.8
Syenite.....	11.6 " 12.7	12.4 " 13.0
Slag.....	14.5 " 15.3	7.2 " 11.1
Quartzite.....	13.8 " 30.0	12.3 " 21.6
Quartzose sandstone.....	14.3 " 26.2	9.9 " 16.6
Quartz.....	12.9 " 17.8	12.3 " 13.2
Silex.....	9.8 " 21.3	14.2 " 17.6
Chalk flints.....	3.5 " 16.8	17.8 " 25.5
Limestone.....	6.6 " 15.7	6.5 " 13.5

356a. Abrasion and Cementation Tests of Stone.—The report of the Massachusetts Highway Commission for 1896 describes in detail the methods employed at the Lawrence Scientific School of Harvard University for testing the qualities of road-building stone.

In making the tests the aim has been to determine the nature of the qualities which constitute fitness or unfitness of the different rocks used for road-making, the effects of diverse methods of treatment used in the process of construction, and the relative value of the bed-rocks and gravels which are found in different parts of the State.

The machines used were designed by Prof. L. W. Page. The abrasion-machine was modelled after the Deval machine used by the French engineers for determining the relative value of the stone used in the construction and maintenance of the national highways of France.

The machine employed for the abrasion tests consists of four cylinders, each 7.9 inches in diameter and 13.4 inches deep, fastened to a shaft so that the axis of each makes an angle of 30 degrees with the axis of rotation. Each cylinder is closed at one end and has a tightly fitting cover at the other. At one end of the shaft is a pulley by which the cylinders are revolved, and at the other end is a revolution-counter. Four tests can be carried on at the same time.

The stone to be tested is broken into pieces, between $2\frac{1}{2}$ inches and $1\frac{1}{2}$ inches in diameter, and carefully washed to remove any foreign matter. In a test 5 kilograms (11.15 pounds) of stone are placed in a cylinder, the cover is bolted on, and the cylinder is rotated at the rate of 2000 revolutions per hour for five hours. At each revolution of the shaft the fragments of stone are thrown twice from one end of the cylinder to the other, grinding them against each other and against the sides of the cylinder. At the end of five hours the machine is stopped, the cylinder opened, and the contents are emptied into a sieve having $\frac{1}{8}$ -inch meshes. The material passing through the sieve is put aside for the cementation test. The sieve and the stone remaining in it are thoroughly washed, and the cylinder is washed to remove the dust that adheres to it. The washed stones are thoroughly dried and weighed, the decrease giving the weight of the detritus worn off by the test. The percentage of the detritus is rarely less than 20 grams per kilogram of stone used (2%); therefore 20 has been adopted as the standard, and the coefficient of quality is obtained by the following formula:

$$q = 20 \times \frac{20}{u} = \frac{400}{u}, u = \text{per cent},$$

in which u represents the weight in grams (15.43 grains) of detritus per kilogram (2.23 lbs.) of stone.

After several tests had been made in the manner above described, it was recognized that the very important property or cementing value of the stone was not investigated. The commission, recognizing this deficiency, accordingly directed its attention to devising some means of supplying it. As no previous attempt had been made in this direction, the commission had to invent its own method, which is as follows:

The stone-dust to be tested is obtained either from the detritus of the abrasion test or by specially reducing the stone. The dust is prepared by passing it through an automatic screen, which consists of a cylinder (39.37 inches long by 4 inches in diameter) of brass wire netting of five different meshes: 100 meshes per inch at one end and decreasing by 20 meshes each time to 20 meshes per inch at the other end, the smallest size being at the end where the dust enters. The screened dust is mixed with distilled water and placed in a circular metal die; a closely fitting plug is then inserted on top of the wet dust, and a pressure of 1422 pounds per square inch is applied. The compressed briquette, circular in section, 0.98 inch in diameter, and of the same height, is removed from the die and laid aside for two weeks, so that it may become thoroughly dry.

The weight of the dust varies with the density and compressibility of the stone, but generally about 0.9 ounce, and 0.24 cubic inch of distilled water is required to make a briquette of the above dimensions.

The dried briquettes are tested by impact in a specially devised machine, which consists of a hammer, weighing 2.2 pounds, arranged like the hammer of a pile-driver. It is raised by a screw, and dropped automatically from any desired height, falling on a plunger which rests on the briquette. The plunger is held in two guides, and attached to it is a lever pivoted at $\frac{1}{4}$ of its length from the plunger, and carries a pencil at its free end. The pencil has a vertical parallel movement five times as great as that of the plunger,

and its movement is registered on a drum against which the pencil presses. The drum rotates through a small angle at each stroke of the hammer; thus an automatic diagram is taken on the behavior of the briquette throughout the whole test. The standard fall of the hammer for a test is 0.39 inch, and the blow is repeated until the bond of cementation of the material is destroyed. The final blow is easily ascertained, for when the hammer falls on the plunger, if the material beneath it can withstand the blow, the plunger rebounds; if not, the plunger stays at the point to which it is driven. The number of blows needed to break the bond is taken as representing the binding power of each stone, and is so used in comparing this property in road materials.

As the surface of a broken-stone road is constantly abraded and recemented, it was considered desirable to determine the recementing properties of the stone tested. Briquettes differing from those described above only in that they were of constant weight instead of constant height were made and tested in the manner described above, and then were remade and retested.

The table on page 264 contains some of the results of these tests.

356b. Coefficients of wear and cementing quality of the rocks of Maryland have been obtained by the Highway Division of the Maryland Geological Survey by the same methods described in Art. 356a, and are as follows:

	Coefficient of Wear.	Cementation Test.
Trap-rocks.....	5.7-26.1	1- 10
Serpentine.....	5.8-21.2	10-300
Granitic and quartzitic.....	2.6-16.3	1- 13
Limestones.....	4.8-16.8	1- 73
Sandstones.....	5. -13.	0- 28

The figures signify:

Wear.	Cementation.	
1- 7	1- 4.....	bad.
7-13	4-10.....	fair.
13-17	10-20.....	good.
17-	20-	excellent.

TABLE SHOWING SPECIFIC DENSITIES, COEFFICIENTS, CEMENTING VALUES, AND RECENTING VALUES OF STONES TESTED.

Name of Stone.	City or Town.	1 Specific Density.	2 Coefficient of Wear.	3* Cementing Value.	4† Cementing Value of 30-gram Briquette.	5‡ Recenting Value of 30-gram Briquette.
<i>Massachusetts Rocks.</i>						
Diorase	Lynn, Essex Co., Mass.	3.03	20.37	56	29
Feistite	Boston, Suffolk Co., Mass.	16.06	23	109	31
Horoblende granite ..	Duxbury, Plymouth ..	2.68	13.46
"	Waltham, Middlesex Co., Mass.	2.63	12.16	16
Gneiss	Lee, Berkshire Co., Mass.	11.43	23
Limestone	Pittsfield, Berkshire Co., Mass.	2.82	9.38	15
Quartzite	Diamond Hill, Cumberland, R. I.	9.07	9
Marble	Lee, Berkshire Co., Mass.	2.74	2.85
<i>New York Rocks.</i>						
Diabase, Bouker	Guttenberg, N. J.	30.40
"	Rockland Lake, N. Y.	17.79
Norite	Cortland, Westchester Co.	7.46
Granite D. Donovan ..	Round Island, Rockland Co.	23.02
Silicious sandstone ..	Lockport, Niagara Co.	17.48
Sandstone	Duanesburg, Schenectady Co.	10.58
Limestone	Howes Cave, Schoharie Co.	9.64
"	Tomkins Cove, Rockland Co.	6.81

* Number of blows required to strain the briquette to their elastic limit.

† Number of blows required to strain the 30-gram briquettes prepared for the recenting test.

‡ The number of blows that the recenting briquettes stood before reaching their elastic limit.

§ From the Report of the Mass. Highway Com. 1896. ¶ Tests made for the New York State Museum by the Mass. High. Com.

357. Size of Stones.—The stones should be broken into fragments as nearly cubical as possible. The size of the cubes will depend upon the character of the rock. If it be granite or trap, they should not exceed $1\frac{1}{2}$ inches in their greatest dimensions; if limestone, they should not exceed 2 inches.

358. The smaller the stones the less the percentage of voids. Small stones compact sooner, require less binding, and make a smoother surface than large ones, but the size of the stone for any particular section of a road must be determined to a certain extent by the amount of traffic which it will have to bear and the character of the rock used.

359. It is not necessary nor is it advisable that the stones should be all of the same size; they may be of all sizes under the maximum. In this condition the smaller stones fill the voids between the larger and less binding is required.




FIG. 24.—SIZE AND SHAPE OF STONE FOR BROKEN-STONE PAVEMENTS.

The proper shape of broken stone is shown in Fig. 24.

360. Breaking the Stone.—Breaking stone for the purpose of using it as a road-covering was until quite recently always effected by hand; now by the use of machinery it is more quickly and cheaply broken.

361. Hand-broken stone still finds favor with European engineers; they claim that it is better broken and has sharper angles than that broken by crushing: and in many districts the occupation affords employment for persons who otherwise would be thrown upon the public for support.

362. In breaking stone by hand the breaker sits and strikes the stone with a small cast-steel chisel-faced hammer, weighing about one pound, fixed at the end of a long, straight-grained but flexible ash stick. The breaker also has another hammer, weighing about five pounds, with which he reduces the size of the large stones before breaking them into proper size. Each breaker is furnished with a gauge-ring through which the stones must pass in every direction.

363. The great cost of hand-broken stone led to the employment of machine crushers; their use effected a reduction in the cost of from 50 to 200 per cent, and increased the amount of daily output from 1 to 50.

364. The objections to machine-broken stone are principally:

- (1) Want of uniformity in the size of stones.
- (2) The stone is frequently flaky with rounded edges, which is a very disadvantageous form for compacting.
- (3) Very tough stones have frequently to be passed several times through the machine before they get properly broken.
- (4) Very soft stones are crushed to powder.

365. Cost of Breaking Stone.—The cost of breaking stone by hand will vary considerably in different localities on account of the character of the stones to be broken and the value of labor.

366. The average amount of stone broken by a good stone-breaker is given by Mr. Codrington in his work on the Maintenance of Macadamized Roads as follows: Hard silicious stones and igneous rocks, 1 to 1½ cubic yards per day; granite, ½ cubic yard per day; river gravel, field-stones, or flints, 3 to 4 cubic yards per day.

367. The cost of a stone-crushing plant and expense of operating may be taken as follows:

Cost of crusher, engine, and boiler set up, complete.....	\$2500.00
Cost of operating:	
1 engineman and fireman	\$3.00
2 laborers feeding	3.50
2 tons of coal.....	8.00
Oil, waste, etc.....	2.00
Repairs.....	10.00—\$26.50

The product will vary with the toughness of the stone to be broken and the size of the machine.

368. The wear and tear of a stone-crusher is very considerable; it has been known to reach as high as 62.5 per cent of the first cost of the machine in one year.

369. To make a stone-breaking machine pay, it is necessary—

(1) To give it nearly constant work.

(2) To exercise care in feeding, to give a sufficient supply without allowing an undue quantity of stone to pass in at one time.

(3) That the machine shall be so located as to reduce to the minimum the expense of handling both the unbroken and the broken stone.

The dimensions and capacity of several crushers are given in Chap. XXIII.

370. It is impossible to estimate the cost of getting the unbroken stone to the crusher and the broken stone back to the road, for that depends entirely upon the distance which must be traversed in cartage and the condition of the grounds over which the loads are hauled. If the loads have to be hauled a considerable distance to or from the crusher, or if heavy grades have to be ascended or rough ground traversed, the time occupied in hauling each load will be increased and less can be hauled in a day, thus lessening the work done by horses and drivers for each day's wages.

Where stone is to be obtained in more than one place along the line of the projected road, it is sometimes more economical to take the crusher to the stone than to have to haul the broken stone a great distance. For this purpose the crusher can be mounted on wheels and the steam roller used to haul and drive the crusher, without the expense of a fixed plant for crushing stone.

371. Cost of Quarrying and Crushing Stone.—The report of the Board of Street Commissioners of the city of Hartford, Conn., for the year 1890 contains the following table of the cost of quarrying and crushing stone for the past ten years.

The increase in the cost of quarrying and crushing stone during the past year is in part chargeable to the extra cost of hauling the stone to the crushers, on account of the added distance at which the stone was procured, also in part by the expense connected with the opening of new quarries.

372. Voids in the Broken Stone.—The voids of broken stone in which the size and shape of the pieces are nearly uniform are about one half the mass. If the pieces are not uniform, the voids are about four tenths of the mass. The voids in gravel vary, but average about one half of the mass. The greatest amount of rolling will not reduce the voids more than one half of the primitive bulk.

TABLE XXXIX.
COST OF QUARRYING AND CRUSHING STONE.

Year.	Cost of Quarrying per cubic yard.	Cost of Crushing per cubic yard.	Cost of Carting to Breaker per cubic yard.	Total Cost of Crushed Stone at the Quarry per cubic yard.	Average Cost Delivered on the Streets per cubic yard.
1881.....	.655 ct.	.586 ct.	.288 ct.	\$1.47	\$1.70
1882.....	.781 ct.	.848 ct.	.287 ct.	1.36	1.87
1883.....	.688 ct.	.265 ct.	.247 ct.	1.15	1.59
1884.....	.665 ct.	.872 ct.	.228 ct.	1.26	1.70
1885.....	.658 ct.	.842 ct.	.224 ct.	1.28	1.66
1886.....	.590 ct.	.289 ct.	.288 ct.	1.12	1.65
1887.....	.595 ct.	.845 ct.	.281 ct.	1.22	1.64
1888.....	.658 ct.	.231 ct.	.288 ct.	1.17	1.68
1889.....	.694 ct.	.819 ct.	.268 ct.	1.28	1.69
1890.....	.889 ct.	.407 ct.	.801 ct.	1.597	2.045

A well-rolled road-covering contains from 70 to 80 per cent of stone.

373. Determination of the Voids in Broken Stone.—The proportion of voids may be determined by experiment in either of the following ways: (1) Determine the specific gravity of the material, and from that the weight of a unit of volume of the solid. Weigh a unit of volume of the loose material. The difference between the weights divided by the first gives the proportion of the voids. (2) Wet the loose material thoroughly, fill a vessel of known capacity with it, and then pour in all the water the vessel will contain. Measure the volume of water required and divide this by the volume of the vessel; the quotient represents the proportion of voids.

The smaller the stone is broken the less the percentage of voids and the heavier a cubic yard will weigh.

374. Weight of Broken Stone.—To ascertain the weight of a cubic yard of broken stone, multiply the weight of a cubic yard of the given stone by the proportion of voids (usually 0.50); the result will be the weight of a cubic yard of the stone when broken.

375. Area covered by One Cubic Yard of Broken Stone.—A cubic yard of ordinary broken stone will, when properly spread, cover an area of about 32 square yards of surface of a roadway.

Since a cubic yard of loose broken stone contains only one half

of its volume, or $13\frac{1}{2}$ cubic feet of solid stone, its weight, allowing 12 cubic feet of solid granite to one ton, is approximately

$$1 \times \frac{13.5}{12.0} = 1\frac{1}{8} \text{ ton.}$$

Again, one cubic yard is equivalent to 36 square yards 1 inch deep; and 1 ton of stone laid without compression to a depth of 1 inch covers an area of $36 \times \frac{1}{1\frac{1}{8}} = 32$ square yards. When the stone is laid and rolled the primitive volume is reduced by about one fourth; and 1 ton of rolled stone laid to a depth of one inch covers an area one fourth less than 32, or $32 \times \frac{3}{4} = 24$ square yards.

376. To Find the Area that can be covered by One Ton of Stone, when the Thickness of the Layer is given.—Divide 32 by the thickness of the layer in inches if unrolled; or divide 24 by the thickness of the layer in inches when rolled. The quotient is the area in square yards.

377. To Find the Area that can be covered by One Cubic Yard of Broken Stone, when the Thickness of the Layer is given.—When the stone is not rolled, divide 36 by the thickness in inches; the quotient is the number of square yards that can be covered. When the stone is rolled, divide 27 by the final thickness in inches; the quotient is the number of square yards.

378. Thickness of the Broken Stone.—The offices of the stone are to endure friction and shed water; its thickness must therefore be regulated by the quality of the material and the amount of the traffic, and not by any consideration as to its own independent power of bearing weight. Macadam considered 10 inches as sufficient for any traffic on any substratum; experience has proved this true in the well-drained and well-kept roads of Europe.

379. The proper rule is to vary the thickness according to the traffic and the grade. Roads of sharp descent do not require as thick covering as those having flat grades.

Mr. J. Owen, County Engineer of Essex County, N. J., adopted the following thicknesses with good results:

For grades flatter than $1\frac{1}{2}\%$	10 inches
“ “ between $1\frac{1}{2}\%$ and $4\frac{1}{2}\%$	8 “
“ “ over $4\frac{1}{2}\%$	6 “

The roads of Bridgeport, Conn. (upwards of 50 miles), built under the direction of Mr. B. D. Pierce, are, with the exception of two short pieces, only 4 inches thick. These roads are subjected to a regular traffic of loads averaging 6000 pounds each; they give entire satisfaction to the public using them, and an ordinary team hauls a net load of 3000 pounds over them.

380. Many roads of 4 and 6 inches thickness have been built that have not proved satisfactory. Their failure is generally attributed to their thinness. This is erroneous; the fault does not always lie in the thinness of the stone covering, but in the method of construction followed. The thin roads that fail are as a rule made by throwing the broken stone on an undrained and unrolled earth roadway, frequently without even removing the mud which covers its surface. In some few cases the stones are rolled with a horse roller, but in the majority the stone is left to be consolidated by the traffic. If roads are to be built in this manner, they must be massive; but no matter how massive they be made, they will have no cohesive strength, they will never be impervious to the mud from below or the rain from above, and will always be unsatisfactory.

380a. The Massachusetts Highway Commission has estimated that non-porous soils drained of ground water will support in their worst condition a load of about 4 pounds per square inch, and the thickness of the broken stone is adjusted to the traffic on this basis. If a division of the load in pounds at any one point by the square of twice the depth of the stone gives a quotient of 4 or less, then the road foundation will be safe at all seasons of the year. On sand or gravel the commission believes that 20 pounds per square inch may be safely placed. Acting on this theory the thickness of stone on State roads varies from 4 to 16 inches; the smallest thickness being placed over good gravel or sand and the greatest over heavy clay. Where the surfacing exceeds 6 inches in depth, the excess may be broken stone, gravel, or ledge stone, the choice depending entirely on the cost, for all are equally effective.

380b. Foundation.—The preparation of the natural soil over which the road is to be constructed to enable it to sustain the superstructure and the weights brought upon it requires the observance of certain precautions the neglect of which will sooner or later result in the deterioration or possible destruction of the road covering. These precautions vary with the character of the soil.

Soils of a siliceous and calcareous nature do not present any great difficulty, as their porous nature generally affords good natural drainage which secures a dry foundation. Their surface, however, requires to be compacted; this is effected by rolling. The rolling should be carried out in dry weather, and any depressions caused by the passage of the roller should be made good with the same class of material as the surrounding soil. The rolling must be repeated until a uniform and solid bed is obtained.

The argillaceous and allied soils, owing to their retentive nature, are very unstable under the action of water and frost, and in their natural condition afford a poor foundation. The preparation of such soils is effected by drainage and by the application of a layer of suitable material to entirely separate the surface from the road material. This material may be sand, furnace ashes, or other material of a similar nature spread in a layer from 3 to 6 inches thick over the surface of the natural soil.

When the road is formed in rock cuttings it is advisable to spread a layer of sand or other material of light nature, so as to fill up the irregularities of the surface as well as to form a cushion for the road materials to rest on.

381. Sand Core for Broken-stone Pavement.—On a well-drained foundation a sand or gravel core will be found as mechanically serviceable as the most costly stone foundation. Such a core covered with a layer of stone measuring when compacted 4 inches thick will form a finer and more lasting surface than a greater thickness of stone laid upon the earth soil and compacted. Telford was aware of this fact; he was willing to prevent by almost any means available the coming in contact of his road material with the earth subsoil, and suggested gravel, sand, or chalk as alternatives to bottoming stones. A requisite, whatever the medium, was that "this bottoming should be made perfectly firm and regular, so as to receive the top workable metal of equal thickness." Thus, although he always advised a paved bottom when it could be had, many miles of roadway were made under Telford's direction without the paved bottom with which his name is associated.

382. The quantity of broken stone required per mile of road for different widths and thicknesses is given in Table XL.

383. Spreading the Stone.—The stone should be hauled upon the roadbed in broad-tired two-wheeled carts and dumped in heaps,

TABLE XL.
NUMBER OF CUBIC YARDS OF BROKEN STONE REQUIRED PER MILE OF ROAD.

Depth of Stone in Inches.	Width of Pavement in Feet.							
	8	16	24	30	32	40	48	60
4	645	1,290	1,935	2,421	2,580	3,225	3,870	4,842
6	968	1,935	2,903	3,632	3,872	4,840	5,808	7,264
8	1,290	2,580	3,870	4,842	5,160	6,450	7,740	9,684
10	1,613	3,225	4,838	6,053	6,452	8,065	9,678	12,106
12	1,935	3,870	5,805	7,263	7,740	9,675	11,610	14,526
14	2,258	4,515	6,773	8,474	9,032	11,290	13,548	16,948
16	2,580	5,160	7,740	9,684	10,320	12,900	15,480	19,368

and be spread evenly with a rake in a layer of as nearly uniform thickness as may be.

384. Thickness of the Layers.—The thickness of the layers will depend upon the final thickness of the covering. If the finished thickness is to be 6 inches, each layer should be of a depth of $4\frac{1}{2}$ inches.

385. Macadam insisted that the stone should not be laid in shovelfuls but scattered over the surface, one shovelful following another and spreading over considerable space. His object in this was to avoid an accumulation of soft stones at one spot, for the rocks from which the stone was obtained were not of uniform hardness, but of all qualities gathered from adjoining fields. The application of this method to stone of uniform quality would be detrimental and have the same effect as screening.

386. Binding.—One half of the volume of loosely spread broken stone is space, and no amount of rolling will reduce it more than one half; therefore to thoroughly consolidate the broken stone some fine material must be added. It may consist of the fragments and detritus obtained in crushing the stone. When this is insufficient, as will be the case with the harder rocks, the deficiency may be made up of clean sand or gravel. The proportion of binder should slightly exceed the voids in the aggregate; it must not be mixed with the stones, but should be spread uniformly in small quantities over the surface and rolled into the interstices with the aid of water and brooms.

387. It is a useless refinement to screen the broken stone; it should be placed in the road as it comes from the breakers, care being taken to prevent the admixture of clay or loam, the presence of which in large quantities is extremely injurious. When present to an injurious extent, the stone must be screened.

388. By using a large quantity of binding material mixed with the stones the amount of rolling is lessened, but at the expense of durability. If there is an excess of binding material in the joints of the stones, the first heavy rain washes it out and the surface of the roadway quickly goes to pieces.

389. The French engineers use clay, sand, or earth from the road excavation when such is suitable, in the proportion of one fourth to one sixteenth of the bulk of the stone. They apply it after the steam roller has been once over the broken stones.

389a. As the quality of the binding used is of vital importance, the employment of inferior material, such as road scrapings or material of a clayey nature, should be avoided, even if the initial cost of the work should be greater when a good binding material is used.

Stone consolidated with improper binding material may present a good appearance immediately after being rolled and be otherwise an apparently good piece of work, still in damp weather a considerable amount of "licking up" by the wheels of the vehicles will take place, which reduces the strength of the coating and causes the surface to wear unequally.

By the application of an immoderate quantity of binding of any description the stone coating will become unsound or rotten in condition, and if the binding be of an argillaceous nature, will expand during frost owing to its absorbent properties, and cause the displacement of the stones. The surface will become sticky, which seriously affects the tractive power of horses, while the road itself will suffer by the irregular deterioration of the surface.

The use of such material for binding as mentioned enables rolling to be accomplished in much less time than when proper binding is used, and the cost of consolidating the stone may be reduced by 25 per cent; but on the other hand the stone coating, which will probably contain under these circumstances from 30 to 40 per cent of soft and soluble material, and possibly present a smooth surface immediately after being rolled, will quickly become "cupped"

by the wheel traffic, a bumpy surface being the result. This is caused by the irregular wear, while the lasting qualities or "life" of the coating will be shortened, giving unsatisfactory results to those travelling over the road, and the work of renewing the surface of the road in this manner may prove a failure on economical grounds. There can be no doubt, and it is now being more generally recognized, that sand as a material for binding in connection with rolling operations, when applied in a limited but sufficient quantity, promotes the durability of the stone coating, while the general results are equally satisfactory; a firm, compact, and smooth surface is obtained, and the subsequent maintenance of the road is minimized.

A great amount of rolling is necessary when sand is employed as a binding material, but economy is promoted, and the results are more satisfactory when sand is used than by the use of a material which gives to the stone an appearance only of having been properly consolidated.

If clean sand be used in combination with the screenings from the crusher a very sound and satisfactory road surface will be obtained.

It should always be remembered that the best road is made, other things being equal, with the least amount of binding consistent with cohesion; provided the crust of the road is properly formed transversely and of sufficient strength, a smooth, even-wearing surface and an economically maintainable road will be the result.

If the use of motor vehicles equipped with pneumatic tires becomes general, it is possible that some other description of binding material will be necessary. The pumping action or suction created by pneumatic tires, especially when propelled at a high speed, causes a considerable movement of the fine particles of the binding material, which on being displaced will convert the covering into a mass of loose stones. This objection can probably be overcome by watering. This will cause an additional expenditure for maintenance, but the cost of sprinkling will be infinitesimal compared with the saving effected in the other items of maintenance, the surface wear of the roads will be greatly decreased and the sanitary condition will be much improved.

389b. Clay Binder on Sand Subgrade.—Some years ago an interesting experimental road was built in Truro, near the extreme

end of Cape Cod, and has proved a success. The soil here is loose sand with practically no surface loam. The drainage is perfect. There is not much snow or frost during winters, and the traffic is light and small in volume. The loose sand subgrade was shaped to the desired cross-section, and on this was spread a natural mixture of 1 part of sand to 2 parts of clay; this layer was 2 inches deep. Over it was spread a 3-inch layer of stone broken to sizes ranging from $\frac{1}{2}$ to $1\frac{1}{2}$ inches. This broken stone was covered with a 1-inch layer of clay and a long-toothed spike harrow was dragged back and forth until the clay and broken stone were well mixed. The entire surface was finally watered and rolled with a 2-ton horse roller, and since its completion an occasional sprinkling of sand to prevent the clay from becoming muddy is all the work that has been needed to keep the road reasonably smooth and free from loose stone.

390. Necessity of Binding Material.—With reference to the necessity of binding material, the following facts are interesting.

Mr. Wm. H. Grant, Superintending Engineer of the New York Central Park, in his report upon the park roads, says:

“At the commencement of the macadam roads, the experiment was tried of rolling and compacting the stone by a strict adherence to Macadam's theory, that of carefully excluding all dirt and foreign material from the stones, and trusting to the action of the roller and the travel of teams to accomplish the work of consolidation. The bottom layer of stone was sufficiently compacted in this way to form and retain, under the action of the rollers (after the compression had reached its practical limit), an even and regular surface; but the top layer, with the use of the heavy roller loaded to its greatest capacity, it was found impracticable to solidify and reduce to such a surface as would prevent the stones from loosening and being displaced by the action of wagon-wheels and horses' feet. No amount of rolling was sufficient to produce a thorough binding upon the stones, or to cause a mechanical union and adjustment of their sides and angles together as to enable them mutually to assist each other in resisting displacement. The rolling was persisted in with the roller adjusted to different weights up to the maximum load (12 tons), until it was apparent that the opposite effect from that intended was being produced. The stones became rounded by the excessive attrition they were subjected to, their more angular parts wearing away, and the weaker and smaller ones being crushed.

"The experiment was not pushed beyond this point. It was conclusively shown that broken stones of the ordinary sizes and of the best quality for wear and durability, with the greatest care and attention to all the necessary conditions of rolling and compression would not consolidate in the effectual manner required for the surface of a road while entirely isolated from and independent of other substances. The utmost efforts to compress and solidify them while in this condition, after a certain limit had been reached, were unavailing."

391. Mr. Deacon, Engineer of Liverpool, England, describes the effect of binding material as follows:

"Under a 15-ton steam roller preceded by a watering-cart, 1200 yards of trap-rock macadam, without binding, can only be moderately consolidated by twenty-seven hours' continuous rolling. If the trap-rock chippings from the stone-breaker are used for binding, the same area may be moderately consolidated by the same roller in eighteen hours. If silicious gravel from $\frac{3}{4}$ inch to the size of a pin's head, mixed with about one fourth part of macadam sweepings obtained in wet weather, be used, the area may be thoroughly consolidated in nine hours.

"Macadam laid according to the last method wears better than that laid by the second, and that laid by the second much better than that laid by the first."

392. Watering.—Wetting the stone expedites the consolidation, decreases crushing under the roller, and assists the filling of the voids with the binder. It should be applied by a sprinkler and not be thrown on in quantity or from the plain nozzle of a hose.

Excessive watering, especially in the earlier stages, tends to soften the foundation, and care should be exercised in its application.

393. Compacting the Broken Stone.—Three methods of compacting the broken stone are practised: (1) by the traffic passing over the road; (2) by rollers drawn by horses; (3) by rollers propelled by steam.

394. The first method is both defective and objectionable. (1) It is destructive to the horses and vehicles using the road. (2) It is wasteful of material; about one third of the stone is worn away in the operation. (3) Dung and dust are ground up with the stone, and the road is more readily affected by wet and frost.

395. The first recorded allusion to the consolidation of roads

by rolling seems to have been made in 1619 by John Shotbolt in England. The first practical application of rollers appears to have been made by the French engineers in 1829. Their first application in England appears to have been made by Sir John E. Burgoyne. Since these dates rolling has been universally adopted on the continent of Europe, not as a refinement but as a necessity, and no road is considered complete until it has been thoroughly compacted by a roller.

396. Advantages of Rolling.—The advantage of rolling broken-stone pavement may be summed up as follows:

(1) The saving of wear and tear of horses and vehicles. Roads should be made for the traffic and not by it.

(2) Comfort of persons using the roads.

(3) Economy, as a saving of from 30 to 50 per cent is effected by reason of the roads being better made, thus obviating the necessity for such frequent sweeping and scraping. If a portion of a road that has not been rolled is broken up and the material washed, it will be found that as much as half of it is soluble matter, mud, dirt, and fine sand. The stones having been thrown loosely upon the road-bed have lain so long before becoming consolidated by the traffic, and have undergone in the mean time such extensive abrasion, that the proportion of mud, dirt, and pulverized material is increased to that extent, and the stones are really only stuck together by the mud. This accounts for the fact that although an unrolled road may indeed after long use have a surface that is pretty good and hard in dry weather, and may offer then a very slight resistance to traction, yet it will quickly become soft and muddy when there is rain. By the employment of a roller of competent weight the stones are well bedded at once, and the surface is consolidated into a sort of stone felt capable of resisting most effectively the action of the traffic, and containing the smallest quantity of soluble matter to form mud in wet weather.

(4) The avoidance of cruelty to horses, as in the case of newly metalled unrolled roads.

397. Horse-rollers.*—Rollers drawn by horses are unsatisfac-

* Many improvements have been made in the construction of horse-rollers during the past few years, such as the use of hollow iron cylinders, which may be weighted by water or sand, and the rotary table, which renders no longer necessary the difficult task of turning the roller bodily, and avoids the ploughing up of a portion of the newly rolled stone.

tory for compacting the broken stone. They are expensive to use, requiring a large number of horses and attendants. The horses' feet displace as many stones as the roller compacts, and if they are of great weight they become clumsy and difficult of manipulation.

398. Steam-rollers.—Steam-rollers were first successfully introduced in France in 1860, since which time they have been almost universally adopted on account of the superiority and economy of the work done. Their use shortens the time required for construction or repair, and effects an indirect saving by the reduced wear and tear of horses and vehicles. They are made in different weights ranging from 3 to 30 tons. For the compacting of broken stone roads the weights in most favor are from ten to fifteen tons; the heavier weights are considered unwieldy and their use is liable to cause damage to the underground structures that may be in the roadway.

399. The advantages of steam rolling may be summed up as follows:

- (1) They shorten the time of construction.
- (2) A saving of road metal, (*a*) because there are no loose stones to be kicked about and worn; (*b*) because there is no abrasion of the stones, only one surface of the stone being exposed to wear; (*c*) because a thinner coating of stone can be employed; (*d*) because no ruts can be formed in which water can lie to rot the stone.
- (3) Steam-rolled roads are easier to travel on account of their even surface and superior hardness and have a better appearance.
- (4) The roads can be repaired at any season of the year.
- (5) Saving both in materials and manual labor.

400. Form of Rollers.—The advantage of the present form of rollers is generally overestimated. The heaviest roller in use does not exert the same pressure per inch of width nor in the same manner that a heavily loaded wagon does, but the demand that a roller should be as heavy per inch of width as a loaded wagon-wheel is per inch of tire cannot be successfully met.

The wheels of the rollers now in use have too wide a bearing on the road surface. The smaller soft spots are bridged over and remain unseen until the road is completed and thrown open for use. The traffic will quickly find these soft spots, and hollows and ruts will form. To obviate this and obtain the best effect from rollers, they should be constructed with both front and rear rolls. The front roll should be formed of disks, having diameters varying about six inches,

set alternately on the axle. The rear roll may be formed of two or more disks of uniform diameter. The ridges left by the front roll will be levelled by the rear roll. The effect produced by a roller of this form will approximate more nearly the effect of loaded wagon-wheels.

Weight of Roller.—The most suitable weight of roller for any given work must necessarily be determined by the nature and character of the material to be consolidated and the object to be attained.

Experience shows that for consolidating trap, granite, and similar rocks, the greatest amount and the best work are obtained by the employment of a roller which exerts a compressive force of from 550 to 600 pounds per inch width of wheel. In the compacting of soft and brittle stones the employment of too heavy a roller will result in crushing the material, thus rendering it useless; therefore it is obviously necessary to make use of a roller adapted to the character of the material to be consolidated. The best wearing results are generally obtained by employing a roller whose weight is slightly in excess of the displacing force or weight carried by vehicles of ordinary construction provided that the material is capable of withstanding the pressure without failure during the process of rolling.

Speed of Rollers.—The travelling speed for all weights of rollers varies from 2 to 3 miles per hour, and they can be operated on grades up to 20 per cent, but 7 per cent seems to be the economical limit.

401. The driving rolls of steam-rollers usually have holes bored in their faces to receive spikes, in order that they may be used for breaking up or disintegrating the road-surface. These, however, apparently do not answer; the working of a machine in this manner shakes and strains it considerably, and the holes in the rollers, which are plugged with wood when not in use for this purpose, are objectionable; the plugs wear out and the road metal gets into holes, and the surface of the road is picked up as the rolling proceeds. Besides this, the spikes seem to have no effect unless the surface of the roadway being operated upon is soft.

402. Amount of Work Performed by Steam-rollers.—The amount of work performed in a given time by the different classes

of steam-rollers necessarily varies, and is less in proportion as their weight and width of rolling surface decrease.

The quantity of material which a steam-roller is capable of consolidating in one day will depend on the quality and nature of the stone, the thickness of the layer, the amount and nature of the binding used, the available water supply, the amount used, the time lost by compulsory stoppages for the passing traffic, and the gradient of the surface under consolidation.

On roads with grades ranging from level to 1 per cent a 10-ton roller working nearly continuously during 10 hours, will thoroughly consolidate a layer of stone $4\frac{1}{2}$ inches in thickness (measured before consolidation) and using just sufficient binder to fill the interstices between the stones and a moderate amount of water, about 30 cubic yards. When working on gradients over 1 per cent a less quantity of material can be rolled, diminishing in amount as the incline becomes steeper. When the number of compulsory stoppages are great, as when working on suburban roads or in streets from which vehicular traffic is not excluded, the quantity of stone consolidated per day will be reduced considerably.

403. Cost of Maintaining Steam Rollers.—The annual cost of maintaining steam rollers as given in the reports of city engineers is as follows:

HARTFORD, CONN.

One 10-ton roller.....	\$4,000.00
Wages of engineer and tenders.....	\$888.57
Coal (40,780 pounds)	111.01
Wood (5 $\frac{1}{2}$ cords).....	31.20
Water for boiler.....	12.00
Repairs, tools, etc.....	210.70
Oil, waste, and packing.....	48.59
Insurance.....	15.00
Total for year.....	\$1,312.07

TOLEDO, OHIO.

Wages.....	\$951.50
Fuel, supplies, and repairs.....	316.29
Total for year.....	\$1,267.79

DULUTH, MINN.

Wages, fuel, repairs, etc	\$2,087.41
---------------------------------	------------

In England the cost per annum for 9 hours per day is about \$2000.

404. Amount of Rolling.—The number of superficial yards rolled per day must vary extremely with circumstances—the class of material, the amount of binding and water used, the gradient and pressure of steam maintained, and the amount of rolling considered necessary. The number of square yards rolled varies from 500 to 3000 per diem, the average of 42 English towns being 1105 square yards per diem.

In Paris 2 to 3.75 ton-miles of roller are applied to every cubic yard of stone. The weight of steam rollers per inch of run is specified to be 448 and 336 pounds, and, for horse rollers 263 pounds. The ton-miles necessary to make a square yard of porphyry wheel-way, or to compact a cubic yard of the same metal, is given as follows: The mean for two models of machines weighing 448 pounds per inch run was, per square yard, with the thickness of 3.9 inches, 0.41 ton-mile; while for the roller of 336 pounds, with a thickness of 2.8 inches, 0.234 ton-mile was required, or 3.78 and 2.99 ton-miles per cubic yard respectively; and for horse rollers, where the thickness was 2.6 inches, the ton-miles required were 0.194 per square yard and 2.69 per cubic yard. The amounts consolidated per ton per hour are in the following proportions: 467 for the heavy rollers, 539 for the light rollers, and 297 for the horse roller, and the number of passages of the rollers were 98.5, 75, and 92. The maximum speed is stated at 2.3 miles per hour. The rolling is done by contract (the city furnishing the water) at a rate per ton-mile varying from 15.26 to 7.63 cents, according to the amount, with an increase of one third in price where the grade exceeds 6 per cent.

The Southern Boulevard, New York City, constructed by Mr. E. P. North, received 0.859 ton-mile per square yard or 5.177 ton-miles per cubic yard.

From careful experiments with blue limestone in England, it has been found that to obtain consolidation with the usual coating of two stones in thickness (each cubic yard broken to 2½-inch gauge, and made to cover about 17 square yards of surface), the steam roller must traverse a patch equal to its own width about 35 times. From this it appears that a cubic yard of broken stone requires 1½ ton-miles to produce consolidation. For binding about

5 per cent of well-weathered road-scraping was used, being spread over the surface when consolidation was nearly effected. Without the use of binding, consolidation was found impossible.

The only guide for the proper amount of rolling is that it must be continued until the stones cease to creep in front or sink under the rolls, and the surface has become smooth and firm.

To ascertain the number of ton-miles per square yard or the number of passages of a roller of given weight, the following formula (deduced by Prof. C. H. Brown) may be used :

Let R = weight of roller per lineal inch in pounds ;

P = number of passages of roller over a given spot ;

T = number of ton-miles per square yard ;

36 = inches in 1 yard ;

1760 = yards in a mile ;

2240 = pounds in 1 ton.

$$\text{Then} \quad T = \frac{36 \times R \times P}{2240 \times 1760} = .00000913RP,$$

$$P = \frac{109511T}{R}.$$

405. Manner of Applying the Roller.—The stone should be spread in a uniform layer $4\frac{1}{2}$ inches thick. This depth will consolidate better than either thicker or thinner. Commence the rolling at the edge or border of the roadway; move up along this edge and return on the other in such manner that during each succeeding trip the edge of the strip previously rolled is overlapped while covering a strip closer to the middle of the road. The trips or passages of the roller should proceed in this manner and be continued until such a degree of firmness is attained that when the roller passes over the centre or the crown of the road its weight, which tends to spread the metal or make it work off towards the sides, may be resisted by the consolidation.

The surface of a well-constructed broken-stone road should, after being rolled, look almost like an encaustic pavement.

The rolling should be done slowly, as nothing is gained by a rapid motion; the fuel consumption being considerably increased without any advantage to the work.

In the execution of rolling it is an important advantage to be able to change, within considerable limits, the weight of the roller, because:

1st. The newly spread stone fragments are most readily fixed in position when exposed to moderate pressure in the beginning; once bedded, they should be rolled under maximum pressure. This has the convenience that the movement of the unballasted roller requires about the same tractive force on loose road metal as the ballasted roller on the more compacted surfacing.

2d. Experience teaches that the time needed for finishing diminishes with the increased weight of rollers. It appears that, with average road metal, a pressure of the unballasted roller of from 72 to 110 pounds per inch and of from 370 to 460 pounds per inch of width of ballasted roller is preferable.

3d. Not only the character of the broken stone, but also the resistance of the substratum, must be considered in the selection of roller weight. On soft or wet subsoil heavy rollers will cause a distortion of the road-bed.

In order to secure the best result, the rolling should be commenced with a roller of light weight, say 3 tons, either steam or horse, provided with hollow cylinders for ballasting with sand or water. After the loose fragments have been crowded together, increase the weight by means of ballast, and when the stones near the edges have been compacted so that there is no noticeable settlement, the rolling with the heaviest roller may be commenced and continued to completion.

The following rules on the rolling of broken-stone roads are given by the Massachusetts Highway Commission:

“When possible roll the subgrade with a steam-roller.

“If the subgrade is too sandy to roll, cover with coarse gravel laid on to a depth of three inches, or as much more as may be needed to give a good foundation.

“Fill any depressions with the same material until the surface is true and even.

“All broken stone must be rolled in screened layers.

“After spreading the first course of broken stone, begin rolling at the sides, and continue thus by running ahead so as to allow from two to five inches of the driving-wheel to pass over the shoul-

der, and backward with the outer edge of the driving-wheel from five to ten inches inside the edge of the broken stone. Roll until the stone ceases to 'wave' in front of the wheels, and until it seems firm underfoot as you walk over it. Next begin on the other side and roll in the same manner. Then work towards the centre until the stone is rolled. Roll each layer of stone in the same manner.

"If the road shows a wavy motion after passing the roller over it three, four, or more times, it may indicate too much moisture in the subgrade. If, on examination, you find this to be true, stop rolling and move ahead, allowing time for the subgrade to dry out.

"With some coarse, hard granite rocks it has been noted that after the roller passes over them a few times they begin to 'crawl,' and the sharp edges break off. A slight sprinkling of sand or stone screenings or water may prevent this. Try one after another of these means until the work progresses to your satisfaction. You must not expect to prevent the stone from shaking as you walk over it, but you need to continue the rolling until the fragments of stone adjacent to where the foot presses do not move as you walk. Most of the rolling must be done before you spread the screenings. After spreading the screenings, water and roll until the mud flushes to the surface. You cannot expect to prevent the stone from kicking out if the teams pass over the road. Keep watch, and in a few days have the roller pass once or twice over the road, after watering, until the loose stones are pressed down out of sight.

"Before spreading any broken stone, great care must be taken to have the subgrade carefully shaped and thoroughly compacted.

"All shoulders must be shaped and left sufficiently high to roll to the proper grade before any broken stone is spread on the road.

"In the case of heavy fills you must not run the roller to the edge of the shoulders unless the fill has had time to settle. Work out slowly on this kind of work.

"In every case the screenings used on the surface as a binder course must be of the same material as the top course of the road.

"Excepting where it may be needed to compact hard granite rocks, as before referred to, you will use water only on the top or binder course.

"You will wet this binder course thoroughly before rolling, but not to the extent of saturating the foundation. You will get

better results and prevent the screenings from being picked up by the wheels of the roller if you apply water and allow it to settle down below the top surface before passing the roller over it. Too much water or too little will give trouble by causing the surface to be picked up.

"You must not under any conditions roll the screening while dry.

"You must not under any conditions allow teams to pass over the road after the screenings are spread and before they are rolled."

406. Cost of Rolling.—The average cost of rolling varies considerably by reason of the amount of rolling considered necessary. In England it varies between one and two cents per square yard. In the United States it varies between 0.015 to 14 cents per square yard.

407. Cost of Broken-stone Pavement.—What the cost of broken-stone pavements will be must depend upon the accessibility and cost of material and labor, which will be quite variable. In Tables XLI and XLII is given the cost in different localities in the United States.

TABLE XLI.

COST OF BROKEN-STONE ROADS.

Locality.	Thickness of Stone. Inches.	Width of Pavement. Feet.	Method.	Cost per Mile.
Bridgeport, Conn.	4	18 to 20	Macadam	\$3,000
Fairfield, Conn.	4	20	Macadam	5,000
Fanwood, Conn.	12	16	Telford	9,580
Franklin Township, N. J. . .	4	15	Macadam	4,700
Kingston, R. I.	8	16 to 20	Macadam	5,500
Linden Township, N. J.	12	16	Telford	11,600
Plainfield, N. J.	4 to 6	16	Macadam	8,000
Rahway, N. J.	12	16	Telford	9,349
Westfield, N. J.	12	16	Telford	9,640
Union Township, N. J.	12	16	Telford	11,900

TABLE XLII.

EXTENT AND COST OF BROKEN-STONE PAVEMENTS IN SOME OF THE
PRINCIPAL CITIES OF THE UNITED STATES IN 1890.

Cities.	Extent. Miles.	Cost per Square Yard.
St. Louis, Mo.....	271.76	\$0.51
Chicago, Ill.....	226.67	0.90* to 1.70 †
Boston, Mass.....	172.00	0.75 to 1.25
Nashville, Tenn.....	111.00	0.45
Providence, R. I.....	110.00	
Philadelphia, Pa.....	90.80	
Hartford, Conn.....	64.00	1.00
Syracuse, N. Y.....	50.00	0.69 to 1.08
Rochester, N. Y.....	46.00	1.25
Paterson, N. J.....	38.00	0.45
New Haven, Conn.....	28.50	0.50 to 1.25
New York, N. Y.....	25.84	1.00 to 1.50 ‡
Worcester, Mass.....	20.00	
Cambridge, Mass.....	20.00	0.70
Harrisburg, Pa.....	20.00	
Toledo, Ohio.....	10.89	1.28
Burlington, Vt.....	7.74	
Washington, D. C.....	6.00	
Richmond, Va.....	5.72	0.75 §
Utica, N. Y.....	2.62	
Oswego, N. Y.....	2.18	
Albany, N. Y.....	1.71	
Milwaukee, Wis.....	1.16	
Los Angeles, Cal.....	1.00	1.17
Schenectady, N. Y.....	0.75	
Cincinnati, Ohio.....		1.25 ¶
Duluth, Minn.....	44.00	
Jersey City, N. J.....	1.50	
East Saginaw, Mich.....	1.00	
Springfield, Mass.....	15.00	
Chelsea, Mass.....	5.00	
Dubuque, Iowa.....	34.60	
Toronto, Can.....	37.27	
Mobile, Ala.....	20.00	
Lowell, Mass.....	10.00	
St. Louis, Mo.....	18.38 †	0.84
Newark, N. J.....	10.84 †	1.75
Kingston, N. Y.....	4.50 †	
Toledo, Ohio.....	1.11 †	
Trenton, N. J.....	0.50 †	

* Limestone and gravel 10 inches deep. † Crushed granite topping.

‡ Telford. § 12 inches deep. ¶ 18 inches deep.

407a. Cost of Broken-stone Roads in Massachusetts.—In Massachusetts the cost of State highway construction under the contract

system has ranged from \$6600 to \$24,547 per mile and has averaged \$10,033, divided as follows:

For excavating and grading.....	\$1,241
" gravel.....	520
" Telford and drains	367
" Macadam and shaping.....	5,694
" Masonry.....	448
" Guard-rails.....	188
" Paved gutters.....	191
" Engineering, superintendence, and inspection.....	679
" Minor constructions, catch-basins, culverts.....	481
" Stone bounds.....	54
" Advertising.....	18
" Weighing stone.....	24
" Sundries.....	178
Total.....	\$10,033

408 Difference in the Cost of European and American Broken-stone Pavements.—As an example exhibiting the difference in the cost of constructing macadam roads in Europe and the United States, we select a first-class highway of the broadest type, one which was built about ten years ago over a level expanse between the villages of Langenfeld and Burgwald, Germany. The road in question is 2100 meters (6888 feet) long, $26\frac{1}{2}$ feet in width, the macadamized wagon track $13\frac{1}{2}$ feet wide and $8\frac{1}{2}$ inches thick. With labor estimated at 36 cents per day except for stone masonry, which costs in country districts from 60 to 75 cents per day, the construction account of this road foots up as follows:

	Germany.	America.
Grading roadway	\$707.61	\$1748.00
Planting and turling slopes.....	89.96	268.88
Bridges and culverts.....	154.70	464.10
Macadamizing	3647.35	7843.50
Milestones, etc.....	11.88	34.14
Tools	75.68	151.36
Damages to adjacent property during work...	155.65	155.65
Tree-planting.....	61.88	185.64
Superintendence of construction	369.85	784.85
Incidentals.....	49.98	49.98
	\$5324.04	\$11640.00
This is equivalent to about.....	\$4092.00 per mile	\$8947.60 per mile

409. Wear of Broken-stone Pavements.—The wear of road materials resulting in their gradual reduction to detritus is due to the joint action of the traffic and the weather. When the wear is confined to the abrasion of the surface, it is the least possible; but when a road is weak from insufficient thickness, or from a yielding foundation, bending and cross-breaking take place under passing loads, and a movement is produced in the body of the road which causes internal wear by the rubbing of the stones against each other; this wear is aggravated by the softening action of water finding its way into the roadbed through cracks in the surface, and by the disintegrating action of frost; the wear and waste are thus far greater than on roads of sufficient strength properly maintained.

410. The relative proportions in which a road is deteriorated by the action of atmospheric changes, wheels, and horses' feet for the generality of roads is approximately as follows:

Atmospheric causes.....	20 per cent
Wheels	35.5 "
Horses' hoofs	44.5 "

411. The effect of horses' feet is to form depressions which, if not immediately eradicated, prepare the way for further injury by the wheels. Horses moving at a walk and drawing heavily-loaded wagons do far more injury than horses travelling quickly and drawing lightly-loaded vehicles.

Rain.—The effect of rain upon a highway is, first, to soften the bed, and next to wash off the portion of the material which the temporary streams can bear along. On an earth road the softening action is highly injurious, as it permits the feet of animals and the wheels of vehicles to penetrate below the surface. On a properly constructed broken-stone road, as well as on all forms of block pavement, the pavement acts as a roof, shedding the water from its surface. If the roadway be skilfully planned, the penetration of water from the sides is avoided, and thus the damage arising from the softening action, as well as from the influence of frost, is done away with. On all forms of earth roads, and on the most of those made of gravel as well, the effect of the penetration of water in loosening the mass of the road-bed is serious, in most cases up to the margin of disaster.

Where a hard road of broken stone or blocks or other material impervious to water is properly shaped, the rainfall is quickly

carried to the side ditches by the arched form of the road. On such roads the water never courses over the roadway for a much greater distance than its width. Thus arranged, the streams, even in a very heavy rainfall, do not gain much volume or attain great speed; therefore their scouring effect is but small. Nevertheless, the storm-water, by removing the dust from the roads and by washing out the binding material between the stones, hastens the wearing of the roadway. This is especially the case where the broken stone is of the softer sort. Where the pavement is composed of the basaltic trap-rocks, the washing influence of the waters is not so serious. On dirt roads the rainfall, especially after times of frost, is the most serious agent of destruction.

The power of water to move and transport materials depends upon the specific gravity, the size and form of the fragments, and upon the velocity of the water, or, what amounts to the same thing, the slope of the roadway. Hence the steeper the grade, the greater the transporting power of the water, and the longer the distance the water will flow over the roadway before it is discharged into the gutters or side ditches.

On steep grades the carrying power is made apparent by gullies; on gentle slopes the grains of the least weight and specific gravity and of the most tabular form are made to occupy the surface of the road, where, after drying, they fall an easy prey to the power of the wind. This sorting action arises from the fact that, other things being equal, the sand grains will arrange themselves in water in the order of their specific gravities, the heaviest at the bottom. An exception to this rule is found where minerals even of a high specific gravity are characteristically of a tabular form, since the resistance they offer to descent, owing to their relatively large surfaces, causes them to arrange themselves at the top with minerals of the lowest density.

The rain falling upon a road serves to concentrate the minerals into layers in the order of their specific gravity. This will not be found true of the micas, for these will be found concentrated near the surface with the minerals of a less density and both made accessible to the action of the wind.

The impact of falling rain-water causes a certain amount of injury by attrition and loosening of those grains which it is able to

move about, and a certain weakening of the coherency of the surface as far down as the water is able to penetrate.

Frost.—The immediate effect of frost action on a broken-stone road, where care has not been taken to keep the foundation dry, is to heave the pavement irregularly, the amount of the uplifting depending on the quantity of water which has become frozen. The effect of this irregular motion is to pull the cemented stones apart, and sometimes to form cracks through which the water can penetrate. Where the broken stone is not well cemented, or where on an earth or gravel there are stones near the surface, the effect is often to push the larger fragments upward to the surface. It may in general be said that all frost action is highly detrimental to a road, and that therefore the utmost care to exclude the water from the hardened part of the way, as well as from the under earth, needs be taken.

When the frost enters the ground the first effect is to convert into ice the water within the zone of its influence. In undergoing this change the fluid expands to the amount of about one-ninth of its bulk. The energy with which this expansion occurs is in all cases sufficient to thrust about the materials of the soil. So long as the road permits water to pass into it, and wherever groundwater can penetrate from the sides beneath a roadway, however well compacted, even if it be quite water-proof, the action of frost is destructive.

The presence of frost in stones is promotive of weakness and rapid crumbling. In fragments of broken stone it operates to increase their brittleness to a considerable degree, and for this reason gives rise to a more rapid disintegration of the screenings and upper portion of the road.

Wind.—The action of wind on roads of all descriptions is considerable. The effect is to remove all the loose material of a fine-grained nature as soon as it becomes dry. On earth roads and those of gravel the wearing action thus accomplished, though it takes place in a more even way, and therefore is less conspicuous, is often as great as that brought about by the rain. On broken-stone roads the effect is considerable, but on the whole not seriously damaging, except where the pavement is made of rocks which easily powder, such as limestone and slate. The diabase

rocks, which carry a considerable percentage of black mica, and the mineral feldspar, which decomposes to clay, also furnish abundant material for the wind's work.

The sorting action of the wind tends to remove the minerals having the least specific gravity, and this will be particularly true when the grains possessing the least density happen to coincide with those of a brittle nature, and which for this reason are most liable to be ground to a condition of fine dust under the action of the wheels.

Wind-blown material is not only objectionable, since it increases the cost of road maintenance, but is an intolerable nuisance to the users of the road and adjacent residents.

The ability of the wind to take up and bear away grains of any rock depends upon several factors. These in the order of their importance are: (1) The form of the particles subjected to the wind's influence; (2) the specific gravity and size of the individual grains; and (3) their accessibility to the action of the wind. The form of the grains will depend upon their original shape in the rock and that which they may be induced to take as an effect of road wear or as a result of chemical change. The most suitable stone to be used for highways, to withstand the action of the wind, is one whose products of abrasion are of a high but uniform specific gravity, and which is free from all minerals that by their tabular form are prone to be thus transported.

A small amount of dust is of value on a road, acting like a cushion to protect the broken stone from the action of the wheels and the animals' feet. The value of this dust-film is further enhanced by a small quantity of moisture.

Disintegration and Decomposition of Road Materials by the Chemical Action of the Elements and Organic and Inorganic Acids.*

—Rain-water impregnated with carbonic acid alone acts as a slow solvent on all the common minerals occurring in the stones used for road covering, attacking even quartz; but a mixture of the various acids, organic or inorganic, acts more rapidly. The organic acids occurring in all water circulating through the soil in fertile regions are carbonic, humic, crenic, and apocrenic. Near cities we must add to the organic acids those derived from gas-plants

* See foot-note, p. 288.

and manufacturing establishments. These acids are largely nitric, sulphuric, and hydrochloric.

The injurious effects of organic and inorganic acids on road-stones are confined for the most part to rocks containing calcite or dolomite, minerals which they readily dissolve and carry away.

*Shrinkage of the Subgrade.**—A road-bed may suffer disruption by shrinkage of the subgrade. It has been determined experimentally that clay shrinks one fifth of its bulk in excessively dry weather and increases to a corresponding degree when wet, and that silicious sands and gravels undergo no change in volume. From this it follows that when a road passes over a clay bed which may become dessicated, injurious results are likely to follow, particularly at a point where the clay abuts a sand substratum which is unaffected by weather changes.

*Gravity** also plays an important part in the work done by running water and falling rain. Through its operation alone there is always a tendency exercised for grains and fragments of rock to work down the slopes towards the sides of the road. Under some circumstances the effect of gravity may completely destroy a road-bed. When the roadway is constructed along a mountainside whose soil is slowly creeping toward the valley, the cut made necessary for the roadway is often sufficient so to weaken the hold of the soil as to precipitate the surface of the country down the slope as a landslide, or cause a slower movement which in the end entails a long-continued and serious expense in the way of repairs. Such movements are particularly common in loose materials in countries where the frost penetrates deeply and the ground becomes soft in the time of thawing. Roads may also be destroyed by avalanches of trees and stones from a point farther up the slope.

*Changes of Temperature** produce expansions and contractions of the rock forming the road-covering, which in extreme cases break the bond holding together the broken stone and cause cracks and fissures.

* Abbreviated from "The Geology of the Common Roads of the United States," by N. S. Shaler, and "The Forces which Operate to Destroy Roads," by C. I. Whittle.

412. The quantity of stone worn away annually from the surface of roads is an exceedingly variable quantity, dependent not only upon the character of the stone and the quantity of the traffic, but also upon the mode of maintaining the road. Mud is an excellent assistant in rapidly grinding down the surface. Many attempts have been made to measure the wear on roads, but no definite conclusions can be arrived at.

413. The wear or loss of thickness on some of the heavily travelled streets of London and Paris has been as much as four inches per annum. In Birmingham, England, the macadam streets have worn down six inches in one year under a traffic of 2484 vehicles in ten hours.

The average loss of thickness on the European roads appears not to exceed one inch per year.

414. The amount of material used annually in England to replace the wear on main roads varies from 40 cubic yards per mile in the country districts to 1000, and in some cases to 1500 cubic yards in the vicinity of large towns. The general average appears to be from 70 to 80 cubic yards per mile, the least being 10 cubic yards per mile.

The average annual consumption of broken stone to replace wear in France and Austria appears to be about 70 cubic yards per mile.

415. The loss of thickness by wear should be restored annually by spreading coats of two or more stones thick and consolidating it with the roller. Before applying the coating the surface of the road should be broken up with picks in cross-courses about 4 inches apart; the depth to which the surface is broken should not exceed 2 inches. Steam rollers are furnished with picks for this purpose, but their employment is not satisfactory or advantageous; if the spikes are short, they have no effect on the road unless it is soft; if they are long, they penetrate the body of the road, breaking the bond, and leave the road a mass of loose stones. Besides the employment of the roller for this purpose shakes and strains it considerably.

416. The practice of spreading the new coating and leaving it to be consolidated by the traffic is open to the same objections as the construction of unrolled roads. It is an obstacle instead of an aid to traffic.

When the stone is spread, the sooner it is rolled solid the better.

417. Recoating the road should be done at that season of the year which will interfere the least with the movement of the traffic. Wet or damp weather is most suitable, but when water is obtainable it may be done at any season.

417a. Effect of Climate on Broken-stone Roads.—Regarding the effect of climate on broken-stone roads, Prof. N. S. Shaler says: "As a roadway is, of all constructions, the most exposed to the action of the weather, the climate of the district in which it lies has a greater effect upon it than upon any other class of buildings. This effect is exercised by the rainfall, changes in temperature, and the winds. A secondary influence arising from the above-mentioned natural conditions is found in the character of the vegetation, which, under favorable conditions, may advantageously affect a road by covering the unused portion of its surface with a network of low-growing plants, such as the grasses.

"In a moderately humid climate, exempt from continuous summer droughts, creeping plants, nourished by the dust from the roads, which in most cases has a considerable fertilizing value, take hold on the shoulders and sides of the way in such a manner as to protect those exposed parts from washing or from the action of the winds. When these conditions prevail it is generally practicable to build a relatively narrow, hardened way with wide shoulders on either side, onto which the passing teams can turn out, finding there, by virtue of the plant-covering, a surface so firm that it will not rut from an occasional passage of wheels. If, however, the shoulders are overdry, as they are sure to become in an enduring drought, the plants are killed and the surface is left exposed."

418. Cost of Maintenance.—The cost of maintaining broken-stone pavements varies between very wide limits. A road with little traffic, well drained, and exposed to the sun and air, with fairly good materials at hand, can be kept in repair at a very small yearly cost, while a suburban or city street may cost several hundred dollars. Unless the amount of the traffic, the quantity of materials used, their price, and other particulars be taken into account, the cost per mile or square yard at which a road is maintained affords little real information, and may be misleading.

In London the cost of maintaining macadam pavements is stated as follows:

In heavy-traffic streets.....	62½ cts. per sq. yd.
In moderate-traffic streets.....	29½ "
In light- " "	14½ "
In lightest- " "	6½ "

In Paris macadam costs about 45 cents per square yard per year. In Boston, Mass., about 50 cents.

The cost of maintaining the high-roads of Austria ranges from \$1032 to \$1571 per mile per annum; of these amounts about 50 per cent (49 to 52) is for materials. The highways of Belgium cost between 6 and 10 cents per square yard per year.

The French roads cost from 1 to 10 cents per square yard per year.

The annual cost of maintaining the government roads of Bavaria in 1877 was, per kilometer, or .62 English mile, as follows:

Cost of material.....	\$54.26
Extra labor.....	11 42
Bridges and culverts.....	2 52
Retaining-walls and gutters.....	.31
Road-paving.....	2.45
Cost of tools.....	1.02
	<hr/>
	\$71.98

or about \$116.09 per English mile. Total number of men employed on the government roads was 1089. The average cost of regular roadmen per English mile was \$45.25.

Total length of government roads:

The total length of government roads macadamized.....	4,223 miles
" " " " " " paved.....	29 "
" " " " " " over bridges.....	6 "
	<hr/>
	4,258 miles

419. Descriptions of Modern Broken-stone Roads.—"First-class metropolitan roads, England: The ground is excavated or filled to the required level, then thoroughly consolidated by rolling. On the earth-bed thus prepared a bottoming or bed 12 inches thick, of "hard core," consisting of brick rubbish, clinker, old broken concrete, broken stone or shivers, or any other hard material in pieces, is spread and rolled down to a thickness of 9 inches, and any loose or hollow places made up to the level.

"Next comes a layer of Thames ballast 5 inches thick, rolled solidly to a thickness of 3 inches. The ballast serves to fill up the vacancies in the bottoming, and, being less costly, saves so much of the cost for broken granite."

Broken granite, or macadam, is laid upon the prepared surface of the ballast in two successive layers 3 inches thick, rolled successively to a combined thickness of 4 inches; a layer of sharp sand $\frac{1}{4}$ or $\frac{3}{4}$ inch thick is scattered over the second layer, and rolled into it with plenty of water.

420. The method adopted in Chicago is as follows: The roadbed is prepared to the required contour and well consolidated with a steam roller. On this surface rubble-stone is carefully placed by hand, with its broadest side downwards, then 12 inches of broken stone are spread, 6 inches at a time, thoroughly rolled, to bond it; it is then topped with 4 inches of crushed trap or other equally hard rock; this is again thoroughly rolled, so as to compact and bind it together.

421. The method adopted in the construction of the Bridgeport, Conn., roads is as follows: The ground is graded and regulated with a gutter 18 inches deep on each side; the soil is then thoroughly rolled with a 15-ton roller, and the stone spread on the surface so prepared. Three varieties of soil are met with in Bridgeport: (1) a fine "dead" sand, which sometimes cannot be rolled on account of its pushing before the roller, without covering it with coarse broken stone—this expedient, acting as a pavement, prevents movement; (2) loam, and (3) a hard-pan with mica disseminated through it. Underdraining has in no case been resorted to, the 18-inch gutters being depended on for drainage. After the broken trap-rock is rolled to a bearing, screenings are added as a binder and the road metal is well and thoroughly filled with them, the whole being rolled until the water flushes on the surface. A strong silicious sand is sometimes used, in part, in place of screenings, and when, in dry weather, the road commences to break up or "ravel," out of easy access by watering-carts, sand is spread over the spot, which quickly consolidates the road. No loam or clay is used as a binder or filler in the construction of the roads, nor in their repair, except when the surface over a ditch is to be replaced and it is too small a patch to justify bringing the roller; then the broken trap is laid down after being mixed with the proper quantity of screen-

ings, and the whole covered with loam. The traffic consolidates it in a short time.

It should be noticed, in connection with the low cost of those roads stated in Table XLII,—about 28 cents per square yard,—that Bridgeport, in addition to the possession of particularly good trap-rock, is exceptionally favored in the location of its quarry—almost exactly two miles from the centre of the city; so that the cost of the stone is 82 cents per gross ton of 21 or 22 cubic feet, delivered to the wagons; and the cost of hauling varies, depending on the distance, from 50 to 75 cents per ton, or between \$1.32 and \$1.57 per gross ton delivered on the road. The trap-rock is broken to 2-inch size by three 7×10 -inch Marsden crushers, placed side by side on a platform, to which cars are drawn from the quarry by a wire rope, wound by the same engine which runs the crushers. The interest on the cost of the roller—an Aveling & Porter, now twenty years old—is not reckoned in the above-mentioned cost.

That the cost of the Bridgeport roads has not been underestimated is apparently made certain by the contract price of such work in the neighboring town of Fairfield, where, with a longer haul, a 4-inch road 20 feet wide was built for 85 cents per lineal foot or 38.3 cents per square yard. This sum included regulating, some grading, and the use of a roller, as well as the contractor's profit.

422. Extracts from Specifications for forming Telford Roads in St. Louis, Mo.

Drainage.—All drains considered necessary by the Street Commissioner to carry off the water shall, when required, be made by the contractor for the work, and shall be paid for at a price agreed upon by the Street Commissioner.

Sub-foundation.—After the curbstones are set, the second grading and shaping of the roadway shall be done. All surplus earth and other material shall be removed and the sub-foundation formed to a depth of eighteen (18) inches below the intended surface of the street, the cross-section thereof to conform in every respect to the cross-section of the pavement when finished. The roadbed shall then be rolled with a roller weighing not less than five (5) tons, when required by the Street Commissioner. All depressions which may appear shall be carefully refilled before any stone is put on.

Lower Course of Telford.—When the street shall be thus graded and formed, a bottom course or layer of limestone of approved quality shall be laid by hand in regular straight courses at right angles with the line of the streets, so as to break joints; the bottom surfaces of the stones shall form as close joints as possible. The stones to be used shall not be less than three (3) inches nor more than eight (8) inches thick, and from five (5) to ten (10) inches long on their bottom surfaces, and must be thoroughly settled to place with hammers. The interstices shall then be filled with stone chips firmly wedged by hand with hammers, and all projecting points shall be broken off. The tops of the stones when levelled off shall have a surface not greater than one third of the base. The foundation or bottom course when finished shall have a regular and uniform depth of not less than seven (7) inches. The bottom course along the curb and under the gutter for a width of four (4) feet, and under the cross-walk for a width of eight (8) feet, shall be thoroughly consolidated by rolling or ramming, and the surface be made even by filling the spaces between the stones with sand in such manner as the Street Commissioner may direct.

Guttering.—After the Telford foundation has been prepared the gutter shall be put down upon a bed of clean coarse sand at least two (2) inches deep. The paving-blocks shall be from six (6) to seven (7) inches deep, four (4) to six (6) inches thick, and eight (8) to twelve (12) inches long. The faces shall be straight, free from bunches, depressions, and inequalities exceeding one half ($\frac{1}{2}$) inch. The faces shall meet at right angles, and the corresponding dimensions of opposite faces shall not vary more than one-half ($\frac{1}{2}$) inch. They must be set vertically on edge, in close contact with each other, in straight rows at right angles with the curb, the blocks in different rows breaking joint by a space not less than four (4) inches. The joints between the blocks shall be filled with clean, sharp sand.

Cross-gutters.—The cross-gutters shall be of such width and shape as may be directed. The stone used therefor shall be from three (3) to six (6) inches thick, nine (9) inches deep, and from six (6) to twelve (12) inches long. The bottom course of stone shall be eight (8) inches thick, nine (9) inches deep, and not less than twelve (12) inches long.

Quality and Finish of Stone Work.—All stones used for gutters, cross-gutters, and cross-walks shall be limestone of the best quality, from ledges known to withstand the effects of frost, and free from seams and all other defects. All paving-stone shall be dressed so as to make close joints at least four (4) inches deep, and have a square bottom not less than three quarters ($\frac{3}{4}$) of the superficial surface of the top of the same stone. All materials shall be fully dressed before they are brought onto the street to be improved. The whole paving must be made tight, compact and smooth, and be fully fed with sand, and must be laid true and uniform, with broken joints, and have a full bond of at least four (4) inches. After the paving is laid it must be sanded on top, the sand swept into the joints with a broom, and be settled down evenly and firmly with a rammer of not less than forty (40) pounds weight.

Macadam or Second Course.—When the Telford foundation has thus been formed, there shall be placed thereon a layer of clean, hard limestone macadam, free from clay, earth, rubbish, or other foreign matter, so broken that the largest pieces shall pass through a two and one half ($2\frac{1}{2}$) inch ring in all their dimensions, and shall be fully broken before it is brought on the line of work. This course shall have such a depth and form of cross-section as may be directed by the Street Commissioner, and shall be thoroughly consolidated by rolling with a roller weighing not less than five (5) tons.

Sand.—The macadam course having been finished, the spaces between the stones shall be well filled with clean, coarse sand, or so much sand as may be directed by the Street Commissioner, which shall be washed in with water from a hose having a rose attached to the nozzle, and then the whole shall be rerolled to the satisfaction of the Street Commissioner. A sprinkling-cart shall not be used unless it is impossible to make a connection with a fire-plug, and then only with the consent of the Street Commissioner. A water license and a permit from the Water Commissioner must first be obtained before a fire-plug can be opened.

Gravel.—The macadam course with binding material having been finished, there shall be placed thereon a layer of good clean gravel, free from clay, animal, or vegetable matter, and containing not more than fifteen (15) per cent of loam or sand, nor shall the largest pebbles exceed one inch in diameter; to be well wetted down or slushed with water and thoroughly rolled to a perfect surface,

TYPE-SECTIONS OF BROKEN-STONE PAVEMENTS.




FIG. 25. COUNTRY ROAD, SIDE-DITCH FILLED WITH COBBLE.




FIG. 26. COUNTRY ROAD, WITH EARTH BERM AND TILE-DRAIN.




FIG. 27. CITY STREET




FIG. 28. CITY STREET, WITH STONE-BLOCK GUTTER.

having such form of cross-section and depth as may be directed by the Street Commissioner.

423. Heads of Specifications for Broken-stone Pavements.

- (1) Preparation of roadbed.
- (2) Foundation (sand, gravel, etc.).
- (3) Quality of the stone.
- (4) Size of the stone.
- (5) Cleanness of the stone. (The stone must at all times be clean and free from clay or other dirt.)
- (6) Spreading the stone.
- (7) Thickness of layers.
- (8) Rolling: weight of roller and amount of rolling.
- (9) Watering.
- (10) Binding, quality and quantity of.
- (11) Interpretation of specifications.
- (12) Omissions in specifications.
- (13) Engineer defined.
- (14) Contractor defined.
- (15) Notice to contractors, how served.
- (16) Preservation of engineer's marks, etc.
- (17) Dismissal of incompetent persons.
- (18) Quality of materials.
- (19) Samples.
- (20) Inspectors.
- (21) Defective work, responsibility for.
- (22) Measurements.
- (23) Partial payments.
- (24) Commencement of work.
- (25) Time of completion.
- (26) Forfeiture of contract.
- (27) Damages for non-completion.
- (28) Evidence of the payment of claims.
- (29) Protection of persons and property.
- (30) Indemnity bond.
- (31) Bond for faithful performance of work.
- (32) Power to suspend work.
- (33) Right to construct sewers, etc.
- (34) Loss and damage.
- (35) Old materials, disposal of.

- (36) Cleaning up.
- (37) Personal attention of contractor.
- (38) Payment of workmen.
- (39) Prices.
- (40) Security retained for repairs.
- (41) Payment, when made. Final acceptance.

CHAPTER VIII.

MISCELLANEOUS PAVEMENTS.

424. Gravel Roads.—Gravel, though not as durable as broken stone, has proved very serviceable as a road covering.

In selecting gravel for this purpose, the chief quality to be sought for is the property of binding. The binding properties are two: the presence of ferruginous clay, which causes the gravel to set or become hard as soon as it is exposed to the action of the atmosphere; and the angular shapes and sizes of the stones.

425. Gravel from the sea-beach and shores of rivers, and that in which the stones are round or oval, with regular smooth surfaces, never forms a good binding material, even if mixed with ferruginous clay. The reason is that the stones which are on the surface have no mechanical hold on those which are beneath or beside them, but being merely cemented by means of the clay they are easily loosened and thrown out of place by the action of the traffic or frost, and even by the alternate actions of drought and moisture.

426. When no gravel but that found in rivers or on the sea-shore can be obtained, one-half of the stones should be broken and mixed with the other half; to the stone so mixed a small quantity of clay or loam, about one-eighth of the bulk of the gravel, must be added: an excess is injurious. Sand is unsuitable: it prevents packing in proportion to the amount added.

427. Preparing the Gravel.—Pit-gravel usually contains too much earth, and should be screened before being used. Two sieves should be provided,—one with meshes of one and one-half inches, so that all pebbles above that size may be rejected, the other with meshes of three quarters of an inch, and the material which passes through it should be thrown away. The expense of screening will be more than repaid by the superior condition of the road formed

by the cleaned material, and the diminution of labor in keeping it in order. The pebbles larger than one and a half inches may be broken to that size and mixed with the cleaned material.

428. Laying the Gravel.—On the roadbed properly prepared a layer of the prepared gravel four inches thick is uniformly spread over the whole width, then compacted with a roller weighing not less than two tons, and having a length of not less than thirty inches. The rolling must be continued until the pebbles cease to rise or creep in front of the roller. The surface must be moistened by sprinkling in advance of the roller, but too much water must not be used. Successive layers follow, each being treated in the above-described manner until the requisite depth and form has been attained.

429. The gravel in the bottom layer must be no larger than that in the top layer; it must be uniformly mixed, large and small together, for if not so the vibration of the traffic and the action of frost will cause the larger pebbles to rise to the surface and the smaller ones to descend, like the materials in a shaken sieve, and the road will never be smooth or firm.

The pebbles in a gravel road are simply imbedded in a paste and can be easily displaced. It is for this reason, among others, that such roads are subject to internal destruction.

430. The binding power of clay depends in a large measure upon the state of the weather. During rainy periods a gravel road becomes soft and muddy, while in very dry weather the clay will contract and crack, thus releasing the pebbles, and giving a loose surface. The most favorable conditions are obtained in moderately damp or dry weather, during which a gravel road offers several advantages for light traffic, the character of the drainage, etc., largely determining durability, cost, maintenance, etc.

431. Repair.—Gravel roads constructed as above described will need but little repairs for some years, but daily attention is required to make these. A garden rake should be kept at hand to draw any loose gravel into the wheel-tracks, and for filling any depressions that may occur.

In making repairs, it is best to apply a small quantity of gravel at a time, unless it is a spot which has actually cut through. Two inches of gravel at once is more profitable than a larger amount. Where thick coating is applied at once it does not all pack, and if,

after the surface is solid, a cut be made, loose gravel will be found; this holds water and makes the road heave and become spouty under the action of frost. It will cost no more to apply six inches of gravel at three different times than to do it all at once.

At every one-eighth of a mile a few cubic yards of gravel should be stored, to be used in filling depressions and ruts as fast as they appear, and there should be at least one laborer to every five miles of road.

432. Cost of Construction in Illinois.—The cost has been about \$900 per mile for a roadway 12 feet wide, 12 inches deep at the centre and 9 inches at the sides.

Table XLIII shows the extent and cost of gravel pavements in some of the principal cities in the United States.

TABLE XLIII.

EXTENT AND COST OF GRAVEL PAVEMENTS IN SOME OF THE PRINCIPAL CITIES OF THE UNITED STATES.

Cities.	Extent. Miles.	Cost of Construction per square yard.
Boston, Mass.....	160.00	\$0.75
Cambridge, Mass.....	67.91	
Richmond, Va.....	46.44	\$0.15 to \$0.20
Washington, D. C.....	38.50	
Grand Rapids, Mich.....	32.37	
Burlington, Vt.....	11.92	
Haverhill, Mass.....		\$0.25

433. Weight of Gravel.—A cubic yard of pit gravel weighs about 3300 pounds. When the distance is not greater than $1\frac{1}{2}$ miles, a team will haul about 7 cubic yards a day; even with hauls of six miles the work can be done at reasonable cost.

434. Bituminous Macadam.—In some towns in England bituminous or asphalt macadamized roadways are made. This consists in mixing ordinary coal-tar with the road metal ordinarily employed for macadamized roads; only it must be borne in mind that the metal employed must be limestone or some other soft material, otherwise it will not wear down evenly with the tar, and thus a lumpy surface will be produced in course of time.

The method of mixing is by heating the stone, which has of course been previously broken to the required size, and then thor-

oughly mixing and incorporating it with the tar. This is carried to the roadway, is spread in the ordinary manner, and well rolled to the proper contour, a surface being afterwards given to it by a coating of about 2 inches thick, composed of a similar mixture, the stones of which are of much smaller size.

Another method is to place about 6 inches of the broken stone upon the necessary foundation. Upon this a boiling mixture, composed of about 50 gallons of creosote oil and 1 ton of pitch, is poured until every interstice is filled with the mixture. Whilst this is still warm, a thin layer of small broken stone is spread upon the surface and well rolled; more small stones or chippings are added, and the whole is rolled until the surface of the roadway has attained its proper contour and presents a perfectly smooth and clean appearance, little inferior to that of real asphalt.

Dry weather is essential whilst this class of roadway is in course of construction, and careful watching is required, as when the skin breaks the whole roadway soon disintegrates. This class of pavement has, however, many advantages over ordinary macadamized roadways when finished, not the least of them being imperviousness to moisture, and the ease with which it may be cleaned.

435. In repairing some of the macadam roads and pavements in Paris, fragments of old asphalt were mixed with the broken stone. The results, as regards wearing qualities, show little improvement over the unmixed stone, but such a pavement keeps remarkably clean during dry weather and does not become as muddy as the true macadam during rainy seasons.

In the middle of summer an unpleasant odor is given out, and the surface has a dirty black color.

436. Concrete Macadam, introduced by Mr. J. Mitchell, London Eng., is composed of broken stone, sand, and Portland cement so proportioned that the spaces, otherwise vacant, and ultimately filled with muddy cementing matter of worn macadam, are filled with an admixture of Portland cement or other hydraulic cement-grout. The concrete thus formed rapidly becomes a uniform and impervious mass which is wholly unaffected by heat or moisture. It is mixed in these proportions:

Broken stones.....	4 measures
Clean, sharp sand.....	1½ to 1¾ "
Portland cement.....	1 "

So for a cubic yard, or 27 cubic feet, of broken metal $6\frac{1}{2}$ cubic feet, or $1\frac{1}{2}$ barrels (of $4\frac{1}{2}$ cubic feet), of Portland cement are required. The broken stone should be of the hardest quality, of uniform size, thoroughly screened; and it should be thoroughly wetted before being incorporated with the cement.

Cement of the best quality must be employed, and the sand should be sharp, clean, and gritty. The surface of the ground is brought to form, and rolled several times. The concrete is then laid on the surface in a layer 3 or 4 inches, and is left for three days to harden. The second layer of 3 or 4 inches is next laid on the first, and immediately rolled to form with a heavy iron roller, as heavy as two or three men can draw. The cement should be left for three weeks, to allow it to become quite hard before the road is opened for traffic, although a week has been found to be a sufficient interval.

Mr. Mitchell states that a concrete road, 7 inches deep at the middle and 5 inches at the sides, is sufficient for ordinary traffic. For heavy traffic a depth of 8 inches is recommended.

The first piece of concrete road was laid in 1865 in Inverness, and consisted of 45 lineal yards of the approach to the freight station of the railway. In 1870, after the road had been under traffic for $4\frac{1}{2}$ years, it was reported that the wear of the surface was scarcely appreciable, whilst the adjoining macadamized road had been coated frequently every year.

Another specimen, 50 yards long and 15 yards wide, was laid in 1866, on George IV. Bridge, Edinburgh, where the traffic is heavy and continuous. At the end of three years and a half under traffic the surface was perfectly sound and immovable.

The amount of vertical wear during the periods above named appears not to have exceeded $\frac{1}{4}$ inch. But Mr. J. H. Cunningham, writing in January, 1875, stated that it was then much worn at the surface, in consequence, he thought, of its great hardness and rigidity.

437. Stone Trackways (Figs. 29 to 32).—Trackways formed of stone slabs were first employed by the Egyptians for moving great weights. In modern times they reappeared in northern Italy, where they are in general use not only in the streets of the principal cities, but also in the smaller towns.

Telford employed a stone trackway on the Holyhead Road to




Fig. 29.—SECTION OF STONE TRACKWAY.




Fig. 30.—PLAN OF TRACKWAY.




Fig. 31.—PLAN OF CROSSING.




FIG. 32.—JUNCTION OF CURVES WITH STRAIGHT LINE.

avoid excessive work of construction. There were two hills each a mile in length, with an inclination of 5 : 100. To reduce this to a $4\frac{1}{2}$ per cent grade would have cost \$100,000, but nearly the same advantage in diminishing the amount of tractive force required was obtained by making stone trackways at a total expense of one half the former amount and retaining the 5 per cent grade with moderate cutting and embankment. To draw one ton over the original hills required a tractive force of 294 pounds; to draw the same load over the trackways laid on the same inclinations required only 132 pounds.

Trackways of both stone and iron have been used in London, Liverpool, Manchester, Glasgow, and other cities.

438. The Italian trackways consist of two parallel lines of granite blocks, usually 14 inches wide, 8 inches deep, and 5 feet in length, bedded in a layer of sand. The lines are 28 inches apart, and the interspace, or footway for horses, as well as the other portions of the roadway, is paved with cobbles obtained from the Po, or from other rivers. These stones should be egg-shaped, with a maximum diameter of from $3\frac{1}{2}$ to $4\frac{1}{2}$ inches and a depth of from $4\frac{1}{2}$ to $5\frac{1}{2}$ inches. The roadway is usually formed with a slight inclination downwards towards the centre. By this arrangement the space between the trams serves as a channel to receive the surface-water, and is provided with stone gratings, placed at suitable intervals, by which the water escapes into the sewers. The surfaces of the trams are slightly inclined towards each other, the inner edges being $\frac{3}{8}$ inch lower than the outer edges; whilst the interspace is concave, having a versed sine or depression of $1\frac{1}{2}$ inches. The foundation of the roadway consists of a layer of screened gravel, about 6 inches deep, watered so as to form a compact mass. Two inches of sand is laid on the gravel, as a bed for the paving-stones. The upper surfaces of the trams are dressed flat and the ends square, to form close joints. The stone gratings for the gulleys are 32 inches long, formed with three slots 12 inches long and $1\frac{1}{2}$ inches wide. After the trams are placed, the other portions of the pavement are completed. After the surface has been well rammed with a wooden rammer, it is watered and covered with a bedding of sand $\frac{3}{4}$ inch deep, so as to fill the joints by degrees. On steep gradients the surfaces of the trams are grooved diagonally.

439. Trackways are expensive to construct (cost about \$14,000

per mile for two lines of track and intermediate paving in the neighborhood of New York), but cost little for repairs and maintenance. Their advantages are many: they combine the opposite qualities required for easy haulage, viz., a smooth surface for the wheels, on which the friction is reduced to the least possible amount, and a rough footway, affording a firm foothold for horses, thus enabling them to exert their utmost tractive power. For this reason they ought to receive more attention than is now accorded them. The friction of their surface is only about $\frac{1}{10}$ of the load, or about one half that of the best block pavement. It is stated that on such trackways in London a horse weighing about 700 pounds could draw on a level 15 tons, and a horse weighing about 1600 pounds could draw 30½ tons.

440. In Glasgow, Scotland, there was a trackway down for forty years. It consisted of cast-iron plates 2 inches thick, 8 inches wide, and cast in lengths of 3 feet. It was laid in Buchanan Street on a 5 per cent grade.

441. The trackways for the wheels may be of granite, or compact sandstone slabs 12 to 24 inches wide, 6 inches thick, and in lengths of 2 to 6 feet. The footway for the horses to be in all cases paved with cobblestones the other portions of the roadway may be paved with cobblestones, granite, or other pavement.

The foundation for the trackways should be constructed as shown in Fig. 29, with all the joints filled with asphaltic paving-cement.

The roadway may be formed in the usual manner with the trackways level (transversely), the surface falling from their outer edge to the gutters; but at frequent intervals in the horse-path catch-basins with iron or stone covers should be placed, connecting with the sewer. At track-crossings or junctions the surface of the slabs should be grooved, so as to afford good foothold for the horses passing over them.

442. "Jasperite."—Jasperite, under what is known as "Drake's Patent," consists of quartzite crushed to sizes of $\frac{1}{2}$, $\frac{1}{4}$, and $\frac{1}{8}$ of an inch, and known as Nos. 3, 4, and 5, respectively. The foundation is composed of irregularly broken stone set to form a rough pavement similar to that used for a Telford road. On this is spread a layer of concrete 1½ inches thick, composed as follows: 1 part of Portland cement, 1 part of sand, and 3 parts of quartzite of the sizes Nos. 3 and 4. This is well mixed, spread, and rammed into

place in such a manner as to form blocks one yard square. These blocks are separated by tarred paper. On the bed so formed is spread a layer one-half inch in thickness, prepared in the same way, but substituting quartzite of the size known as No. 5. This pavement is in use in Sioux Falls, S. D., and Wichita, Kan. The cost per square yard is about \$2.50, with a five-year guarantee.

443. Artificial Granite Blocks are formed from the chippings of granite quarries. It is mixed at the place where it is to be used with Portland cement in sufficient quantity to make a thorough bond between the pieces, and put down in blocks or squares so as to form separate stones as it were. Its surface is kept comparatively rough by the cement wearing below the points of the granite. Its advantage is, presumably, cheapness.

444. Plank Roads.—In localities where timber is abundant and other materials are unobtainable, planks may be employed to form pavements. When new and well laid they form a comfortable carriageway both for haulage and pleasure, but make when worn and displaced a very disagreeable road.

445. The method most generally adopted in constructing plank roads consists in laying a flooring or track 8 feet wide, composed of boards from 9 to 12 inches in width and 3 inches in thickness, which rest upon two parallel rows of stringers or sills laid lengthwise in the road and having their centre lines about 4 feet apart or 2 feet from the axis of the road. Sills of various-sized scantling have been used, but experience seems in favor of scantling about 12 inches in width, 4 inches in thickness, and in lengths of not less than 15 to 20 feet. Sills of these dimensions laid flatwise and firmly embedded present a firm and uniform bearing to the boards and distribute the pressure they receive over so great a surface that, if the soil upon which they rest is compact and is kept well drained, there can be but little settling and displacement of the road-surface from the usual loads passing over it. The better to secure this uniform distribution of the pressure, the sills of one row are so laid as to break joints with the other, and to prevent the ends of the sills from yielding the usual precaution is taken to place short sills at the joints, either beneath the main sills or on the same level with them.

The boards are laid perpendicular to the axis of the road, experience having shown that this position is more favorable to their

wear and tear than any other, and is besides the most economical. Their ends are not in an unbroken line, but so arranged that the ends of every three or four project alternately, on each side of the axis of the road, 3 or 4 inches beyond those next to them, for the purpose of presenting a short shoulder to the wheels of vehicles to facilitate their coming upon the plank surface when from any cause they may have turned aside. On some roads the boards have been spiked to the sills, but this is unnecessary, the stability of the boards being best secured by well packing the earth between and around the sills, so as to present a uniform bearing surface to the boards, and by adopting the usual precautions for keeping the sub-soil well drained and preventing any accumulation of rain-water on the surface. The boards for plank roads should be selected from timber free from the usual defects, such as knots and shakes, which would render it unsuitable for ordinary purposes, as durability is an essential element in the economy of this class of road-construction. Boards of 3 inches in thickness offer all the requisites of strength and durability that can be obtained from timber in its ordinary state, in which it is used for plank roads.

Besides the wooden track of 8 feet, an earthen track of 12 feet in width is made, which serves as a summer road for light vehicles and as a turnout for loaded ones. This, with the wooden track, gives a clear road-surface of 20 feet, the least that can be well allowed for a frequented road. It is recommended to lay the wooden track on the right-hand side of the approach of a road to a town or village, for the proper convenience of the rural traffic, as the heavy trade is to the town. The surface of this track receives a cross-slope from the side towards the axis of the road outwards of 1 in 32. The surface of the summer road receives a cross-slope in the opposite direction of 1 in 16. These slopes are given for the purpose of facilitating a rapid surface for draining. The side drains are placed for this purpose parallel to the axis of the road and connected with the surface in a suitable slope.

Where from the character of the soil good summer roads cannot be had, it would be necessary to make wooden turnouts from space to space, to prevent the inconvenience and delay of miry roads. This can be effected by laying at these points a wooden track of double width, to enable vehicles meeting to pass each other. It is recommended to lay these turnouts on four or five sills, to spring

the boards slightly at the centre, and spike their ends to the exterior sills.

In some of the earlier plank roads a width of 16 feet was given to the wooden track, the boards of which were laid upon four or five rows of sills. But experience soon demonstrated that this was not an economical plan, as it was found that vehicles kept the centre of the wooden surface, which was soon worn into a beaten track, whilst the remainder was only slightly impaired. This led to the abandonment of the wide track for the one now usually employed, which answers all the purposes of the traffic and is much more economical, both in the first outlay and for subsequent renewals and repairs. Plank roads possess great advantages in a densely-wooded country, and will be found superior to every other kind as a temporary expedient.

446. The cost per mile ranges from \$1000 to \$4000, and the life is about eight years.

447. Log Roads.—When a road passes over soft swampy ground, always kept moist by springs which cannot be drained without too much expense, and which is surrounded by a forest, it may be cheaply and rapidly made passable by felling a sufficient number of young trees, as straight and as uniform as possible, and laying them side by side across the road at right angles to its length. This arrangement is well known under the term “corduroy road.” Though its successive hills and hollows offer great resistance to draught and are very unpleasant to persons riding over it, it is nevertheless a very valuable substitute for a swamp, which in its natural state would at times be utterly impassable.

448. Charcoal.—In some of the Western States, where wood is abundant and cheap, roads covered with charcoal have been made as follows: Logs from six inches to two feet in diameter and from twelve to twenty-four feet long are cut and piled lengthwise along the road about six feet high, being nine feet on the bottom and two on top, and then covered with straw and earth, or simply with sods, and burned in the manner of coal-pits. The covering is taken from the sides of the road, and the ditches thus formed afford good drainage. After the timber is converted into charcoal, the earth is removed to the side of the ditches, the coal raked down to a width of fifteen feet, leaving it two feet thick at the center and one at the sides, and the road is completed.

449. A road thus made in Michigan cost \$660 per mile, and is said to be very compact and free from mud or dust. At a season when the mud on the adjoining earth road was half-axletree deep, on the coal road there was not the least standing, and the impress of the feet of a horse passing rapidly over it was like that made on hard-washed sand, as the surf recedes, on the shore of the lake. The water was not drained from the ditches, and yet there were no ruts or inequalities in the surface of the coal road, except what was produced by more compact packing on the line of travel. It is probable that coal will fully compensate for the deficiency of limestone and gravel in many sections of the West, and, where a road is to be constructed through forest land, that coal may be used at a fourth the expense of limestone.

450. Iron.—Iron is eminently durable, but as a pavement it is a failure. It is so slippery even when roughened that horses cannot gain a foothold on it. About thirty years ago Cortlandt Street in New York was paved with it. In order to guard against slipperiness the surface was made rough and consisted of hexagonal projections about an inch in size, separated by depressions of about the same size. It was both rough and noisy; the horses caught their calks in the depressions and twisted off their shoes, and in spite of its roughness the horses fell frequently and with disastrous results in tearing their knees on the sharp projections. It remained in use but a short time and was replaced with stone. Combinations of wood and iron, concrete and iron, are frequently introduced and experimented with, but so far none have been a practical success.

450a. Furnace Slag.—Slag and cinders from iron and copper works may be employed with advantage when they are procurable, and when no stone sufficiently tough to withstand the action of heavy traffic can be obtained. They are both very durable, but care is required in the selection of the tougher sorts. They have no binding properties, and on this account are sometimes used with limestone; a rough surface will, however, always result from the unequal wear of two materials so different in hardness. Limestone scrapings, coal ashes or clay, laid on as a binding material, aid consolidation very much, and also prevent injury to horses' feet from the sharp edges of the fresh-laid slag.

450b. Blocks formed by casting furnace slag in moulds are in use in England and other parts of Europe. Their quality varies with

the amount of silica contained: if this be about 35 per cent, the resulting blocks are tough; but if below 30 per cent, the block is brittle and easily broken. The process employed in England for the manufacture of these blocks, and which seems to produce a tough and durable article, is to run the slag from the furnace into a ladle, then pour it from this into iron moulds of the desired shape and size contained on an iron plate arranged to revolve; contact with the moulds chills the outside of the slag block immediately, and as the plate makes a half revolution the bottom of the mould is opened by mechanical means and the chilled block dropped either on a bed of sand or a conveyer. From here, and while the interior of the block is still in a molten condition, it is placed in an annealing oven, which, when fully charged, is sealed and allowed to cool, no heat being used other than that furnished by the blocks themselves.*

450c. Chert.—This material is employed for street and road paving in some of the Southern States, notably Alabama, where it is found in inexhaustible quantities overlying the red sandstone, which forms the covering of the red hematite iron ore, and underlying the sub-carboniferous limestone. The cities of Montgomery and Birmingham, Ala., and Macon and Savannah, Ga., have several miles of streets paved with it. There is also in both States several miles of country roads covered with it.

Chert is a valuable substitute for broken stone, especially where stone is scarce or of unsuitable character; it furnishes an excellent surface and wears well under traffic with but little dust or mud.

The material is usually laid upon a foundation of furnace slag or other convenient material, but in the absence of such it is laid directly upon the earth surface. The thickness employed varies from 3 to 5 inches. It is simply spread, sprinkled, and rolled. In Birmingham, Ala., the cost of the chert is 80 cents per cubic yard on the street, and the cost of the furnace slag, including hauling, spreading, and rolling, is from 30 to 40 cents per cubic yard.

The name "chert" is also applied to the slag derived from the blast furnaces in Alabama. This material is also employed for street and road paving.

450d. Florida Clay.—This name is given to a sandstone rock de-

* Scoria blocks are rarely free from internal cavities. When these are located near the upper surface the destruction of the block is materially accelerated.

posit found in Florida, the material from which has been extensively used in several towns of Florida for street and sidewalk paving. Its use has been the means of converting streets so sandy that travel over them was very slow and difficult into driveways over which travel is easy and pleasant.

The composition of this "clay" is as follows:

Moisture.....	4.20 per cent.
Silica	69.08 " "
Aluminum silicate.....	18.21 " "
Iron oxide.....	8.53 " "
Calcium carbonate.....	trace.

The most valuable constituent of this material, when used as a covering for roads, is, no doubt, the oxide of iron, which acts as a cement, rendering the material capable of becoming compact and hard.

For use the material is quarried and without any preparation is spread over the roadway to the depth of several inches, then sprinkled with water and compacted with a roller. It is of a reddish color, due to the presence of the oxide of iron. After being travelled over for a short time it becomes very compact and nearly as hard as it was in its native bed.

450e. Tar-macadam.—A paving composition called "tar-macadam" has been introduced in England; it consists of granite, coal-tar, refined asphaltum, and creosote oil in the proportions of 1 ton of granite broken into 1½-inch fragments, 12 gallons of coal-tar, 28 pounds of asphaltum, and 2 gallons of creosote oil; the ingredients are heated and thoroughly incorporated. The pavement is formed as follows: The foundation is composed of a layer of hard clinkers and broken stone, 10 inches in thickness, well consolidated by rolling with a 12-ton steam-roller; this is covered with a layer 4 inches thick of stone broken into 2½-inch fragments. This is also compacted by rolling; upon this is spread a 3-inch layer of the "tar-macadam"; this is thoroughly compacted by rolling and then covered with a 1-inch layer of limestone screenings mixed with the same cementing materials that are used in the macadam. This last layer is sprinkled with clean dry limestone screenings and rolled. The work should only be done in dry weather; the rolling should average 10 hours for each 100 square yards, and the traffic should not be admitted until at least 24 hours after the work is completed. The cost is from 84 cents to \$1.00 per square yard.

450f. Artificial Stone.*—Pavements formed of artificial stone or concretes composed of hydraulic cement, crushed stone, sand, and gravel, with sometimes the addition of some indurating mineral substance, as baryta, litharge, etc., have been tried; they are usually manufactured under a patent, either in place or in the form of blocks at a factory. While artificial stone is eminently suitable as a paving material for footwalks, it quickly fails under the action of horses' hoofs and wheels when used as a carriageway pavement.

450g. Hydraulic cement concrete is used in several cities as a paving material for alleys and is found very suitable; the following specifications show how these pavements are formed (see also Art. 786):

Specifications for Hydraulic Cement Pavement.—The material shall be excavated from the entire area proposed to be paved to a depth of eighteen (18) inches below the surface of the finished pavement; the excavation thus formed shall be filled to a depth of fourteen (14) inches with clean steam ashes or cinders, and these shall be thoroughly compacted by ramming. Upon the foundation so formed shall be laid a concrete composed of 1 part of Portland cement (either of Hilton or Manheimer brand) and 3 parts of clean, sharp, coarse sand, thoroughly mixed dry and made into mortar with the least quantity of water, and thoroughly intermixed with broken stone or furnace slag in such quantity (about 7 parts) that, when tamped or rammed solidly in place, free mortar will rise to the surface and exhibit a depth of three (3) inches of the said concrete. Upon this concrete foundation a surface mixture shall be laid one (1) inch in thickness, composed of 1 part of Portland cement (Dyckerhoff or Star Stettin brand) and 2 parts of crushed granite, with just sufficient water to make a stiff mortar; this surface coat shall be thoroughly compacted by tamping; and shall be dressed with a small quantity of dryer, composed of one half pure cement and one half flint sand, floated over the entire surface as a finish.

450h. Clinkers.—The clinkers produced by burning street sweepings and garbage and the *débris* produced in the manufacture of gas, consisting of the clinkers, old retorts, fire-bricks, ash-pan and coke refuse, have all been tried for paving both footpaths and

* Is used to some extent for the paving of carriageways in Bellefontaine, O., Sioux Falls, S. Dak., Grenoble, France, and in several cities in Germany. For the paving of alleys it is used in Philadelphia and other cities.

carriageways; in the former they are generally satisfactory, but in the latter they quickly fail.

The materials are prepared for use by crushing to a size of about one inch; the crushed material is screened; the portion that will not pass through a one-quarter inch screen is used for the top finish, and the coarser portion for the foundation. The materials so separated are mixed with either Portland cement or coal-tar, and laid in place in the usual manner; or they may be formed into blocks at a factory and shipped to the place of use. (Mixed with cement it is used at Hersey, a suburb of London, and is said to give satisfaction.)

450i. Glass.—An experiment with this material is being made in Lyons, France; the Rue de la République has been paved with *ceramocrystal*, or devitrified glass. This new product is obtained from broken glass heated to a temperature of 1250° F. and compressed in matrices by hydraulic force. The glass pavement is laid in the form of blocks 8 inches square, each block containing sixteen parts in the form of checkers. These blocks are so closely fitted together that water cannot pass between them, and the whole pavement looks like one gigantic checker-board. As a pavement it is said to have a greater resistance than stone, it is a poor conductor of cold, and ice will not form on it readily; dirt does not accumulate upon it so easily as upon stone, and it will not retain microbes.

450j. Novaculite (from the Latin *novacula*, a razor) is an uncrystallized quartzite, very much like flint, and occurs in large quantities in southern Illinois, Missouri, and Arkansas. It is employed for carriageway and sidewalk paving (under a patent) and appears to give satisfaction. Its composition is stated to be as follows:

Silica.....	94.48
Alumina.....	1.28
Iron oxide.....	3.12
Loss by ignition.....	1.12
	<hr/>
	100.00

Prof. J. B. Johnson says it is the hardest of rocks, scratches glass like a diamond, and resists all disintegrating action of the weather.

450k. Destructor Concrete.—In several English cities where crematories are employed for the destruction of the garbage, etc., the clinker therefrom is used for making concrete slabs. The clinker is ground very fine, and mixed in the proportion of one of Portland cement to two of clinker. The mass of clinker and cement, after being mixed, is passed through a hydraulic press and formed into slabs 2 inches in thickness, and are used for footpath paving under the name of "Destructor" concrete.

450l. Cork.—Pavements made from granulated cork mixed with asphalt and other cohesive substances are employed in London and other European cities to deaden the noise in the neighborhood of hospitals and churches. The ingredients are compressed into blocks measuring 9 by 4½ by 2 inches. The blocks are imbedded in tar and rest upon a concrete foundation 6 inches thick. The cost per square yard (32 blocks), including jointing material, but exclusive of laying and foundation, is about \$2.50.

It is claimed that as a paving material it is non-absorbent, non-slippery, practically noiseless, more durable than wood, perfectly sanitary, and not subject to expansion and contraction.

Blocks which have been under traffic for a number of years seem to have come through the ordeal with a satisfactory result which the name of the material would hardly suggest.

450m. Copper Slag.—Paving-bricks are made in Germany from copper slag. The slag is run into heated cast-iron moulds having a capacity of 36 bricks; immediately after filling the moulds and their contents are thickly covered with sand and allowed to stand undisturbed for seventy-two hours. When thoroughly cooled each brick is struck a strong blow with a hammer, and those containing blow-holes crack.

450n. Steel Trackways.—The experimental pieces of these trackways which have been constructed consist of two parallel lines of steel plates, eight inches wide, laid at a sufficient distance apart to receive the wheels of vehicles of the standard gauge. The plates are provided on one edge with a flange one-half inch wide, and on the under side with a flange about 6 inches deep, which, when bedded in the earth of the roadway, supports the rail without the use of cross-ties. Tie-rods are used at intervals of about 10 feet.

The advantages claimed for this style of road by its advocates are: 1. That it can be built without greater cost in most cases, and probably with less cost in many cases, than any other hard and durable road; 2. That it will last many times as long as any other known material for road purposes, and with much less repair; 3. That the power required to move a load over the steel trackway is only a small fraction of the power required to move the same load over any other kind of road.



FIG. 32A.—CROSS-SECTION OF STEEL TRACKWAY.

During 1892 a steel trackway was constructed between Valencia and Grao, Spain, at a cost of \$28,518. It is traversed daily by an average of 3200 vehicles, each of which pays a toll of about eight-tenths of a cent. The annual cost of maintenance is about \$380. The trackway replaces a stone road which cost \$5470 a year to maintain.

450o. India Rubber in large sheets about 1 inch in thickness has been tried at Hanover, and is said to be an excellent paving material. A small sample has been in use at the entrance to the Euston Railroad Station, London, for about 14 years, during which period the cost of repairs has been small. The sheets are laid upon a concrete foundation, and are held down by strips of iron which clasp the edges tight upon each side. It seems to meet nearly all the requirements of a perfect paving material, being exceedingly durable, not slippery, and absolutely noiseless and impervious. Its cost, however—about \$34 per square yard—prohibits its general use.

450p. Artificial Paving-stones are manufactured in Germany from a mixture of coal-tar, sulphur, chlorate of lime, glass or furnace slag. The process employed is to mix the tar and sulphur at a moderate temperature, and to this mixture add the chlorate of lime. The mixture is allowed to cool, then broken into small fragments and mixed with fragments of glass or blast-furnace slag

This mixture is heated to a moderate temperature, placed in moulds of the desired form, and subjected to a pressure of about 3000 pounds per square inch. The specific weight of the stone is 2.20, and the resistance to crushing 315 pounds to the square centimetre; the resistance to wear and tear in use is said to be half as great as that of Swedish granite.

The advantages claimed are: Durability equal to that of many stone roads; resistance to changes of temperature; a roughness of surface which gives horses a good foothold; non-transmission of sound; facility of cleansing on account of the closeness of the joints.

450q. Asphaltina is a patented material composed of coal-tar, resin, and sulphur.

450r. Asphalt-granite Pavement.—In this pavement the binder is laid on a concrete foundation in the ordinary manner, and while it is still soft fragments of granite or other hard stone, broken to a roughly pyramidal shape, are imbedded in the asphalt with their points upward, and just below the level of the surface of the finished pavement. The final layer of asphalt is put on over these stones and fills the interstices between them, and appears as smooth as an ordinary pavement. The object of this construction is to render the pavement non-slippery.

CHAPTER IX.

FOUNDATIONS.

451. THE stability, permanence, and maintenance of any pavement depends upon its foundation. If the foundation is weak, the surface will quickly settle unequally, forming depressions and ruts. With a good foundation the condition of the surface will depend upon the material employed for the pavement and the manner of laying it.

452. The essentials necessary to the forming of a good foundation are:

(1) The entire removal of all vegetable, perishable, and yielding matter. It is of no use to lay good material on a bad substratum.

(2) The drainage of the subsoil wherever necessary. A permanent foundation can only be secured by keeping it dry; for, where water is allowed to pass into and through it, its weak spots will be quickly discovered and settlement will take place.

(3) The thorough compacting of the natural soil by rolling with a roller of proper weight and shape until it forms a uniform and unyielding surface.

(4) The placing on the natural soil so compacted a sufficient thickness of an impervious and incompressible material which will effectually cut off all communication between the soil and the bottom of the pavement.

453. The character of the natural soil over which the roadway is to be built has an important bearing upon the manner of forming and the kind of foundation; each class of soil will require different treatment. Whatever its character, it must be brought to a dry and tolerably hard condition by draining and rolling. Sands and gravels which do not hold water present no difficulty in securing a solid and secure foundation; clays and soils retentive of water are the most difficult. Clay should be excavated to a depth of at least 18 inches below the surface of the finished covering, and the space

so excavated filled in with sand, furnace-slag, ashes, coal-dust, oyster-shells, broken brick, or other materials which are not excessively absorbent of water. Whichever of these materials is used, it should be thoroughly consolidated before laying the pavement.

In ground saturated with water a foundation may be formed of logs or layers of fascines; but unless the nature of the ground is such as will always insure the timber being kept in a wet or damp state, it will soon rot and the road will go to pieces. Therefore they should never be employed unless under unavoidable circumstances.

454. Sand.—Sand and planks, gravel, and broken stone have been successively used to form the foundation for pavements; but although eminently useful materials, their use for this purpose has been and always must prove a failure. They are inherently weak and possess no cohesion, and the main reliance both for strength and wear must be placed upon the surface-covering. This covering, being usually (except in case of sheet asphalt) composed of small units with joints between them varying from one half to one and a half inches possesses no elements of cohesion, and under the blows and vibrations of traffic the independent units or blocks will settle and be jarred loose. They are porous and the subsoil quickly becomes saturated with urine and surface-waters percolating through the joints; winter frosts upheave them and the surface of the street becomes blistered and broken up in dozens of places. The defects of plank foundations are stated in Art. 186.

Although sand, gravel, etc., by themselves are unsuitable as foundation materials for block pavements, still when used with judgment they form excellent foundations for broken-stone roads.

455. Sand Foundation.—The natural soil having been trimmed and thoroughly compacted by rolling to the cross-section which is to be given to the covering, a layer of sand four inches thick is spread uniformly, thoroughly wetted by sprinkling, and rolled; two other layers of four inches each are in like manner added and rolled. The compression effected by a roller weighing ten tons will reduce the thickness of twelve inches to eight a greater final thickness than this is unnecessary unless the natural soil is very yielding, when it may be increased to twelve or sixteen inches.

456. Blast-furnace Slag.—The ordinary brittle slag makes a very good foundation for a road, particularly on clay or wet soils, as by rolling the top pieces form a powder that fills the interstices

between the lower fragments so thoroughly that neither clay nor mud can work up through the layer, and on this the more durable wearing materials can be placed. It was found impossible to form any roads on the soft clay surface of the Centennial Fair grounds at Philadelphia until their beds had been prepared by a layer of well-rolled furnace-slag, after which they stood heavy teaming without under-drainage; the binding of the fragments of slag with the thorough filling of the interstices preventing any mud from working up through the first or cover layer, thus keeping the road from breaking up.

457. Concrete.—As a foundation for all classes of pavement (broken stone excepted) hydraulic-cement concrete is superior to any other. When properly constituted and laid it becomes a solid coherent mass capable of bearing great weight without crushing, and which if it fail at all must fail altogether. It is the most costly, but this is balanced by its permanence and saving in the cost of repairs to the pavement which it supports. It admits of access to subterraneous pipes with less injury to the neighboring pavement than any other, for the concrete may be broken through at any point without unsettling the foundation for a considerable distance around it, as is the case with sand or other incoherent material; and when the concrete is replaced and set, the covering may be reset at its proper level without the uncertain allowance for settlement which is necessary in other cases.

458. Thickness of Concrete.—The thickness of the concrete bed must be proportioned by the engineer; it should be sufficient to provide against breaking under transverse strain caused by the settlement of the subsoil. On a well-drained soil six inches will be found sufficient, but in moist and clayey soils twelve inches will not be excessive. On such soils a layer of sand or gravel, spread and compacted before placing the concrete, will be found very beneficial.

459. Concrete (called *beton* by the French engineers) is a species of artificial stone composed of (1) the matrix, which may be either lime or cement mortar, usually the latter, and (2) the aggregate, which may be any hard material, as gravel, shingle, broken stone, shells, brick, slag, etc.

The essential quality of concrete seems to be that the material of the aggregate should be of small dimensions, so that the cement-

ing medium may act in every direction round them, and that the latter should on no account be more in quantity than is necessary for that purpose. The aggregate should be of different sizes, so that the smaller shall fit into the voids between the larger. This requires less mortar and with good aggregate gives a stronger concrete. Broken stone is the most common aggregate.

It is usual to require that the stone shall be broken so as to pass any way through a 2-inch ring. To insure compact packing the aggregate should consist of a mixture of broken stone ranging from 1 to 3 inches, and pebbles which are at least equal to the strength of the mortar. Sun-dried or rain-soaked material is to be strictly avoided. The choice of the cementing substance, lime or cement, depends upon the use of the concrete.

460. The strength of concrete depends upon the cohesion of the matrix, adhesion to the aggregates, irregular bonding or interlocking of the coarser fragments, and upon the strength and proportion of each ingredient.

Concrete for pavement foundations should be dense and homogeneous, with the voids of the aggregate thoroughly filled with mortar, and the latter must again be so constituted that the voids between the grains of sand shall be closely filled by the cement paste.

Good concrete has a specific gravity of 1.5 to 2.5, according to its composition of crushed bricks or heaviest stones. A cubic yard weighs from 2500 to 3900 pounds.

461. Proportions.—The proportions of the ingredients required for the manufacture of concrete may be ascertained by measuring the respective voids.

The proportion of voids may be determined by experiment in either of the ways described in Art. 373, page 207.

The voids of broken stone, in which the size and shape of the pieces are nearly uniform, are about 0.5 of the mass. If the pieces are not uniform, the voids are about 0.4 of the mass. The voids in gravel vary, but average about 0.5 of the mass.

462. The voids between the grains of sand will probably average 33 per cent; that is to say, 67 per cent of the cubic contents to be occupied by the mortars are absorbed by the solids of the grains of sand and 33 per cent are to be filled in with cement, so that a mortar of one part of cement to two of sand, and no more, is

required for water-tight work. A strong water-tight concrete will contain by volumes as follows: cement, sand, stone, as 1 : 2 : 5; and with fine Portland this mixture may reach after four weeks a compressive strength of 175 tons per square foot. The eight volumes of material fill finally a space of about 5.2 volumes.

463. The addition of water must be limited to the actual requirements, which fluctuate for natural cements between 50 and 55 per cent, and for Portland cement between 40 and 45 per cent, of the weight of the cement used. Plasticity is only to be attained by diligently tamping an apparently dry mass until water appears on the surface.

464. The following are some of the more usual proportions:

American hydraulic cement.....	1 part
Sand.....	2 parts
Broken stone.....	8 "
Portland cement..	1 part
Sand.....	3 parts
Broken stone.....	.5 to 7 "
Portland cement.....	1 part
Sand.....	2½ parts
Gravel.....	3 "
Broken stone	5 "

Tests of this formula showed a filling of voids within 6% of the whole volume. One barrel of cement weighing 380 pounds net made 1.18 cubic yards of concrete weighing when dry 136 pounds per cubic foot. Cost per cubic yard, \$6.

For one cubic yard of concrete of stone, gravel and sand, without voids, the following quantities of materials are required:

Broken stone 50% of its bulk voids.....	1.00	cubic yard
Gravel to fill voids in the stone.....	.50	" "
Sand " " " gravel.....	.25	" "
Cement " " " sand.....	.125	" "

For one cubic yard of concrete of stone and sand without voids, the following quantities of materials are required:

Broken stone 50% of its bulk voids.....	1.00	cubic yard
Sand to fill voids in the stone.....	.50	" "
Cement " " " sand.....	.25	" "

465. Mixing.—The concrete may be mixed by hand or by machinery. In the first method the cement and sand are mixed dry. About half the sand to be used in a batch of concrete is spread evenly over the mortar board, then the dry cement spread evenly over the sand, and then the remainder of the sand is spread on top of the cement. The sand and cement are then mixed with a hoe or by turning and re-turning with a shovel. It is very important that the sand and cement be thoroughly mixed. A basin is then formed by drawing the sand and cement to the outer edges of the box, and the water is poured into it. The sand and cement are then thrown back upon the water, the whole mass thoroughly mixed with the hoe or shovel, and then levelled off. The broken stone should be sprinkled with sufficient water to remove all dust and thoroughly wet the entire surface. The amount of water required will vary considerably with the absorptive power of the stone and the temperature of the air. The wet stone is then to be spread evenly over the top of the mortar, and the whole mass thoroughly mixed by turning up with a shovel. When the aggregate consists of broken bricks or other porous material it should be thoroughly wetted and time allowed for absorption previous to use; otherwise it will take away part of the water necessary to effect the setting of the cement.

466. Laying.—After mixing, the concrete is conveyed in wheelbarrows and compacted in position by ramming in layers. When the thickness is to be 6 inches it should be laid in one layer; if thicker, in two equal layers, the surface of the first layer being moistened before spreading the second. If too much water has been used in mixing, it will be impossible to compact it by ramming. When ready for use the concrete should be quite coherent and capable of standing at a steep slope without the water running from it. Ramming, when properly done, consolidates the mass about 5 or 6 per cent, rendering it less porous, and very materially stronger. The rammers are, like those used in street-paving, of wood, about 4 feet long, 6 to 8 inches in diameter at foot, with a lifting-handle, and shod with iron; weight about 35 pounds. They are let fall six or eight inches. The men using them, if standing on the concrete, should wear india-rubber boots to protect their feet from corrosion by the cement.

The ramming should be continued only until the water begins

to ooze out on the upper surface. Too severe or long-continued pounding injures the strength of the concrete by forcing the broken stone to the bottom of the layer, and by disturbing the incipient set of the cement. When the concrete is rammed, walking should not be permitted on it for at least 12 hours; 24 would be better. It is necessary to give the concrete abundance of time to dry and set. This precaution is indispensable. If an undue amount of moisture should remain after the superstructure is laid, it will destroy the homogeneous qualities of the concrete.

467. A correctly proportioned concrete has fully as much strength as the cement-mortar used in mixing it. By diminishing the aggregate below the calculated quantity the cost of concrete is increased without benefit to strength.

The transverse strength of concrete ranges between 50 and 400 pounds, depending upon the character of the cement and skilfulness of manipulation.

468. Compressive Strength.—Trautwine says that cubes of Portland cement, sand, and broken stone, "well made and rammed, should, either in air or in water, require to crush them at different ages not less than about as follows:

Age in months.....	1	3	6	9	12
Tons per square foot.....	15	40	65	85	100

Under favorable conditions of materials, workmanship, and weather, the strengths may be from 50 to 100 per cent greater."

The compressive strength of 6-inch cubes of concrete exposed to the air for six months, as determined in connection with the construction of the St. Louis Bridge, was as follows: with the proportions of 1 part cement (Akron and Louisville), 1 part sand, and 4 parts broken limestone, the mean compressive resistance for nine trials was 1200 pounds per square inch (85 tons per square foot); and with the proportions of 1, 2, 4, respectively, the average resistance for twelve trials was 940 pounds per square inch (70 tons per square foot).

Tests with the United States testing-machine at Watertown, Mass., between steel gave an average of 1544 pounds per square inch (110 tons per square foot) for 4-inch to 6-inch cubes of concrete 46 months old composed of 1 part Rosendale cement-paste, $1\frac{1}{2}$ parts sand, and 6 parts broken stone. Under the same condi-

tions, concrete composed of 1 part Rosendale cement-paste, 3 parts sand, and 6 parts broken stone stood 1021 pounds per square inch (73 tons per square foot). Another sample of cement gave 1078 pounds per square inch (77 tons per square foot) for concrete 22 months old composed of 1 part cement paste, 3 parts sand, and 4 parts broken stone. Ten experiments with a single sample of Portland cement gave 3067 pounds per square inch (219 per square foot) for concrete composed of 1 part cement paste, 3 parts sand, and 6 parts broken stone. The concrete under the Washington monument, composed of 1 part Portland, 2 parts sand, 3 parts pebbles, and 4 parts broken stone, when six months old stood 2000 pounds per square inch (144 tons per square foot).

Experiments made in connection with the construction of the Vyrnwy dam—built to impound water for the supply of Liverpool, England—gave an average strength from six experiments, for cubes of mortar composed of 1 part Portland cement and 2 parts of sand from 32 to 37 months old, crushed between pine cushions $\frac{1}{4}$ inch thick, of 4428 pounds per square inch (284.7 tons per square foot); and cubes of concrete composed of gravel and sufficient mortar composed as above to fill the interstices gave an average strength, for two cubes 35 and 36 months old, of 3497 pounds per square inch (224.9 tons per square foot). The blocks were made from the concrete actually used in the work, and were moulded by ordinary workmen without supervision, with the intention of securing blocks representative of the concrete as laid in the work. For cubes of the concrete tested between "mill-boards" (straw-boards) the same series of experiments gave results as follows:

Age of the Blocks. Months.	Number of Experiments.	Mean Crushing Strength.	
		Lbs. per sq. in.	Tons per sq. ft.
32-36	3	2,865	170.4
20-30	6	2,278	164.0
5-8	2	1,742	125.5
1-2 $\frac{1}{2}$	7	1,477	106.4

469. Cost.—The cost of concrete varies greatly, depending upon the kind of mortar, whether lime or cement; upon the richness

of the mortar; upon the proportion of aggregate to mortar, upon the cost of the ingredients and of the labor, etc.

It varies from \$4.00 to \$6.00 per cubic yard with Rosendale cement, and from \$6.00 to \$9.00 per cubic yard with the Portland cement. The cost for pavement foundations ranges from 94 cents to \$1.50 per square yard.

PORTLAND-CEMENT CONCRETE.

Proportions:

Cement.....				1 part
Sand.....				8 parts
Broken stone.....				5 "
Portland cement.....	1.28 bbls.	at \$2.60	=	\$3.38
Sand.....	0.50 cu. yd.	" 1.80	=	0.65
Broken stone.....	0.90 "	" 1.23	=	1.12
Labor.....	0.91 day	" 1.75	=	1.59
Foreman.....	0.07 "	" 3 00	=	0.21
Total cost of one cubic yard in place.....				\$6.90

470. An excellent concrete is made of 80 parts of furnace-slag (crushed) and 20 parts of asphaltic cement; the slag and cement should be heated before mixing, and be laid while hot.

471. As the value of concrete depends principally upon the matrix or cementing medium, a thorough knowledge of the mortar and the characteristics of its ingredients is indispensable for successful manipulation.

The material employed for the manufacture of mortar are:

- (1) Lime (common and hydraulic).
- (2) Hydraulic cements (natural and artificial).
- (3) Sand.

472. **Common Lime** is derived from the calcination of pure and impure limestones, and is extensively employed for the manufacture of mortar used in building construction. It is unsuitable for the manufacture of concrete. Concretes in which it is used as a matrix are permeable, weak, and liable to rupture from sudden shock. Lime mortar sets or hardens slowly, and if deprived of air setting may never take place, as it hardens mainly through the aid of carbonic acid gas, which it absorbs slowly from the atmosphere.

Hydraulic Lime is in many respects similar to common lime, but possesses the property of hardening under water. This class of

lime is much used in Europe, but there is none produced in the United States.

473. Hydraulic Cement is of two classes, natural and artificial. The American natural or Rosendale type of cement is made by burning in ordinary draw-kilns cement rock composed of limestone intimately mixed with silica, alumina, magnesia, etc., and grinding the calcined product to powder. The cement thus produced depends for its uniformity upon the homogeneity of the rock from which it is made.

These cements are of a porous, globular texture, with a specific gravity of about 2.7. They do not heat up nor swell sensibly whilst they are mixed; they set quickly in air, but harden slowly under water, without shrinking, and attain great strength with well-developed adhesive force.

Color.—The color of these cements gives no clue to their cementitious value, since it is chiefly due to oxides of iron and manganese, which bear no direct relation to the hydraulic properties.

To insure efficient chemical action in hardening, the grinding must be carried to the production of impalpable powder. These cements bear admixture of sand to double their own volume and over. For mixing pure cements from 30 to 40 per cent of water must be added.

Many American cements of this class contain large percentages of carbonate of magnesia. Pure carbonate of magnesia, when burned at a moderate heat, ground to fine powder, and made into paste with sea-water, makes a cement which is superior in hardness and strength to any other, not excepting even Portland cement. These cements give good adhesion to stones and bricks, because they part with their surplus water more slowly than the others. Whenever judiciously selected and conscientiously manipulated they have given full satisfaction. Many causes co-operate in affecting rocks of the compound character required for the production of hydraulic cements. Deleterious material is disseminated through the various strata of a quarry in constantly and widely changing proportions, each stratum exhibits heterogeneous features. Hence it taxes judgment, begotten of large experience, honesty, carefulness, and skill, to keep up reasonably uniform quality.

Different quarries show dissimilar stones. The best brands vary greatly in chemical composition. Fineness, density, thorough and

homogeneous mixture, humidity, accessory ingredients, enter largely into the problems.

To preserve the activity and strength of the natural cements, air and moisture must be excluded by careful packing and dry storage of the barrels; otherwise the premature development of carbonate of lime will interfere with the subsequent hydration.

Prof. DeSmedt found for our native Virginia cements in pure state, after 30 days' exposure, 170 to 250 pounds tensile strength per square inch, which increased in 11 months to 316 to 381 pounds. Mixed with equal proportions of sand he obtained from 116 to 155 pounds and 180 to 190 pounds as above.

Gillmore states the adhesion of Rosendale cement to front bricks, after 28 days, when pure to be 30 pounds, and when mixed with one or two parts of sand 16 and 12 pounds.

Clarke reports the tensile strength of these Rosendale cements, pure, after one and twelve months, as 145 and 290 pounds respectively; when mixed 1 to 1, to 116 and 256 pounds; when mixed 1 to 2, 60 and 180 pounds; and when mixed 1 to 3, 35 and 121 pounds after the same periods.

One cubic foot of Rosendale cement weighs 49 to 59 pounds. The proportion of tensile to compressive strength averages probably after a month 1 to 4, and rises after two years about 1 to 6 or 7.

The specifications of the Engineers' Department of the District of Columbia require seven days after mixture, for neat, natural cement, 95 pounds, and for mixtures with one and two parts of sand 56 and 22 pounds tensile strength per square inch, respectively. The gradual increase of strength by time is carefully noted and establishes the reputation of the accepted brands.

474. Natural Portland Cement.—Portland cement derives its name from the resemblance which hardened mortar made of it bears to a stone found in the isle of Portland, off the south coast of England. It is manufactured in those rare cases where rocks are traced which contain combinations of lime and silica of alumina in the chemical proportions and physical condition found necessary for producing artificial Portland.

The treatment then differs from that of ordinary cement only in the higher temperature for burning. There are extensive works of this class around Perlmoos in Germany, Grenoble in France, etc.

475. Artificial Portland Cement.—Fully 95 per cent of all the

Portland cement used at the present day is artificial. It is made by thoroughly mixing together, in suitable proportions, clay and finely pulverized carbonate of lime (either chalk, marl, or compact limestone), burning the mixture in kilns at a high temperature, and then grinding the burned product between ordinary millstones. The result is an impalpable, dense, drossy, steel-hard powder, having a specific gravity of 3.0 to 3.15. A few weeks' storage seasons the powder and makes it ready for use.

As accessory ingredients, sulphate of lime and other combinations of sulphur occur in Portland cement, which, combining with seven chemical equivalents of water, and even more, cause considerable increase of volume. This explains why a large percentage of sulphuric acid endangers the durability of hydraulic cements, while a small addition of it tends to increase their strength.

If the contents of clay in Portland cement rise above 50 per centum of the calcined lime (overclayed cement), complete vitrification is to be feared during the burning; the lack of cementing substance (lime) is felt, and the cement becomes an inert mass unfit for use. On the other hand, an "overlimed" cement tends toward quick setting and blowing or expansion. These effects, due to the presence of free caustic lime, may be remedied by airing such cement for a day or more, when the caustic lime will absorb carbonic acid from the air and become a neutral body for the cement. There is for each material one most favorable proportion in which the tendencies to shrinking and to expanding neutralize each other, so that a good cement is the result.

The chemical reactions require for cement burned at white heat only half as much water as those burned at moderate heat; this no doubt contributes to the superior strength of the Portland. Water in the proportion of 20 to 25 per cent of the weight of the cement generally suffices for mixing pure cement. Mixtures with sand, according to its dry or moist state, require increased quantities. By far the strongest mortar, with or without sand, results from mixtures in a state of incoherent dampness, with no more plasticity than absolutely necessary for the work in hand.

Too long-continued stirring or excess of water prevents setting, a paste being formed which slowly hardens by shrinkage, caused by evaporation and pressure, analogous to fat lime.

Normal material and treatment result in slow and cool setting

but comparatively low adhesive power. The tensile strength increases for a slow-setting Portland cement gradually for about two years, while the compressive strength increases for many years.

All Portland cements bear the admixture of large quantities of sand, but an excess retards setting and reduces the tensile strength. Mixtures of 1, 2, 3, and 4 parts of sand to one part of cement showed one year after mixing a reduction of 25, 50, 60, and 70 per centum (Michaelis and Grant's tests). An excess of sand makes a harsh, raw mixture, difficult of manipulation and hence unsuitable for architectural work.

Magnesia as a prominent ingredient of the limestone, used as raw material for producing Portland cement, acts badly, even treacherously. It does not harden hydraulically either with silica or with alumina; hence it remains as calcined magnesia, simply ballast, which lessens the quantity of hydraulic substances. Mixed with water it forms a hydrate of no high cementitious value. The absorption of water proceeds the slower the stronger the magnesia has been calcined. In consequence the hydration takes place at a time when the hydraulic hardening of Portland cement is virtually completed, and the swelling, due to larger masses of magnesia, causes a destruction of this cohesion already attained, and this has caused the collapse of bridges and buildings, and the crumbling of plastering on walls in France, according to the observations of Lechartier, Deville, and Calvert. This belated increase of volume escapes observation under the ordinary tests for expansion and requires special caution. Portland cements containing more than 5 per cent of magnesia should be rejected.

476. Characteristics of Portland Cement.

Color.—The color should be a dull greenish gray, caused by the dark ferruginous lime and the intensely green maganese salts. Any variation from this color indicates the presence of some impurity: blue indicates an excess of lime; dark green, a large percentage of iron; brown, an excess of clay; a yellowish shade indicates an underburned material.

Fineness.—It should have a clear, almost floury feel in the hand; a coarse, gritty feel denotes coarse grinding. The fineness should be such that 80 per cent will pass through a sieve of 2500 meshes to the square inch.

Weight.—It should weigh from 84 to 88 pounds per cubic foot.

A cement weighing from 70 to 80 pounds per cubic foot is invariably a weak one, though it may be of the requisite fineness; at the same time a heavy cement if coarsely ground is also weak and will have no carrying capacity for sand.

Light weight may be caused by laudable fine grinding, or by objectionable underburning. In testing, weight and fineness must be taken in conjunction.

Specific Gravity, between 3 and 3.05. As a rule the strength of Portland cement increases with its specific gravity.

Tensile Strength.—When moulded into a briquette and placed in water for seven days it should be capable of resisting a tensile strain of from 300 to 400 pounds per square inch.

Setting.—A pat made with the minimum amount of water should set in not less than three hours nor take more than six hours.

Expansion and Contraction.—Pats left in the air or placed in water should during or after setting show neither expansion nor contraction, either by the appearance of cracks or change of form.

A cement that possesses the foregoing properties may be considered a fair sample of Portland cement and would be suitable for any class of work.

Portland cement, although the best material that can be used as a cementing medium, should not be used by any one who is not prepared to take the trouble and incur the trifling expense of testing it; because if manufactured with improper proportions of its constituents, or improperly burnt, it may do more mischief than the poorest lime.

477. Cement Tests.—As the value of cements varies greatly with their physical properties, and since one lot of cement is liable to differ very much from another lot of the same brand, it is necessary, in order to obtain an idea of their relative merits, to make a series of tests as to the effect that the amount of sand, water, temperature, pressure, age, etc., has upon them.

How to carry out and interpret the results of various tests of cements involves great care and study and erroneous conclusions may be arrived at when undertaken by those not thoroughly acquainted with the subject and with the particular cements to be tested.

478. The properties of a cement which are usually examined to determine its constructive value are (1) color, (2) weight, (3) activity, (4) soundness, (5) fineness, and (6) strength. The last three are the most important.

479. Color.—As previously stated, the color of American natural cements has no influence upon its quality. The color of these cements is generally brown, ranging from very light to dark brown. Sometimes a very light color indicates an inferior or underburned rock. With Portland cement it is different; the color has an important bearing upon its quality; it should be dull greenish gray, and any deviation from this indicates impurities, as stated in Art. 476.

480. Weight.—For any particular cement the weight varies with the degree of heat in burning, the degree of fineness in grinding, and the density of packing. Other things being the same, the harder-burned varieties are the heavier. The finer a cement is ground the more bulky it becomes, and consequently the less it weighs.

The weight per unit of volume is usually determined by sifting the cement into a measure as lightly as possible, and *striking* the top level with a straight-edge. In careful work the height of fall is specified. Since the cement absorbs moisture, the sample must be taken from the interior of the package. The weight per cubic foot is neither exactly constant, nor can it be determined precisely; and for the practical purpose of the user is of very little service in determining the value of a cement. However, it is often specified as one of the requirements to be fulfilled.

481. The following values, determined by sifting the cement with a fall of three feet into a box having a capacity of one tenth of a cubic foot, may be taken as fair average for ordinary cements. The difference in weight for any particular kind is mainly due to a difference in fineness.

Portland, English and German.....	77 to 90 lbs. per cu. ft.			
" fine ground French.....	69	"	"	"
" American.....	95	"	"	"
Roman.....	54	"	"	"
Rosendale	49 to 56	"	"	"
Lime of Telf	50	"	"	"

Since a bushel is 1.244 cubic feet, the weight per bushel can be approximately obtained by adding 25 per cent to the above quantities. However, it is better to make the cubic foot the standard unit measure.

482. Activity.—A mortar is said to have set when it has attained such a degree of induration that its form cannot be altered without causing a fracture, i.e., when it has entirely lost its plasticity. Some cements set quickly, while others are comparatively slow in developing the first indications of hydraulicity. This property is called hydraulic quickness or activity. A quick-setting cement is especially valuable in constructions under water.

A distinction should be carefully made between hydraulic activity and hydraulic energy or strength. The former refers to the time required to attain a small degree of strength, and the latter to the amount of strength ultimately attained. There is no necessary relation between time of setting and ultimate strength; but, as a general rule, the slow-setting cements ultimately attain to a greater strength than quick-setting ones.

The activity of cement may be increased by adding a quicker-setting cement, as plaster of paris, lime, clay, or even grease,—all such ingredients, particularly the last, weakening the resulting mortar.

483. “The effects of a variation of temperature upon the hydraulic quickness of mortars—whether derived from hydraulic cement, a mixture of common lime and pozzuolana, or produced by artificial means—is very marked: so much so, indeed, that in all comparative tests of this kind it is important to adopt some fixed standard of temperature, not only for the water with which the cement is mixed, as well as that in which the cement is immersed, but for the dry ingredients and the surrounding atmosphere. All cements are not equally sensitive to a variation of temperature.”

The rise in temperature is much more apparent in the setting of quick-setting cements than in others, because the external cooling is relatively much less.

Herzog obtained the following results concerning the rise in temperature of a Portland cement, which he formed while wet into a prism 10 centimeters long and at another time into a prism 20 centimeters long. In each case the original temperature was 13.5 degrees C.

TEN CENTIMETERS LONG.

Immediately after moulding.....	16	degrees C.
After 30 minutes.....	17	" "
" 70 "	17.5	" "
" 4 hours	18	" "
" 5 "	18.5	" "
" 6 "	23.5	" "
" 7 hours and 30 minutes.....	27	" "
" 8 " max ..	29.5	" "

TWENTY CENTIMETERS LONG.

Immediately after moulding.....	19	degrees C.
After 1 hour and 30 minutes.....	20.5	" "
" 2 " " 30 "	22	" "
" 4 " " 30 "	24	" "
" 5 " " 30 "	38	" "
" 7 "	43	" "
" 8 "	45	" "
" 8 " and 80 minutes, max	45.5	" "

Thus we see that the temperature increased 16 degrees in one case and 32 degrees in the other; accordingly the rise in temperature was proportional to the side of the cement-prism. Thus it will be seen that all theories about the rise in temperature of setting cements have no value unless they take the volume of cement into account.

484. The quantity of water used in gauging the cement has great influence upon the tensile strength and must be regulated according to the kind of cement, since every cement has a certain given capacity for water; of course, however, in practice a quantity that is somewhat greater than this must generally be used.

In the following table by Feichtinger it will be seen that the amount of water absorbed from the air by Portland cements (column 1) and hydraulic limes (columns 2, 3, 4) varies considerably with the time.

In practice about 50 per cent of water is generally used, which is a great excess, so that there is usually about 30 per cent of water to be driven off by evaporation. If an undue amount be employed, the tensile strength is reduced to a considerable extent. On the other hand, if the quantity be as small as possible consistent with proper manipulation, the result will be much higher. From numerous

TABLE XLIV.
AMOUNT OF WATER ABSORBED BY CEMENT AND LIME

	1 per cent.	2 per cent.	3 per cent.	4 per cent.
Fresh ground.....	.99	1.28	.61	6.79
After 4 hours.....	1.41	1.67	.71	7.80
" 20 ".....	2.29	2.08	1.14	8.26
" 8 days.....	5.62	3.42	1.82	8.07
" 7 ".....	6.58	3.85	2.15	11.20
" 14 ".....	7.96	4.46	2.63	11.80
" 28 ".....	10.52	8.30	6.20	14.48
" 80 ".....	11.56	9.50	7.40	14.65

experiments it has been found that, as a general rule, a proportion of 1 part of water to 3 parts of cement by measure, or 1 to $3\frac{1}{2}$ by weight, is the best, both as regards convenience of mixing and results. With a much less quantity the gauging would be so stiff as to render the manipulation most difficult; the risk of air-holes, the reduction of which to a minimum is a point to be particularly attended to, would be augmented; the angles of the mould would be imperfectly filled, and generally a very imperfect briquette formed. Consequently the results of such tests would be unsatisfactory and unreliable. In general practice it will be found that a slight variation in the above-mentioned proportions will be necessary, depending upon the age and degree of fineness of the cement, but only to a limited extent.

485. Effect of Age on the Cement.—The age of Portland cement, although strictly not a condition of manufacture, is an important element in its economical and safe use. Cement not only improves generally by keeping, but the older the cement the less danger will there be of its blowing, as the free lime would be acted upon by the atmosphere, causing it to slake and reducing the danger and expansion to a minimum. The age has also been found to exert considerable influence upon the rate of setting, causing it to require a much longer time to set than new cement.

486. Tests of Activity.—To test hydraulic activity, mix cement with 25 to 30 per cent of its weight of clean water having a temperature of between 65 and 70 degrees Fahr., to a stiff plastic mortar, and make one or two cakes or pats two or three inches in diameter and about $\frac{1}{2}$ inch thick. As soon as the cakes are pre-

pared immerse in water at 65 degrees Fahr., and note the time required for them to set hard enough to bear respectively a $\frac{1}{16}$ -inch wire loaded to weigh $\frac{1}{2}$ of a pound and a $\frac{1}{4}$ -inch wire loaded to weigh 1 pound. When the cement bears the light weight, it is said to have begun to set; when it bears the heavy weight, it is said to have entirely set. Cements, however, will increase in hardness long after they can just bear the heavy wire. The activity of the cement is measured by the interval which elapses between the time when the first weight is supported and that when the second is just borne. Notice that with the wires as above the weight per unit of surface in the second case is 16 times as much as in the first. Hence it is not necessary to have the diameters as stated, but only to have the pressure per unit of area 16 times greater in the one case than in the other. The same wire may be used in both tests, the load only being varied. Different kinds and brands of cement vary greatly in the time required to set. Some brands of Rosendale cement will support the heavy wire in two minutes, and some brands of Portland in not less than 12 hours. Cold retards the setting. Freshly-ground cements set quicker than old ones. The quick-setting cements usually set so that experimental samples can be handled within five to thirty minutes after mixing. The slow-setting cements require from 1 to 8 hours.

487. Quick- and Slow-setting Cements.—Cements which set in less than half an hour are termed quick-setting, and those which do not set before two hours, slow-setting. These distinct definitions ought to be specially introduced in important specifications, where they will prevent misunderstandings as to what is meant by a slow-setting cement. Excepting special cases, slow-setting cements are more trustworthy.

488. Soundness.—Soundness refers to the property of not expanding or contracting or cracking or checking in setting. These effects may be due to free lime, free magnesia, or to unknown causes. Testing soundness is therefore determining whether the cement contains any active impurity. An inert adulteration or impurity affects only its economic value, but an active impurity affects also its strength and durability.

The most simple test for detecting expansion in a cement is to make small pats with a trowel, about 3 or 4 inches square, and place them in water when sufficiently set, where they should

remain a few days. If the cement be good, they will show no alteration in form; but any cracks showing on the edges, or other deviations from the original shape of the pats, indicate that the cement is of an expansive nature and therefore not to be trusted. But because a cement will not stand this test it is not in all cases to be condemned as useless, as its expansive or blowing property may be attributable to its being used too soon after leaving the mill. A proper process of cooling, placing it in a thin layer on a dry floor for a short time, will correct the defect.

Contraction due to the cement being over-clayed may be detected by a similar test to that for expansion.

The soundness of a cement may also be tested by placing some mortar in a glass tube (a swelled lamp-chimney is excellent for this purpose) and pouring water on top. If the tube breaks, the cement is unfit for use in damp places. A less delicate and less valuable test than either of the above is to note whether the cement heats when mixed with water. A thermometer is sometimes used in making this test.

The tests of soundness should not only be carefully conducted, but should extend over considerable time. Occasionally cement is found which seems to meet the usual tests for soundness, strength, etc., and yet after a considerable time loses all coherence and falls to pieces.

489. Fineness.—The question of fineness is wholly a matter of economy. Cement, until ground, is a mass of partially vitrified clinker which is not affected by water and which has no setting power. It is only after it is ground that the addition of water induces crystallization. Consequently the coarse particles in a cement have no setting power whatever, and may for practical purposes be considered only as so much sand and essentially an adulterant.

There is another reason why it should be well ground. A mortar or concrete being composed of a certain quantity of inert material bound together by a cementing material, it is evident that to secure a strong mortar or concrete it is essential that each piece of aggregate shall be entirely surrounded by the cementing material, so that no two pieces are in actual contact.

Obviously, then, the finer a cement the greater surface will a given weight cover, and the more economy will there be in its use.

Fine cement can be produced by the manufacturers in three ways: (1) by supplying the millstones with comparatively soft, underburnt rock which is easily reduced to power; (2) by running the stones more slowly, so that the rock remains longer between them; or (3) by bolting through a sieve and returning the unground particles to the stones. The first process produces an inferior quality of cement, while the second and third add to the cost of manufacture.

490. Measuring Fineness.—The degree of fineness of a cement is determined by measuring the per cent which will not pass through sieves of a certain number of meshes per square inch. The committee of the American Society of Civil Engineers recommended the determination "by weight of the per cent that is rejected by sieves of 2500, 5476, and 10,000 meshes to the square inch respectively, the first-mentioned sieve being of No. 35, the second of No. 37, and the third of No. 40, wire gauge. These sieves are usually referred to by the number of meshes per linear inch; the first being known as No. 50, the last as No. 100. It is stated that, as sold, the number of meshes varies somewhat, and the number of wires is generally less by about 10 per cent than the number of the sieve. The diameter of the holes is about equal to the diameter of the wire.

German Portland cements are commonly ground finer than English. "Most English manufacturers grind their cement to such a degree of fineness that when sifted through a sieve having 2500 holes (50 by 50) to the square inch, it shall leave a residue of not more than 10 per cent by weight. Cement ground to this fineness will leave from 19 to 20 per cent of residue on a 4900 (70 by 70) sieve, and practically nothing on a 625 (25 by 25) sieve." This is supposed to be the most economical degree of fineness.

Different brands of Rosendale cement vary considerably in their fineness. Those of the best reputation will leave from 4 to 10 per cent residuum on the No. 50 sieve; other brands, from 10 to 23 per cent.

491. Strength.—Although in ordinary practice cements are subject only to compression, yet at the present time all tests are made with a view to ascertaining their tensile strength. The reason for this is that comparatively light strains produce rupture; and that when rupture does take place, the strain causing it is really

due to tension produced by the sinking of one part of the structure and not to compressive force.

492. The Testing-machine.—The details of the form of the specimen to be tested (the briquette), as recommended by the Committee of the American Society of Civil Engineers, are given in Fig. 33. The method of placing the briquette in the machine is shown in Fig. 34. In applying the stress, it is also recommended to make the initial strain 0, and increase it regularly at the rate of 400 pounds per minute until rupture takes place. "For a weak mixture one half the speed is recommended."

There are many machines on the market, made specially for testing the strength of cement. Fig. 35 represents a cement-testing machine which can be made by an ordinary mechanic at an expense of only a few dollars. Although it does not have the conveniences and is not as accurate as the more elaborate machines, it is valuable where the quantity of work will not warrant a more expensive one, and in many cases is amply sufficient.

It was devised by F. W. Bruce for use at Fort Marion, St. Augustine, Florida, and reported to the *Engineering News* by Lieutenant W. M. Black, U. S. A.

The machine consists essentially of a counterpoised wooden lever 10 feet long, working on a horizontal pin between two broad uprights 20 inches from one end. Along the top of the long arm runs a grooved wheel carrying a weight. The distances from the fulcrum in feet and inches are marked on the surface of the lever. The clamp for holding the briquette for tensile tests is suspended from the short arm, 18 inches from the fulcrum. Pressure for shearing and compressive stresses is communicated through a loose upright, set under the long arm at any desired distance (generally 6 or 12 inches) from the fulcrum. The lower clip for tensile strains is fastened to the bed-plate. On this plate the cube to be crushed rests between blocks of wood, and to it is fastened an upright with a square mortise at the proper height for blocks to be sheared. The rail on which the wheel runs is a piece of light T iron fastened on top of the lever. The pin is iron, and the pin-holes are reinforced by iron washers. The clamps are wood, and are fastened by clevis joints to the lever-arm and bed-plate respectively. When great stresses are desired, extra weights are hung on




Fig. 33. FORM OF BRIQUETTE.




Fig. 34.




Fig. 35.

the end of the long arm. Pressures of 3000 pounds have been developed with this machine.

493. Most of the tests made in this country and England are carried out for the purpose of ascertaining the strength of neat cements, although such material is rarely, if ever, used without the admixture of sand. In Europe, on the other hand, the practice was established about ten years ago, both by manufacturers and engineers, to determine the value of a cement by testing it when mixed with sand into mortar, the usual proportions of the mixture being three volumes of sand to one volume of cement. It is obvious that the latter practice is preferable, since thereby a knowledge of the strength and properties of the binding material actually used in the work will be gained, and furthermore because no valid inference as to the cohesion of a mortar can be drawn from a statement of the tensile strength of the neat cement.

Tests of this kind should, therefore, be made with cement-mortar mixed in the same proportions as contemplated in the work itself, and also with the same sand if practicable, inasmuch as the quality of the latter exerts a marked influence upon the resulting strength of the mortar. In general, it may be said that the greater the proportion of sand in the mortar tested the more accurately can the actual cementing quality of the cement be indicated.

494. Cement-mortar is composed of hydraulic cement and sand in varying proportions, depending upon the kind and quality of the cement. Cement-mortar differs from lime-mortar in its setting, in that it sets within itself without the aid of external elements. Moreover, cement forms by the addition of water a chemical combination throughout all its parts, and setting or hardening takes place throughout the whole mass almost simultaneously. The strength of cement over lime mortar is shown by tests at the Watervliet (N. Y.) Arsenal to be about two to one in favor of the former.

495. Quality of Mortar.—Good mortar should have plasticity when mixed with large quantities of sand, and after solidification compressive strength and tensile strength, as evidence of independent cohesion, power to resist the action of frost and heat, and adhesive qualities for cementing blocks into monolithic bodies. It is to be invariable in volume during and after solidification, to be weather-proof and, for hydraulic works, also water-tight.

496. Quality of Sand.—The sand imparts crushing strength,

lessens shrinkage, and saves expense in lime-mortars. Hydraulic cements require sand only at exposed surfaces. Otherwise it serves as an adulterant for reducing a surplus of strength and density to actual requirements of a given bulk. The sand should be clean, sharp, large-grained, not too uniform in size, free from loam, vegetable or clayey substances, well screened, and, if necessary, washed. Admixed particles of clay adhere to the sand and form diaphragms between sand and mortar, which for durable hardening require close contact.

Since sand is mostly used in greater quantities than the cementing substances, it equals them in importance. It is in all classes embedded in the matrix as a mechanical mixture. The tensile and crushing strengths of the same cement, with equal quantities of different qualities of sand, vary more than those of different brands of cement within the same group do among themselves.

497. Quality of Water.—Fresh or salt water may be used in mixing the mortar, provided it is clean; but salt water may, with some natural cements, hinder the setting.

498. Quantity of Water.—In regard to the proper amount of water to be used in tempering a cement-mortar, it may be said that this will depend upon the quality and quantity of sand, as also upon the quality of the cement. From the numerous and careful experiments with Portland and Rosendale cements, made a few years ago by Mr. Eliot C. Clarke, C.E., and published in the Transactions of the American Society of Civil Engineers for April, 1885, the inference was drawn that, “as a rule, American cements require more water than Portland, fine-ground more than coarse, and quick-setting more than slow-setting cements.” For experimental purposes in the laboratory, the amount of water added by Mr. Clarke to the dry mixture of sand and cement was usually about one fourth of the weight of the Portland and one third of the weight of the American cement contained in the batch; but these amounts were increased or diminished somewhat in order to obtain mortars of uniform consistency. Mr. Clarke adds, in mixing mortars on the site of public works, and particularly for concrete works, much larger quantities of water than are used by him for testing purposes are commonly added by workmen in order to render the labor of mixing and spreading less difficult, but that the result of this procedure is always a greater or less loss of strength.

For the standard tests of cement-mortars by European engineers the rules prescribe one part by weight of cement, three parts by weight of normal sand, and four tenths of a part by weight of clean fresh water.

499. Strength of Mortar.—Three classes of strength are required in all mortars, viz., adhesive, compressive, and shearing. These strengths are all dependent upon the strength of the cement, the strength of the sand, and upon the adhesion of the former to the latter.

500. Adhesive Strength.—It is commonly assumed that after the lapse of a moderate time the adhesive and cohesive strengths of cement-mortars are about equal, and that in old work the former exceeds the latter. Modern experiments, however, fail to establish the truth of this assumption, and indicate rather that the adhesion of such mortars to bricks or stones is much less than the tensile strength during the first few months; also that the relation between the adhesive and cohesive strengths of both neat cements and mixtures with sand are very obscure. It has been found that the adhesion of mortars to bricks or stone varies greatly among the different kinds of these materials, and particularly with their porosity; it also varies with the quality of the cement, the character, grain, and quantity of sand, the amount of water used in tempering, the amount of moisture in the stone or brick, and the age of mortar. Some cements which exhibit high tensile strength give low values for adhesion, and conversely cements which are apparently poor when tested for cohesion show excellent adhesive qualities. Quick-setting cements are usually found to give greater adhesive strength than slow-setting ones, while in the case of cohesion the opposite is generally true. Under these circumstances, therefore, it is manifest that a test, at various stages of age, of the adhesive properties of a binding material like cement-mortar should be regarded as a very important one, in the case of masonry structures which must soon after completion be subjected to other than compressive strains, and it is to be regretted that so comparatively little information respecting such tests with cements and mortars as made at the present time is available.

To assist somewhat in arriving at a fair measure of the strength of hydraulic mortars at different periods of time, as well as the proper composition of the same, the statistics given in Table XLV have been compiled from a great variety of sources.

TABLE XLV.
ADHESIVE STRENGTH OF MORTARS.

Reference number. Age, in days when Tested.	Kind of Cement Used.	Materials cemented to- gether.	Average Adhesive Strength in lbs. per sq. in.					Authority.
			Neat Cement.	Cement, 1. Sand, 1.	Cement, 1. Sand, 1.	Cement, 1. Sand, 3.	Cement, 1. Sand, 4.	
1	7	Quick-setting cement			*23			Robertson, 1858
2	7	Slow			*15			"
3	7	Portland						I. J. Mann, 1888
4	7	"						"
5	7	"						"
6	7	"						"
7	7	Hydraulic lime						Dr. Böhme, 1863
8	7	Portland						Prof. Warren, '87
9	7	"						"
10	16	Quicklime						Boistard
11	16	Lime and cement						"
12	28	Hydraulic lime						Dr. Böhme, 1863
13	28	Portland						Prof. Warren, '87
14	28	"						"
15	30	Quick-setting cement						Rober son, 1858
16	30	Slow						"
17	30	Rosendale						Gen. Gillmore, '68
18	30	"						"
19	30	Portland						I. J. Mann, 1888
20	30	"						"
21	30	"						"
22	30	"						"
23	30	"						"
24	30	Blue lias lime						Building News, '80
25	30	"						"
26	30	"						"
27	30	"						"
28	30	"						"
29	30	"						"
30	30	"						"
31	90	Hydraulic lime						Dr. Böhme, 1863
32	90	Portland						Bauschinger, 1873
33	110	Hydraulic lime						"
34	180	Quicklime						Rondolet, 1831
35	180	"						"
36	180	"						Robertson, 1858
37	180	"						"
38	180	Portland						I. J. Mann, 1888
39	180	"						"
40	"	"						"
41	270	Lime and pozzuolana						J. White, 1832
42	320	Rosendale						Gen. Gillmore, '68
43	1 yr.	Quicklime						Vicat, 1818
44	"	Good quicklime						"
45	"	Ordinary hydraulic lime						"
46	"	Good						"
47	"	"						"
48	"	"						"
49	"	Portland						Mallet, 1829
50	"	"						"
51	"	"						"
52	"	"						"
53	"	"						"
54	"	"						"
55	"	"						"

* Proportions of sand not given, but presumably about those indicated in headings of table.

† Standard sand used in mixture. ‡ Clean river sand used in mixture.

§ Crushed sandstone used in mixture. ¶ Fine river sand used in mixture.

|| Coarse particles in cement sifted out before testing.

501. Shearing Strength.—In recent times elaborate experiments to ascertain the shearing strength of mortar, both in the joints of brickwork and separate blocks, have been made by Prof. Bauschinger of Munich. The results are too numerous for a verbal description, and they are accordingly given in Table XLVI. None of the values obtained are very large, ranging after ninety days from 70 to 7 pounds per square inch on brickwork with mortar mixed in the proportion of three parts of relatively fine river sand to one of cement-lime. The shearing strength of cubes of mortar also appears to be considerably greater than that of the comparatively thin joints in brickwork, and to be influenced by the quality of the sand.

TABLE XLVI.
SHEARING STRENGTH OF CEMENTS AND MORTARS.

Age in Days when Tested.	Kind of Cement.	Average Shearing Strength in lbs. per sq. in.						Authority.
		Neat Cement.	Cement, 1. Sand, 1.	Cement, 1. Sand, 2.	Cement, 1. Sand, 3.	Cement, 1. Sand, 4.	Cement, 1. Sand, 5.	
	I. <i>Shear in, and parallel to, bed-joints of brick- work.</i>							
43	Portland (Bonn)*.....	78.5	Prof. Bauschinger, 1873.
49	" " *.....	78.9	64	
52	" " *.....	155	106.6	
90	" (Perlimoo)*.....	22.7	
90	Hydraulic lime*.....	76.8	
90	Quicklime*.....	7.1	
	II. <i>Shear in cubes of ce- ments and mortars dried in air.</i>							
50	Portland (Bonn)*.....	369.7	369.7	284.4	142.2	Prof. Bauschinger, 1873.
60	" (Perlimoo)*.....	256.0	406.3	383.9	362.6	320.0	
1 w'k	† " " §.....	224.7	108.1	66.8	
"	† " " §.....	301.5	123.7	78.2	
2 w'ks	† " " §.....	270.2	128.0	93.9	
"	† " " §.....	322.8	163.5	122.3	
4 w'ks	† " " §.....	257.4	153.6	112.3	
"	† " " §.....	341.3	199.1	137.9	
8 w'ks	† " " §.....	258.8	196.2	167.8	
"	† " " §.....	376.8	237.5	199.1	

* Fine river sand.

† Coarse sand.

‡ Average values for series of four different brands of quick-setting cements.

§ Clean, medium sand.

† Average values for series of four different brands of slow-setting cements.

As in the case of adhesion, no exact relation between the tensile and the shearing strengths of mortar placed in brickwork can yet be deduced, owing to the lack of sufficient data; but, on the other hand, the experiments show that the shearing strength of blocks or cubes of mortar is about 20 per cent greater than the tensile strength under the same circumstances.

502. Compressive Strength.—But few experiments have been made upon the compressive strength of mortar. An examination of the results of about sixty experiments made with the Watertown testing-machine seems to show that the compressive strength of mortar, as determined by testing-cubes, is from 8 to 10 times the tensile strength of the same mortar at the same age. Data determined by submitting cubes of mortar to a compressive strain are of little or no value as showing the strength of mortar when employed in thin layers, as in the joints of masonry. The strength per unit of bed area increases rapidly as the thickness of the test-specimen decreases, but no experiments have ever been made to determine the law of this increase for mortar.

503. Tensile Strength.—The following table, carefully compiled from a large number of reliable experiments, gives the tensile strength of cement-mortar:

TABLE XLVII.
TENSILE STRENGTH OF CEMENT-MORTAR.

Composition of the Mortar.		Age of Mortar.							
		Rosendale.				Portland.			
Cement	Sand.	1 Week.	1 Month.	6 Months	1 Year.	1 Week.	1 Month.	6 Months	1 Year.
1	0	100	180	275	300	300	400	450	500
1	1	60	100	180	225	175	250	340	375
1	2	25	60	125	170	120	150	245	290
1	3	20	40	80	120	90	110	175	220
1	4	15	25	60	90	75	75	130	170
1	5	10	15	50	80	60	65	110	130
1	6	6	10	45	75	50	35	90	100

504. Fineness of Sand.—Vicat, in the course of elaborate experiments with limes and mortars in the early part of this century,

established standards for size of grain of what he termed coarse sand and fine sand, as follows; coarse sand being such as will pass through a sieve of 64 meshes per square inch and be retained on one of 289 meshes per square inch, while fine sand will pass through a sieve of 289 meshes per square inch and be retained on one of 625 meshes per square inch. On this definition he ranked the superiority of coarse, mixed, and fine sands with limes according to the following schedule:

For eminently hydraulic limes, 1, fine; 2, mixed; 3, coarse.

For slightly hydraulic limes, 1, mixed; 2, fine; 3, coarse.

For fat or quick limes, 1, coarse; 2, mixed; 3, fine.

It will suffice to say that with cement-mortars much better results are obtained when the sand is of the size of grain above described and is sharp and clean.

Mr. Clarke says that when the sand was formed of a mixture of fine and coarse grains nearly as good results were attained as with coarse grains alone.

Before leaving this subject it may be of interest to refer briefly to the experiments made at Wilhelmshaven in 1877 by H. Arnold, C.E., as published in the Journal of the Hanoverian Architects and Engineers' Society for 1883, and from which was found that the size of grain and quality of the sand used in Portland-cement mortar are important factors in its ultimate strength. With six different kinds of substantially clean sands and the same brand of cement mixed into mortar in the proportions of three volumes of sand to one volume of cement, the tensile strength after seven days ranged from 101 to 243 pounds per square inch, and after twenty-eight days from 133 to 311 pounds per square inch, thus exhibiting extremely wide variations, depending largely upon the size and roughness of the grains of sand.

In every instance it was found that a greater strength was developed with a coarse-grained sand free from very fine particles and dust than with a fine-grained sand, both being equally sharp. Mr. Arnold also points to the fact deduced from his experiments, that with the same cement but different sands of similar size of grain, the cohesion of the mortar may be found to vary considerably, and will probably depend upon the chemical composition of the sand. He therefore concludes that in order to obtain satisfactory results from the cement-mortar used in the construction of

public works, the quality of the sand available in the particular locality should first be taken into careful consideration.

If no other than a fine sand happens to be available and a given strength of the mortar is to be attained at the end of one week, experiments should be made to learn whether the proportions of sand to cement named in the specifications should be changed, since the strength diminishes rapidly with the quantity of sand used; and in such an event it may also be advisable to use an entirely different kind of cement. It is a necessary condition of success in mortar-making that every particle of the sand or "aggregate" be completely covered with the cement or "matrix;" and since, when the grains in a given volume are small, the magnitude of the total surface to be covered is greater than when the grains are large, it follows that fine sand requires a larger proportion of cement than coarse sand. Any specification or plan contemplating the use of a good coarse sand must, therefore, be altered if fine sand alone is used, or else the quality of the work will be impaired.

In support of the foregoing remarks, it has been quite generally observed by engineers that when most of our American natural cements are mixed entirely with fine sand the process of hardening is greatly retarded, even if not entirely prevented; while the same cements, when tested neat, exhibit a cohesive strength ranging from 50 to 136 pounds in twenty-four hours, thus showing conclusively the effect of admixing the fine material. An instructive instance of this kind was noticed some years ago, when an excellent quality of Akron "Star" cement was mixed with very fine sand from the Pinnacle pits in the proportion of $2\frac{1}{4}$ parts sand to 1 part of cement. For several days the mass remained in a plastic state in the tin can in which it had been deposited, and upon being removed and exposed to the air upon a window-sill for several months it displayed very little strength and broke in handling. On the approach of cold weather the largest fragment was kept in an apartment constantly heated by steam, and after lying undisturbed therein for three months pieces could easily be broken off with the fingers. At the present time, after having attained an age of one year, it is still quite friable and entirely unfit for use. Another mass of mortar prepared at the same time from the same cement, but with clean, coarse sand, mixed in the proportions

of 3 parts of sand to 1 part of cement, indurated promptly and exhibited far better qualities.

TABLE XLVIII.
EFFECT OF SIZE OF GRAIN OF SAND ON TENSILE STRENGTH OF
CEMENT-MORTAR.

Denomination of Size of Grains.	Tensile Strength of Mortar mixed 3 : 1 with			
	Dangast Sand after		Crushed Granite after	
	7 days.	28 days.	7 days.	28 days.
Hulled barley.....	177	213	194	255
Oatmeal.....	162	191	176	234
Standard.....	131	177	164	242
Grass-seed.....	134	164	144	193
Grit.....	141	160	186	193
Coarse dust.....	64	87	87	134
Fine dust.....				

TABLE XLIX.
CHARACTER OF SIEVES FOR SIFTING SANDS.

Number of Sieve.	Number of Holes per lineal inch.	Number of Holes per square inch.	Size of Hole of Length of Side in inches.	Diameter of Wire in inches.
1.....	20	400	.08101	.01899
2.....	30	900	.02119	.01214
3.....	50	2500	.01119	.00881
4.....	80	6400	.00599	.00510
5.....	170	28900	.00309	.00279

505. Portland cement acquires its strength more quickly than Rosendale. Both cements, but especially the Rosendale, harden more and more slowly as the proportion of sand mixed with them increases; and whereas neat cement and rich mortars attain nearly their ultimate strength in six months or less, weak mortars continue to harden for a year or more. It has also been found that after a period of about a year weak mortars often lose in strength or tenacity what they may gain in hardness, from the fact of their

becoming brittle. Specimens of such mortar two years old break very irregularly. Mortars less than one month old are relatively weak, and hence the advantage of waiting as long as possible before loading masonry structures. Portland-cement mortars are especially useful in cases where the structure is necessarily subjected to severe strains within so short a period as one week, as frequently happens in the case of pavements.

506. Permeability of Mortar.—The permeability of mortar is increased as the proportion of the cement decreases. It increases with the coarseness of the sand. Mortars made with a mixture of sand of various sizes are relatively non-porous and non-permeable. Mortars mixed dry are more permeable than those mixed wet or of a "normal consistency."

507. Effect of Frost upon Mortars.—It is a matter of common knowledge that ordinary quick-lime mortar which is exposed to the action of frost before it has become well set or indurated will thereby become greatly injured in its adhesive and cohesive properties; and hence where such mortar is used it is customary to suspend all building operations on the arrival of the cold season. Should, however, it be necessary to proceed with the construction, experienced masons and builders sometimes make use of a quick-setting cement-mortar in place of lime, and cease work when the weather is at all severe. It is, therefore, of importance to learn something of the behavior of cements under such circumstances.

The impression seems to prevail quite extensively that cement-mortars are not appreciably injured by freezing, and that masonry may safely be constructed at any temperature below the freezing point at which a man can still work, provided that either brine or salt be used instead of fresh water, or that the materials be first heated. With regard to the use of brine or salt it may be remarked that whether the mortar will be injured thereby or not seems to depend principally upon the character of the cement. Most of the natural or "Roman" cements suffer a considerable loss of strength if mixed with salt water, while the Portland cements do not appear to be materially affected.

Respecting the practice of heating the cement, sand, and water before mixing, and then using the hot mortar in cold weather upon frosty stones or bricks, or depositing it in icy water, the experiments of William W. Maclay, C.E., submitted in 1877 to the American

Society of Civil Engineers, show indisputably that such a method of treatment is erroneous, and that a great amount of injury is effected when heated mortar, even if made of Portland cement, is immersed directly in cold water. The tests were all made with Burham Portland cement, which, when tested neat at ordinary temperature, gave a tensile strength of 278 pounds per square inch after seven days. In one series of experiments the ingredients of the mortar all had a temperature of about 40 degrees Fahr., and in another they were heated to 100 degrees Fahr. These two sets of briquettes were kept for seven days in precisely the same manner, and were broken on the same day, so that any changes in temperature during this period would necessarily affect them alike. The averages of the tensile strengths acquired show that by first heating the ingredients to about 100 degrees, then mixing them in air having a temperature of from 13 to 37 degrees, and afterward exposing the briquettes for six days to the winter weather, their strength in the case of neat cement was only from 7 to 20 per cent of that attained when the materials were mixed without heating, or with the temperature of the mortar at 40 degrees; and in the case of mortar mixed in the proportion of 2 sand to 1 cement, the tensile strength of the heated mortar after 28 days was only 30 per cent of that reached by the cold mortar at 40 degrees. From these and other similar experiments Mr. Maclay concludes that the mixing of cement-mortar with highly-heated materials for use above water in very low temperatures greatly reduces its normal strength, and that for use below icy water its value will thereby be almost entirely destroyed. If mortar must be used at all in such weather, it should be used cold, and the only condition to be observed is that the materials shall be free from frost at the time of using. "In the experiments where the materials were mixed cold and then exposed to the winter weather, Portland-cement mortar appeared to set without freezing even in as low a temperature as 13 degrees Fahr., except when it was windy; but where the briquettes were made of hot mortar they invariably froze, as was proven by their becoming soft again when the temperature rose."

Portland cement was found to possess the peculiarity, also noticed by many other writers on the subject, of setting in a low temperature wherein other varieties of cement will surely freeze. No definite limits of this action, however, have yet been assigned.

Mr. E. Leblanc exposed cakes of Portland-cement mortar to frost immediately after mixing and before any setting had occurred, with the result that "they cracked deeply and in part became disintegrated, but the detached fragments after being thawed were found perfectly hard." In Mr. Maclay's experiments none of the Portland-cement briquettes when mixed cold cracked in the slightest degree even when exposed to as low a temperature as 11 degrees Fahr., and they all became hard after thawing. This seems to be the prevailing opinion among engineers. Mr. J. Dutton Steele, C.E., in discussing the paper of Mr. Maclay, states that "cement-mortar is not seriously impaired by being laid in frost, as its property of setting is simply held in suspense during the time it remains frozen." Gen. Q. A. Gillmore, U.S.A., in his work on Beton, etc., remarks that "when the temperature is not much below the freezing point during the day, work may be safely carried on if care be taken to cover over the new material at night. After it has once set and has had a few hours to harden, neither severe frost nor alternate freezing and thawing has any effect upon it."

In the report of the work performed at the Royal Testing Laboratory of Berlin in 1886 there is an account of a number of experiments for ascertaining the effect of frost upon the strength of Portland cement, both neat and when mixed into mortar in the proportion of 3 parts of sand to 1 part of cement. These tests were made in two distinct series, the first one involving only a single exposure to frost on and during the sixth day after mixing, while in the second series the briquettes were treated as follows: First, allowed to indurate for twenty-four hours in the air of a warm room; second, exposed for twenty-four hours to a freezing temperature of from + 10 degrees to + 5 degrees Fahr.; third, thawed four hours in a warm room; fourth, placed under water until tested.

The experiments were made with six different brands of cement, and for each set of briquettes exposed to frost another similarly constituted set was kept in temperatures above the freezing point to serve as a basis of comparison of tensile strength. Upon testing the frozen and unfrozen samples, it was found that the effect of frost varied greatly with the quality of the cement; the loss in tensile strength incurred by such freezing ranging after seven days from 2 to 22 per cent in the case of neat cement, and from 3 to 24

per cent in the case of the mortar mixed as above described; also ranging after 28 days from 2 to 12 per cent in the case of neat cement, and from 1 to 33 per cent in the case of the mortar. It should be noted particularly that the foregoing results were derived when pure, clean, and standard materials only were used. On the other hand, where the cement was adulterated with 30 per cent of pulverized slag from a blast-furnace the loss in strength by freezing was much greater than above given, especially in the case of the mortar. After seven days this loss ranged from 6 to 62 per cent, and after 28 days from 21 to 44 per cent, standard sand having been used.

Other interesting experiments with regard to the effect of frost on Portland-cement mortar were carried out early in 1886 at Hamburg, Germany, by Mr. Moeller, C.E., and an account thereof is contained in the *Deutsche Bauzeitung* for November 17, 1886.

The results showed that Portland-cement mortar, whose time of setting is lengthened by the addition of sand or lime, or both, suffers severely in loss of tensile strength by the action of frost, and that such loss becomes greater as the proportion of sand or lime is increased; further, that a quick-setting Portland cement will indurate in spite of the frost, provided that it be protected therefrom for two days after having been tempered, and that it be as dry as possible before exposure to the cold. It was also found that the mixing of such materials with brine renders the mortar more capable of resisting the influence of frost, and that this statement likewise holds true for slow-setting compounds, such as 1 part of cement, 1 part of lime, and 3 parts of sand. Mortars thus prepared and mixed with fresh water instead of brine, and kept for two days at a temperature of $+41$ degrees Fahr., and then exposed to the frost, lost nearly all strength, so that even after four months pieces could easily be broken off from the briquettes with the fingers; whereas when tempered with strong brine their strength after seven months was about fourteen times greater. Accordingly, if the mortar can be kept from freezing for a few days by the use of salt or brine, so as to allow the setting to take place, much benefit is sure to be derived.

It may also be deduced from these experiments that when it becomes absolutely necessary to lay masonry in freezing weather, quick-setting Portland cements, mixed with small proportions of

sand and water, should alone be employed; and when a satisfactory quality of work is expected or required, the use of brine or salt should be resorted to, as well as the protection of the newly-laid masonry at night by means of adequate coverings. In case, however, that the temperature is lower than 23 degrees Fahr. even these precautions will not prevent more or less damage.

Under such circumstances, moreover, it is self-evident that the stones or bricks should be free from snow or ice and as dry as practicable; also that all the materials, including the sand and cement, be free from frost by being kept at a temperature above the freezing point for some days before being used in the work. The safest rule, however, is to cease operations with mortars of any kind during the prevalence of frost.

In a paper read before the American Society of Civil Engineers in July, 1886, its author, Alfred Noble, C.E., states that "in the construction of the lock at the St. Mary's Falls Canal, the laying of masonry was discontinued about October 20 of each year, on account of the frequent recurrence of freezing weather. On the last day of the work done in 1877 mortars made of Portland cement and of a good quality of American natural cement were used in adjoining portions of the same wall. Both mortars were mixed in the proportions of 1 cement to 1 sand, and the masonry was laid during a light rain. The following spring the surface of the Portland-cement mortar was sound, showing perfectly the marks of the rain-drops, while the natural-cement mortar was disintegrated to a depth of three or four inches." Mr. Noble also mentions a few other cases where Portland-cement mortar was used in laying masonry during very cold weather without affecting the subsequent induration of the mortar noticeably. The inference to be drawn from his paper is that if it becomes imperative to use mortar in freezing weather, Portland cement should be used.

Similar effects of frost were also noticed by Mr. Francis Collingwood, C.E., on the Rosendale-cement mortars, mixed in the proportion of 2 sand to 1 cement, used for the masonry of the East River Bridge, since he states that "the tops of the various pieces of masonry were always gone over carefully in the spring. The concrete which had been put in late would usually be found disintegrated to a depth of from one to four inches, but below this it was found sound. The rule seems to be that it was unsound only

so far as it was exposed alternately to freezing and thawing; and wherever it had taken a set before freezing, and had not been thawed out for some time, it was sound." The experience of Mr. George S. Morison, C.E., with cements as given in his discussion of Mr. Noble's paper, was in full accord with what was therein stated, and in his extensive practice as a designer and builder of large bridges he uses Portland cement exclusively in all places where the mortar is liable to freeze before setting. Mr. Eliot C. Clarke, C.E., also mentioned that in experimenting with concretes of Rosendale and Portland cements which had been exposed to the weather for three years he found that the former was injured and disintegrated from year to year, while the latter were not affected at all.

Recent expressions of opinion from many other excellent authorities respecting the action of frost on cement-mortars are to the same effect as above recited. It is generally agreed that the freezing of freshly-prepared cement-mortar will not destroy its capacity to harden after becoming thawed, but exactly how much its cohesive and adhesive strength will thereby become impaired does not appear to be definitely known; neither is the effect of repeated freezing and thawing very clearly pointed out. In our winters it frequently happens that water freezes in the shade, while at the same time ice melts in the sunlight, and hence under such circumstances in a wall facing south a slow-setting mortar in the face will be alternately frozen and thawed, while that in the rear will continue to remain frozen. This condition of the work cannot fail to be prejudicial to its ultimate strength, and manifestly demands that a strong and quick-setting mortar be used if the laying of masonry be continued in freezing weather. Numerous instances of failure of walls and abutments built in winter may be cited which are fairly attributable to the thawing out of the frozen mortar after the warm weather has set in, whereby it becomes almost as soft as when first mixed. In such cases the thawed mortar acts rather as a lubricant than as an efficient binding material, and if the structure is then subjected to lateral forces of considerable magnitude, deformation or failure is sure to follow unless a very wide margin of safety has been allowed in the design. When, however, the dimensions are fixed with reference to economy and the use of ordinarily good materials and workmanship, as

generally happens, the action of frost becomes a very serious factor in the stability and durability of the work, and therefore care should be taken in the proper selection of the cement. It must always be remembered that frozen cement-mortar will not set so long as it remains frozen, and that when it becomes thawed it is simply in the condition of material freshly mixed, which, while in that state, imparts no more strength to the structure than sand, ashes, mud, or other inert matter.

A rather close observation for a number of years of the effects of frost on Buffalo and Akron cement-mortars, mixed in the proportion of two sand to one cement and three sand to one cement, leads to the conclusion that such mortars entirely disintegrate to a depth of several inches in exposed joints of masonry laid in cold weather; also that when used as coatings or renderings of rough stone surfaces a flaking thereof occurs by frost which leads to rapid disintegration. If it is imperative that masonry be built in freezing weather, a quick-setting Portland cement-mortar should be used, instead of such as is prepared with natural cements; also that even when Portland cement is used with brine, work should be suspended when the temperature is lower than 25 degrees Fahr., if good results are to be expected; and finally, smaller proportions of sand should be used than during the prevalence of higher temperatures.

508. The standard of tensile strength required by German engineers of Portland-cement mortar, prepared by mixing one unit of weight of cement with three like units of normal sand, and four tenths of such a unit of clean fresh water, and tested after an exposure of one day in air and twenty-seven days in water, is 227 pounds per square inch and a resistance to compression of 2300 pounds per square inch.

509. English Specifications for Portland Cement.—The following is a summary of the specifications used by Mr. Henry Faija, an accepted English authority:

Fineness.—To be such that the cement will pass through a sieve having 625 holes (25") to the square inch, and leave only 10 per cent residue when sifted through a sieve having 2500 holes (50") to the square inch.

Expansion or Contraction.—A pat made and submitted to

moist heat and warm water at a temperature of about 100 degrees Fahr. shall show no sign of blowing in twenty-four hours.

Tensile Strength.—Briquettes of slow-setting Portland, which have been gauged, treated, and tested in the prescribed manner, to carry an average tensile strain, without fracture, of at least 176 pounds per square inch at the expiration of three days from gauging; and those tested at the expiration of seven days to show an increase of at least 50 per cent over the strength of those at three days, but to carry a minimum of 350 pounds per square inch.

For quick-setting Portland at least 176 pounds per square inch at three days, and an increase at seven days of 20 to 25 per cent, but a minimum of 400 pounds per square inch. Very high tensile strengths at early dates generally indicate a cement verging on an unsound one."

510. Data for Estimates.—The following data will be found useful in estimating the amounts of the different ingredients necessary to produce any required quantity of mortar:

One barrel of lime (230 pounds) will make about $2\frac{1}{4}$ barrels (0.3 cubic yard) of stiff lime-paste. One barrel of lime-paste and three barrels of sand will make about three barrels (0.4 cubic yard) of good lime-mortar. One barrel of unslaked lime will make about 6.75 barrels (0.95 cubic yard) of one to three mortar.

A barrel of Portland cement weighs 400 pounds gross, or about 375 net. Hudson River Rosendale weighs 300 pounds net per barrel. Western Rosendale weighs 265 pounds net per barrel.

A barrel of Rosendale, as packed at the manufactories on the Hudson will measure from 1.25 to 1.40 barrels if measured loose. A barrel of Western Rosendale will make about 1.1 barrels if measured loose. A commercial barrel of Portland will make about 1.2 barrels if measured loose.

One cubic foot of dry cement (shaken down but not compressed) mixed with 0.33 cubic foot of water will give 0.63 cubic foot of stiff paste. One barrel (300 pounds) of finely ground Rosendale cement will make from 3.70 to 3.75 cubic feet of stiff paste; or 79 to 83 pounds of cement-powder will make about one cubic foot of stiff paste. Volume for volume, Portland will make about the same amount of paste as Rosendale; or 100 pounds of Portland will make a cubic foot of stiff mortar.

511. Machine-mixed mortars and concretes are superior to hand-

mixed. In hand-mixing the first drawback is the liability to error in measuring out correct and uniform proportions of prescribed materials. Mortar men make mistakes which generally happen to be against the proper proportions of cement. The quantity of sand will also vary according to whether it is measured in wet or dry condition, packed or loose. Next the workmen fail to intermix the cement and sand thoroughly before adding the water—an important point. Again, they will ease up on the labor required to mix all well together after applying water, and to facilitate the operation will over-dose the water. A further error occurs in assuming that all barrels of cement contain equal quantities. The necessity of a close supervision will be recognized in these particulars.

512. Specifications for Concrete (Boston).—The American cement-concrete shall be made of one part of American hydraulic cement, two parts of clean, sharp sand, and five parts of clean broken stone or screened gravel-stones by measure.

The Portland-cement concrete shall be made of one part Portland cement, three parts of clean, sharp sand, and seven parts of clean broken stone or screened gravel-stones by measure.

The stone for the concrete shall be free from clay, dirt, or other objectionable material; no stone shall be larger than $2\frac{1}{2}$ inches and but very few less than $\frac{1}{4}$ inch in their greatest dimensions.

The mixing shall be done in proper boxes, in a manner satisfactory to the engineer; and after the materials are wet the work must proceed rapidly until the concrete is in place and is so thoroughly rammed that water flushes to the surface and all the interstices between the stones are entirely filled with mortar. The surface of the concrete foundation must be floated and made exactly parallel with the crown of the pavement to be laid, and must be suitably protected from the action of the sun and wind until set. It shall be allowed to set a sufficient time, to be determined by the engineer, before walking over or working upon it shall be allowed.

513. Specifications for Concrete (Berlin).—The concrete is to be prepared from a mixture of cement and sand or a mixture of cement, sand, and broken granite or limestone. In making it at least one barrel of cement in the standard proportion of 180 kilos gross or 170 kilos net weight is to be used with one cubic meter of sand or of sand and stone. The proportions of sand and broken stone are to be determined in each case by the inspector. If in exceptional

cases a greater proportion of cement is employed to obtain quicker setting, a corresponding payment will be made for each barrel used, as given in the schedule of prices.

The cement is to be weighed whenever the inspector desires. In order that the proportions may exactly conform to the specifications, the sand or mixture of sand and stone is to be measured in boxes holding exactly one half or one cubic meter.

The mixing is done on a platform that must be 30 centimeters (11.8 inches) larger all around than the bottom of the measuring-boxes. The sides are to be provided with strips to prevent the falling of the material. In order to insure regular work at least five mixing-boards are to be set up at each place of working.

Sand and cement are to be twice mixed dry before water is added. After the addition of the water the mass must be immediately worked to a stiff condition. During the preparation of the concrete, all the foreign bodies in the cement or sand are to be carefully removed. If, during the process of mixing, a portion of the concrete, of sand or stone, falls from the platform, it must not be again added to the mass and used in the concrete, but must be removed.

Laying the Concrete.—In order to insure the exact formation of the concrete foundation, a series of templates are to be laid on the road-bed from 4 to 5 meters apart and parallel to the axis of the street. The greatest care must be taken to have these templates at the proper height, and all out of alignment must be immediately removed.

When the road-bed has been finally brought to the proper grade the concrete is to be laid between the templates and thoroughly tamped and worked into a profile corresponding to that of the finished street surface.

Use of the Concrete after its Preparation.—While the concrete is setting, it is to be sprinkled with water so that the surface is continually moist, and as long as it remains soft the work must be protected by suitable guards from intruders.

No concrete shall be prepared at a temperature below 2 degrees Reaumur ($36\frac{1}{2}$ degrees Fahr.). Concrete just laid is to be protected for two days, when frost begins, by a covering of mats or bundles of straw.

The foundation must have exactly the same profile as the upper

surface of the finished pavement is to receive. It is especially necessary that the surface be free from all inequalities, elevations as well as depressions. Work must not begin on the construction of the foundation until the inspector has definitely stated that the work on the roadbed has been finished in the manner prescribed in the regulations.

514. Specifications for Concrete (New York).—One part of American cement, equal to the best quality of freshly burned Rosendale cement, two parts of clean, sharp, washed sand, free from clay, to be thoroughly mixed dry and then made into mortar with the least possible amount of water; to this shall be added three parts of sound stone, broken with a hammer, the largest of which will pass through a 2-inch ring, the broken stone to be wet before being added to the mortar. The whole mass shall then be shoveled over until it is thoroughly mixed before it is put in place; it shall then be put in place and rammed until it is thoroughly compacted and has a clean mortar surface.

The whole operation of mixing and laying each batch will be performed as expeditiously as possible, by the employment of a sufficient number of skilled men.

The upper surface will be made exactly parallel with the pavement when laid, and, if necessary, will be protected from the action of the sun and wind until set.

No concrete will be allowed to be used which has been mixed more than three hours.

The concrete shall be laid to a depth of 6 inches.

515. Concrete for Foundations, as used in Paris.—The proportions by bulk are:

Cement	1 part
Sand	4 parts
Gravel	6 "
Water	1½ "

or one of cement to ten of sand and gravel.

The concrete is mixed on a large mortar-board, the mixers moving the board ahead as the work advances, and never being more than a few feet from the spot where the concrete is to be placed.

A square wooden form is placed on the mortar-board; into this is dumped successively, in the order named, 2 barrows of gravel,

$\frac{1}{2}$ sack of cement, 1 barrow of gravel, $\frac{1}{2}$ sack of cement, 2 barrows of sand. The form is then removed, and the mass turned over dry with the shovel by two men working side by side. It is then turned a second time by the two men, while a third sprinkles on the water from a pot. The mass is then turned over a third time, and shoveled from the board directly into place.

This concrete sets quickly, and every evening the surface of that laid during the day is covered with a thin coat of pure cement.

516. Specifications for Preparation of Roadbed.—The subsoil or other matters (be it earth, rock, or other material) shall be excavated and removed to a depth of inches below the top line of the proposed pavement. Should there be any spongy material, vegetable or other objectionable matter, in the bed thus prepared, all such material must be entirely removed, and the space filled with clean gravel or sand carefully rammed.

The roadbed shall be truly shaped and trimmed to the required cross-section and grade, and rolled to ultimate resistance with a roller weighing not less than ten tons; such portions of the roadbed as cannot be reached by the roller shall be consolidated with hand rollers or tampers.

Note.—The employment of ashes, garbage, or other objectionable matter should not be permitted for filling on the streets of cities and towns.

Rock shall be excavated to a depth of 2 feet below the level of the finished grade, and the space so excavated shall be refilled to subgrade level with gravel, steam ashes, or other approved material, and thoroughly consolidated.

516a. Foundation employed in Liverpool.—The foundation employed in Liverpool for heavy-traffic pavements is described by Mr. P. H. Boulnois, City Engineer, as follows: "The ground having been prepared in the usual way, and the channel (gutter) and curb stones fixed in position, a stratum of stones (which should by preference be of a non-absorbent character), broken so as to pass all ways through a 3-inch ring, is spread evenly over the surface of the ground, and upon this is placed a layer of cement mortar mixed in the proportions of one of Portland cement to six of fine, sharp, clean gravel in the method to be described hereafter. Upon this layer of mortar is placed another layer of broken stone—the whole of the stones

in each layer to be thoroughly watered while the work is proceeding—and this stone is forced into the interstices of the first layer by the use of flat beaters of wrought iron, weighing 16 pounds each, shaped like square shovels, with handles at an angle of 33 degrees.

"This process is repeated until the proper level and contour is reached, and the surface is finished off parallel to the exact curvature of the carriageway.

"The foundation thus prepared is left until the concrete is sufficiently set or hardened to receive the pavement, which, if possible, should not be less than ten days, although this period may be shortened, where the exigencies of the traffic render it imperative, by strengthening the proportion of cement to gravel, care to be taken in all cases to periodically water the surface of the concrete to assist the ultimate hardening, and in very hot weather it is advisable to cover the surface of the concrete with old cement-bags saturated with water.

"The proportions of broken stone, gravel, and cement used in such a concrete are as follows:

"*Before Mixing.*—Broken stone, 8 parts; gravel, 6 parts; cement, 1 part.

"*After Mixing.*—Broken stone and gravel, mixed together, 11 parts; cement, 1 part; three parts of gravel having been expended in filling the interstices of the stones.

"The method adopted for insuring that the cement mortar shall contain the proper proportions as carried out in Liverpool is as follows: An apparatus is used consisting of a set of double mixing-boards, each 7 feet by $3\frac{1}{2}$ feet, having $1\frac{1}{4}$ -inch deal sides and back 9 inches high, and $1\frac{1}{2}$ -inch deal bottom lined with sheet iron. A partition in the centre divides the board into two compartments; at the back of each compartment is a box for measuring the gravel, with a capacity of 1 cubic foot, 14 inches square at the top, 10 inches square at the bottom, and 12 inches deep. It is hinged to the back of the board by strong iron eyes and bolts.

"Any number of mixing-boards being placed side by side, about 1 foot apart, the water-supply is arranged as follows: A length of flexible hose is attached at one end to the nearest hydrant, and at the other end to the ball-tap of a sheet-iron regulating-cistern,

containing 18 gallons, fixed on a light angle-iron frame, about 4 feet from the ground to the bottom of the cistern; this is placed at one end of the series of mixing-boards. Opposite to the inlet-pipe is an outlet-pipe of flexible tubing attached to the cistern by brass unions; water is conveyed through this pipe to a horizontal wrought-iron pipe, 7 feet long, supported upon light iron standards placed over the back of each mixing-board. Attached to this pipe is a pair of brass swivel rose-ended pipes with stop-taps; these roses are so arranged as to discharge the water in a gentle rain-like spray over the centre of each mixing-compartment. This arrangement may be extended to any number of boxes, the service-pipes being connected by flexible tubing.

"The cement is measured in light iron bowls having a capacity of $\frac{1}{4}$ cubic foot.

"The usual arrangement for mixing concrete is as follows: The mixing-boards are placed with their backs to a heap of gravel, the cement being stored at one end, also at the back of the boxes; a laborer with a mixing-shovel is detailed off to each mixing-compartment; a man at the back fills each measuring-box with gravel; the mixer in front tips over this box with his shovel, emptying the gravel into the mixing-board; a boy brings a bowlful of cement from the store and spreads it over the gravel; the mixer turns over the contents of his board until the cement and gravel are thoroughly mixed in a dry state; he then turns the tap of the rose-pipe, and allows the water to flow over the mixture until sufficient moisture for setting is obtained, the quantity of water used varying with the dampness of the gravel. The concrete is now thrown into wheelbarrows and conveyed to its destination. One mixer in nine hours can turn out ninety such mixings, which are equal to 6 $\frac{1}{2}$ cubic yards."

516b. Specifications for Concrete (Chicago).—PROPORTIONS.—One part cement, three parts sand, seven parts broken stone; sand and cement mixed dry; water then added to make a stiff mortar, to which the stone is immediately added and mixed (water being added if necessary) until each particle of stone is covered with mortar. The concrete is deposited in one layer and rammed to a true and smooth surface. The subgrade is kept moist, and the

concrete is sprinkled as necessary and left exposed for at least seven days.

MATERIALS.—*Portland Cement*, 92 per cent passing through a No. 100 sieve, passing the "boiling test," setting in 45 minutes or more; tensile strength (neat) 400 pounds in 7 days, 175 pounds for 1 cement to 3 sand, with 15 per cent increase, in 28 days.

Sand, clean, dry; grains $\frac{1}{8}$ inch and less, not more than 30 per cent voids; weighing 109 pounds per cubic foot.

Stone, limestone, clean, between $1\frac{1}{2}$ inches and 1 inch in largest dimensions.

CHAPTER X.

RESISTANCE TO TRACTION.

517. The resistance to traction on highways is occasioned (1) by the want of uniformity in the surface of the road, the weight of the load having to be lifted over the projecting points and out of hollows and ruts, thus diminishing the effective load which the horse may draw to such as it can lift.

(2) The want of strength of the roadbed itself, however free its surface may be from asperities or cavities, if its substructure be of such a nature that it will yield to the pressure of the wheels, adds another impediment to the movement of a load over it, with the additional disadvantage that while the horse is endeavoring to lift the load from a cavity or hollow, the fulcrum, which in the first case was supposed to be fixed and rigid, is in the latter yielding and variable, subjecting the horse to the constant effort of lifting, instead of simply drawing.

518. Want of Uniformity in the Surface.—The power required to draw a wheel over a stone or any obstacle, such as *S* in Fig. 36, may be thus calculated. Let *P* represent the power sought, or




FIG. 36.

that which would just balance the weight on the point of the stone, and the slightest increase of which would draw it over.

This power acts in the direction CP with the leverage of BO or DE . Gravity, represented by W , resists in the direction CB with the leverage of BD . The equation of equilibrium will be $P \times CB = W \times BD$, whence

$$P = W \frac{BD}{CB} = W \frac{\sqrt{CD^2 - BC^2}}{CD - AB}$$

Let the radius of the wheel = $CD = 26$ inches, and the height of the obstacle = $AB = 4$ inches. Let the weight $W = 500$ pounds, of which 200 pounds may be the weight of the wheel and 300 pounds the load on the axle. The formula then becomes

$$P = 500 \frac{\sqrt{676 - 484}}{26 - 4} = 500 \frac{13.85}{22} = 314.7 \text{ pounds.}$$

The pressure at the point D is compounded of the weight and the power, and equals

$$W \frac{CD}{CB} = 500 \times \frac{25}{22} = 591 \text{ pounds,}$$

and therefore acts with this great effect to destroy the road in its collision with the stone, in addition there is to be considered the effect of the blow given by the wheel in descending from it. For minute accuracy the non-horizontal direction of the draught and the thickness of the axle should be taken into account. The power required is lessened by proper springs to vehicles, by enlarged wheels, and by making the line of draught ascending.

519. Resistance of Penetration.—This resistance is that of a medium distributed over the submerged portion of the circumference of a wheel, in advance of the perpendicular line drawn from the centre of the wheel to the plane of the road. The following investigation furnishes a formula for calculating, with sufficient degree of accuracy, the resistance of gravel, loose stones, soft earth, or clay.

Let AOB , Fig. 37, be a wheel drawn over the horizontal surface CDE of the road, in the direction OF , and let the road be of such a consistency that the wheel penetrates to the depth

DB below the surface, leaving a track *BG* behind it. The arc *BC* is the submerged portion of the circumference, and it may be assumed to be identical with the chord of the arc *BC*. Now the resistance is distributed over the surface *BC*, and it may be taken




FIG. 37.

as acting on this surface perpendicularly to the plane of the road, or vertically and directly opposed to the gross weight, consisting of the weight of the wheel and the load upon it. To simplify the investigation, let it be supposed that the upper portion of the road is homogeneous, as clay or sand; then the resistance to penetration is nothing at the surface, and it increases as the depth; and the upward resistance along the line of submersion, BC , is a maximum at B and it vanishes at C , and the varying intensity of the graduated pressure may be represented by an isosceles triangle, of which the centre of gravity, H , situated at one third of its length, BH , from the base, B , is also the centre of resistance, and therefore also the centre of pressure under the load; and the radial line OH is the resultant of the pressure of the load, measured in force and direction by the vertical OI , and the tractive force, measured by the horizontal line HI or OK . But the vertical OI may be taken as equal to the radius OB , and the horizontal HI may be taken as one third of the semi-chord of submersion CD ; whence the proportion

Load : tractive force :: $OB : CD$:: radius of wheel : $\frac{1}{2}$ semichord;

and the resistance to traction is equal to the product of the load by the third of the semichord divided by the radius of the wheel.

But the length of the semichord CD may be more easily determined by calculation from the measured depth of submersion DB . It is equal to the square root of the products of the segments into which the diameter AB is divided by the plane of the road CDE , or to $\sqrt{AD \times DB}$; and the whole of the calculations is embraced by the equation

$$\text{Tractive force } OK = \frac{1}{3} \times \frac{W \sqrt{AD \times DB}}{OB} \dots (1)$$

The work done in compressing the material of the road is easily indicated diagrammatically, by supposing the wheel to advance through a space equal to the semichord CD , or the length of the submersion. Thus, in Fig. 38, the wheel AB is supposed to roll




FIG. 38.




FIG. 39.

forward and to occupy the position $A'B'$. The work done in compressing the road is proportioned to the four-sided area $BCC'B'$, comprised between the circumferential segments BC and $B'C'$, and this area is, by the properties of the circle, equal to the original rectangular area $BDCB'$.

Now, suppose a wheel ABA , Fig. 39, of larger diameter with the same gross weight, to travel over the same surface. It is obvious that, if it could sink to the same depth, db , as that for the smaller wheel, the length of immersion, dc , would be increased, and the rectangle, $db \times dc$, representing work, would be greater

than that performed by the smaller wheel in the first example. Such a supposition cannot be admitted: the depth of immersion, dB , for the larger wheel, must be less than that, db , for the smaller wheel, though the length of immersion dC , must be greater than that dc , for the smaller wheel, but not so much greater as if the wheel were sunk to the first depth, db .

In fine, larger wheels sink less but spread more into the surface than the smaller wheels, in such proportion that the area of the rectangle representing work of submersion is constant for all sizes of wheels. In this instance, accordingly, the rectangle $db \times dc =$ the rectangle $dB \times dC$.

It might be thought that, on this principle of the constancy of the work of submersion, in a soft road, the resistance to traction must be the same for all diameters of wheels. But, as the rectangle of work is spread over a longer space, dC , for the larger wheel, than the space, dc , for the smaller wheel, it follows, on the contrary, that the resistance or force of traction varies in some proportion inversely as the diameter, being less as the diameter is greater. This conclusion accords with experience; but though the actual law of variation may not be strictly deducible in the line of reasoning here traced, it is nevertheless useful to carry the reasoning to its logical conclusion. Let a and A be the diameters respectively of the smaller and the larger wheels, b and B the depths of immersion, and c and C the lengths of immersion, or dc and Dc , respectively. As already stated, the areas of immersion are equal to each other, or

$$bc = BC. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

Also, the values of c and C are, by the properties of the circle, expressible by the products \sqrt{ab} and \sqrt{AB} , for all cases that need occur in practice; and, by substitution in the equation (2),

$$b\sqrt{ab} = B\sqrt{AB}; \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

and, squaring both sides,

$$ab^3 = AB^3. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

Finally, extracting the cube root of each side of this equation (4), the equation (5) is obtained,

$$b\sqrt[3]{a} = B\sqrt[3]{A}, \dots \dots \dots (E)$$

which may be developed into the proportion

$$b : B :: \sqrt[3]{A} : \sqrt[3]{a}; \dots \dots \dots (6)$$

showing that the depth of immersion varies as the cube root of the diameter. But, as $bc = BC$, and $b : B :: C : c$, then,

$$C : c :: \sqrt[3]{A} : \sqrt[3]{a}, \dots \dots \dots (7)$$

showing that the length of immersion is as the cube root of the diameter. It has already been seen that the force of traction is as the length of immersion; therefore, finally,

520. The circumferential or rolling resistance of wheels to traction on a level road is inversely proportional to the cube root of the diameter.

On this principle of resistance, it follows that, to reduce the rolling resistance of a wheel one half, for instance, the diameter must be enlarged to eight times the primary diameter.

The deduction of M. Morin, that the resistance varies simply in the inverse ratio of the diameter of the wheel,—so that, for example, a wheel of twice the diameter would only incur half the resistance,—has been generally accepted. But this deduction is not supported by the foregoing analysis of forces, and there is good reason for renouncing it, in the more recent experiments of M. Dupuit. He placed model wheels or rollers of various diameters at the summit of an inclined plane, succeeded by a horizontal plane, on which they rolled down by the force of gravity and arrived at a state of rest after having expended the energy acquired in falling through the height of the plane. From these and other experiments he drew the following deductions:

On macadamized roads in good condition, and on uniform surfaces generally,

(1) The resistance to traction is directly proportional to the pressure.

- (2) It is independent of the width of the tire.
 (3) It is inversely as the square root of the diameter.
 (4) It is independent of the speed.

M. Dupuit admits that on paved roads which give rise to constant concussion, the resistance increases with the speed, whilst it is diminished by an enlargement of the tire up to a certain limit.

The resistance produced by the hollows between the stones of a pavement is of a different character. According to M. Gerstner, the resistance arising from such a surface is directly proportional to the load, to the square of the velocity, and to the ratio of the width of the cavity to the radius of the wheel, and inversely proportional to the width of the paving-stones.

521. Friction.—The resistance of friction arises from the rubbing of the wheels against the surfaces with which they come in contact, and will always exist. The friction of surfaces is variable, and can be determined only by experiment. Friction of the axles and resistance of the air are causes of resistance to motion but their consideration may be neglected, as their effects are constant, and independent of the imperfections of the road.

522. Many experiments have been made at various times to ascertain, in functions of the quality and condition of the road-surfaces, the measure of the tractive force, or the force required to overcome the resistances which oppose themselves to the movement of a vehicle along horizontal roads of different degrees of smoothness and hardness and covered with different materials.

Table L presents the results of those experiments. The frac-

TABLE L.
 RESISTANCE TO TRACTION ON DIFFERENT ROAD-SURFACES.
 (RUDOLF HERING).

Character of Road.	Resistance in Terms of Load.	Pounds per ton.	Velocity.	Authority.
Sand.....	$\frac{1}{16}$	448	Pace	Bevan
Sandy road.....	$\frac{1}{16}$	187	8' to 12' per sec.	Morin
Gravel (loose).....	$\frac{1}{16}$	320	Pace	Bevan
" (4 in. thick).....	$\frac{1}{16}$	224	"	Morin
" (common road).....	$\frac{1}{16}$	140	"	Machell
" (road).....	$\frac{1}{16}$	86	8' per sec.	Bumford
" "	$\frac{1}{16}$	90	12' per sec.	"

RESISTANCE TO TRACTION ON DIFFERENT ROAD-SURFACES—*Continued.*

Character of Road.	Resistance in Terms of Load.	Pounds per ton.	Velocity.	Authority.
Gravel (hard rolled).....	$\frac{1}{16}$	75	Pace	{ Bevan Minard
Turf (wet).....	$\frac{1}{8}$	280	"	Morin
" (dry and hard).....	$\frac{1}{16}$	124	"	"
" " " ".....	$\frac{1}{16}$	90	Bevan
Earth (ordinary road).....	$\frac{1}{16}$	224	Pace	"
Earth (dry and hard).....	$\frac{1}{16}$	101-75	"	Morin
Clay (hard).....	$\frac{1}{16}$	112	Bevan
Cobblestones (ordinary)....	$\frac{1}{16}$	280	Trot
" " " ".....	$\frac{1}{16}$	140	Pace
" (good, $3\frac{1}{2}$ in.).....	$\frac{1}{16}$	150	Trot	Kossack
" " " ".....	$\frac{1}{16}$	75	Pace	"
Macadam (little used).....	$\frac{1}{16}$	140-97	Morin
" (bad).....	$\frac{1}{16}$	160	Pace	Gordon
" (old).....	$\frac{1}{16}$	90	Navier
" (ordinary).....	$\frac{1}{16}$	90	Trot	{ MacNeill Perdon't
" " " ".....	$\frac{1}{16}$	64	Pace	Kossack
Macadam (good, slightly muddy).....	$\frac{1}{16}$	75-41	Morin
Macadam (best French)....	$\frac{1}{16}$	45	Navier
Macadam (very hard and smooth).....	$\frac{1}{16}$	45	MacNeill
Macadam (best).....	$\frac{1}{16}$	64	Trot	Rumford
" " " ".....	$\frac{1}{16}$	50	Pace	"
" " " ".....	$\frac{1}{16}$	48-37	Gordon
" " " ".....	$\frac{1}{16}$	52-30	Morin
Belgian block (ordinary)...	$\frac{1}{16}$	56	Pace	MacNeill
Bel. block (Boulev., Paris).	$\frac{1}{16}$	50-34	Navier
" " (good).....	$\frac{1}{16}$	75	Trot	Rumford
" " " ".....	$\frac{1}{16}$	37	Pace	"
" " (well laid)....	$\frac{1}{16}$	85	MacNeill
" " (good).....	$\frac{1}{16}$	50-26	Morin
Granite block (ordinary)...	$\frac{1}{16}$	90	{ Perdon't Poncelet
" " (good).....	$\frac{1}{16}$	183	Trot	Minard
" " " ".....	$\frac{1}{16}$	45	Pace	Rumford
" " (good Lond.).....	$\frac{1}{16}$	86	Gordon
Planked roadway.....	$\frac{1}{16}$	56-40	Morin
Asphalt.....	$\frac{1}{16}$	17	Gordon
Granite tramway.....	$\frac{1}{16}$	14	"
Iron tramway.....	$\frac{1}{16}$	11	"
Sleighs on snow 8 in. thick $\frac{1}{2}$ in. runner, temperature 26° Fahr.....	$\frac{1}{16}$	75
Loose sand (experimental)...	320
Best gravel (park road)	51
Best clay.....	98	U. S.
Best macadam.....	38	Dept.
Block pavement (poor).....	42	Agri-
Cobblestone.....	54	culture.
Asphalt (poor).....	26

tions which are generally rounded off, indicate the part of the whole weight which is equivalent to the resistance of drawing it on a level road. An examination of this table will clearly show the great economy in horse-power by using the hardest and smoothest material for road-coverings. For instance, if 1 horse can just draw a load on a level road on iron rails, it will require $1\frac{1}{2}$ horses to draw it on asphalt, $3\frac{1}{2}$ on the best Belgian-block pavement, 7 on good cobblestone pavement, 13 on bed cobblestone, 20 on an ordinary earth road, and 40 on a sandy road.

523. The following deductions are from the experiments of MM. Dupuit and Morin:

1st. The resistance to traction on uniform smooth surfaces is directly proportional to the load, and inversely as the square root of the diameter of the wheels.

2d. It is independent of the width of the tire when this quantity exceeds 3 or 4 inches.

3d. It is independent of the speed.

4th. On paved surfaces which give rise to constant concussion, it increases with the speed.

5th. Upon soft roads of earth or sand or turf, or roads fresh and thickly gravelled, the resistance to traction is independent of the velocity.

6th. At a walking pace, the resistance is the same, under the same circumstances, for vehicles with springs and for vehicles without springs.

7th. The destruction of the road is, in all cases, greater as the diameter of the wheels is less, and it is greater in vehicles without than with springs.

524. The comparative ease of draft on various surfaces is largely influenced by the amount of foothold afforded, and it may be doubted if dynamometer experiments, however carefully made, are altogether conclusive. The tractive force is influenced by the diameter of the wheels, the friction of the wheels on the axles, and the speed, as well as by the resistance of the road surface; and these must be all taken into account to obtain accurate results. Recent experiments on London and Paris street pavements gave the following results, speed 2 to 6 miles per hour:

TABLE LI.
TRACTION FORCE ON A LEVEL.

Surface.	Pounds per ton.	
	London.	Paris.
Macadamized.....	40.7 to 44.29	32.12 to 39.88
Asphalt	39.0 " 39.32
Wood.....	33.62 " 36.03	33.44 to 39.16
Granite....	26.2 " 27.00	35.20

525. Gravity.—The grade of the road, or the quantity by which it differs from a level. The grade resistance is due to the force of gravity, and is the same on both good and bad roads, and unlike the others may be determined from the laws of mechanics, whilst the former are determinable entirely by experiment on the road in question. The resistance due to gravity on any incline in pounds per ton = $\frac{2240}{\text{rate of grade}}$.

TABLE LII.
RESISTANCE DUE TO GRAVITY ON DIFFERENT INCLINATIONS.

Grade 1 in.....	20	30	40	50	60	70	80	90	100	200	300	400
Rise in feet per mlie.....	264	176	132	105	88	75	66	58	52	26	17	13
Resistance in lbs. per ton	112	74½	56	45	38	32	28	25	22	11½	7½	5½

526. The additional resistance caused by inclines may be investigated in the following manner: Suppose the whole weight to be borne on one pair of wheels, and that the tractive force is applied in a direction parallel to the surface of the road.

Let *AB* in Fig. 40 represent a portion of the inclined road, *C* being a vehicle just sustained in its position by a force acting in the direction *CD*. It is evident that the vehicle is kept in its position by three forces; namely, by its own weight *W* acting in the vertical direction *CF*, by the force *F* applied in the direction *CD* parallel to the surface of the road, and by the pressure *P* which the vehicle exerts against the surface of the road acting in the direction *CE* perpendicular to the same. To determine the relative magnitude

of these three forces, draw the horizontal line AG and the vertical one BG ; then, since the two lines CF and BG are parallel and are




FIG. 40.

both cut by the line AB , they must make the two angles CFE and ABG equal; also the two angles CEF and AGB are equal; therefore the remaining angles FCE and BAG are equal, and the two triangles CFE and ABG are similar. And as the three sides of the former are proportional to the three forces by which the vehicle is sustained, so also are the three sides of the latter; namely, AB or the length of the road is proportional to W , or the weight of the vehicle; BG , or the vertical rise in the same, to F , or the force required to sustain the vehicle on the incline; and AG , or the horizontal distance in which the rise occurs, to P , or the force with which the vehicle presses upon the surface of the road. Therefore

$$W : AB :: F : GB,$$

and

$$W : AB :: P : AG.$$

And if to AG such a value be assigned that the vertical rise of the road is exactly one foot, then

$$F = \frac{W}{AB} = \frac{W}{\sqrt{AG^2 + 1}} = W \cdot \sin A,$$

and

$$P = \frac{W \cdot AG}{AB} = \frac{W \cdot AG}{\sqrt{AG^2 + 1}} = W \cdot \cos A,$$

in which A is the angle BAG .

527. To find the force requisite to sustain a vehicle upon an inclined road (the effects of friction being neglected), divide the weight of the vehicle and its load by the inclined length of the road, the vertical rise of which is one foot, and the quotient is the force required.

528. To find the pressure of a vehicle against the surface of an inclined road, multiply the weight of the loaded vehicle by the horizontal length of the road, and divide the product by the inclined length of the same; the quotient is the pressure required.

529. The force with which a vehicle presses upon an inclined road is always less than its actual weight; the difference is so small that, unless the inclination is very steep, it may be taken equal to the weight of the loaded vehicle.

530. To find the resistance to traction in passing up or down an incline, ascertain the resistance on a level road having the same surface as the incline, to which add, if the vehicle ascends, or subtract, if it descends, the force requisite to sustain it on the incline; the sum or difference, as the case may be, will express the resistance.

531. Tractive Power and Gradients.—The necessity for easy grades is dependent upon the power of the horse to overcome the resistance to motion composed of the four forces, friction, collision, gravity, and the resistance of the air.

All estimates on the tractive power of horses must to a certain extent be vague, owing to the different strengths and speeds of animals of the same kind, as well as to the extent of their training to any particular kind of work. Authorities on the subject differ widely, and sometimes express themselves in a loose manner that throws doubt on their meaning.

532. The draught or pull which a good average horse, weighing 200 pounds, can exert on a level, smooth road at a speed of $2\frac{1}{2}$ miles per hour is 100 pounds, equivalent to 22,000 foot-pounds per minute, or 13,200,000 foot-pounds per day of 10 hours.

533. The tractive power diminishes as the speed increases and perhaps, within certain limits, say from $\frac{3}{4}$ to 4 miles per hour, nearly

in inverse proportion to it. Thus the average tractive force of a horse, on a level, and actually pulling for 10 hours, may be assumed approximately as follows:

TABLE LIII.
TRACTION POWER OF HORSES AT DIFFERENT VELOCITIES.

Miles per hour.	Tractive Force. Pounds.	Miles per hour.	Tractive Force. Pounds.
$\frac{1}{2}$	333.33	$2\frac{1}{2}$	111.11
1.....	250	$2\frac{1}{2}$	100
$1\frac{1}{2}$	200	$2\frac{1}{2}$	90.91
$1\frac{1}{2}$	166.66	3.....	83.33
$1\frac{1}{2}$	142.86	$3\frac{1}{2}$	71.43
2.....	125	4.....	62.50

534. The work done by a horse is greatest when the velocity with which he moves is $\frac{1}{3}$ of the greatest velocity with which he can move when unloaded; and the force thus exerted is 0.45 of the utmost force that he can exert at a dead pull.

TABLE LIV.
DURATION OF A HORSE'S DAILY LABOR AND MAXIMUM VELOCITY UNLOADED.

Duration of Labor. Hours.	Maximum Velocity. Miles per hour.	Duration of Labor. Hours.	Maximum Velocity. Miles per hour.
1.....	14.7	6.....	6.0
2.....	10.4	7.....	5.5
3.....	8.5	8.....	5.2
4.....	7.8	9.....	4.9
5.....	6.6	10.....	4.6

535. The tractive power of a horse may be increased in about the same proportion as the time is diminished, so that when working from 5 to 10 hours, on a level, it will be about as shown in the following table:

TABLE LV.

Hours per day.	Traction (pounds).	Hours per day.	Traction (pounds).
10.....	100	7.....	146 $\frac{2}{3}$
9.....	111 $\frac{1}{3}$	6.....	166 $\frac{2}{3}$
8.....	125	5.....	200

The tractive power of teams is about as follows :

1 horse	= 1
2 horses.....	$0.95 \times 2 = 1.90$
3 "	$0.85 \times 3 = 2.55$
4 "	$0.80 \times 4 = 3.20$

Table LVI is useful as showing the maximum amount of labor a horse of average strength is capable of performing at different rates of speed.

TABLE LVI.

Speed in Miles per hour.	Duration of the Day's Work.	Resistance to Traction assumed at Pounds.	Useful Effect of One Horse working 1 day in tons drawn 1 mile.*	
			On Level Iron Rails. Tons.	On Level Maca- dam. Tons.
2½	11½	88½	115	14
3	8	88½	92	12
3½	5¾	88½	82	10
4	4½	88½	72	9
5	2¾	88½	57	7.2
6	2	88½	48	3.0
7	1½	88½	41	5.1
8	1¼	88½	36	4.5
9	1¼	88½	32	4.0
10	¾	88½	28.8	3.6

* The actual labor which a horse can perform is greater, but he is injured by it.

536. Loss of Tractive Power on Inclines.—In ascending inclines a horse's power diminishes rapidly; a large portion of his strength is expended in overcoming the resistance of gravity due to his own weight and that of the load. Table LVIII shows that as the steepness of the grade increases the efficiency of both the horse and the road-surface diminishes; that the more the horse's energy is expended in overcoming gravity the less remains to overcome the surface-resistance.

Table LVII shows the gross load which an average horse, weighing 1200 pounds, can draw on different kinds of road-surfaces, on a level and on grades rising five and ten feet per one hundred feet.

TABLE LVII.

Description of Surface.	Level.	5 per cent. Grade.	10 per cent. Grade.
	Pounds.	Pounds.	Pounds.
Asphalt.....	18,216
Broken stone (best condition).....	6,700	1,840	1,080
“ “ (slightly muddy).....	4,700	1,500	1,000
“ “ (ruts and mud).....	8,000	1,390	890
“ “ (very bad condition).....	1,840	1,040	740
Earth (best condition).....	3,600	1,500	990
“ (average condition).....	1,400	900	660
“ (moist but not muddy).....	1,100	780	600
Stone-block pavement (dry and clean).....	8,300	1,920	1,090
“ “ (muddy).....	6,250	1,800	1,040
Sand (wet).....	1,500	675	390
“ (dry).....	1,087	445	217

The formula which shows the relation of the tractive force to the weight of the load is

$$K = \mu Q + (G + Q) \tan \alpha,$$

in which K represents the mean tractive power of the horse, taken at $\frac{1}{2}$ of its weight, equal to 165 of its weight, equal to 165 pounds;

μ the coefficient of resistance to traction;

Q the load, including the weight of the wagon;

G the mean weight of the horse = $165 \times 5 = 825$ pounds;

α the angle of inclination.

Q , the load in the above expression, is equal to

$$\frac{K - G \tan \alpha}{\mu + \tan \alpha},$$

and this form has been utilized for the computation of Table LVIIa, showing the load (with vehicle) that the average horse, exerting an average tractive force, can pull up a continuous incline having various grades and different coefficients of resistance, without requiring reinforcement at any time.

While the above formula holds good for all inclinations shown in the table, it must be stated that it is no longer applicable for excessive grades, for the tractive force in reality diminishes so rapidly that at an angle of 30 degrees it becomes zero.

TABLE LVIIIa.

Grade tan α	Values μ					Grade tan α	Values μ				
	$\frac{1}{10}$	$\frac{1}{8}$	$\frac{1}{6}$	$\frac{1}{5}$	$\frac{1}{4}$		$\frac{1}{10}$	$\frac{1}{8}$	$\frac{1}{6}$	$\frac{1}{5}$	$\frac{1}{4}$
	Load Q in Pounds.						Load Q in Pounds.				
0.000	8950	4950	3300	1650	825	0.022	3497	2654	2040	1204	661
0.002	7425	4627	3141	1601	808	0.025	3206	2476	1925	1155	642
0.004	6737	4335	2994	1555	793	0.028	2956	2315	1819	1109	623
0.008	5657	3835	2731	1467	761	0.033	2599	2078	1660	1086	591
0.010	5325	3690	2612	1435	747	0.040	2200	1800	1467	943	550
0.012	4847	3424	2502	1385	732	0.050	1764	1483	1238	825	495
0.016	4217	3079	2300	1309	708	0.066	1285	1113	963	666	415
0.020	3718	2796	2121	1237	675	0.100	687	610	550	418	275

537. The decrease in the load which a horse can draw upon an incline is not due alone to gravity; it varies with the amount of foothold afforded by the road-surface. The tangent of the angle of inclination should not be greater than the coefficient of tractional resistance; therefore it is evident that the smoother the road-surface the easier should be the grade. The smoother the surface the less the foothold, and consequently the load. Table LVIII shows the decrease in the loads caused by various road-coverings on grades from 1 to 20 per cent.

TABLE LVIII.

EFFECT OF GRADES UPON THE LOADS A HORSE CAN DRAW ON DIFFERENT PAVEMENTS.

Grade.	Earth.	Broken Stone.	Stone Blocks.	Asphalt.
Level.....	1.00	1.00	1.00	1.00
1:100.....	.80	.66	.72	.41
2:100.....	.66	.50	.55	.25
3:100.....	.55	.40	.44	.18
4:100.....	.47	.33	.36	.13
5:100.....	.41	.29	.30	.10
10:100.....	.26	.16	.14	.04
15:100.....	.10	.05	.07
20:100.....	.0408

538. The loss of tractive power on inclines is greater than any investigation will show; for, besides the increase of draught caused by gravity, the power of the horse is much diminished by fatigue

upon a long ascent, and even in greater ratio than man, owing to its anatomical formation and great weight. Though a horse on a level is as strong as five men, on a grade of 15 per cent, it is less strong than three; for three men carrying each 100 pounds will ascend such a grade faster and with less fatigue than a horse with 300 pounds.

539. A horse can exert for a short time twice the average tractive pull which he can exert continuously throughout a day's work; hence, so long as the resistance on the incline is not more than double the resistance on the level, the horse will be able to take up the full load which he is capable of drawing.

540. Steep grades are thus seen to be objectionable, and particularly so when a single one occurs on an otherwise comparatively level road, in which case the load carried over the less inclined portions must be reduced to what can be hauled up the steeper portion.

541. The bad effects of steep grades are especially felt in winter, when ice covers the roads, for the slippery condition of the surface causes danger in descending, as well as increased labor in ascending; the water of rains also runs down the road and gulleys it out, destroying its surface, thus causing a constant expense for repairs. The inclined portions are subjected to greater wear from the feet of horses ascending, thus requiring thicker covering than the more level portions, and hence increasing the cost of construction.

542. It will rarely be possible, except in a flat or comparatively level country, to combine easy grades with the shortest and most direct route. These two requirements will often conflict; in such a case increase the length. The proportion of this increase will depend upon the friction of the covering adopted. But no general rule can be given to meet all cases as respects the length which may thus be added, for the comparative time occupied in making the journey forms an important element in any case which arises for settlement. Disregarding time, the horizontal length of a road may be increased, to avoid a 5 per cent grade, seventy times the height.

Table LIX shows with sufficient exactness for most practical purposes the force required to draw loaded vehicles over inclined roads. The first column expresses the rate of inclination; the second, the pressure on the plane in pounds per ton; the third, the tendency down the plane (or force required to overcome the effect of gravity) in pounds per ton; the fourth, the force required to haul one ton up

TABLE LIX.

Rate of Grade. Feet per 100 feet.	Pressure on the Plane in lbs. per ton.	Tendency down the Plane in lbs. per ton.	Power in lbs. required to haul one ton up the Plane.	Equivalent Length of Level Road. Miles.	Maximum Load in lbs. which a Horse can haul.
0.0	2240	00	45.00	1.000	6270
0.25	"	5.60	50.60	1.121	5876
0.50	"	11.20	56.20	1.242	4978
0.75	"	16.80	61.80	1.373	4490
1	* "	22.40	67.40	1.500	4145
1.25	"	28.00	73.00	1.622	3880
1.50	"	33.60	78.60	1.746	3584
1.75	"	39.20	84.20	1.871	3290
2	"	45.00	90.00	2.000	3114
2.25	"	50.40	95.40	2.120	2935
2.50	"	56.00	101.00	2.244	2725
2.75	"	61.83	106.83	2.363	2620
3	2289	67.20	112.20	2.484	2486
4	2288	89.20	134.20	2.982	2063
5	2287	112.00	157.00	3.444	1800
6	2283	134.40	179.40	3.986	1568
7	2282	156.80	201.80	4.844	1367
8	"	179.20	224.20	4.982	1235
9	2231	201.60	246.60	5.480	1125
10	2229	224.00	269.00	5.977	1080

* Near enough for practice, actually 2239.688.

Pressure on the plane = weight \times nat cos of angle of plane.

the incline; the fifth, the length of level road which would be equivalent to a mile in length of the inclined road—that is, the length which would require the same motive power to be expended in drawing the load over it as would be necessary to draw it over a mile of the inclined road; the sixth, the maximum load which an average horse weighing 1200 pounds can draw over such inclines, the friction of the surface being taken at $\frac{1}{10}$ of the load drawn.

543. Character of Vehicles.—The character of the vehicles used upon a roadway has a great influence upon its endurance to the beat of the wheels. The great defect of our vehicles is that for a given load the tires of the wheels are too narrow. It has been proved by repeated and careful experiments that wheels with tires two and a half inches wide cause double the wear of wheels which have tires four and a half inches wide. It is true that on ill-conditioned and muddy roads a narrow wheel-tread is advantageous, for the reason that the thick mud has a less extended hold when it wraps around the felloes and spokes; but with this arrangement

the interests of the roadway are sacrificed to the convenience of the individual who drives upon it.

544. Vehicles with Narrow Tires.—Vehicles with narrow-tired wheels carrying heavy loads cause much damage, particularly on roads where they run in one track; the knife-like tire cuts into the road covering, forming ruts which each succeeding vehicle deepens; thus the cost of maintenance is considerably increased. The proper width of tire, or proper load for a given width of tire, is a question that deserves more attention than is usually accorded to it.

545. The best width of tire measured when new is shown in Table LX.

These widths are best for easy traction and the maximum wear of the road-surface. To make the tires wider does not diminish the force required to move the load, and unnecessarily increases the dead weight of the vehicles. For carriages, coupés, and vehicles for light passenger use the tires need not exceed $2\frac{1}{2}$ inches and should never be less than 2 inches.

The width of tires should be established by law.

The French Commission, presided over by Morin and Dupuit, recommends as maximum width of tire $4\frac{1}{2}$ inches, and as minimum width $2\frac{3}{8}$ inches.

The best European practice allows only from 500 to 900 pounds per inch width of tire. In the United States loads ranging from 1000 to 5000 pounds per inch width of tire are quite common.

TABLE LX.

Load on each Wheel.	Description of Vehicles.			
	Two Wheels without Springs. Inches.	Two Wheels with Springs. Inches.	Four Wheels without Springs. Inches.	Four Wheels with Springs. Inches.
$\frac{1}{2}$ ton	6	8	5	3
$\frac{1}{4}$ "	6	8	5	3
1 "	5	$3\frac{1}{2}$
$1\frac{1}{2}$ "	5	4
2 "	6	$4\frac{1}{2}$

546. The freight and market wagons of France have tires from 3 to 10 inches in width, usually from 4 to 6 inches. The four-

NOTE.—All laws regarding the width of tires in London have been abolished.

wheeled freight-wagons have tires rarely less than 6 inches and the rear axle is about 14 inches longer than the fore, so that the rear wheels run on a line about an inch outside of the line of the fore-wheels. The varied gauge is also usually observed with cabs, hacks, and other four-wheeled vehicles.

547. In Bavaria the width of the wheel-tires is laid down by law as follows:

2-wheeled carts with 2 horses.....	4.183 inches
“ “ “ 4 “	6.180 “
4-wheeled carts with 2 “	2.596 “
“ “ “ 3 or 4 horses.....	4.183 “
“ “ “ 5 to 8 “	6.180 “

Carts with more than four and wagons with more than eight horses are not allowed to use the road except under special permit from the authorities.

548. In Austria the width of tires for wagons carrying 2½ tons is 4.33 inches, and for wagons carrying 4½ tons 6.30 inches.

548a. In June, 1892, the Studebaker Bros. Mfg. Co. of South Bend, Ind., made a series of tests to determine the relative merits of wide and narrow tires with regard to the resistance they offered to traction upon different road-surfaces. The wagon employed was a regular 3½-inch thimble-skein wagon having in one set of tests wheels 3 feet 8 inches and 4 feet 6 inches in diameter, and in another set 3 feet 6 inches and 3 feet 10 inches. A Fairbanks dynamometer was attached to the double-tree, and the team exerted their pull through the instrument to move the load.

The tests showed that the width of tire has very little effect upon the power required to move loads upon hard surfaces, such as stone blocks, hard sand, or gravel, the power required to move a load of one ton (2240 pounds) being on

Stone blocks with 1½-in. tire	168 pounds;	with 4-in. tire	180 pounds.
Hard sand “ “ “ “	383 “	“ “ “ “	360 “
Hard gravel “ “ “ “	344 “	“ “ “ “	311 “

Upon soft ground, such as mud and grass sods, into which the narrow tires would cut, the wide tires have a slight advantage, the power required to move one ton (2240 pounds) being on

Soft mud with 1½-in. tire	476 pounds;	with 4-in. tire	412 pounds.
Sod “ “ “ “	610 “	“ 3 “ “	537 “

The power required to keep the load in motion after being started was found to range from 25 to 50 per cent less than

that required to start it. It was also found that less power was required to start the load when wheels of large diameter were employed, and that the diameter of the wheel had no apparent effect on the power required to keep the load in motion.

Numerous tests of the influence of width of tire on draft of wagons have been made at the University of Missouri. The following is a brief summary of the results:

The width of the tires used was one and one-half inches and six inches. The draft was determined by a self-recording dynamometer. The net load in every trial was 2000 pounds.

The loads which could be hauled with the same draft were on:

	1½-inch Tire.	6-inch Tire.
<i>Macadam</i>	2000 lbs.	2518 lbs.
<i>Gravel</i> , good condition.....	2000 "	2482 "
<i>Dirt</i> , dry and hard.....	2000 "	2500 "
<i>Clay</i> , with mud, deep and drying on top and spongy underneath (1).....	2000 "	3200 "

(1) In this condition of road the broad tires show to their greatest advantage. As the road dries and becomes firmer the difference between the draft of the broad and the narrow tires gradually diminishes until it reaches about 25 to 30 per cent on dry, hard, smooth dirt, gravel, or macadam, in favor of the broad tire. On the other hand, as the mud becomes softer and deeper, the difference between the draft of the two types of tires rapidly diminishes until the condition is reached when the mud adheres to both styles of wheels. Here the advantage of the broad tires ceases entirely, and the draft required for the narrow tires is considerably less.

Clay, surface dry, with deep ruts cut by narrow tires in the ordinary use of the road. The first run of the broad tire over the narrow-tire rut showed a materially increased draft when compared with that of the narrow tire run in its own rut. The second run of the broad tire in the same track where the rut was not deep completely eliminated this disadvantage, and showed a lighter draft for the broad tire than the narrow tire showed in the first run. When the ruts were eight inches deep with rigid walls three runs of the broad tire in its own track over the ruts were required to eliminate the disadvantage.

The conditions which showed results unfavorable to the broad tires were :

Gravel, wet and sloppy.

Dirt.—1. When sloppy, muddy, or sticky on the surface and firm or hard underneath.

2. When covered with a very deep, loose dust and hard underneath.

3. When the mud is very deep and so sticky that it adheres to the wheels of both types.

The experimenters concluded that the best width of tire for a combination farm and road wagon is six inches, and that both axles should be the same length, so that the front and hind wheels will run in the same track.

549. Size of Wheels.—The wheels of a vehicle serve a twofold purpose. In the first place, they diminish the friction on the ground by transferring it from the circumference to the nave and axle; and in the second place, they serve to raise the vehicle more easily over obstacles met with on roads.

550. The friction is diminished in the proportion of the circumference of the axle to that of the wheel; and hence the larger the wheel and the smaller the axle the less is the friction.

The mechanical advantage of the wheel in surmounting an obstacle may be computed from the principle of the lever.

Let the wheel, Fig. 41, touch the horizontal line of traction in the point *A* and meet a protuberance *BD*. Suppose the line of draught




FIG. 41.

CP to be parallel to *AB*. Join *CD* and draw the perpendiculars *DE* and *DF*. We may suppose the power to be applied at *E* and the weight at *F*, and the action is then the same as the bent lever *EDF* turning round the fulcrum at *D*. Hence $P : W :: FD : DE$.

but $FD : DE :: \tan FCD : 1$, and $\tan FCD = \tan 2(DAB)$; therefore $P = W \tan 2(DAB)$. Now it is obvious that the angle DAB increases as the radius of the circle diminishes; and therefore, the weight W being constant, the power required to overcome an obstacle of a given height is diminished when the diameter is increased. Large wheels are therefore the best adapted for surmounting inequalities of the road.

551. There are, however, circumstances which provide limits to the height of the wheels of vehicles. If the radius AC exceeds the height of that part of the horse to which the traces are attached, the line of traction CP will be inclined to the horse, and part of the power will be exerted in pressing the wheel against the ground. The best average size of wheels is considered to be about 6 feet in diameter.

552. Wheels of large diameter do less damage to a road than small ones, and cause less draught for the horses.

553. With the same load a two-wheeled cart does far more damage than one with four wheels, and this because of their sudden and irregular twisting motion in the trackway.

554. Umpfenbach recommends the following wheel diameters for vehicles frequenting good roads :

1. For two-wheeled freight-carts, 5 feet 3 inches to 5 feet 9 inches.
2. For four-wheeled freight-wagons, front wheels 3 feet 1 inch, hind wheels 3 feet 9 inches to 4 feet 2 inches.

These diameters should be increased from 6 to 12 inches for traffic on bad roads.

554a. **Effect of Springs on Vehicles.**—Experiments have shown that vehicles mounted on springs materially decrease the resistances to traction, and diminish the wear of the road, especially at speeds beyond a walking pace. Going at a trot they were found not to cause more wear than vehicles without springs at a walk, all other conditions being similar. Vehicles with springs improperly fixed cause considerable concussion, which in its turn destroys the road covering.

CHAPTER XI.

LOCATION OF COUNTRY ROADS.

555. THE considerations governing the location of country roads are dependent upon the commercial condition of the country to be traversed. In old and long-inhabited sections the controlling element will be the character of the traffic to be accommodated. In such a section the route is generally predetermined, and therefore there is less liberty of a choice and selection than in a new and sparsely settled district, where the object is to establish the easiest, shortest, and most economical line of intercommunication according to the physical character of the ground.

556. Whichever of these two cases may have to be dealt with, the same principle governs the engineer, namely, to so lay out the road as to effect the conveyance of the traffic with the least expenditure of motive power consistent with economy of construction and maintenance.

557. Economy of motive power is promoted by easy grades, by the avoidance of all unnecessary ascents and descents, and by a direct line; but directness must be sacrificed to secure easy grades and to avoid expensive construction.

558. Reconnoissance.—The selection of the best route demands much care and consideration on the part of the engineer. To obtain the requisite data upon which to form his judgment he must make a personal reconnoissance of the district. This requires that the proposed route be either ridden or walked over and a careful examination made of the principal physical contours and natural features of the district. The amount of care demanded and the difficulties attending the operations will altogether depend upon the character of the country.

559. The immediate object of the reconnoissance is to select one or more trial lines, from which the final route may be ultimately determined.

When there are no maps of the section traversed, or when those which can be procured are indefinite or inaccurate, the work of reconnoitring will be much increased.

560. In making a reconnaissance there are several points which, if carefully attended to, will very considerably lessen the labor and time otherwise required. Lines which would run along the immediate bank of a large stream must of necessity intersect all the tributaries confluent on that bank, thereby demanding a corresponding number of bridges. Those, again, which are situated along the slopes of hills are more liable in rainy weather to suffer from washing away of the earthwork and sliding of the embankments; the others which are placed in valleys or elevated plateaux, when the line crosses the ridges dividing the principal water-courses will have steep ascents and descents.

561. In making an examination of a tract of country, the first point to attract notice is the unevenness or undulations of its surface, which appears to be entirely without system, order, or arrangement; but upon closer examination it will be perceived that one general principle of configuration obtains even in the most irregular countries. The country is intersected in various directions by main water-courses or rivers, which increase in size as they approach the point of their discharge. Towards these main rivers lesser rivers approach on both sides, running right and left through the country, and into these, again, enter still smaller streams and brooks. The streams thus divide the hills into branches or spurs having approximately the same direction as themselves, and the ground falls in every direction from the main chain of hills towards the water-courses, forming ridges more or less elevated.

562. The main ridge is cut down at the heads of the streams into depressions called gaps or passes; the more elevated points are called peaks. The water which has fallen upon these peaks is the origin of the streams which have hollowed out the valleys. Furthermore, the ground falls in every direction towards the natural water-courses, forming ridges more or less elevated running between them and separating from each other the districts drained by the streams.

563. The natural water-courses mark not only the lowest lines, but the lines of the greatest longitudinal slope in the valleys through which they flow.

564. The direction and position of the principal streams give

also the direction and approximate position of the high ground or ridges which lie between them.

565. The position of the tributaries to the larger stream generally indicates the points of greatest depression in the summits of the ridges, and therefore the points at which lateral communication across the high ground separating contiguous valleys can be most readily made.

566. The instruments employed in reconnoitring, are:—The compass, for ascertaining the direction; the aneroid barometer, to fix the approximate elevation of summits, etc.; and the hand-level, to ascertain the elevation of neighboring points. If a vehicle can be used, an odometer may be added, but distances can usually be guessed or ascertained by time estimates or otherwise, closely enough for preliminary purposes. More outfit than the above (the use of which is supposed to be understood), with the best maps obtainable and a succession of travelling companions who possess a local knowledge of the country, will not be particularly useful.

567. The reconnoissance being completed, instrumental surveys of the routes deemed most advantageous should be made. When the several lines are plotted to the same scale, a good map can be prepared from which the exact location of the road can be determined.

568. In making the preliminary surveys the topographical features should be noted for a convenient distance to the right and left of the line, and all prominent points located by compass-bearings. The following data should be also obtained: the importance, magnitude, and direction of all streams and roads crossed; the character of the material to be excavated or available for embankments, the position of quarries and gravel-pits, and the modes of access thereto; and all other information that may effect a selection.

569. Topography.—There are various methods of delineating upon paper the irregularities of the surface of the ground. The method of most utility to the engineer is that by means of "contour lines." These are fine lines traced through the points of equal level over the surface surveyed, and denote that the level of the ground throughout the whole of their course is identical; that is to say, that every part of the ground over which the line passes is at a certain

height above a known fixed point termed the datum, this height being indicated by the figures written against the line.

The intervals between the lines vertically is equal and may be 1, 3, 5, 10, or more feet apart; 5 feet will be found the most useful.

The rate of inclination of the ground may be estimated by the relative proximity or distance apart of the lines. Where the ground is comparatively level they are far apart; where the surface is very hilly they lie close together.

These lines by their greater or less distance apart have the effect of shading, and make apparent to the eye the undulations and irregularities in the surface of the country.

Fig. 42 shows an imaginary tract of country the physical features of which are shown by contour lines.

570. Map.—The map should show the lengths and direction of the different portions of the line, the topography, rivers, water-courses, roads, railroads, and other matters of interest, such as town and county lines, dividing lines between property, timbered and cultivated lands, etc.

Any convenient scale may be adopted; 400 feet to an inch will be found the most useful.

Fig. 43 shows a map of this kind.

571. Memoir.—The descriptive memoir should give with minuteness all information such as the nature of the soil, character of the several excavations whether earth or rock, and such particular features as cannot clearly be shown on the map or profile.

Special information should be given concerning the rivers crossed, as to their width, depth at highest known flood, velocity of current, character of banks and bottom, and the angle of skew which the course makes with the line of the road.


572. Levels.—Levels should be taken along the course of each line, usually at every 100 feet, or at closer intervals depending upon the nature of the country.


In taking the levels, the heights of all existing roads, railroads, rivers, or canals should be noted. "Bench-marks" should be established at least every half-mile that is, marks made on any fixed object such as a gate-post, side of a house, or, in the absence of these, a cut made on a large tree. The height and exact description of each bench-mark should be recorded in the level book.

573. Cross-levels.—Wherever considered necessary levels at



Fig42.





right angles to the centre line should be taken. These will be found useful in showing what effect a deviation to the right or left of the surveyed line would have. Cross-levels should be taken at the intersection of all roads and railroads to show to what extent, if any, these levels will have to be altered to suit the levels of the proposed road.

574. Profile.—A profile is a longitudinal section of the route, made from the levels. Its horizontal scale should be the same as that of the map; the vertical scale should be such as will show with distinctness the inequalities of the ground.

Fig. 44 shows the manner in which a profile is drawn and the nature of the information to be given upon it.

575. Bridge Sites.—The question of choosing the site of bridges is an important one. If the selection is not restricted to a particular point, the river should be examined for a considerable distance above and below what would be the most convenient point for crossing; and if a better site is found, the line of the road must be made subordinate to it. If several practicable crossings exist, they must be carefully compared in order to select the one most advantageous. The following are controlling conditions: (1) Good character of the river-bed, affording a firm foundation. If rock is present near the surface of the river-bed, the foundation will be easy of execution and stability and economy will be insured.

(2) Stability of the river-banks, thus securing a permanent concentration of the waters in the same bed. (3) The axis of the bridge should be at right angles to the direction of the current. (4) Bends in the river are not suitable localities and should be avoided if possible. A straight reach above the bridge should be secured if possible.

576. Principles to be observed in making the Final Selection.

In making the final selection the following principles should be observed as far as practicable.

(a) To follow that route which affords the easiest grades. The easiest grade for a given road will depend upon the kind of covering adopted for its surface

(b) To connect the places by the shortest and most direct route commensurate with easy grades.

(c) To avoid all unnecessary ascents and descents. When a road is encumbered with useless ascents, the wasteful expenditure of power is considerable.

(d) To give the centre line such a position, with reference to the natural surface of the ground, that the cost of construction shall be reduced to the smallest possible amount.

(e) To cross all obstacles (where structures are necessary) as nearly as possible at right angles. The cost of skew structures increases nearly as the square of the secant of the obliquity.

(f) To cross ridges through the lowest pass which occurs.

(g) To cross either under or over railroads; for grade crossings mean danger to every user of the highway. Guards and gates frequently fail to afford protection, and the daily press is filled with accounts of accidents more or less serious; and while statistics fail to give total casualties, the aggregate must be great.

577. Examples of Cases to be Treated.—In laying out the line of a road, there are three cases which may have to be treated, and each of these is exemplified in the contour map Fig. 42, page 393. First, the two places to be connected, as the towns A and B on the plan, may be both situated in the same valley, and upon the same side of it; that is, they are not separated from each other by the main stream which drains the valley. This is the simplest case. Secondly, although both in the same valley, the two places may be on opposite sides of the valley, as at A and C, being separated by the main river. Thirdly, they may be situated in different valleys, sep-

arated by an intervening ridge of ground more or less elevated, as at A and D. In laying out an extensive line of road, it frequently happens that all these cases have to be dealt with; frequently, perhaps, during its course.

The most perfect road is that of which the course is perfectly straight and the surface practically level; and, all other things being the same, that is the best road which answers nearest to this description.

Now in the first case, that of the two towns situated on the same side of the main valley, there are two methods which may be pursued in forming a communication between them. A road following the direct line between them, shown by the thick dotted line *AB*, may be made, or a line may be adopted which will gradually and equally incline from one town to the other, supposing them to be at different levels, or which should keep, if they are on the same level, at that level throughout its entire course, following all the sinuosities and curves which the irregular formation of the country may render necessary for the fulfilment of these conditions. According to the first method, a level or uniformly inclined road might be made from one to the other; this line would cross all the valleys and streams which run down to the main river, thus necessitating deep cuttings, heavy embankments, and numerous bridges; or these expensive works might be avoided by following the sinuosities of the valley. When the sides of the main valley are pierced by numerous ravines with projecting spurs and ridges intervening, instead of following the sinuosities, it will be found better to make a nearly straight line cutting through the projecting points in such a way that the material excavated should be just sufficient to fill the hollows.

Now, of all these, the best is the straight and uniformly inclined, or the level road, although at the same time it is the most expensive. If the importance of the traffic passing between the places is not sufficient to warrant so great an outlay, it will become a matter of consideration whether the course of the road should be kept straight, its surface being made to undulate with the natural face of the country; or whether, a level or equally inclined line being adopted, the course of the road should be made to deviate from the direct line and follow the winding course which such a condition is supposed to necessitate.

In the second case, that of two places situated on opposite sides of the same valley, there is, in like manner, the choice of a perfectly straight line to connect them, which would probably require a high embankment if the road was kept level, or steep inclines if it followed the surface of the country; or by winding the road, it may be carried across the valley at a higher point, where, if the level road be taken, the embankment would not be so high, or, if kept on the surface, the inclination would be reduced.

In the third case, there is, in like manner, the alternative of carrying the road across the intervening ridge in a perfectly straight line, or of deviating it to the right and left, and crossing the ridge at a point where the elevation is less.

The proper determination of the question which of these courses is the best under certain circumstances involves a consideration of the comparative advantages and disadvantages of inclines and curves. What additional increase in the length of a road would be equivalent to a given inclined plane upon it; or, conversely, what inclination might be given to a road as an equivalent to a given decrease in its length? To satisfy this question it is requisite to know the comparative force required to draw different vehicles with given loads upon level and upon variously inclined roads—a subject which is treated in Chapter X.

The route which will give the most general satisfaction consists in following the valleys as much as possible and rising afterward by gentle grades. This course traverses the cultivated lands, regions studded with farm-houses and factories. The value of such a line is much more considerable than that of a route by the ridges. The water-courses which flow down to the main valley are, it is true, crossed where they are the largest, and require works of large dimensions, but also they are fewer in number.

578. Intermediate Towns.—Suppose that it is desired to form a road between two distant towns, A and B, Fig. 45, and let us for the present neglect altogether the consideration of the physical features of the intervening country, assuming that it is equally favorable whatever line we select. Now at first sight, it would appear that under such circumstances a perfectly straight line drawn from one town to the other would be the best that could be chosen. On more careful examination, however, of the locality, we may find that there is a third town, C, situated somewhat on one side of the

straight line which we have drawn from A to B; and although our primary object is to connect only the two latter, that it would nevertheless be of considerable service if the whole of the three




FIG. 45.

towns were put into mutual connection with each other. Now this may be effected in three different ways, any one of which might, under the circumstances, be the best. In the first place, we might, as originally suggested, form a straight road from A to B, and in a similar manner two other straight roads from A to C, and from B to C, and this would be the most perfect way of effecting the object in view, the distance between any two of the towns being reduced to the least possible. It would, however, be attended with considerable expense, and it would be requisite to construct a much greater length of road than according to the second plan, which would be to form, as before, a straight road from A to B, and from C to construct a road which should join the former at a point D, so as to be perpendicular to it. The traffic between A or B and C would proceed to the point D and then turn off to C. With this arrangement, while the length of the roads would be very materially decreased, only a slight increase would be occasioned in the distance between C and the other two towns. The third method would be to form only the roads AC and CB, in which case the distance between A and B would be somewhat increased, while that between AC or B and C would be diminished, and the total length of road to be constructed would also be lessened.

As a general rule it may be taken that the last of these methods is the best and most convenient for the public; that is to say, that if the physical character of the country does not determine the course of the road, it will generally be found best not to adopt a

perfectly straight line, but to vary the line so as to pass through all the principal towns near its general course.

579. Mountain Roads.—The location of roads in mountainous countries presents greater difficulties than in an ordinary undulating country; the same latitude in adopting undulating grades and choice of position is not permissible, for the maximum gradient must be kept before the eye perpetually. A mountain road has to be constructed on the maximum grade or at grades closely approximating it, and but one fixed point can be obtained before commencing the survey, and that is the lowest pass in the mountain range; from this point the survey must be commenced. The reason for this is that the lower slopes of the mountains are flatter than those at their summit; they cover a larger area and merge into the valley in diverse undulations. So that a road at a foot of a mountain may be carried at will in the desired direction by more than one route, while at the top of a mountain range any deviation from the lowest pass involves increased length of line. The engineer having less command of the ground, owing to the reduced area he has to deal with and the greater abruptness of the slopes, is liable to be frustrated in his attempt to get his line carried in the direction he wishes it to follow.

580. It is a common practice to run a mountain survey up-hill, but such practice should be avoided. Wherever an acute-angled zigzag is met with on a mountain road near the summit, the inference to be drawn is that the line being carried up-hill on reaching the summit was too low and the zigzag was necessary to reach the desired pass. The only remedy in such a case is by a resurvey beginning at the summit and running down-hill. This method requires a reversal of the usual one. The grade line is first staked out and its horizontal location surveyed afterwards. The most appropriate instrument for this work is a transit with a vertical circle on which the telescope may be set to the angle of the maximum grade.

581. Loss of Height.—Loss of height is to be carefully avoided in a mountain road. By loss of height is meant an intermediate rise in a descending grade. If a descending grade is interrupted by the introduction of an unnecessary ascent, the length of the road will be increased over that due to the continuous grade by the length of the portion of the road intervening between the summit

of the rise and the point in the road in a level with that rise—a length which is double that due on the gradient to the height of the rise. For example, if a road descending a mountain rises at some intermediate point to cross over a ridge or spur, and the height ascended amounts to 110 feet before the descent is continued, such a road would be just one mile longer than if the descent had been uninterrupted; for 110 feet is the rise due to a half-mile length at 1:24.

582. Water on Mountain Roads.—Water is needed by the workmen and during the construction of the road; it is also very necessary for the traffic, especially during hot weather; and if the road exceeds 5 miles in length provision should be made to have it either close to or within easy reach of the road. With a little ingenuity the water from springs above the road, if such exist, can be led down to drinking-fountains for men, and to troughs for animals.

In a tropical country it would be a matter for serious consideration if the best line for a mountain road 10 miles in length or upwards, but without water, should not be abandoned in favor of a worse line with a water-supply available.

583. Halting-places.—On long lines of mountain roads halting-places should be provided at convenient intervals.

584. Alignment.—No hard and fast rule can be laid down for the alignment of a road; it will depend both upon the character of the traffic on it and upon the "lay of the land." To promote economy of transportation it should be straight; but if straightness is obtained at the expense of easy grades that might have been obtained by deflections and increase of length, it will prove very expensive to the community that uses it.

585. Where curves are necessary, employ the greatest radius possible and never less than fifty feet. They may be circular or parabolic. The parabolic will be found exceedingly useful for joining tangents of unequal length, and for following contour lines; its curvature being least at its beginning and ending, makes the deviations from a straight line less strongly marked than by a circular arc (see Figs. 46 to 49).

586. When a curve occurs on an ascent, the grade at that place must be diminished in order to compensate for the additional resistance of the curve.

TYPES OF CURVES.




Fig. 46

SIMPLE CURVE




Fig. 47.


COMPOUND
CURVE

Fig. 48.


REVERSE
CURVE

FIG. 49.

DOUBLE-REVERSE CURVE

587. The width of the wheelway on curves must be increased. This increase should be one quarter of the width for central angles between 90 and 120 degrees, and one half for angles between 60 and 90 degrees.

588. Excessive crookedness of alignment is to be avoided, for any unnecessary length causes a constant threefold waste: first, of the interest of the capital expended in making that unnecessary portion; secondly, of the ever-recurring expense of repairing it; and thirdly, of the time and labor employed in travelling over it.

589. The curving road around a hill may be often no longer than the straight one over it, for the latter is straight only with reference to the horizontal plane, while it is curved as to the vertical plane; the former is curved as to the horizontal plane, but straight as to the vertical plane. Both lines curve, and we call the one passing over the hill straight only because its vertical curvature is less apparent to our eyes.

590. The difference in length between a straight road and one which is slightly curved is very small. If a road between two places ten miles apart were made to curve so that the eye could nowhere see farther than one quarter of a mile of it at once, its length would exceed that of a straight road between the same points by only about four hundred and fifty feet.

591. Zigzags.—The method of surmounting a height by a series of zigzags, or by a series of reaches with practicable curves at the turns, is objectionable.

(1) An acute-angled zigzag obliges the traffic to reverse its direction without affording it convenient room for the purpose. The consequence is that with slow traffic a single train of vehicles is brought to a stand, while if two trains of vehicles travelling in opposite directions meet at a zigzag a block ensues.

(2) With zigzags little progress is made towards the ultimate destination of the road; height is surmounted, but horizontal distance is increased for which there is no necessity or compensation.

(3) Zigzags are dangerous. In case of a runaway down-hill the zigzag must prove fatal.

(4) If the drainage cannot be carried clear of the road at the end of each reach, it must be carried under the road in one reach only to appear again at the next, when a second bridge, culvert, or drain will be required, and so on at the other reaches. If the


drainage can be carried clear at the termination of each reach, the lengths between the curves will be very short, entailing numerous zigzag curves, which are expensive to construct and maintain.

592. Final Location.—The route being finally determined upon, it requires to be located. This consists in tracing the line, placing a stake at every 100 feet on the straight portions and at every 50 or 25 feet on curves. At the tangent points of curves, and at points of compound and reverse curves, a larger and more permanent stake should be placed. Lest those stakes should be disturbed in the process of construction, their exact distance from several points outside of the ground to be occupied by the road should be carefully measured and recorded in the note-book, that they may be replaced. The stakes above referred to show the position of the centre line of the road, and form the base line from which all operations of construction are carried on. Levels are taken at each stake, and cross-levels are taken at every change of longitudinal slope.

593. Construction Profile.—The construction or working profile is made from the levels obtained on location. It should be drawn to a horizontal scale of 400 feet to the inch and a vertical scale of 20 feet to the inch. Fig. 50 represents a portion of such a profile. The figures in column A represent the elevation of the ground at every 100 feet, or where a stake has been driven, above datum. The figures in column B are the elevations of the grade above datum. The figures in column C indicate the depth of cutting or height of fill; they are obtained by taking the difference between the level of the surface of the ground and the level of the road. The two straight parallel lines represent the grade of the road; the upper line is intended to show the upper surface of the road when finished, while the lower line represents what is termed the sub-grade or formation level. All the dimensions refer to the formation level, to which the surface of the ground is to be formed to receive the road-covering.

At all changes in the rate of inclination of the grade line a heavier vertical line should be drawn.

594. Gradient.—The grade of a line is its longitudinal slope, and is designated by the proportion between its length and the difference of height of its two extremes. The ratio of these two quantities gives it its name: if the road ascends or falls one foot in every twenty feet of its length, it is said to have a grade of 1 : 20



or a 5 per cent grade. Grades are of two kinds, maximum and minimum. The maximum is the steepest which is to be permitted and which on no account is to be exceeded. The minimum is the least allowable for good drainage. (For method of designating grades see Table LXIII.)

595. Determination of Gradients.—The maximum grade is fixed by two considerations, one relating to the power expended in ascending, the other to the acceleration in descending the incline.

There is a certain inclination, depending upon the degree of perfection given to the surface of the road, which cannot be exceeded without a direct loss of tractive power. This inclination is that in descending which, at a uniform speed, the traces slacken, or which causes the vehicles to press on the horses; the limiting inclination within which this effect does not take place is the angle of repose.

596. The angle of repose for any given road-surface can be easily ascertained from the tractive force required upon a level with the same character of surface. Thus if the force necessary on a level to overcome the resistance of the load is $\frac{1}{40}$ of its weight, then the same fraction expresses the angle of repose for that surface.

597. On all inclines less steep than the angle of repose a certain amount of tractive force is necessary in the descent as well as in the ascent, and the mean of the two drawing forces, ascending and descending, is equal to the force along a level road. Thus on such inclines as much mechanical force is gained in the descent as is lost in the ascent. From this it might be inferred that when a vehicle passes alternately each way along the road, no real loss is occasioned by the inclination of the road; such is not, however, practically the fact with animal power, for whilst it is necessary in the ascending journey to have either a less or a greater number of horses than would be requisite if the road were entirely level, no corresponding reduction can be made in the descending journey. On inclines which are more steep than the angle of repose, the load presses on the horses during their descent, so as to impede their action, and their power is expended in checking the descent of the load; or if this effect be prevented by the use of any form of drag or brake, then the power expended on such drag or brake corresponds to an equal quantity of mechanical power expended in the ascent, for which no equivalent is obtained in the descent.

598. Men and all animals can ascend steeper slopes than they can descend. A man walks slowly up-hill and quickly down-hill. A horse does the reverse: the steeper the ascent the faster, until fatigued, he attempts to travel, while in descending he moves at a slow trot which gradually subsides into a walk. Consequently the inclination which admits of high speed in descending practically controls the maximum grade.

599. The maximum grade for a given road will depend (1) upon the class of traffic that will use it, whether fast and light, slow and heavy, or mixed, consisting of both light and heavy; (2) upon the character of the pavement adopted; and (3) upon the question of cost of construction. Economy of motive power and low cost of construction are antagonistic to each other, and the engineer will have to weigh the two in the balance.

600. It is evident, therefore, that no fixed maximum gradient can be adopted in all situations.

For fast and light traffic the grades should not exceed 2 per cent; for mixed traffic 3 per cent may be adopted; while for slow traffic combined with economy 5 per cent should not be exceeded. This grade is practicable but not convenient.

601. The maximum grade for various paving materials is as follows:

Stone blocks.....	all grades
Wood.....	5 per cent
Asphalt.....	2½ "
Brick.....	5 "
Broken stone.....	8 "

602. The maximum grade adopted by the French engineers for macadamized roads is 5 per cent or 1 : 20. The maximum adopted by Telford was 1 : 30.

603. It is obvious from Table LVIII that the smoother the road-surface the easier must be the grade. From this fact it has been deduced that on rough-surfaced roads steeper grades are permissible than on smooth roads. This deduction is misleading. The force of gravity which has to be overcome is the same whether the road-surface be rough or smooth. The rough surface affords better foothold for the horse than the smooth surface, and thus assists him to exert his utmost force, but the great friction produced between the wheels and the rough surface requires the expenditure

of greater tractive force than would be required on a smooth surface. In practice there is no pavement which combines the opposite requirements of an even smooth surface for the wheels and a sufficiently rough surface affording good foothold for the horses, and a compromise of advantages must therefore be made in most cases. Where the extent and importance of the traffic will warrant the expense, stone trackways afford an excellent method for overcoming the disadvantage of smooth pavements on inclines.

604. To Determine the Maximum Grade.—Let L denote the gross load to be hauled up an incline; f , the proportion of the resistance to the load on a level; S , the sine of the angle of the incline. Then $(f + S) \cdot L$ is the greatest resistance to be overcome in ascending the incline; and this should not exceed the greatest tractive force which the horse is capable of exerting. Let P be that force; then $(f + S) \cdot L$ should not be greater than P , or S should not be greater than $\frac{P}{L} - f$. This condition is essential and fixes the maximum grade.

To avoid excessive acceleration of speed in descending S should not exceed f .

The proportion of the resistance f differs, as shown in Table LXI very much for different sorts of road coverings. It consists of two parts, one arising from friction and another arising from vibration, and increases with the velocity of transit.

TABLE LXI.

VALUE OF f .

Stone pavement.....	0.015 = $\frac{1}{66}$
Broken stone....	0.020 = $\frac{1}{50}$
Gravel road.....	0.067 = $\frac{1}{15}$
Soft sand and loose gravel.....	0.148 = $\frac{1}{7}$

For the allowable maximum grade Bockelberg proposes the following expression:

$$2\mu Q = \mu Q + (G + Q) \tan \alpha$$

in which μ = the coefficient of resistance to traction;

Q = the load, including the weight of the wagon;

G = the mean weight of the horse = $165 \times 5 = 825$ pounds.

α = angle of inclination.

The mean tractive power (k) of the horse is taken at one-fifth of its weight = 168 pounds, which enables the animal to move on a level plane a load Q equal to its tractive pull divided by the coefficient of resistance; that is,

$$Q = \frac{K}{\mu}; \text{ or, in the average horse, } \frac{165}{\mu} \text{ pounds.}$$

On macadamized roads having a coefficient of $\frac{1}{10}$ a horse will pull without exertion $Q = 165 \div \frac{1}{10} = 4950$ pounds.

The maximum allowable grade depends upon the additional effort that a horse is able to exert above its mean tractive pull, and it is generally conceded that on grades of moderate length, not over 2300 feet, it may exert twice the amount of the adopted mean. Now since μQ expresses the mean tractive force, we have $2\mu Q$ for the maximum pull, which must equal the weight of the load, wagon, and horse, corrected for the grade, and the character of road-surface, or $2\mu Q = \mu Q \cos \alpha + (Q + G) \sin \alpha$.

This expression may be simplified by dropping $\cos \alpha$ from the first member, because on inclinations up to 1 in 10 it remains nearly unity; and in the second member the term $\sin \alpha$ may be changed into $\tan \alpha$, for the reason that their difference is too small to affect the result, and the tangent has the advantage of expressing in a more direct manner the amount of the grade. This reduces the formula down to $2\mu Q = \mu Q + (Q + G) \tan \alpha$.

In the further consideration of this subject the weight of the horse may be omitted, which is perfectly admissible in grades of moderate length. Then the formula becomes $2\mu Q = \mu Q + \tan \alpha$, which is $\mu = \tan \alpha$.

This means that the tangent of the permissible inclination, which in a reach of moderate length does not require an additional horse to overcome it, is equal to the coefficient of resistance to traction. On a well-paved road, therefore, where $\mu = \frac{1}{10}$, rises greater than 1 in 50 ought not to occur, while on poor earth roads a grade of 1 in 10 is not excessive. The coefficient of resistance to traction for different road-surfaces is given in Table L, page 372.

604a. To Determine the Most Advantageous Grade (J. H. Striedinger and Otto von Geldern).—Although the maximum permissible degree of inclination has been set forth in the foregoing, it has not

been decided yet whether such grades are the most advantageous, or whether it would not be better to adopt a still smaller grade. In order to settle this question definitely, it is proper to consider every element that affects the actual cost of transportation, and to aim at reducing this as much as possible.

The expenditures of moving a load upon a highway depend upon:

1. The angle of inclination α .
2. The coefficient of resistance to road traction μ .
3. The tractional force k which draught-animals are able to exert at a mean velocity c during a mean working time t .
4. The law according to which the tractional power of animals varies with the change in the mean velocity or working time.

In consideration of this factor, Mascheck's formula has been used, which expresses the tractive force in this wise:

$$K_1 = K \left[3 - 2 \frac{v}{c} \right].$$

In order to make this clear, it is well to refer to a short theoretical consideration of this point. The work L of animal locomotors is, like all mechanical work, the product of a power K , (the tractive force) into the velocity v , and into a certain element of time Z during which that power is exerted; therefore $L = K_1 v Z$. These three factors differ in every draught-animal according to individual conditions, but they hold such a relation to each other that an increase in tractional force diminishes velocity and time; an acceleration of the velocity reduces the force and time; while a more extended duration of work will weaken the force and lower the velocity.

The following formula of Mascheck has been generally employed:

$$K_1 = K \left[3 \frac{v}{c} \frac{Z}{t} \right],$$

in which

K = a mean tractive force;

c = a mean velocity;

t = a mean working time.

It may be readily demonstrated that with these mean factors the maximum work performed is

$$L \text{ max} = Kct.$$

K is usually taken at 165 pounds; $c = 3.6$ feet per second; $t = 8$ hours. Then the work done in one hour will equal 2,147,310 foot-pounds.

If the values c , K and t , and with them the maximum day's work, cannot be reached (if, for instance, a greater velocity be required), we must endeavor to obtain a relative maximum, which is tied to the condition $\frac{v}{c} = \frac{Z}{t}$.

Introducing this value reduces Mascheck's formula to the expression

$$K_1 = K \left(3 - 2\frac{v}{c} \right) = K \left(3 - 2\frac{Z}{t} \right).$$

This formula furnishes results in harmony with practical experience as long as the values of K , c , and t do not exceed the mean values beyond reasonable limits. Bockelberg, for instance, assumes $c = 4$ feet; Sganzin places the most advantageous velocity that an animal will assume when it is neither held in nor urged on as follows:

A heavy horse, 2.93 feet.

A lighter animal, 3.66 feet.

5. The weight of the unloaded wagon Q , the mean of which has been taken at 1320 pounds, $= 8K$.

6. The weight of the load Q .

7. The weight of the draught-animal, taken at $5K = 825$ pounds for one horse.

8. The monetary value of the daily work of the animal.

9. The probable cost of both the new roadway construction and the maintenance of the highway. Considering all these factors, a mathematical deduction has led to certain results that express the most advantageous grade, which it is not necessary to carry out in detail here. Launhardt, by a careful analysis in this line, and by assuming the following values: $u = \frac{1}{30}$, $Q = 1320$ pounds, and $G = 825$ pounds, has arrived at the following conclusions:

Dependent upon the amount of traffic, and the cost of construction and maintenance of the highway, the most advantageous grade varies:

For mountainous country.....	between $\frac{1}{10}$ and $\frac{1}{15}$
“ hilly country.....	between $\frac{1}{10}$ “ $\frac{1}{15}$
“ level country.....	between $\frac{1}{15}$ “ $\frac{1}{20}$

and for an ordinary traffic on roads built at an average cost:

In mountainous country.....	1 : 24
In hilly country.....	1 : 30
In level country.....	1 : 44

These deductions give results somewhat smaller than those laid down by the road regulations of European countries. In one item, in that of hilly country, however, there is shown considerable deviation from practice; the others nearly agree with the results of theoretical deduction.

604b. Cost of Grades.—The increased cost of transportation caused by grades may be ascertained approximately by the formula

$$\text{Cost} = \frac{(I - R)}{2R} NV,$$

in which R = percentage of resistance to traction on a level surface;

I = percentage of resistance due to inclination of grade;

N = number of full one-horse loads per day;

V = value of horse, harness, and vehicle, and

The amount which can be economically spent in reducing a grade is found approximately by the formula

$$\frac{(I - A)}{2R} NV,$$

in which A = percentage of resistance due to the inclination of the lower grade.

605. Grade of Mountain Roads.—Although mountain roads are in general projected for slow traffic, yet as civilization and wealth in a country increase, roads adapted to the use of wheeled vehicles gradually become used by an increasing amount of quick traffic. Ascending grades of 1:20, 1:18, 1:16 are too steep to permit of carriages drawn by horses ascending for any distance except at a foot-pace. Hack conveyances with relays at short distances can and do pro-

ceed more rapidly over hill roads with these grades, but such service is accompanied with a great amount of cruelty to the draught animals. Private horses are not called upon to work like hired hackneys, which are supposed to be able to do double the work they were capable of in their younger, and better, days; therefore, continuous grades of 1:16, 1:18, 1:20 means, as respects private quick traffic, its conversion into slow traffic. On the descent of such inclinations horses can only travel with safety at a slow trot, which probably subsides into a walk at the turns and when meeting other traffic. To ride down a slope of 5 per cent for a long distance is disagreeable.

With a gradient of 4 per cent on a mountain road the slow traffic would be so well suited that ten miles continuous ascent could be surmounted without a halt or undue exertion on the part of the draught animals. Such a grade would not reduce quick traffic to a walk throughout an ascent, and it would permit of horses descending with safety at six to eight miles an hour.

606. Minimum Grade.—From the previous considerations it would appear that an absolutely level road was the one to be sought for, but this is not so; there is a minimum or least allowable grade which the road must not fall short of, as well as a maximum one which it must not exceed. If the road was perfectly level in its longitudinal direction, its surface could not be kept free from water without giving it so great a rise in its middle as would expose vehicles to the danger of overturning.

The minimum grade established in France by the Corps des Ponts et Chaussées is .008, or 1 in 125; this may be adopted as the minimum, and in a perfectly level country the road should be artificially formed into gentle undulations approximating this minimum limit.

607. Undulating Grades.—From the fact that the power required to move a load at a given velocity on a level road is decreased on a descending grade to the same extent that it is increased in ascending the same grade, it must not be inferred that the animal force expended in passing alternately each way over a rising and falling road will gain as much in descending the several inclines as it will lose in ascending them. Such is not the case. The animal force must be sufficient, either in power or number, to draw the load over the level portions and up the steepest inclines

of the road, and in practice no reduction in the number of horses can be made to correspond with the decreased power required in descending the inclines.

The popular theory that a gentle undulating road is less fatiguing

TABLE LXII.
DIFFERENT METHODS OF DESIGNATING THE SAME GRADES.

American Method. Feet per 100 feet.	English Method.	Feet per Mile.	Angle with the Horizon.
$\frac{1}{4}$	1: 400	13.2	0° 8' 36"
$\frac{1}{2}$	1: 200	26.4	0 17 11
$\frac{3}{4}$	1: 150	39.6	0 22 55
1	1: 100	52.8	0 34 23
1 $\frac{1}{4}$	1: 80	66	0 42 53
1 $\frac{1}{2}$	1: 66 $\frac{2}{3}$	79.2	0 51 28
1 $\frac{3}{4}$	1: 57 $\frac{1}{2}$	92.4	1 0 51
2	1: 50	105.6	1 8 6
2 $\frac{1}{4}$	1: 44 $\frac{1}{2}$	118.8	1 17 39
2 $\frac{1}{2}$	1: 40	132	1 25 57
2 $\frac{3}{4}$	1: 36 $\frac{1}{2}$	145.2	1 34 23
3	1: 33 $\frac{1}{3}$	158.4	1 43 03
3 $\frac{1}{4}$	1: 30 $\frac{1}{2}$	171.6	1 51 42
3 $\frac{1}{2}$	1: 28 $\frac{1}{2}$	184.8	2 0 16
3 $\frac{3}{4}$	1: 26 $\frac{1}{2}$	198	2 8 51
4	1: 25	211.2	2 17 26
4 $\frac{1}{4}$	1: 23 $\frac{1}{2}$	224.4	2 26 10
4 $\frac{1}{2}$	1: 22 $\frac{1}{2}$	237.6	2 34 36
4 $\frac{3}{4}$	1: 21	250.8	2 43 35
5	1: 20	264	2 51 44
6	1: 18 $\frac{1}{2}$	316.8	3 26 12
7	1: 14 $\frac{2}{3}$	369.6	4 0 15
8	1: 12 $\frac{1}{2}$	422.4	4 34 26
9	1: 11 $\frac{1}{3}$	475.2	5 8 31
10	1: 10	528	5 42 37

ing to horses than one which is perfectly level is erroneous. The assertion that the alternations of ascent, descent, and levels call into play different muscles, allowing some to rest while others are exerted, and thus relieving each in turn, is demonstrably false, and contradicted by the anatomical structure of the horse. Since this doctrine is a mere popular error, it should be utterly rejected, not only because false in itself, but still more because it encourages the building of undulating roads, and this increases the labor and cost of transportation upon them.

608. Level Stretches.—On long ascents it is generally recommended to introduce level or nearly level stretches at frequent intervals in order to rest the animals. These are objectionable when

they cause loss of height, and animals will be more rested by halting and unharnessing for half an hour than by travelling over a level portion. The only case which justifies the introduction of levels into an ascending road is where such levels will advance the road towards its objective point; where this is the case there will be no loss of either length or height, and it will simply be exchanging a level road below for a level road above.


609. Establishing the Grade.—When the profile of a proposed route has been made, a grade line is drawn upon it (usually in red) in such a manner as to follow its general slope, but to average its irregular elevation and depressions.

If the ratio between the whole distance and the height of the line is less than the maximum grade intended to be used, this line will be satisfactory; but if it be found steeper, the cuttings or the length of the line will have to be increased: the later is generally preferable.

610. The apex or meeting point of all curves should be rounded off by a vertical curve shown in Figs. 51 to 53.

The formula for these curves is given in Art. 935.

EXAMPLES OF THE APPLICATION OF VERTICAL CURVES.



FIGS. 51 TO 53.

CHAPTER XII.

WIDTH AND TRANSVERSE CONTOUR.

611. A road should be wide enough to accommodate the traffic for which it is intended, and should comprise a wheelway for vehicles and a space on each side for pedestrians.

612. The wheelway of country highways need be no wider than is absolutely necessary to accommodate the traffic using it; in many places a track wide enough for a single team is all that is necessary. But the breadth of the land appropriated for highway purposes should be sufficient to provide for all future increase of traffic. The wheelways of roads in rural sections should be double; that is, one portion paved (preferably the centre) and the other left with the natural soil. The latter if kept in repair will for at least one half the year be preferred by teamsters.

613. The minimum width of the paved portion, if intended to carry two lines of travel, is fixed by the width required to allow two vehicles to pass each other safely. This width is 16 feet. If intended for a single line of travel, 8 feet is sufficient but suitable turnouts must be provided at frequent intervals. The most economical width for any roadway is some multiple of eight.

614. Wide roads are the best; they expose a larger surface to the drying action of the sun and wind, and require less supervision than narrow ones. Their first cost is greater than narrow ones, and that nearly in the ratio of the increased width.

615. The cost of maintaining a mile of road depends more upon the extent of the traffic than upon the extent of its surface, and unless extremes be taken the same quantity of material will be necessary for the repair of the road whether wide or narrow which is subjected to the same amount of traffic. The cost of spreading the materials over the wide road will be somewhat greater, but the cost of the materials will be the same. On narrow roads the traffic, being confined to one track, will wear more severely than it spread over a wider surface.

616. The width of land appropriated for road purposes varies in the United States from 49½ to 66 feet; in England and France

from 26 to 66 feet. And the width or space macadamized is also subject to variation; in the United States the average width is 16 feet; in France it varies between 16 and 22 feet; in Belgium $8\frac{1}{2}$ feet seems to be the regular width, while in Austria it varies from $14\frac{1}{2}$ to $26\frac{1}{2}$ feet.

Figs. 85-92, pages 461-463, show the subdivision of the roadway into wheelway, sidewalks, and ditches.

617. Width of Mountain Roads.—Mountain roads should be proportioned in width to the amount of traffic; they should be neither too wide nor too narrow. If of excessive width, the cost of construction is increased; if too narrow, traffic will be interrupted by blockades. An economical width is 24 feet, and the stone covering should extend from gutter to gutter. If the center only is covered, the road will soon be destroyed, as, by reason of the curves on a mountain side predominating over straight reaches, the traffic will hug either one side of the road or the other.

Table LXIII shows the number of acres required per mile for different widths of roadway.

TABLE LXIII.

ACRES REQUIRED PER MILE FOR DIFFERENT WIDTHS OF ROADWAY.

[illegible]

618. Transverse Contour.—The centre of all roadways should be higher than the sides. The object of this is to facilitate the flow of the rain-water to the gutters. Where a good surface is maintained a very moderate amount of rise is sufficient for this purpose. Earth roads require the most and asphalt the least. The rise should bear a certain proportion to the width of the carriageway. The most suitable proportions for the different paving materials is shown in the following table:

TABLE LXIV.

AMOUNT OF TRANSVERSE RISE REQUIRED FOR DIFFERENT PAVEMENTS.



Kind of Surface.		Proportion of the Carriageway Width.
Earth	Rise at centre	$\frac{1}{80}$
Gravel	"	$\frac{1}{80}$
Broken stone.....	"	$\frac{1}{80}$
Stone blocks.....	"	$\frac{1}{80}$
Wood.....	"	$\frac{1}{100}$
Brick.....	"	$\frac{1}{80}$
Asphalt.....	"	$\frac{1}{80}$

619. Form of Transverse Contour.—All authorities agree that the form should be convex, but they differ in the amount and form of the convexity. Circular arcs, two straight lines joined by a circular arc and ellipses all have their advocates, but the best form for streets will be found to be a parabolic curve starting from the edge of the gutter next the carriageway or one foot from the curb line. Fig. 54 shows this form, which is obtained in the following manner: Divide the ordinate or the width between the edge of the gutter and the centre of the street into 10 equal parts, and raise perpendiculars the length of which will be determined by multiplying the rise at the center by the respective number of each perpendicular in the diagram. The amounts thus obtained can be added to the rod readings, and the stakes set at the proper distance across the street with their tops at this level will give the true curve.

620. For country roads a curve of suitable convexity may be obtained as follows: Give $\frac{1}{3}$ of the total rise at $\frac{1}{4}$ the width from the centre to the side, and $\frac{2}{3}$ of the total rise at $\frac{1}{2}$ the width (Fig. 55).

621. Excessive height and convexity of cross-section contract the width of the wheelway, by concentrating the traffic at the

TRANSVERSE CONTOUR OF STREETS AND ROADS.



centre, that being the only part where a vehicle can run upright. The force required to haul vehicles over such cross-sections is increased, because an undue proportion of the load is thrown upon two wheels instead of being distributed equally over the four. The continual tread of horses' feet in one track soon forms a depression which holds water, and the continuous travel of vehicles in one track soon wears ruts which retain water, and the surface is not so dry as with a flatted section, which allows the traffic to distribute itself over the whole width.

622. Sides formed of straight lines are also objectionable. They wear hollow, retain water, and defeat the object sought by raising the centre.

623. **Concave Form.**—In Triest, Austria, the early pavements were laid concave, i.e., inclining to the middle, along which, under the surface-canals or sewers extended with gratings at intervals for the admission of surface-drainage. The same method, but with open channels through the centre, is practised in several South American towns. Experience has proved that this plan is not desirable or convenient for traffic.

624. The required convexity should be obtained by rounding the formation surface, and not by diminishing the thickness of the covering at the sides.

625. On hillside and mountain roads it is generally recommended that the surface should consist of a single slope inclining inwards. There is no reason for or advantage gained by this method. The form best adapted to these roads is the same as for a road under ordinary conditions, viz., that described in Art. 619.

626. With a roadway raised in the centre and the rain-water draining off to gutters on each side, the drainage will be more effectual and speedy than if the drainage of the outer half of the road has to pass over the inner half. The inner half of such road is usually subjected to more traffic than the outer half. If formed of a straight incline, this side will be worn hollow and retain water. The inclined flat section never can be properly repaired to withstand the traffic. Consequently it never can be kept in good order, no matter how constantly it may be mended. It is always below par. When heavy rain falls it is seriously damaged.

CHAPTER XIII.

EARTH-WORK.

627. Earth-work.—The term “earth-work” is applied to all the operations performed in the making of the excavations and embankments to prepare them for receiving the road-covering. In its widest sense it comprehends work in rock as well as in the looser material of the earth’s crust.

628. Equalising Earth-work is a term applied to the process of so adjusting the formation or sub-grade level of an intended work that the earth from the cuttings shall be as nearly as possible sufficient to make the embankments and no more. The art of making this adjustment by the eye upon a profile of the ground with sufficient accuracy is soon acquired by practice. In most cases it is essential to economy in the cost of the work. For any surplus of embankment over cutting must be made up by borrowing, and the earth from any surplus of cutting over embankment must be wasted, both of these operations involve additional cost for labor and land. But cases sometimes occur in which it is more economical to make an embankment from borrow-pits close at hand than to bring the necessary material from a far-distant cutting on the line of the works, or in which it is more economical to waste part of the material from a cutting than to send it to a far-distant embankment on the line of the works, and these points must be decided by the engineer to the best of his judgment in each particular case.

629. Transverse Balancing.—When the road lies along the side of a hill, so that it is partly in excavation and partly in embankment, it is necessary to so place its centre line that these two parts of cross-section may balance. When the ground has a uniform slope the desired end would be obtained (if the side slopes were the same for excavation and embankment and if no shrinkage existed),

by locating the centre line of the road upon the surface of the ground. In other cases, as when the side of the excavation slopes 1 to 1 and that of the embankment 2 to 1, a formula to determine the position of the centre line may be readily established.

630. If earth be wanted for a neighboring embankment, the amount of excavation may be easily increased by moving the centre of the road farther into the hill, with the additional advantage of lessening its liability to slip. The line may be thus changed on the map according to the notes of the cross-section in the level book, and be subsequently moved by a corresponding quantity on the ground.

631. When the slope of the ground is very steep the transverse balance must be disregarded and the road made chiefly in excavation, to avoid the insecurity of a high embankment.

632. Borrow-pits.—When the excavations on the line of the road do not furnish sufficient material for the embankments, the deficiency is obtained either by widening the excavations, or from an excavation termed a “borrow-pit,” made in the vicinity of the embankment.

633. Spoil-banks.—If the excavations furnish more material than is required for the embankments, the excess is generally deposited in a convenient place on the land adjoining the excavation, in banks termed “spoil-banks.”

Both these cases are expensive and objectionable. It is therefore very desirable to make the excavation and embankment “balance” each other. If the calculations show much disparity in the two amounts, the location of the line should be changed in some way so as to effect the desired equality.

634. The equalization must, however, be restrained within certain limits, for it should evidently be abandoned when, in order to form sufficient excavation to make the embankment, it would be necessary to go to such a distance that the cost of transport would exceed the cost of borrowing for the banks and wasting the distant excavation in spoil-banks.

635. The comparison of the price of transport with that of excavation and land will therefore determine the distance within which the balancing must be established.

636. The form to be given to the borrow-pits and spoil-banks will depend in a great degree upon the locality; they should as far as

practicable be located so that the cost of removal of the earth shall be the least possible.

637. Staking out Borrow-pits.—Borrow-pits should be staked out by the engineer and their contents calculated, unless the contractor is to be paid by embankment measurements. A number of cross-profiles are taken of the original surface, and (on the same lines) on the bottom of the pit, after it is excavated, which furnish the depth of cutting at each required point. Borrow-pits should be regularly excavated so that they may not present an unsightly appearance when abandoned.

638. Shrinkage.—The equality recommended must be taken with an important qualification, dependent upon the fact that earth transferred from excavation to embankment shrinks, or settles so as to occupy less space in the bank than it did in its natural state.

Rock, on the contrary, occupies more space when broken.

639. In estimating the relative amounts of excavation and embankment required, allowance must be made for difference in the spaces occupied by the material before excavation and after it is settled in embankment. The shrinkage of the different materials is about as follows :

Gravel	8 per cent
Gravel and sand.....	9 " "
Clay and clay earths.....	10 " "
Loam and light sandy earths.....	12 " "
Loose vegetable soil.....	15 " "
Puddled clay.....	25 " "

Rock, on the other hand, increases in value by being broken up, and does not settle again into less than its original bulk. The increase may be taken at fifty per cent.

Thus an excavation of loam measuring 1000 cubic yards will form only about 880 cubic yards of embankment, or an embankment of 1000 cubic yards will require about 1120 cubic yards measured in excavation to make it. A rock excavation measuring 1000 yards will make from 1500 to 1700 cubic yards of embankment, depending upon the size of the fragments.

640. The lineal settlement of earth embankments will be about in the ratio given above; therefore either the contractor should be instructed in setting his poles to guide him as to the

height of grade on an earth embankment to add the required percentage to the fill marked on the stakes, or the percentage may be included in the fill marked on the stakes. In rock embankments this is not necessary.

641. Failure of Earth-work.—The failure of earth-work is due to the slipping or sliding of its parts on each other, and its stability arises from resistance to the tendency so to slip.

In solid rock, that resistance arises from the elastic stress of the material, when subjected to a shearing force; but in the mass of earth, as commonly understood, it arises partly from the friction between the grains, and partly from their mutual adhesion; which latter force is considerable in some kinds of earth, such as clay, especially when moist.

But the adhesion of earth is gradually destroyed by the action of air and moisture, and of the changes of the weather, and especially by alternate frost and thaw; so that its friction is the only force which can be relied upon to produce permanent stability.

642. The temporary additional stability, however, which is produced by adhesion, is useful in the execution of earth-work, by enabling the sides of a cutting to stand for a time with a vertical face for a certain depth below its upper edge. That depth is greater, the greater the adhesion of the earth as compared with its heaviness; it is increased by a moderate degree of moisture, but diminished by excessive wetness.

The following are some of its values :

Earth.	Greatest depth of tem. vert. face.
Clean dry sand and gravel from.....	0 to 1 foot.
Moist sand and ordinary surface mould from.....	8 " 6 feet
Clay (ordinary) from.....	10 " 16 "
Compact gravel from.....	10 " 15 "

643. One of the effects of the temporary stability due to adhesion is seen in the figure of the surface left after a "slip" has taken place in earth-work. That surface is not a uniform slope, inclined at the angle of repose, but is concave in its vertical section, being vertical at its upper edge, and becoming less and less steep downwards. It is not capable, however, of preserving that figure; for the action of the weather, by gradually destroying the adhesion of the earth, causes the steep upper part of the concave face to crumble

down, so that the whole tends to assume a uniform curved slope in the end.

644. The Permanent Stability of earth, which is due to friction alone, is sufficient to maintain the side either of an embankment or of a cutting at a uniform slope, whose inclination to the horizon is the angle of repose, or angle whose tangent is the coefficient of friction. This is called the natural slope of the earth. The customary mode of describing the slope of earth-work is to state the ratio of the horizontal breadth to its vertical height, which is the reciprocal of the tangent of the inclination.

645. The angles of repose for different earths are given in Table LXV. But for all practical purposes it may be said that all earths, sand, and gravel, stand at a slope of 33 degrees 41 minutes, or $1\frac{1}{4}$ to 1. If the slopes of an excavation in sand are to be left unprotected by sodding, they should be given a slope of $2\frac{1}{4}$ to 1. The ratio of slopes, their angles and length, are given in Table LXVI.

TABLE LXV.

NATURAL SLOPES OF EARTHS (WITH HORIZONTAL LINE).

Gravel (average).....	40 degrees
Dry sand	38 "
Wet "	32 "
Vegetable earth.....	28 "
Compact earth.....	50 "
Shingle.....	39 "
Rubble.....	45 "
Clay (well drained)	45 "
" (wet).....	16 "

TABLE LXVI.

LENGTHS AND ANGLES OF SLOPES.

Slope.	Angle with Horizon	Length. (Height taken as 1.00.)	Slope.	Angle with Horizon	Length. (Height taken as 1.00.)
$\frac{1}{2} : 1$	75° 58'	1.0307	$1\frac{1}{4} : 1$	33° 41'	1.802
$\frac{1}{3} : 1$	63 26	1.118	$1\frac{1}{2} : 1$	29 44	2.016
$\frac{1}{4} : 1$	53 8	1.25	2 : 1	26 34	2.236
1 : 1	45 0	1.4142	3 : 1	18 26	3.162
$1\frac{1}{4} : 1$	38 40	1.6	4 : 1	14 2	4.124

646. The inclinations generally given in practice to the various materials are as follows:

Loose earth, loam and gravel	1½ to 1
Sand.....	3 " 1
Soft greasy clay.....	3 " 1
Rock (sound)	0½ " 1

647. Effect of Moisture.—The presence of moisture in earth to an extent just sufficient to expel the air from its crevices seems to increase its coefficient of friction slightly; but any additional moisture acts like a lubricant in diminishing friction, and tends to reduce the earth to a semi-fluid condition, or to the state of mud. In this state, although it has some cohesion, or viscosity, which resists rapid alteration of form, it has no frictional stability; and its coefficient of friction and angle of repose, are each of them null.

Hence it is obvious that the frictional stability of earth depends to a great extent on the ease with which the water that it occasionally absorbs can be drained away. The safest materials for earth-work are fragments of rock, shingles, gravel, and clean sand; for these materials allow water to pass through without retaining more of it than is beneficial. The cleanest sand, however, may be made completely unstable and reduced to the state of "quick sand" if it is contained in a basin of water-holding materials so that water mixed amongst its particles cannot be drained off.

The property of retaining water and forming a paste with it belongs specially to clay, and to earths of which clay is an ingredient. Such earths, how hard and firm soever they may be when first excavated, are gradually softened, and have both their frictional stability and their adhesion diminished by exposure to the air. In this respect mixtures of sand and clay are the worst; for the sand favors the access of water, and the clay prevents its escape.

The properties of earth with respect to adhesion and friction are so variable that the engineer should never trust to tables or to information obtained from books to guide him in designing earth-works, when he has it in his power to obtain the necessary data either by observation of existing earth-works in the same stratum or by experiment.

648. Inclination of Side Slopes.—The proper inclination for the side slopes of cuttings and embankments depends on the nature of the soil and the action of the atmosphere and of internal moisture upon it.

“In common soils, as ordinary garden earth formed of a mixture of clay and sand, compact clay, and compact stony soils, although the side slopes would withstand very well the effects of the weather with a steeper inclination, it is best to give them two base to one perpendicular, as the surface of the roadway will, by this arrangement, be well exposed to the action of the sun and air, which will cause rapid evaporation of the moisture of the surface. Pure sand and gravel may require a greater slope according to circumstances. In all cases where the depth of the excavation is great the base of the slope should be increased.

“In excavations through solid rock, which does not disintegrate on exposure to the atmosphere, the side might be perpendicular; but as this would exclude in a great degree the action of the sun and air, which is essential to keeping the road-surface dry and in good order, it is necessary to make the side slopes with an inclination varying from one base to one perpendicular, to one base to two perpendicular, or even greater, according to the locality; the inclination of the slopes on the south side in northern latitudes being the greater, to expose better the road-surface to the sun-rays.

“The slaty rocks generally decompose rapidly on the surface when exposed to moisture and the action of frost. The side slopes in rocks of this character may be cut into steps and then be covered by a layer of vegetable mould sown in grass-seed, or else the earth may be sodded in the usual way.”

649. Form of Side Slopes.—The natural, strongest, and ultimate form of earth slopes is a concave curve, in which the flattest portion is at the bottom. This form is very rarely given to the slopes in constructing them; in fact, the reverse is often the case, the slopes being made convex, thus saving excavation for the contractor and inviting slips.

In cuttings exceeding 10 feet in depth the forming of concave slopes will materially aid in preventing slips, and in any case they will reduce the amount of material which will eventually have to be removed when cleaning up. Straight or convex slopes will continue to slip until the natural form is attained.

A revetment or retaining wall at the base of a slope will save excavation.

In excavations of considerable depth, and particularly in soils liable to slips, the slope may be formed in terraces, the horizontal offsets or benches being made a few feet in width with a ditch on the inner side to receive the surface-water from the portion of the side slope above them. These benches catch and retain earth that may fall from the slopes above them. (See Fig. 56.)




FIG. 56. HILLSIDE ROADS.

650. Covering of Slopes.—It is not usual to employ any artificial means to protect the surface of the side slopes from the action of the weather; but it is a precaution which in the end will save much labor and expense in keeping the roadways in good order. The simplest means which can be used for this purpose consists in covering the slopes with good sods, or else with a layer of vegetable mould about four inches thick, carefully laid and sown with grass-seed. These means are amply sufficient to protect the side slopes from injury when they are not exposed to any other causes of deterioration than the wash of the rain and the action of frost on the ordinary moisture retained by the soil.

A covering of brushwood or a thatch of straw may also be used with good effect; but from their perishable nature they will require frequent renewal and repairs.

“Where stone is abundant a small wall of dry stone may be constructed at the foot of the slopes to prevent any wash from them being carried into the ditches.”

651. Slips.—“The stratified soils and rocks in which the strata have a dip or inclination to the horizon are liable to slips, or to give way by one stratum becoming detached and sliding on another,

which is caused either from the action of frost or from the pressure of water which insinuates itself between the strata. The worst soils of this character are those formed of alternate strata of clay and sand, particularly if the clay is of a nature to become semi-fluid when mixed with water. The best preventives that can be resorted to in these cases are to adopt a system of thorough drainage, to prevent the surface-water of the ground from running down the side slopes, and to cut off all springs which run towards the roadway from the side slopes. The surface-water may be cut off by means of a single ditch, termed a catch-water ditch, excavated a few feet back from the crest of the slope, so that it intercepts the water before it reaches the slope of the excavation, and convey it off to the most convenient natural water-courses. Usually this ditch will be required only on the up-hill side of the road; for in almost every case it will be found that the side slope on the down-hill side is, comparatively speaking, but slightly affected by the surface-water.

“Where slips occur from the action of springs, it frequently becomes a very difficult task to secure the side slopes. If the sources can be easily reached by excavating into the side slopes, drains formed of layers of fascines or brushwood may be placed to give an outlet to the water and prevent its action upon the side slopes. The fascines may be covered on top with good sods laid with the grass side beneath, and the excavation made to place the drain filled in with good earth well rammed. Drains formed of broken stone or cobbles covered in like manner on top with a layer of sod to prevent the drain from becoming choked with earth may be used under the same circumstances as fascine drains. Where the sources are not isolated and the whole mass of the soil forming the side slopes appears saturated, the drainage may be effected by excavating trenches a few feet wide at short intervals to the depth of some feet into the side slopes, and filling them with boulders or broken stone, or else a general drain of stone may be made throughout the whole extent of the side slope by excavating into it. When this is deemed necessary it will be well to arrange the drain like an inclined retaining-wall with buttresses at intervals projecting into the earth farther than the general mass of the drain. The front face of the drain should, in this case, also be covered with a layer of sods with the grass side next to the stones

forming the drain, and upon this a layer of good earth should be compactly laid to form the face of the side slopes. The drain need only be carried high enough above the toe of the side slope to tap all the sources, and it should be sunk sufficiently below the roadway to give it a secure footing."

"The drainage has been effected, in some cases, by sinking wells or shafts at some distance behind the side slopes, from the top surface to the level of the bottom of the excavation and leading the water which collects in them by pipes into the drains at the foot of the side slopes. In others a narrow trench has been excavated, parallel to the axis of the road, from the top surface to a sufficient depth to tap all the sources which flow towards the side slope, and a drain formed either by filling the trench wholly with stone or else by arranging an open conduit at the bottom to receive the water collected, over which a layer of brushwood is laid, the remainder of the trench being filled with stone."

652. Embankments.—The best materials for embankments are those whose frictional stability is the greatest and the most permanent, such as fragments of rock, shingle, gravel, and clean sand. Clay forms safe embankments, provided it is dry, or nearly dry, when laid down. Wet clay, vegetable mould, and mud are unfit for use in embankments; so also is peat, except when dry.

653. An embankment may be made in three ways: (1) In one layer. (2) In two or more thick layers. (3) In thin layers.

(1) *In One Layer.*—This being the cheapest and quickest




FIG. 57.

method consistent with stability, is that followed in all earth-works in which there is no special reason requiring it to be performed by the other methods. In Fig. 57 *BAC* represents the natural surface of

the ground; DA , part of the base of a cutting; AEC , an embankment the construction of which is carried forward in the direction AE of its full width and height (including a sufficient allowance for settlement), by running dump-carts on temporary tracks from the cutting along the top of the embankment, and tipping them at E , so that the earth runs down and spreads itself over the sloping end EC of the bank, which is called the "tip." Embankments formed in this manner are deficient in compactness, for the particles of earth which are emptied from the top of the bank will temporarily stop in their descent at the point of the slope at which the friction becomes sufficient to balance their gravity; and when more earth comes upon them, they will give way and slide lower down, causing the portions above them to slip and crack, and thus delay for a long time the complete consolidation.

Tipping or dumping the earth over the sides of banks made in the above manner should not be allowed, for the earth so dumped is liable afterwards to slip off.

The solidity of embankments formed in the above manner may be increased by filling from the sides towards the centre in order that the earth may arrange itself in layers with a dip from the sides inwards.




FIG. 58. CROSS-SECTION OF EARTH EMBANKMENT, SHOWING METHOD OF PLACING THE LAYERS.

As the rapidity with which a bank can be made by this method is dependent upon the number of tipping or dumping points, it is usual to form the bank wider at top and narrower at the bottom than it is finally to be, maintaining of course the requisite area of cross-section; the excess at the top (the angles AB , Fig. 59) being subsequently moved down to the bottom, thus securing the required width of base and inclination of side slopes.

It is mistaken economy to first form embankments narrow and

afterwards widen them by lateral additions, for the new material will never unite perfectly with the old.

(2) *In Thick Layers.*—This process has been used in some embankments of great height. It consists in completing the construction of the embankment up to a certain height by the process of end-dumping already described; leaving that layer for a time to settle, and then making a second layer in the same way, and so




FIG. 59.

on. It involves much additional time and labor, and is seldom employed. It is, however, useful in making embankments of hard clay or shale, which, when first dumped, consists of angular lumps that lie with vacant spaces between them and do not form a compact mass until partially softened and broken down by the action of air and moisture.

(3) *In Thin Layers.*—This process consists in spreading the earth in horizontal layers of from 9 to 18 inches deep, and rolling or ramming each layer so as to make it compact and firm before laying down the next layer. Being a tedious and costly process, it is used in special cases only, of which the principal are the filling in behind retaining walls, behind wings and abutments of bridges and culverts, and over their arches.

654. Side Slopes of Embankments.—In forming the embankments the side slopes should be made with a greater inclination than that which the earth naturally assumes, for the purpose of giving them greater durability, and to prevent the width of the top surface along which the roadway is made from diminishing by every change in the side slopes, as it would were they made with the natural slope. To protect the side slopes more effectually they should be sodded, or sown in grass-seed, and the surface water of the top should not be allowed to run down them, as it would soon wash them into gulleys and destroy the embankment. In

localities where stone is plentiful a sustaining wall of dry stone may be advantageously substituted for the side slopes.

The toe or foot of embankments has a tendency to spread; this may be resisted by excavating a small trench along the toe, or by buttressing with a low stone wall.

655. Drainage of Embankments.—The only drains required for embankments over good ground are the ordinary side ditches, with occasional culverts to convey the water from them into the natural water-courses. When springs are crossed, stone drains or culverts may be built to carry the water clear of the embankment.

656. Embankments over Plains.—When a roadway is carried across an extensive plain, it is almost always necessary, in order to keep its surface dry, that it should be raised above the general level of the ground; and where inundations occur, the requisite height may be considerable. In Fig. 60, *A* represents a cross-section



FIG. 60. SECTION OF EMBANKMENTS OVER PLAINS.

tion of an embankment for this purpose, the materials for which are obtained by digging a pair of trenches alongside of it. These trenches, by collecting surface-water and discharging it into the nearest river or other main drainage channel, tend to shorten the duration of floods in the neighborhood of the line.

657. Embankments across Marshes.—When the ground is so soft that an embankment made in the ordinary way would sink in it, different expedients are to be employed according to the kind and degree of difficulty to be overcome. The following list of expedients is arranged in the order of an increasing scale of difficulty:

(1) By digging side drains parallel to the site of the intended embankment, the firmness of the natural ground may be increased.

(2) If the material of the natural ground has a definite angle of repose, though much flatter than that of the material of the embankment, the slopes of the embankment may be formed to the same angle, thus giving it a broader foundation than it would have with its own natural slope.

(3) A foundation may be made for the embankment by digging a trench and filling it with a stable material.

(4) The ground may be compressed and consolidated by driving short piles.

(5) The embankment may be made of materials light enough to form a sort of raft, floating on the soft ground, such as hurdles, fascines, timber platforms, or dry peat. Dry peat was the material used by George Stephenson to carry the Liverpool and Manchester Railway across Chat Moss. Its heaviness, when well dried in the air, is about 30 pounds per cubic foot; and when saturated with water, 63 pounds. On the dry-peat embankment was placed a platform of two layers of hurdles to carry the ballast.

(6) Should all other expedients fail, a marsh or bog may still be crossed by throwing in stones or gravel and sand, until an embankment is formed resting on the hard stratum below, and with its top rising to the required level. It is found that the material of the embankment assumes the same natural slope that it would do in the air.

Mr. George W. Waite, C.E., gives the following description of a road constructed by him in 1868 in the village of Hyde Park (now in the city of Chicago):

"The line crossed a marsh about one mile wide which extended from about two miles west, easterly to Lake Michigan, and south-easterly to Calumet River, a distance of two miles, and was at that time all covered with water from a few inches to two feet deep. Wild rice grew all over that portion of the marsh, about 8 feet high, and the stalks were from $\frac{1}{4}$ to $\frac{1}{2}$ inch in diameter at the bottom. Through the central portion of the marsh was an open water-way about 10 feet wide in the channel proper, with no perceptible current, which widened out into small lakes every few hundred feet.

"The channel and lakes had from 3 to 4 feet of water and about the same depth of black slush or decayed vegetable matter.

"Soundings showed the turf to be about 1 foot thick, with from 2 to 6 feet of soft black vegetable mould underneath, then a hard bottom of blue clay.

"The method of construction was as follows: Beginning at the dry ground on the south end, an 18-foot inch board, 1 foot wide, was placed lengthwise on the outside, 9 feet from the centre, then

one in the centre, 6 feet in advance of the first, and then one on the opposite side, 6 feet in advance of the middle one. Then the three pieces laid lengthwise were covered with 18-foot sound boards 1 inch thick, laid crosswise and nailed as fast as laid to keep them in their places. On these were placed three more, lengthwise as at first, one in the centre and one on each side, and these were nailed through into the under ones. Next all the wild rice for a space of about 75 feet on each side was cut down and pitched with forks onto the floating platform or roadbed. It made a compact covering about 2 feet thick. At the end of the first 500 feet a turn-around for teams on one side was made of boards doubled, 36 feet square, thoroughly nailed.

"Then the whole 500 feet of roadbed was covered 16 feet wide with about 15 inches thick of stone, and on this was placed 3 inches of crushed stone.

"After finishing the first 500 feet the turn-around was removed to the end of the second 500 feet, and so on to completion. Near the middle of the marsh was a lake which the line crossed, some 200 feet wide. This was covered with a bent bridge 50 feet long, and the balance with floats, the same as the marsh but wider. The bridge was placed on the pond-lily roots that everywhere abounded in the bottom of all these small lakes, and left about 2 feet higher than needed to allow for settling, but it has not yet settled more than some 6 inches, although a pole can be run down between the network of roots and into the slush underneath about 3 feet below the bottom of the sills before the hard bottom is reached.

"The road settled on an average about 2 feet, with the exception of two or three short distances where it settled 3 feet, but it did not break through the turf in any place. At a high stage of water some places for a few feet in length would be 1 foot under water.

"The road has stood over 23 years and has been considerably travelled, and is in good condition at the present time (1892). It has had but very little top-dressing during the whole time. Since the road was constructed the marsh has nearly all been drained and has mostly become solid, and the land in it, which at that time was not worth \$25.00 per acre, has just been sold for \$2500.00 per acre."

658. Embankments across Boga.—Undrained moss consists of.

about 90 per cent of water and 10 per cent of vegetable matter, and consequently while in that condition it is quite incapable of sustaining a roadway; but in most cases the surface of the underlying solid ground is above the level of the waterways of the district, and by gradual drainage the fluid mass may be condensed into a more or less solid peat. The drainage should not be effected at too rapid a rate, as there is a liability of the escaping water carrying off with it the particles of vegetable matter, causing the sides of the ditches to collapse, and producing fissures on the surface of the moss which, becoming filled with water or ice, extend more and more.

The drainage of the strip of moss along the site of the intended roadway should be effected by side drains, carried gradually down and into the solid underlying ground. And if this can be done, it is probable that the moss by conversion into peat will be reduced by about one third of its total thickness. The sides of the drains, instead of being sloped, should be cut in a series of steps or benches, each of about three feet deep and three feet broad, down to the requisite level, so as to expose as large a surface as possible to the influence of wind and sun, and thereby produce a comparatively hard skin of peat, and consequently lessen the destructive action of frost.

The side ditches should be cut parallel to the axis of the roadway and at a distance from the centre line on each side of 30 or more feet, depending upon the width of the berm intended to be left between the edge of the roadway and the side ditch. The berm should not be less than six feet. Transverse drains should be cut at right angles to the side drains, and at distances apart not exceeding 30 feet. These transverse drains should extend across and beyond the side drains from 50 to 100 feet. The material excavated from these drains should not be deposited near their edges, or slips will probably occur; it may be spread on the roadway site. After the draining is completed, the roadway may be formed of sand and surfaced with broken stone.

659. Embankments on Hillsides.—When the axis of the roadway is laid out on the side slope of a hill, and the road is formed partly by excavating and partly by embanking, the usual and most simple method is to extend out the embankment gradually along the whole line of the excavation. This method is insecure; the

excavated material if simply deposited on the natural slope is liable to slip, and no pains should be spared to give it a secure hold, particularly at the toe of the slope. The natural surface of the slope




FIG. 61. SHOWING METHOD OF CONSTRUCTION ON HILLSIDES.

should be cut into steps as shown in Figs. 61, 62. The dotted line AB represents the natural surface of the ground, CEB the excavation, and ADC the embankment, resting on steps which have been cut between A and C . The best position for these steps is perpendicular to the axis of greatest pressure. If AD is inclined




FIG. 62. SHOWING METHOD OF CONSTRUCTION ON HILLSIDES.

at the angle of repose of the material, the steps near A should be inclined in the opposite direction to AD , and at an angle of nearly

90 degrees thereto, while the steps near *C* may be level. If stone is abundant, the toe of the slope may be further secured by a dry wall of stone.

On side hills of great inclination the above method of construction will not be sufficiently secure; retaining-walls of stone must be substituted for the side slopes of both the excavations and embankments. These walls may be made of stone laid dry, when stone can be procured in blocks of sufficient size to render this kind of construction of sufficient stability to resist the pressure of the earth. But when the blocks of stone do not offer this security, they must be laid in mortar. The wall which forms the slope of the excavation should be carried up as high as the natural surface of the ground. Unless the material is such that the slope may be safely formed into steps or benches as shown in Figs. 61 and 62, the wall that sustains the embankment should be built up to the surface of the roadway, and a parapet wall or fence raised upon it, to protect pedestrians against accident. (See Figs. 56 and 63.)

660. Roadways on Rock-slopes.—On rock-slopes when the inclination of the natural surface is not greater than one perpendicular to two base, the road may be constructed partly in excavation and partly in embankment in the usual manner or, as shown in Figs. 63, 64, 65, by cutting the face of the slope into horizontal




FIG. 63. SHOWING METHOD OF CONSTRUCTION ON HILLSIDES.

steps with vertical faces, and building up the embankment in the form of a solid stone wall in horizontal courses, either dry or laid in mortar. Care is required in proportioning the steps, as all attempts

to lessen the quantity of excavation by increasing the number and diminishing the width of the steps require additional precautions against settlement in the build-up portion of the roadway.




FIG. 64. SHOWING METHOD OF CONSTRUCTION ON HILLSIDES.

When the rock-slope has a greater inclination than 1:2 the whole of the roadway should be in excavation.

In some localities roads have been constructed along the face of nearly perpendicular cliffs on timber frameworks consisting of horizontal beams, firmly fixed at one end by being let into holes drilled in the rock, the other end being supported by an inclined strut which rests against the rock in a shoulder cut to receive it. There are also examples of similar platforms suspended instead of being supported.

661. The vertical faces of rock-cliffs present the most formidable obstacles to the formation of roads. When the rock is sufficiently hard and not liable to early disintegration a half-tunnel like *DEF*, Fig. 66, may be formed by blasting; but if it be too soft and rotten to admit of this being done, the best plan, if the cliff be of any great height *BE* above the formation level, is to blow out the whole piece *GEF* by a large mine at *E*. Mining should not, as a rule, be employed where there is a chance of the strata being blown out downwards according to the dip, for a piece may be blown out, like the shaded portion Fig. 67, when much time and expense are entailed in rectifying the level.

The general mode of attacking a vertical cliff and of forming a half-tunnel is shown in Fig. 68. The large blasts, *a, a, a, a*, driven 8 feet in depth, at an angle of 45 degrees, are 7 feet 3 inches apart horizontally and 5 feet vertically. The small holes, *b, b*, etc., 3 feet

EXAMPLES OF ROADS ON ROCK SLOPES.




Fig 65




Fig 66.




Fig 67.




Fig.68.

apart and 3 feet deep, which are not fired, serve to determine and facilitate rupture at the proper level. These blasts, when fired, generally blow out or loosen a piece like *ABCD*. The remaining space, *BEF*, is blown out in the same manner.

662. Rock Excavation.—Excavation in hard rock is usually performed by means of some explosive material inserted in a hole bored in the rock, and when ignited it loosens the mass and permits of its being broken up into pieces of the required size.

The diameter and depth of the hole vary with the quantity of rock to be loosened at each blast, and also with the strength of the explosive used.

The quantity of rock loosened, other conditions being the same, is roughly proportional to the cube of the "line of least resistance," which is generally the shortest distance from the centre of the charge to the surface of the rock.

If E = the quantity of the explosive in pounds, and
 L = the line of least resistance in feet, then

$$\begin{aligned} E &= CL^3; \\ C &= .032 \text{ blasting powder;} \\ &= .005 \quad \text{" cotton;} \\ &= .003 \text{ nitroglycerine or dynamite.} \end{aligned}$$

Ordinary blasting powder, 1 pound of which occupies about 30 cubic inches, is ignited by means of a fuse, which burns at the rate of about 2 feet per minute, varying slightly with each coil.

In estimating it is usual to allow $\frac{1}{4}$ of a pound of powder to each cubic yard of solid rock. The actual quantity required will vary with the nature of the rock and its degree of compactness or looseness, the latter requiring most powder.

Dynamite and nitroglycerine should be fired by percussion. Detonating tubes or caps are made for the purpose, which explode on being ignited either by an ordinary fuze or by a galvanic battery.

663. Blasting.

If L = least line of resistance in feet;

X = number of ounces of powder required to blast any rock
 when $L = 2$ feet;

P = quantity of powder in ounces required,—then

$$P = \frac{XL^3}{8},$$

or, when $X = 4$ ounces,

$$P = \frac{L^3}{2}.$$

L should not exceed one half the depth of hole.

TABLE LXVII.
AMOUNT OF CHARGE WHEN $X = 4$ OUNCES.

L		Charge of Powder.		L		Charge of Powder.	
feet.		lbs.	oz.	feet.		lbs.	oz.
1		0	1	5		8	14½
2		0	4	6		6	12
3		0	18½	8		16	0
4		2	0				

In small blasts one pound of powder will loosen about 4½ tons.

In large blasts one pound of powder will loosen about 2½ tons.

Thirty cubic inches of powder weigh one pound. Hence we have the following table, showing the capacity of drill-holes:

TABLE LXVIII.
CAPACITY OF DRILL-HOLES.

Diameter of Hole in inches.	Area in square inches.	Ounces of Powder in one inch deep.	Powder in one foot deep.	Depth of hole in inches to contain one lb. of Powder.
1	0.7854	0.419	lbs. oz. 0 5.028	38.197
1½	1.7671	0.942	0 11.800	16.976
2	3.1416	1.676	1 4.112	9.549
2½	4.9087	2.618	1 15.416	6.112
3	7.0686	3.770	2 18.240	4.244

664. In blasting no loud report should be heard nor stones be thrown out. The best effect is produced when the report is trifling, and when the mass is lifted and thoroughly fractured without the projection of fragments. If the rock be only shaken by a blast and not moved outward, a second charge in the same hole will be very effective.

Any kind of compact brush, such as pine or cedar boughs, laid on rocks about to be blasted, will almost completely prevent the flying of fragments, and thus lessen the danger to persons and buildings in the vicinity.

So much, however, depends upon the character of the rock to be excavated, whether it is hard or soft, stratified or unstratified, and whether the position of the excavation allows of arranging the drill-holes in the most advantageous manner, that the above figures must be regarded as only approximately correct.

665. Holes for blasting rock are bored either by hand or machine drills. Shallow cuts, loose boulders, etc., are more cheaply bored by hand, but deep and extensive cuttings are more economically carried out by the use of machine drills operated either by steam or compressed air.

666. Hand-drilling.—The speed with which holes may be bored in rock varies of course with the hardness of the rock and the diameter of the hole. The smaller the diameter of the hole the greater the depth that can be bored in a given time; and the depth will be greater in proportion than the decrease of the diameter.

The average rate of progress made by a good drillman working a churn-drill in granite and the harder rocks is about as follows :

Diam. of Drill. Inches.	Depth bored per hour. Inches.
3	4
2½	5
2¼	6
2	8
1½	10

When the hole exceeds four feet in depth two men are required to operate the drill.

667. Machine-drilling.—Machine drills bore holes from $\frac{3}{4}$ to 6 inches in diameter. The rate of progress is controlled by the same conditions as hand-drilling, and ranges from three to ten feet per hour, depending on the character of the rock and the size of the machine.

668. Cost of Rock Excavation.—The cost of simply excavating rock is from four to six times that of earth, and is largely controlled by the skill of the overseer, especially as regards carrying the excavation to its full depth. If this is not done, the amount left in

the bottom, especially if it is of little depth, will cost several times more per yard to remove it than the cost per yard of the main cut.

669. Earth Excavation—Loosening the Earth.—The loosening of the material in shallow cuttings and in light soils is done best by the plough, and its removal is economically executed with drag or wheeled scrapers. Gravel, clay, and hardpan require to be loosened by the pick, or if the depth be great, explosives may be employed.

670. Transport of Earth.—The transport of earth is effected in the following ways :

(a) *Throwing with a Shovel*, when the distance horizontally does not exceed 12 feet nor vertically 6 feet.

(b) *Wheelbarrows* may be employed running upon a plank for distances up to 200 feet.

(c) *Carts.*—Between 200 and 500 feet two-wheeled dump-carts may be used.

(d) *Scrapers.*—The economical limit for drag-scrapers is about 150 feet. Wheeled scrapers may be employed up to 500 feet.

(e) For hauls over 500 feet, where a large amount of work is to be done, a track with dump-cars drawn by horses will be found profitable.

(f) *Dump-wagons.*—The dump-wagon is a recent invention; it consists of a four-wheeled wagon, the body of which turns on a horizontal axle, so that it can be tipped over by a single movement of a lever and the earth dumped out. Their capacity varies from 35 to 45 cubic feet. They may be economically employed in long hauls.

The distance, however, depends much upon the difficulty of getting out the earth. With hard clay, requiring two picks to a shovel, and with a small surface to work upon, two carts upon an ordinary road will take away all that a dozen men can get out; while with an easy soil, where one pick will keep half a dozen shovels busy, a larger number of vehicles will be required, or a quicker haul, which may be obtained by putting down a track. The less the haul, or the greater the speed of transport, the fewer may be the number of vehicles to remove a given amount of material. The chief point to be gained is to arrange the different classes of laborers so that none shall be kept waiting. Everything depends upon the tact for management possessed by the overseer.

671. Loosening and Transporting by Machinery.—A machine

called the New Era Grader (Fig. 211) (Chap. XXIII) has been developed for both loosening the earth and automatically transporting and depositing it in the bank when the material is obtained from side ditches, as in the case of building a bank across a plain.

The machine consists of a plough which loosens and raises the earth, depositing it upon a transverse carrying-belt, which conveys it from the excavation to the bank. The carrier-belt is of heavy three-ply rubber 3 feet wide, and can be adjusted to deliver the earth at 14, 17, 19, or 22 feet from the plough.

The machine will work in any material that can be loosened with a plough. The motive power is horses, usually twelve in number.

The capacity of the machine varies from 100 to 150 cubic yards per hour, depending upon the resistance of the material to be moved.

The number of attendants required to operate the machine is three. The cost per cubic yard loosened and placed in bank will depend upon wages and team-hire. With wages at 20 cents per hour for laborers, and horsehire at 10 cents each per hour, the cost per cubic yard would be 1.80 cents.

The machine can also be used to excavate material in deep cuts. When so employed, dump-wagons are used to transport the earth. The carrier of the machine is set to deliver at 10 feet; the wagons are driven under it and automatically loaded with from $1\frac{1}{4}$ to $1\frac{1}{2}$ yards of earth in from 20 to 30 seconds. The machine can thus load from 60 to 80 wagons per hour.

672. Cost of Earth-work.—Regarding the cost of executing earthwork, no fixed rules can be given; it depends largely upon the location, kind and cost of labor, and character of the management. In general it ranges from 10 to 35 cents per cubic yard.

The several items that go to make up the total cost of earthwork are the loosening of the earth, either by ploughs, picks, or explosives, the loading it into the barrows, carts, or other vehicles, the moving and emptying it, the spreading it out upon the embankment, the return of the vehicle, the keeping of the road in order, the wear and tear of tools and vehicles, the interest on the cost of the equipment, the wages of the overseers, and the contractor's profit.

673. Haul.—The cost of removing excavated material when the

distance does not exceed a certain specified limit is included in the price per cubic yard of the material as measured in the cutting. But when the material must be carried beyond this limit, the extra distance is paid for at a stipulated price per cubic yard per 100 feet. The extra distance is known by the name of "haul," and is to be computed by the engineer with respect to so much of the material as is affected by it.

The contractor is entitled to the benefit of all short hauls (less than the specified limit), and material, so moved should not be averaged against that which is carried beyond the limit. Therefore, in all cuts the material of which is all deposited within the limiting distance, no calculation of haul is to be made.

The contractor must haul free that portion of the cutting no one yard of which is carried beyond the specified limit. Therefore this portion is first to be determined in respect to its extent, and the number of cubic yards contained in it is to be deducted from the total content of the cutting, before estimating the haul upon the remainder. Find on the profile of the line two points, one in excavation and the other in embankment, such that while the distance between them equals the specified limit, the included quantities (allowing for shrinkage) of excavation and embankment shall just balance. These points are easily found by trial with the aid of the cross-sections and calculated quantities, and become the starting points from which the haul of the remainder of the material is to be estimated.




Fig. 69. ILLUSTRATING CALCULATION OF OVERHAUL.

Fig. 69 represents a cut and fill in profile. The distance AB is the limit of free haul. The materials taken from AO just make the fill OB and without charge for haul; but the haul for every cubic yard taken from AC and carried to the fill BD is subject

to charge for the distance it is carried, less AB . It would be impossible to find the distance that each separate yard is carried, but we know from mechanics that the average distance for the entire number of yards is the distance between the centres of gravity of the cut AC , and of the fill BD , which is made from it. If, therefore, X and Y represent the centres of gravity, the actual average haul is the sum of the distances ($AX + BY$), and this (expressed in feet) multiplied by the number of cubic yards in the cut AC gives the product to which the price for haul applies.

If a cut is divided and parts are carried in opposite directions, the calculation of each part terminates at the dividing line. If a portion of the material in AC is wasted, it must be deducted and the haul calculated on the remainder.

The specified limit is sometimes made as low as 100 feet, sometimes as high as 1000 feet. A limit of about 300 feet, however, is usually most convenient, as it includes the wheelbarrow work and a large part of the carting, while it protects the contractor on such long hauls as may occur.

674. Calculating the Amount of Earth-work.—The quantity of excavation and embankment expressed in cubic yards is required to be known, in order to compare the amount of work to be done upon the different trial lines which may have been surveyed. For this purpose the method of averaging end areas is sufficiently exact; or if expedition is desired, the quantities may be taken from any of the many tables of quantities which for level cross-section are reliable. For other than level cross-section the tables will be in error, even with the use of the auxiliary formula given with them for the purpose of ascertaining the extra amounts to be added for irregular sections. The error in the quantities obtained by using the tables for irregular sections will be of no practical moment; in fact, it will be more an advantage by allowing a leeway of about 3 or 4 per cent in excess.

675. After final location a more accurate calculation is required, for the reason that the contractors who usually perform the work are paid, not by the day, nor in the lump, but at a certain price per cubic yard, the exact determination of which is therefore required to ascertain their just dues. For this purpose the prismatic formula is the only one to use. It is as follows: *To the sum*

of the end areas add four times the middle area. Multiply the sum by one sixth of the length. Divide the product by 27.

676. Calculation of Half-widths and Areas.—The boundaries of a piece of earth-work in general are as follows:

- (1) The base, or subgrade surface, which forms the bottom of a cutting or the top of an embankment.
- (2) The original surface of the ground, which forms the top of a cutting and the bottom of an embankment.
- (3) The sides, or slopes, which connect the base with the natural surface, and whose inclination is the steepest consistent with the permanent stability of the material.

677. Examples of Cross-sections.—Figs. 70 to 76 represent examples of cross-sections of pieces of earth-work, in each of which *DE* is the base, *AB* the natural surface, and *DA* and *EB* are the slopes. In Fig. 70 the natural surface is horizontal; in Figs. 73, 74, 75, 76 it slopes sideways, being what is termed "side-long ground." Figs. 71, 72 represent forms that occasionally occur. Figs. 70 to 76 represent cuttings; to represent embankments it is only necessary to conceive them to be turned upside down. Figs. 75, 76 represent pieces of earth-work, of which one side, *CEB*, is in cutting called "side cutting" and the other, *CDA*, in embankment.

The half-width of a piece of earth-work is the horizontal distance measured at right angles from a given point in the centre-line of the base to one edge of the cutting or embankment; and although it is called "half-width," it is very generally different at opposite sides of that centre line.

Each half-width consists of two parts: the real half-width of the base, which is fixed by the design of the work, and the horizontal breadth of one slope, which is to be found by calculation or by drawing.

In each of the figures 70 to 76, *C* represents a point in the centre-line, as marked on the ground; *F*, the point vertically above or below it in the centre-line of the base; *DG* and *EH* are vertical lines through the edges of the base; *DF* and *FE* are the half-widths of the base.

In Fig. 70, where the ground is level across, *GA* and *HB* are the widths of the slope, and *CA* and *CB* the half-widths of the earth-work.

In Figs. 74, 75, and 76, where the ground slopes sideways, the

EXAMPLES OF EARTH-WORK CROSS-SECTIONS.




Fig. 70.




Fig. 71




Fig. 72.




Fig. 73




Fig. 74




Fig. 75




Fig. 76.

vertical lines through D , F , and E are produced, if necessary, and are cut at right angles by horizontal lines, ALM and BNP , drawn through the edges of the earth-work. AL and BN are the widths of the slopes; and MA and PB are the half-widths of the earth-work.

When the natural surface of the ground is rugged, the best method of determining the widths of the slopes is by measurement upon a series of cross-sections of the proposed work plotted to the same scale horizontally and vertically.

678. Calculation of Sectional Areas of Earth-work.—The computation of the areas of a series of cross-sections of a piece of earth-work is necessary to ascertain its volume or cubical quantity. If the ground is rugged, it may be necessary to find the area of each cross-section by measurements made upon a drawing; but if the ground is nearly or exactly level across, or has nearly or exactly a uniform sidelong slope, the area of a given cross-section can be computed from the same data which serve to compute the width of the slopes.

679. Formulas for the Calculation of Areas.

Fig. 70.
$$\text{Area} = \frac{CF}{2} \cdot (AB + DE).$$

Figs. 71, 72, 73.
$$\text{Area} = AB \cdot \frac{CF}{2} + \frac{DE}{4} \cdot (GD + HE).$$

Fig. 74.
$$\text{Area} = \frac{1}{2}(\cotan X - \cotan V)^2 - DE^2 \cdot K.$$

(For values of K see Table LXIX.)

Fig. 75.
$$\text{Area of the larger triangle} = \frac{(PB + FO)EH}{2}$$

Fig. 75.
$$\text{Area of the smaller triangle} = \frac{(AM - OF) \cdot DG}{2}.$$

Fig. 76. In this figure C and F coincide, that is, there is neither cut nor fill, the triangles are similar, and the area is expressed by the same formula given for Fig. 75.

The letters on Figs. 70 to 76 denote:

L = angle of side slopes with horizon.

X = angle of natural surface with horizon.

S = ratio of slopes, usually $1\frac{1}{2} : 1$.

$$S = \cot L = \frac{AG \text{ or } HB}{CF} = \frac{AB - DE}{2CF}.$$

AG and $HB = CF \cdot S = CF \cdot \cot L$.

$AB = 2CF \cdot S + DE$.

TABLE LXIX.

VALUES OF K FOR DIFFERENT SLOPES. (G. L. MOLESWORTH.)

Angle of Ground. X .	Values of K .				
	$\frac{3}{4}$ to 1.	$\frac{3}{4}$ to 1.	$\frac{3}{4}$ to 1.	1 to 1.	$1\frac{1}{2}$ to 1.
10°	.0922	.0967	.1016	.107	.1199
12	.1123	.119	.1265	.1351	.1562
14	.1329	.1424	.1533	.1661	.1992
16	.1543	.1672	.1794	.2008	.2512
18	.1766	.1937	.2145	.2407	.3164
20	.2	.2222	.25	.2857	.4009
22	.2252	.2538	.2907	.3389	.5128
24	.25	.2857	.3342	.4012	.6702
26	.2777	.3225	.3846	.4761	.909
28	.3067	.362	.4421	.5675	1.8123
30	.3373	.4058	.5091	.6830	2.1551
32	.3703	.4545	.5882	.8333	
34	.4058	.5091	.6830	1.0373	
36	.444	.5707	.7987	1.3297	
38	.4854	.641	.9434	1.7857	
40	.5307	.7225	1.131	2.6041	
42	.5807	.8183	1.385		
44	.6364	.9345	1.754		
46	.6983	1.0729	2.315		
48	.7692	1.25			
50	.8488	1.475			

Fig. 77 shows a profile and cross-sections of a piece of earth-work.

The letters denote:

0 = a zero point, or the point at which a cutting ends and an embankment begins.

L = the distance between two parallel cross-sections.

l = the distance from a cross-section to the zero point.




TABLE LXX.

(EARTH-WORK.)

CONTENTS OF 1-FOOT LENGTH IN CUBIC FEET.
(For lengths of 100 feet move decimal two places.)

Height. Ft.	Central Portion. Base in feet.							Contents of Both Slopes.							Height. Ft.
	20	30	33	40	50	60	66	1:1	1:1	1:1	1:1	1:1	1:1	1:1	
1	20	30	33	40	50	60	66	.25	.5	.75	1	1.5	2	3	1
2	40	60	66	80	100	120	132	1	2	3	4	6	8	12	2
3	60	90	99	120	150	180	198	2.25	4.5	6.75	9	13.5	18	27	3
4	80	120	132	160	200	240	264	4	8	12	16	24	32	48	4
5	100	150	165	200	250	300	330	6.25	12.5	18.75	25	37.5	50	75	5
6	120	180	198	240	300	360	396	9	18	27	36	54	72	108	6
7	140	210	231	280	350	420	462	12.25	24.5	36.75	49	73.5	98	147	7
8	160	240	264	320	400	480	528	16	32	48	64	96	128	192	8
9	180	270	297	360	450	540	594	20.25	40.5	60.75	81	121.5	162	243	9
10	200	300	330	400	500	600	660	25	50	75	100	150	200	300	10
11	220	330	363	440	550	660	726	30.25	60.5	90.75	121	181.5	242	363	11
12	240	360	396	480	600	720	792	36	72	108	144	216	288	432	12
13	260	390	429	520	650	780	858	42.25	84.5	126.75	169	253.5	338	507	13
14	280	420	462	560	700	840	924	49	98	147	196	294	392	588	14
15	300	450	495	600	750	900	990	56.25	112.5	168.75	225	337.5	450	675	15
16	320	480	528	640	800	960	1056	64	128	192	256	384	512	768	16
17	340	510	561	680	850	1020	1122	72.25	144.5	216.75	289	433.5	578	867	17
18	360	540	594	720	900	1080	1188	81	162	243	324	486	648	972	18
19	380	570	627	760	950	1140	1254	90.25	180.5	270.75	361	541.5	722	1083	19
20	400	600	660	800	1000	1200	1320	100	200	300	400	600	800	1200	20
21	420	630	693	840	1050	1260	1386	110.25	220.5	330.75	441	661.5	882	1323	21
22	440	660	726	880	1100	1320	1452	121	242	363	484	726	968	1452	22
23	460	690	759	920	1150	1380	1518	132.25	264.5	396.75	529	793.5	1068	1587	23
24	480	720	792	960	1200	1440	1584	144	288	432	576	864	1152	1728	24
25	500	750	825	1000	1250	1500	1650	156.25	312.5	468.75	625	937.5	1250	1875	25
26	520	780	858	1040	1300	1560	1716	169	338	507	676	1014	1352	2028	26
27	540	810	891	1080	1350	1620	1782	182.25	364.5	546.75	729	1093.5	1458	2187	27
28	560	840	924	1120	1400	1680	1848	196	392	588	784	1176	1568	2352	28
29	580	870	957	1160	1450	1740	1914	210.25	420.5	630.75	841	1261.5	1682	2528	29
30	600	900	990	1200	1500	1800	1980	225	450	675	900	1350	1800	2700	30
31	620	930	1023	1240	1550	1860	2046	240.25	480.5	720.75	961	1441.5	1922	2883	31
32	640	960	1056	1280	1600	1920	2112	256	512	768	1024	1536	2048	3072	32
33	660	990	1089	1320	1650	1980	2178	272.25	544.5	816.75	1089	1633.5	2178	3267	33
34	680	1020	1122	1360	1700	2040	2244	289	578	867	1156	1734	2312	3468	34
35	700	1050	1155	1400	1750	2100	2310	306.25	612.5	918.75	1225	1837.5	2450	3675	35
36	720	1080	1188	1440	1800	2160	2376	324	648	972	1296	1944	2592	3888	36
37	740	1110	1221	1480	1850	2220	2442	342.25	684.5	1026.75	1369	2053.5	2738	4107	37
38	760	1140	1254	1520	1900	2280	2508	361	722	1083	1444	2166	2888	4332	38
39	780	1170	1287	1560	1950	2340	2574	380.25	760.5	1140.75	1521	2281.5	3042	4563	39
40	800	1200	1320	1600	2000	2400	2640	400	800	1200	1600	2400	3200	4800	40
41	820	1230	1353	1640	2050	2460	2706	420.25	840.5	1260.75	1681	2521.5	3362	5043	41
42	840	1260	1386	1680	2100	2520	2772	441	882	1323	1764	2646	3528	5292	42
43	860	1290	1419	1720	2150	2580	2838	462.25	924.5	1386.75	1849	2773.5	3698	5547	43
44	880	1320	1452	1760	2200	2640	2904	484	968	1452	1936	2904	3872	5808	44
45	900	1350	1485	1800	2250	2700	2970	506.25	1012.5	1518.75	2025	3037.5	4050	6075	45
46	920	1380	1518	1840	2300	2760	3036	529	1058	1587	2116	3174	4232	6348	46
47	940	1410	1551	1880	2350	2820	3102	552.25	1104.5	1656.75	2209	3313.5	4416	6627	47
48	960	1440	1584	1920	2400	2880	3168	576	1152	1728	2304	3456	4606	6912	48
49	980	1470	1617	1960	2450	2940	3234	600.25	1200.5	1800.75	2401	3601.5	4802	7203	49
50	1000	1500	1650	2000	2500	3000	3300	625	1250	1875	2500	3750	5000	7500	50

The cubical contents between sections 5 and 6 and between sections 7 and 8 may be ascertained by the prismoidal formula; the contents between the zero point and the continuous cross-sections by the following formula:

$$\text{Cubic contents in feet} = l \cdot CF \left(\frac{CF \cdot S}{3} + \frac{DE}{2} \right).$$

680. Zero Point.—The zero point should be found on the ground. If this has not been done, it may be ascertained as follows: Take the cut and the fill at the stations between which it lies; then, the sum of the cut and the fill : the cut :: the distance from the cut to the fill : the distance from the cut to the zero point.

681. Earth-work Table.—Table LXX contains the contents in cubic feet for each foot in length of the central portion and side slopes of embankments or cuttings. To use table, note the contents for the central portion due to the required base and depth, add contents given for the required slope and depth, and multiply by the length; the product divided by 27 gives cubic yards.

CHAPTER XIV.

DRAINAGE—CULVERTS.

682. Drainage.—The drainage of roadways is of two kinds, viz., surface and subsurface. The first provides for the speedy removal of all water falling on the surface of the pavement; the second provides for the removal of the underground water found in the body of the road, a thorough removal of which is of the utmost importance and essential to the life of the road-covering. A road-covering placed on a wet undrained bottom will be destroyed by both water and frost, and will always be troublesome and expensive to maintain; perfect subsoil drainage is a necessity and will be found economical in the end even if it requires considerable expense to secure it.

683. The methods employed for securing the subsoil drainage must be varied according to the character of the natural soil, each kind of soil requiring different treatment.

684. The natural soils may be divided into the following classes: silicious, argillaceous, and calcareous; rock, swamps, and morasses.

685. The silicious and calcareous soils, the sandy loams and rock present no great difficulty in securing a dry and solid foundation. Ordinarily they are not retentive of water and therefore require no underdrains; ditches on each side of the road will generally be found sufficient.

686. The argillaceous soils and softer marls require more care; they retain water and are difficult to compact, except at the surface; and they are very unstable under the action of water and frost.

The drainage of these soils may be effected by transverse drains and deep side ditches of ample width. The transverse drains are placed across the road, not at right angles but in the form of an in-

verted V (Λ), with the point directed up-hill; the depth at the angle point should not be less than 18 inches below the subgrade surface, and each branch should descend from the apex to the side ditches with a fall of not less than 1 inch in 5 feet. The distance apart of these drains will depend upon the wetness of the soil; in the case of very wet soil they should be at intervals of 15 feet, which may be increased to 25 feet as the ground becomes drier and firmer.

687. The transverse drains are best formed of unglazed circular tile of a diameter not less than 3 inches, jointed with loose collars. The tiles are made from terra-cotta or burnt clay, are porous, and far superior to all other kinds of drains. They carry off the water with greater ease, rarely if ever get choked up, and only require a slight inclination to keep the water moving through them.

The tiles are made in a variety of forms, as horseshoe sole, double sole, and round, the name being derived from the shape of their cross-sections. Round tile is superior to all other forms. The inside diameter of these tiles varies from $1\frac{1}{2}$ to 6 inches, but they are manufactured as large as 24 inches. Pieces of the larger pipe serve as collars for the smaller sizes. They are made in lengths of 12, 14, and 24 inches, and in thickness of shell from $\frac{1}{4}$ of an inch to 1 inch.

The collar which encircles the joint of the small tile allows a large opening, and at the same time prevents sand and silt from entering the drain. Perishable material should not be used for jointing. When laid in the ditch they should be held in place by small stones. Connections should be made by proper Y-branches.

The outlets may be formed by building a dwarf wall of brick or stone, whichever is the cheapest or most convenient in the locality. The outlet should be covered with an iron grating to prevent vermin entering the drain-pipes, building nests and thus choking up the water-way. (See Fig. 82.)

Silt-basins should be constructed at all junctions and wherever else they may be considered necessary; they may be made from a single 6-inch pipe (Fig. 83), or constructed of brick masonry as shown in Fig. 84.

The trenches for the tiles should be excavated at least 3 feet wide on top and 12 inches on the bottom. After the tiles are laid the trenches must be filled to subgrade level with round field or

cobble stones; stones with angular edges are unsuitable for this purpose. Fine gravel, sand, or soil should not be placed over the drains. Bricks and flat stones may be substituted for the tiles, and the trenches filled as above stated.

Figs. 78 to 81 show different forms of underdrains.

688. Cost of Drains per Foot.—The cost (including labor and materials) of different drains may be taken as follows:

2-inch round tile.....	\$0.19 to \$0.28 per foot
3- " " "	0.22 " 0.35 " "
4- " " "	0.25 " 0.40 " "
Triangular brick.....	0.22 " 0.35 " "
Brick, 4 inches by 4 inches.....	0.40 " 0.95 " "
Stone.....	0.35 " 0.50 " "

Drainage with tiles will cost less than with any other material and will be more satisfactory in the end.

689. As tile-drains are more liable to injury from frost than those of either brick or stone, their ends at the side ditches should not in very cold climates be exposed directly to the weather, but may terminate in blind drains, or a few lengths of vitrified clay-pipe reaching under the road a distance of about 3 to 4 feet from the inner slope of the ditch.

690. Another method of draining the road-bed offering security from frost is by one or more rows of longitudinal drains. These drains are placed at equal distances from the side ditches and from each other, and discharge into cross-drains placed from 250 to 300 feet apart, more or less, depending on the contour of the ground. The cross-drains into which they discharge should be of ample dimensions. On these longitudinal lines of tiles the introduction of catch-basins at intervals of 50 feet will facilitate the removal of the water. These catch basins may be excavated 3 or more feet square and as deep as the tiles are laid. After the tiles are laid the pit is filled with gravel and small stones.

691. Fall of Drains.—It is a mistake to give too much fall to small drains, the only effect of which is to produce such a current through them as will wash away or undermine the ground around them, and ultimately cause their own destruction. When a drain is once closed by any obstruction no amount of fall which could be given it will again clear the passage. A drain with a considerable current through it is much more likely to be stopped from foreign

TYPES OF DRAINS.




FIG. 78.—BLIND DRAIN.




FIG. 79.—POLE DRAIN.




FIG. 80.—STONE DRAIN.




FIG. 81.—TILE DRAIN.






FIG. 83.—SILT-BASIN. FIG. 82.—OUTLET. FIG. 84.—SILT-BASIN.

matter carried into it, which a less rapid stream could not have transported.

A fall of 1 inch in 5 feet will generally be sufficient, and 1 inch in 30 inches should never be exceeded.

692. Side Ditches are provided to carry away the subsoil-water from the base of the road, and the rain-water which falls upon its surface; to do this speedily they must have capacity and inclination proportionate to the amount of water reaching them. The width of the bed should not be less than 18 inches; the depth will vary with circumstances, but should be such that the water-surface shall not reach the subgrade, but remain at least 12 inches below the crown of the road. The sides should slope at least $1\frac{1}{2}$ to 1.

The longitudinal inclination of the ditch follows the configuration of the general topography, that is, the lines of natural drainage. When the latter has to be aided artificially, grades from 1 in 500 to 1 in 800 will usually answer.

In absorbing soil less fall is sufficient, and in certain cases level ditches are permissible. The slopes of the ditches must be protected where the grade is considerable. This can be accomplished by sod revetments, riprapping, or paving.

These ditches may be placed either on the road or land side of the fence. In localities where open ditches are undesirable they may be constructed as shown in Figs. 87 to 89, and may be formed of stone or tile pipe, according to the availability of either material. If for any reason two cannot be built, build one; it is better than none.

Springs found in the road-bed should be tapped and led into the side ditches.

693. Drainage of the Surface.—The drainage of the roadway surface depends upon the preservation of the cross-section, with regular and uninterrupted fall to the sides, without hollows or ruts in which water can lie, and also upon the longitudinal fall of the road. If this is not sufficient the road becomes flooded during heavy rain-storms and melting snow, and is considerably damaged.

The removal of the surface-water from country roads may be effected by the side ditches, into which, when there are no sidewalks, the water flows directly. When there are sidewalks, gutters are formed between the roadway and footpath, as shown in Figs. 85 to 90, and the water is conducted from these gutters into the side ditches by tile-pipes laid under the walk at intervals of about 50

feet. The entrance to these pipes should be protected against washing by a rough stone paving. In the case of covered ditches under the footpath, the water must be led into them by first passing through a catch-basin. These are small masonry vaults covered with iron gratings to prevent the ingress of stones, leaves, etc. Connection from the catch-basin to the ditch is made by a tile-pipe about 6 inches in diameter. The mouth of this pipe is placed a few feet above the bottom of the catch-basin, and the space below it acts as a depository for the silt carried by the water, and is cleaned out periodically. The catch-basins may be placed from 200 to 300 feet apart. They should be made of dimensions sufficient to convey the amount of water which is liable to flow into them during heavy and continuous rain.

694. If on inclines the velocity of the water is greater than the nature of the soil will withstand, the gutters should be roughly paved. In all cases the slope adjoining the foot-path should be covered with sod.





A velocity of 30 feet a minute will not disturb clay with sand and stone. 40 feet per minute will move coarse sand. 60 feet a minute will move gravel. 120 feet a minute will move round pebbles 1 inch in diameter, and 180 feet a minute will move angular stones $1\frac{1}{2}$ inches in diameter.

The scour in the gutters on inclines may be prevented by small weirs of stones or fascines constructed by the roadmen at a nominal cost. At junctions and cross-roads the gutters and side ditches require careful arrangement so that the water from one road may not be thrown upon another; cross-drains and culverts will be required at such places.

695. **Water-breaks** to turn the surface-drainage into the side ditches should not be constructed on improved roads. They increase the grade and are an impediment to convenient and easy travel. Where it is necessary that water should cross the road a culvert should be built.

696. On side hill or mountain roads catch-water ditches should be cut on the mountain side above the road, to cut off and convey the drainage of the ground above them to the neighboring ravines. The size of these ditches will be determined by the amount of rainfall, extent of drainage from the mountain which they intercept, and by the distances of the ravine water-courses on each side.

The inner road-gutter should be of ample dimensions to carry

CROSS-SECTIONS OF ROADS, SHOWING METHODS OF DRAINING
AND DIVISION INTO WHEELWAY, WALKS, ETC

off the water reaching it; when in soil it should be roughly paved with stone. Where paving is not absolutely necessary, but it is desirable to arrest the scouring action of running water during heavy rains, stone weirs may be erected across the gutter at convenient intervals. The outer gutter need not be more than 12 inches wide and 9 inches deep. The gutter is formed by a depression in the surface of the road close to the parapet or revetted earthen protection-mound. The drainage which falls into this gutter is to be led off through the parapet, or other road-side protection at frequent intervals. The guard-stones on the outer side of the road are to be placed in and across this gutter, just below the drainage-holes, so as to turn the current of the drainage into these holes or channels. On straight reaches with parapet protection, drainage-holes with guard-stones should be placed every 20 feet apart. Where earthen mounds are used and it may not be convenient to have the drainage-holes or channels every 20 feet, the guard-stones are to be placed in advance of the gutter to allow the drainage to pass behind them. This drainage is either to be run off at the cross-drainage of the road, or to be turned off as before by a guard-stone set across the gutter.

At re-entering turns, where the outer side of the road requires particular protection, guard-stones should be placed every 4 feet. As all re-entering turns should be protected by parapets, the drainage-holes through them may be formed as close together as desired.

697. Culverts.—Culverts are necessary for carrying under a road the streams it crosses, and also for conveying the surface-water collected in the side ditches from the upper side to that side on which the natural water-courses lie.

698. Especial care is required to provide an ample way for the water to be passed. If the culvert is too small, it is liable to cause a washout, entailing interruption of traffic and cost of repairs, and possibly may cause accidents that will require the payment of large sums for damages. On the other hand, if the culvert is made unnecessarily large, the cost of construction is needlessly increased. Any one can make a culvert large enough; but it is the province of the engineer to design one of sufficient but not extravagant size.

699. The area of water-way required depends (1) upon the rate of rainfall; (2) the kind and condition of the soil; (3) the character and inclination of the surface; (4) the condition and inclination of the bed of the stream; (5) the shape of the area to be

drained, and the position of the branches of the stream ; (6) the form of the mouth and the inclination of the bed of the culvert ;




FIG. 90.—COUNTRY HIGHWAY.




FIG. 91.—ROAD IN EMBANKMENT.




FIG. 92.—SUBURBAN STREET.

CROSS-SECTIONS OF ROADS, ILLUSTRATING DRAINAGE, ETC.

and (7) whether it is permissible to back the water up above the culvert, thereby causing it to discharge under a head.

(1) It is the maximum rate of rainfall during the severest storms which is required in this connection. This certainly varies

greatly in different sections, but there are almost no data to show what it is for any particular locality, since records generally give the amount per day and rarely per hour, while the duration of the storm is seldom recorded. Further, probably the longer the series of observations the larger will be the maximum rate recorded, since the heavier the storm the less frequent its occurrence; and hence a record for a short period, however complete, is of but little value in this connection. Further, the severest rainfalls are of comparatively limited extent, and hence the smaller the area the larger the possible maximum precipitation. Finally, the effect of the rainfall melting snow would have to be considered in determining the maximum amount of water for a given area.

The maximum rainfall as shown by statistics is about one inch per hour (except during heavy storms), equal to 3630 cubic feet per acre. Owing to various causes, not more than 50 to 75 per cent of this amount will reach the culvert within the same hour.

Inches of rainfall \times 3630 = cubic feet per acre.

Inches of rainfall \times 2,323,200 = cubic feet per square mile.

(2) The amount of water to be drained off will depend upon the permeability of the surface of the ground, which will vary greatly with the kind of soil, the degree of saturation, the condition of the cultivation, the amount of vegetation, etc.

(3) The rapidity with which the water will reach the water-course depends upon whether the surface is rough or smooth, steep or flat, barren or covered with vegetation, etc.

(4) The rapidity with which the water will reach the culvert depends upon whether there is a well-defined and unobstructed channel, or whether the water finds its way in a broad thin sheet. If the water-course is unobstructed and has a considerable inclination, the water may arrive at the culvert nearly as rapidly as it falls; but if the channel is obstructed, the water may be much longer in passing the culvert than in falling.

(5) The area of the water-way depends upon the amount of the area to be drained; but in many cases the shape of this area and the position of the branches of the stream are of more importance than the amount of the territory. For example, if the area is long and narrow, the water from the lower portion may pass through the culvert before that from the upper end arrives; or, on the other hand, if the upper end of the area is steeper than the lower, the water from the former may arrive simultaneously with

that from the latter. Again, if the lower part of the area is better supplied with branches than the upper portion, the water from the former will be carried past the culvert before the arrival of that from the latter; or, on the other hand, if the upper portion is better supplied with branch water-courses than the lower, the water from the whole area may arrive at the culvert at nearly the same time. In large areas the shape of the area and the position of the water-courses are very important considerations.

(6) The efficiency of a culvert may be materially increased by so arranging the upper end that the water may enter it without being retarded. The discharging capacity of a culvert can also be increased by increasing the inclination of its bed, provided the channel below will allow the water to flow away freely after having passed the culvert.

(7) The discharging capacity of a culvert can be greatly increased by allowing the water to dam up above it. A culvert will discharge twice as much under a head of four feet as under a head of one foot. This can be done safely only with a well-constructed culvert.

700. The determination of the values of the different factors entering into the problem is almost wholly a matter of judgment. An estimate for any one of the above factors is liable to be in error from 100 to 200 per cent, or even more, and of course any result deduced from such data must be very uncertain. Fortunately, mathematical exactness is not required by the problem nor warranted by the data. The question is not one of 10 or 20 per cent of increase; for if a 2-foot pipe is insufficient, a 3-foot pipe will probably be the next size, an increase of 225 per cent; and if a 6-foot arch-culvert is too small, an 8-foot will be used, an increase of 180 per cent. The real question is whether a 2-foot pipe or an 8-foot arch-culvert is needed.

701. Calculating Area of Water-way.—Numerous empirical formulas have been proposed for this and similar problems; but at best they are all only approximate, since no formula can give accurate results with inaccurate data.

702. Mr. Rudolph Hering, C.E., gives the following formula for calculating the size of the water-way for culverts and drains:

$$Q = Cr \sqrt[4]{\frac{S}{A}},$$

in which

Q = the number of cubic feet per acre per second reaching the mouth of the culvert or drain.

C = a coefficient ranging from .31 to .75, depending upon the nature of the surface; .62 is recommended for general use.

r = average intensity of rainfall in cubic feet per acre per second.

S = the general grade of the area per thousand feet.

A = the area drained, in acres.

703. Valuable data on the proper size of any particular culvert may be obtained (1) by observing the existing openings on the same stream; (2) by measuring, preferably at time of high water, a cross-section of the stream at some narrow place; and (3) by determining the height of high water as indicated by drift and the evidence of the inhabitants of the neighborhood. With these data and a careful consideration of the various matters referred to in Art. 674, it is possible to determine the proper area of water-way with a reasonable degree of accuracy.

704. On mountain roads or roads subjected to heavy rainfall culverts of ample dimensions should be provided wherever required, and it will be more economical to construct them of masonry. In localities where boulders and other débris are likely to be washed down during wet weather, it will be a good precaution to construct catch-pools at the entrance of all culverts and cross-drains for the reception of such matter. In hard soil or rock these catch-pools will be simple well-like excavations, with their bottom two or three feet below the entrance-sill or floor of the culvert or drain. Where the soil is soft they should be lined with stone laid dry; if very soft, with masonry. The size of the catch-pools will depend upon the widths of the drainage works. They should be wide enough to prevent the drains from being injured by falling rocks and stones of a not inordinate size.

The use of catch-pools obviates the necessity of building culverts and drains at an angle to the axis of the road. Oblique structures are objectionable, as being longer than if set at right angles, and by reason of the acute- and obtuse-angled terminations to their piers, abutments, and coverings.

705. Materials for Culverts.—Culverts may be of stone, brick,

vitriified earthenware, cement, or iron pipe. Wood should be absolutely avoided.

For small streams and for a limited surface of rainfall either class of pipes, in sizes varying from 12 to 24 inches in diameter, will serve excellently. They are easily laid, and if properly bedded, with the earth tamped about them, are very permanent. Their upper surface should be at least 18 inches below the road-surface; and the upper end should be protected with stone paving so arranged that the water can in no case work in around the pipe.

When the flow of water is estimated to be too great for two lines of 24-inch pipes, a culvert is required. If stone abounds, it may be built of large roughly squared stones laid either dry or in mortar. When the span required is more than 5 feet, arch-culverts either of stone or brick masonry may be employed. For spans above 15 feet the structure required becomes a bridge.

706. Cement and Earthenware Pipe Culverts.—*Construction.*—In laying the pipe the bottom of the trench should be rounded out to fit the lower half of the body of the pipe with proper depressions for the sockets. If the ground is soft or sandy, the earth should be rammed carefully, but solidly in and around the lower part of the pipe. The top surface of the pipe should, as a rule, never be less than 18 inches below the surface of the roadway, but there are many cases where pipes have stood for several years under heavy loads with only 8 to 12 inches of earth over them. No danger from frost need be apprehended, provided the culverts are so constructed that the water is carried away from the level end. Ordinary soft drain-tiles are not in the least affected by the expansion of frost in the earth around them.

The freezing of water in the pipe, particularly if more than half full, is liable to burst it; consequently the pipe should have a sufficient fall to drain itself, and the outlet should be so low that there is no danger of back-waters reaching the pipe. If properly drained, there is no danger from frost.

Jointing.—In many cases, perhaps in most, the joints are not calked. If this is not done, there is liability of the waters being forced out at the joints and washing away the soil from around the pipe. Even if the danger is not very imminent, the joints of the larger pipes, at least, should be calked with hydraulic cement, since the cost is very small compared with the insurance against damage

ABUTMENTS FOR PIPE CULVERTS.




Fig. 93.



Fig. 94.



Fig. 95




Fig. 96.

thereby secured. Sometimes the joints are calked with clay. Every culvert should be built so that it can discharge water under a head without damage to itself.

The end sections should be protected with a masonry or timber




Fig. 96a. SINGLE PIPE CULVERT.




Fig. 96b. DOUBLE PIPE CULVERT.

bulkhead, although it is often omitted. A parapet wall of rubble masonry or brick-work laid in cement is best (see Fig. 93). The foundation of the bulkhead should be deep enough not to be disturbed by frost. In constructing the end wall, it is well to increase the fall near the outlet to allow for a possible settlement of the interior sections. When stone and brick abutments are too expensive, a fair substitute can be made by setting posts in the ground and spiking plank on, as shown in Fig. 95. When planks are used, it is

best to set them with considerable inclination towards the roadbed to prevent their being crowded outward by the pressure of the




Fig. 96c. TRIPLE PIPE CULVERT.




Fig. 96d. SECTION OF PIPE CULVERT.

embankment. The upper end of the culvert should be so protected that the water will not readily find its way along the outside

of the pipes, in case the mouth of the culvert should become submerged.

When the capacity of one pipe is not sufficient, two or more may be laid side by side as shown in Figs. 96a to 96c. Although two small pipes do not have as much discharging capacity as a single large one of equal cross-section, yet there is an advantage in laying two small ones side by side, since the water need not rise so high to utilize the full capacity of the two pipes as would be necessary to discharge itself through a single one of larger size.

707. Cost.—Price of earthenware and cement pipe vary greatly with the conditions of trade, and with competition and freight. Current (1892) prices, subject from 40 to 65 per cent discount for culvert-pipe in car-load lots, f. o. b. at the factory, are about as follows:

TABLE LXXI.
COST AND WEIGHT OF VITRIFIED CULVERT-PIPE.

Inside Diameter. Inches.	Price per foot. Cents.	Area. Square feet.	Weight per foot. Pounds.	Number of feet in Car-load of 24,000 lbs.
12	85	.78	48	500
15	125	1.23	67	358
18	170	1.76	84	286
20	225	2.18	99	242
24	325	3.14	140	172

TABLE LXXII.
COST AND WEIGHT OF PORTLAND CEMENT-PIPE.

Inside Diameter. Inches.	Price per foot. Cents.	Area. Square feet.	Weight per foot. Pounds.	Number of feet in Car-load of 24,000 lbs.
12	85	.78	57	450
15	125	1.23	77	320
18	178	1.76	110	230
20	225	2.18	135	180
24	325	3.14	165	150

708. Iron Pipe-culverts.—During recent years iron pipe has been used for culverts on many prominent railroads, and may be used on roads in sections where other materials are unavailable.

In constructing a culvert with cast-iron pipe the points requiring particular attention are (1) tamping the soil tightly around the pipe to prevent the water from forming a channel along the outside, and (2) protecting the ends by suitable head walls and, when necessary laying riprap at the lower end. The amount of masonry required for the end walls depends upon the relative width of the embankment and the number of sections of pipe used. For example, if the embankment is, say, 40 feet wide at the base, the culvert may consist of three 12-foot lengths of pipe and a light end wall near the toe of the bank; but if the embankment is, say, 32 feet wide, the culvert may consist of two 12-foot lengths of pipe and a comparatively heavy end wall well back from the toe of the bank. The smaller sizes of pipe usually come in 12-foot lengths, but sometimes a few 6-foot lengths are included for use in adjusting the length of the culvert to the width of the bank. The larger sizes are generally 6 feet long.

709. Cost.—Prices of cast-iron pipe vary greatly with competition and the conditions of trade. Table LXXIII shows current prices (1892), subject to commercial discount:

TABLE LXXIII.
DIMENSIONS, WEIGHT, AND PRICES OF IRON PIPE.

Inside Diameter.	Thickness.	Weight per foot.	Price per foot.
12 inches	$\frac{7}{16}$ inch	60 pounds	96 cents
16 "	"	86 "	140 "
20 "	"	118 "	188 "
24 "	"	175 "	280 "
30 "	"	240 "	384 "
36 "	"	320 "	512 "
42 "	"	400 "	640 "
48 "	1 "	510 "	816 "

710. The approximate relative cost of the different forms of culvert per lineal foot for each square foot of waterway is as follows:

Rubble.....	40 cents
Earthenware or cement pipe.....	80 "
Iron pipe.....	46 "

711. Stone Box-culverts.—The simplest form of stone culvert is what is known as the box-culvert. It consists of two side walls,

EXAMPLES OF BOX-CULVERTS.




FIG. 97.—END ELEVATION.




FIG. 98.—SECTION AB.




FIG. 99.—PLAN.




FIG. 100.—SECTION CD.




FIG. 101.—SECTION OF CULVERT ON A HILLSIDE.

which may be built of stone laid dry or in mortar, and a covering of flags. Where large flat stones can readily be procured it forms a very economical structure. Under high embankments the thickness of the covering-stone must be increased. Figs. 97 to 101 show the form of this class of culverts and the dimensions given in Table LXXIV will serve as an approximate guide for general use.

TABLE LXXIV.
DIMENSIONS FOR BOX-CULVERTS.

Area.	Opening.	Side Wall.	Depth of Cover.	Length of Cover.
4 feet	2' × 2'	2' × 2'	12 inches	5 feet
9 "	3 × 3	3 × 2½	16 "	6 "
16 "	4 × 4	4 × 3	20 "	7 "
25 "	5 × 5	5 × 3½	22 "	8 "
36 "	6 × 6	6 × 4	24 "	9 "

712. Arch-culverts.—The form of an arch may be the semi-circle, the segment, or a compound formed of a number of circular curves of different radii. Full-centre arches or entire semicircles offer the advantages of simplicity of form, great strength, and small lateral thrust; but if the span is large they require a correspondingly great rise, which is often objectionable. The flat or segmental arch enables us to reduce the rise, but it throws a great lateral strain on the abutments. The compound curve gives, when properly proportioned, a strong arch, with a moderate lateral action, is easily adjustable to different ratios between the span and the rise, and is unsurpassed in its general appearance. In striking the compound curve, the following conditions are to be observed: the tangents at the springing must be vertical, the tangent at the crown horizontal, and the number of centres must be uneven.

713. The depth of the arch-stone, or thickness of voussoir, depends upon the form and size of the arch, the character of the masonry, and the quality of the stone. The following table gives the depths for semicircular arches, the second column being for hammer-dressed beds, the third for beds roughly dressed with the chisel, and the fourth for brick masonry.

EXAMPLE OF ARCH-CULVERTS.




FIG. 102.—SECTIONAL ELEVATION.




FIG. 104.—SECTION AB.




FIG. 103.—PLAN.




FIG. 105.—SECTION CD.

TABLE LXXV.

Span in feet.	Thickness of Arch in inches.		
	First-class Masonry.	Second-class Masonry.	Brick Masonry.
6	12	15	13
8	13	16	16
10	14	17	20
12	15	19	20
14	16	20	24
16	17	21	24
18	18	23	24
20	19	24	24
25	20	25	28
30	21	26	28
35	22	28	28
40	23	29	32
45	24	30	32
50	25	31	32

Professor Rankine remarks that the precise determination of the depth of the keystone of an arch would be an almost impracticable problem from its complexity, and that the best course in practice is to assume a depth for the keystone according to an empirical rule founded upon the dimensions of good existing examples of bridges. For such a rule he gives the following:

Depth in feet = $\sqrt{(.12 \text{ radius at crown})}$ for a single arch.

Depth in feet = $\sqrt{(.17 \text{ radius at crown})}$ for an arch of a series.

Mr. Trautwine gives the following rule: For first-class cut stone of hard material take 0.36 of the square root of the radius of the crown; for second-class work, .40 of the square root; and for brick or rubble arches, 0.45 of the square root. The results by the latter are slightly in excess of those by Professor Rankine's formula.

714. Thickness of Abutments.—Numerous rules have been given for obtaining the thickness of the abutments for arches. The most elaborate of these are from their form applied with difficulty to the cases commonly occurring in practice, and many of the elements entering into the solution of the problem are quite indeterminate, depending as they do upon the character of the masonry and upon the workmanship. In place of rules, therefore, we present merely an empirical table, embracing the results of a considerable degree of practice.

EXAMPLE OF ARCH-CULVERTS.




FIG. 106.—END ELEVATION.




FIG. 107.—PLAN.




FIG. 108.—SECTION AB.

Table LXXVI gives the minimum thickness of abutments for arches of 120 degrees where the depth of crown does not exceed 3 feet.

Calculated from the formula

$$T = \sqrt{6R + \left(\frac{3R}{2H}\right)^2} - \frac{3R}{2H},$$

in which D = depth or thickness of crown in feet;

H = height of abutment to springing in feet;

R = radius of arch at crown in feet;

T = thickness of abutment in feet.

TABLE LXXVI.

MINIMUM THICKNESS OF ABUTMENTS FOR ARCHES OF 120 DEGREES
WHERE THE DEPTH OF CROWN DOES NOT EXCEED 3 FEET.

Span of Arch.	Height of Abutment to Springing, in feet.				
	5	7.5	10	20	30
8 feet	3.7	4.2	4.8	4.6	4.7
9 "	3.9	4.4	4.6	4.9	5.0
10 "	4.2	4.6	4.8	5.1	5.2
12 "	4.5	4.7	5.2	5.6	5.7
14 "	4.7	5.2	5.5	6.0	6.1
16 "	4.9	5.5	5.8	6.4	6.5
18 "	5.1	5.8	6.1	6.7	6.9
20 "	5.3	6.0	6.4	7.1	7.2
22 "	5.5	6.2	6.6	7.3	7.6
24 "	5.6	6.4	6.9	7.6	7.9
30 "	6.0	7.0	7.5	8.4	8.8
40 "	6.5	7.7	8.4	9.6	10.0
50 "	6.9	8.2	9.1	10.5	11.1
60 "	7.2	8.7	9.7	11.4	12.0
70 "	7.4	9.1	10.2	11.8	12.9
80 "	7.6	9.4	10.6	12.8	13.6
90 "	7.8	9.7	11.0	13.4	14.3
100 "	7.9	10.0	11.4	14.0	15.0

NOTE.—The thickness of abutment for a semicircular arch may be taken from the above table by considering it as approximately equal to that for an arch of 120 degrees having the same radius of curvature; therefore by dividing the span of the semicircular arch by 1.155 it will give the span of the 120-degree arch requiring the same thickness of abutment.

TABLE LXXVII.

DIMENSIONS, WEIGHT, AND PRICES OF DRAIN-TILE.

Inside Diameter. Inches.	Area in inches.	Weight per foot.	Price per 1000 feet.*	Curves and Reducers. Each.*	No. Feet to Carload.
2	3.141	8	\$15.00	\$0.20	8000
3	7.068	4½	25.00	0.20	6000
4	12.566	6½	45.00	0.25	4000
5	19.625	9	75.00	0.30	3000
6	28.274	12	100.00	0.40	2200
7	38.484	15	110.00	0.50	2000
8	50.265	22	150.00	0.70	1250
9	63.617	26	200.00	0.75	1000
10	78.539	33	250.00	1.00	850
12	113.09	44	325.00	1.25	750
15	176.71	60	450.00	1.50	500
18	254.46	92	700.00	2.25	350
20	314.16	106	1000.00	3.00	250
21	345.00	110	1250.00	4.00	225
24	452.39	150	1625.00	5.00	200

* Subject to discount.

TABLE LXXVIII.

DISCHARGING CAPACITY OF CIRCULAR PIPES IN CUBIC FEET PER MINUTE.

Diameter of Pipe.	Inclination. Inches per 100 feet.				
	2	4	6	12	24
Inches	cu. ft.	cu. ft.	cu. ft.	cu. ft.	cu. ft.
2	1.71	2.54	3.97	3.61	4.95
3	3.07	4.69	5.24	6.16	8.28
4	6.28	9.62	10.92	12.43	17.51
5	15.42	20.91	21.49	20.72	29.29
6	27.46	37.24	42.45	37.95	51.23
12	97.50	139.10	179.15	196.25	277.54
15	171.37	243.94	297.22	320.41	440.55
18	270.32	393.69	495.95	545.77	762.15
20	327.54	461.23	575.92	649.73	904.42
24	555.08	794.59	992.53	1176.97	1579.15

CHAPTER XV.

BRIDGES, RETAINING-WALLS, PROTECTION WORKS, TUNNELS, FENCING.

715. Bridges.—The construction of bridges is an important subject, and should not be attempted without the professional services of a civil engineer. Neglect of this precaution, and an inadequate conception by the people of the risks to their own and other persons' lives produced by faulty bridge design, are causes to which may be attributed many of the numerous failures of highway bridges annually recorded.

As the subject is so extensive, but a few general remarks will be made in this volume.

No one bridge is adapted to every situation; each one must be designed to sustain the amount and character of the load to which it will be subjected.

716. All bridges should be proportioned to sustain the strains produced by the following loads:

(1) *The dead load*, which is the weight of the structure itself, and in certain cases some extraneous loading. The dead load is taken as uniformly distributed over the bridge.

(2) *The live load*. The live load on a bridge is the moving load passing over it. In calculating the dimensions of the several parts forming the superstructure of a bridge, the heaviest load which is likely to traverse it should be taken.

Live loads are of varied character; they comprise the weight of loaded vehicles passing either singly or in continuous strings, portable engines, agricultural machinery, steam road-rollers, and the weight of a crowd of people densely packed.

(3) The wind-pressure, including both direct and indirect effects.

(4) Variations of temperature.

Valuable information on the subject of highway bridges is to be

found in the specifications for highway bridges of iron and steel by J. A. Waddell.

717. Nothing improves the appearance and attractiveness of a road so much as a handsome bridge. And it need cost no more to construct than a homely, uncouth structure.

718. Materials for Bridges.—Bridges may be either of stone, brick, wood, steel, iron, or iron and wood. For permanence and beauty, stone or stone and brick is preferable. Steel and iron make handsome bridges, but require more attention than stone. Wood is the least permanent, and cheapest in first cost.

719. Timber Bridges.—In many localities timber is the only material available for bridges. Therefore a few directions for their construction may be useful. The simplest form of wooden bridge is that of plain stringers laid across the stream and covered with plank. The width of the openings which such beams span should not exceed 16 feet. For greater widths, supports in the form of piles may be introduced, thus dividing the long span into a number of shorter ones; but such supports are obstructions to the stream and liable to damage in time of freshets. It is, therefore, desirable to avoid their use. Other forms of support must therefore be devised for strengthening the beams. This may be effected by supports from below or above. Of supports from below, the simplest are shorter timbers (bolsters or corbels) placed under the main ones to which they are firmly bolted, and projecting about one third of the span.

Still more effective are oblique braces or struts supporting the middle of the beam, and resting at their lower ends in shoulders formed in the abutments. Similar braces may be applied to the bolsters (Fig. 113); but as the span increases, these braces become so oblique as to lose much of their efficiency. A straining-piece is therefore interposed between them. Openings up to thirty-five feet may thus be spanned.

For longer spans, the bolsters, braces, and straining-beams may be combined as in Fig. 114. The principle of this method may be extended to very wide openings.

But in many cases supports from below may be objectionable, as exerting too much thrust against the abutments, and being liable to be carried away by freshets, etc. The beams must in such cases be strengthened by supports from above.

TYPES OF TIMBER BRIDGES.



Fig 109.



Fig 117.




Fig.110.




Fig.118




Fig.111




Fig.119.




Fig.112



Fig.120.




Fig.113.




Fig.121.




Fig.114.




Fig.122.



Fig.115.




Fig.123.



Fig.116.



Fig.124

HEAVY LINES WOOD. LIGHT LINES IRON.

The simplest form of such is shown in Fig. 115, in which the horizontal beam is supported by an upright "king-post" to which it is attached by an iron strap, or by the upright "king-post" being formed of two pieces bolted together, and enclosing the beam between them. The king-post itself is supported by the oblique braces, or struts, which rest against notches in the horizontal beam.

Since the king-post acts as a suspending tie, an iron rod may be advantageously substituted for it; the struts may be also stiffened by iron ties, binding them to the main timbers as in Fig. 116.

For longer spans, a straining-beam may be introduced between the struts as in Fig. 121, in which the posts are represented as enclosing the beam.

The diagrams of simple bridges, Figs. 125 to 132, and Tables LXXIX and LXXX give the spans for which they may be employed and the dimensions of the several parts.

Fig. 129 shows the iron washer used at the end of the beam. The latter should be at right angles to the direction of the rod. It is better to have two rods instead of one rod under each beam. This allows the rods to be outside of the beam, as shown in the figure, instead of requiring holes to be bored through it, thereby weakening it. Fig. 130 shows the shoe used at the foot of the post and which holds the rods in place. Figs. 131 and 132 show the same method of construction applied to bridges of greater width and span.

Combination structures of wood and iron require constant watchfulness, to repair and replace damages arising from decay or defective material.

Iron Bridges.—The first cost of iron or steel bridges is greater than that of wood or combination structures; but where economy of the public funds is desired, the first two materials are to be preferred, because the annual cost of repairs to the wooden structure will in a very few years equal, if not greatly exceed, the additional sum required for the construction of the all-metal bridge. Moreover, the metal structure will outlive two if not more timber ones.

Figs. 132*a*, 132*b*, 132*c* show types of iron bridges.

To ascertain the saving in favor of iron, see Chapter XXIV.

720. The substructures of bridges should be of masonry. Timber should not be used if it can possibly be avoided. Such struc-




Fig. 125. LONGITUDINAL SECTION.




Fig. 126. TRANSVERSE SECTION.

TABLE LXXIX.

DIMENSIONS FOR FIGS. 125 AND 126.

Span. Feet.	Girders. Inches.	Floor-beams. Inches.	Floor. Inches.	Railing. Inches.
5	8 × 10	6 × 6	4	3 × 4
10	10 × 14	"	"	"
15	12 × 18	"	"	"
20	14 × 22	"	"	"




Fig. 127. LONGITUDINAL SECTION.




Fig. 128. TRANSVERSE SECTION.


Fig. 129.
DETAIL OF WASHER.Fig. 130.
DETAIL OF SHOE.

TABLE LXXX.

DIMENSIONS FOR FIGS. 127 TO 133.

Span. Feet.	Girders. Inches.	Diameter of Rods. Inches.	Post. Inches.
15	12 × 15	1 $\frac{3}{8}$	8 × 12
20	12 × 18	1 $\frac{1}{2}$	8 × 12
25	14 × 18	2	8 × 14
30	15 × 20	2 $\frac{1}{8}$	4 × 15




Fig. 131. LONGITUDINAL SECTION.

tures are unsatisfactory owing to early decay caused by the destroying action of air and water.

For directions and specifications for the construction of iron




Fig. 132. TRANSVERSE SECTION.

and steel highway bridges the excellent specifications of Messrs. G. Bouscaren, Theodore Cooper, Edwin Thacher, and J. A. Waddell may be consulted.

721. Retaining-walls.—Retaining-walls are structures of stone laid dry or in mortar, and are employed under various forms to support the sides of roads on hillsides, or places where land for the slopes is not obtainable (see Figs. 133 to 136).

722. Thickness of Walls.—Retaining-walls require a certain thickness to enable them to resist being overthrown by the thrust of the material which they sustain. The amount of this thrust depends upon the height of the mass to be supported and upon the quality of the material.

723. Surcharged Walls.—A retaining-wall is said to be surcharged when the bank it retains slopes backwards to a higher level than the top of the wall; the slope of the bank may be either equal to or less, but cannot be greater, than the angle of repose of the earth of the bank.

724. Proportions of Retaining-walls.—In determining the proportions of retaining-walls experience, rather than theory, must be our guide. The proportions will depend upon the character of the material to be retained. If the material be stratified rock with in-




Fig. 132a.




Fig. 132b.




Fig. 132c.

terposed beds of clay, earth, or sand, and if the strata incline toward the wall, it may require to be of far greater thickness than




FIG. 133.




FIG. 134.




FIG. 135.




FIG. 136.

any ordinary retaining-wall; because when the thin seams of earth become softened by infiltrating rain, they act as lubricants, like

soap or tallow, to facilitate the sliding of the rock strata; and thus bring an enormous pressure against the wall. Or the rock may be set in motion by the action of frost on the clay seams. Even if there be no rock, still if the strata of soil dip toward the wall, there will always be danger of a similar result; and additional precautions must be adopted, especially when the strata reach to a much greater height than the wall.

725. Form of Retaining-walls.—Retaining-walls are built of numerous forms of profile or cross-section, varying from the rectangular to the triangular. A triangle is that figure which is theoretically the most economical; and the nearer that practical conditions will allow of its being conformed to the better.

All other things being equal, the greater the face-batter the greater will be the stability of the wall; but considerations connected with the functions of the wall limit the full application of this condition, and walls are usually constructed with only a moderate batter on the face, the diminution towards the top being obtained by a back batter worked out in a series of offsets. Walls so designed contain no more material and present greater resistance to overturning than walls with vertical backs.

726. Dry stone retaining-walls are best suited for roads on account of their self-draining properties and their cheapness. If these dry walls are properly filled in behind with stones and chips, they are, if well constructed, seldom injured or overthrown by pressure from behind. If the stone is stratified with a flat cleavage, the construction of retaining and parapet walls is much facilitated. If the stone has no natural cleavage, great care is necessary to obtain a proper bond. If walls built of such stone are of coursed rubble, care is required that the masons do not sacrifice the strength of the walls to the face appearance. The practice of building walls with square or rectangular-faced stones, tailing off behind, laid in rows, one course upon the other, the rear portions of the walls being of chips and rough stones, set anyhow, cannot be condemned too strongly. Such a construction, which is very common, has little transverse and no longitudinal strength.

Little or no earth should be used for back filling if stone is available. Where earth filling is used, it should only be thrown in and left to settle itself; on no account should it be wetted and rammed.

The foundation of retaining-walls should be particularly secure; the majority of failures which have occurred in such walls have been due to defective foundations.

727. Failure of Retaining-walls.—Retaining-walls generally fail (1) by overturning or by sliding, or (2) by bulging out of the body of the masonry. Sliding may be prevented by inclining the courses inward. An objection to this inclination of the joints in dry walls is that rain-water, falling on the battered face, is thereby carried inwards to the earth backing, which thus becomes soft and settles. This objection may be overcome by using mortar in the face-joints to the depth of a foot, or by making the face of the wall nearly vertical.

728. Protection of Retaining-walls.—The top of the walls should be protected with a coping of large heavy stones laid as headers.

Where springs occur behind or below the wall, they must be carried away by piping or otherwise got rid of.

The back of the wall should be left as rough as possible, so as to increase the friction of the earth against it.

729. Weep-holes.—In masonry walls, weep-holes must be left at frequent intervals, in very wet localities as close as 4 feet, so as to permit the free escape of any water which may find its way to the back of the wall. These holes should be about 2 inches wide and should be backed with some permeable material, such as gravel, broken stone, etc.

730. Formula for calculating Thickness of Retaining-walls.—

E = weight of earth-work per cubic yard.

W = weight of wall.

H = height of wall.

T = thickness of wall at top.

$T = H \times \text{tabular number (Table LXXXI).}$

731. Surcharged Walls.—In calculating the strength of surcharged walls substitute Y for H , Y being the perpendicular at the end of a line, $L = H$ measured along the slope to be retained (Fig. 136).

$Y = 1.71H$ in slopes of 1 : 1;

$= 1.55H$ “ “ “ $1\frac{1}{2}$: 1;

$= 1.35H$ “ “ “ 2 : 1;

$= 1.31H$ “ “ “ 3 : 1;

$= 1.24H$ “ “ “ 4 : 1.

TABLE LXXXI.
COEFFICIENTS FOR RETAINING-WALLS.

Batter of Wall.	E : W :: 4 : 5		E : W :: 1 : 1	
	Clay.	Sand.	Clay.	Sand.
1 in 4	.088	.029	.115	.054
1 in 5	.122	.065	.155	.092
1 in 6	.149	.092	.183	.118
1 in 8	.184	.125	.218	.153
1 in 12	.221	.160	.256	.189
Vertical	.800	.289	.336	.267

732. Retaining-walls of dry stone should not be less than 3 feet thick at top, with a face of 1 in 4 and back perpendicular, the courses laid perpendicular to the face-batter. Weep-holes are unnecessary unless the walls are in very wet situations.

Retaining-walls of masonry should be at least 2 feet thick at top, back perpendicular and face battered at the rate of 1 in 6.

733. On steep hillside or mountain roads retaining-walls should be built—

- (1) At all re-entering curves.
- (2) At all culverts and bridges.
- (3) On the edge of precipitous places, where there is no room for a bank.
- (4) Where the bank slope and the ground slope are nearly or quite parallel to each other.
- (5) Where a bank would be of excessive length owing to the angle of the natural ground slope.
- (6) Where a wall would be cheaper than a bank.

Retaining-walls on the edge of dangerous precipices, having to support great weight, should be built of masonry. All others may be of dry stone.

734. Protection of Roads.—All roads should be protected, but hillside and mountain roads which are unprotected can only be classed as dangerous. Blocks of stone of not less than 2½ to 3 feet in height, and set with not more than 3 feet between them, afford a fair protection on a mountain road not very precipitous

at its outer edge, and there is an advantage attendant upon their use that no outer gutter is necessary, for the drainage passes over the bank in every direction, and after the first year or two but little damage occurs to the banks from this cause.

735. The proper amount of protection required for the dangerous portions of a mountain road is best obtained by stone parapets and earthen mounds. Parapets should not be less than 3 feet in height and, if of masonry, $1\frac{1}{2}$ feet in thickness.

If stone parapets be built dry, they should be at least 2 feet in thickness, and the coping should be set in mortar; otherwise they are too easily deranged, and cartmen halting on the road and desiring to block the wheels of their vehicles invariably resort to them for a stone for this purpose. Next in order of protection afforded by the use of stone may be mentioned the plan of placing large blocks of rough stone and boulders on the edge of the road and touching each other. If of good size and well set, considerable protection is afforded by this method, which is cheap. Dry stone parapet walls should never be employed if masonry walls can be afforded, and should on no account be used on precipitous curves. Parapets should be employed to protect all embankments of a road which have stone-wall revetments, and the outside of all cuttings in rock. They should also be built on each side of the road at all cross-drainage works, and should be adopted at all situations where stone is available from cuttings. Where the embankments are of earth, earthen mounds are to be preferred on the score of economy. These earthen mounds should not be less than 3 feet in height, and they are best formed, both for appearance and for their own preservation, by being revetted with dry stone inside. Earthen mounds constructed in this manner afford the most secure protection for traffic, as, if well rounded off on the outer side, they do not yield to any concussion, however violent.

736. Wooden railings should never be employed to protect dangerous places on a mountain road. They afford no real protection to the traffic, but only give a sense of protection to passing vehicles which do not come into collision with them, and show to unexcited animals that the way is barred in that direction.

737. Besides the protection so necessary for the safety of the travelling public, the roads themselves require protection at their

edges from passing vehicles. Cart-wheels, if not prevented from hugging the very edge of the road, and from slipping, either from design or accident, into the gutters, do great damage. Curb-stones get forced out of their places, and if one be displaced, others soon follow, to the destruction of the road edge as well as of the gutters themselves. These become blocked with loose stones, and when rain falls greater destruction to the road ensues. It is necessary, therefore, to protect the edges of mountain roads where they are likely to be damaged by wheel traffic, which occurs chiefly on the inside of salient and outside of re-entering curves.

738. Guard-stones about 9 inches square and of sufficient length should be placed every 4 or 5 feet apart at the curbs, clear of the



FIG. 137.

gutter, on the hill side of salient curves. The re-entering curves must also be protected on the inner curve, which is the outer side of the roadway, by means of similar guard-stones, which, however, in this situation are set up in the gutters themselves.

739. Roads along the seashore, margin of rivers and lakes, may be constructed according to either of the methods shown in Figs. 137 to 139.

In Fig. 137, two rows of piles, spaced about 10 feet centre to centre, are driven, one row along the toe of the slope and another along the crest of the slope, and capped with a 3-inch plank; between each pile and fastened thereto a 4×6 inch or heavier stringer is placed. On these stringers a layer of matched tongued and grooved plank 2 or 3 inches thick are laid and spiked.

In Fig. 138 a bulkhead is formed as follows: a row of piles, spaced 6 feet centre to centre, is driven to a solid bearing and capped with a heavy stick of timber. To the piles waling-sticks are bolted, one immediately at the head, the other at or below the

natural surface of the beach; on the land side of the waling-sticks matched sheet-piling is driven and spiked to the upper waling-stick. Anchor-piles are driven on the land side at such distance from the main piles as will form an angle of from 30 to 45 degrees. The main piles may be fastened to the anchor-piles by wrought-iron tie-rods, and bevelled cast-iron washers or timber may be used




FIG. 138.

for the same purpose. A brace-stick of either round or square timber should be placed in the angle formed between the tie-rod and head of the anchor pile. The face of the main piles at high-water mark should be protected by a chafing-stick. Fender-piles may also be used if the water is navigable for large boats.




FIG. 139.

In Fig. 139 a masonry wall is shown, built on a timber platform. To this class of work the same rules apply as to retaining-walls.

740. Tunnels.—For highways, generally no tunnels can be allowed. They are too costly, and can only be employed under

exceptional circumstances. If a tunnel would shorten the road by a length, the cost of which would equal, or nearly so, the extra cost of the road through the tunnel, the construction of the tunnel would be justified. The saving in tractive energy to the public using the road would, in most cases, be a saving too indirect to be imported into the calculation.

741. Fencing.—Fences are usually built by the property-owners, but occasionally the road-builder is called upon to include fencing in his work; therefore the following few remarks may be useful.

The requirements of a highway fence are somewhat different from those of ordinary farm fences. They must possess sufficient strength to withstand the rough usage to which they are frequently subjected. In northern climates they must be of such construction as will offer the least obstacle to drifting snow and thus prevent as much as possible the blocking of the roadway. In all situations they must be durable and present a pleasing appearance.

The materials employed for fences are earth in the form of mounds either with or without hedges, stone laid dry or in mortar, wood and metal in a variety of forms.

The mound and ditch shown in Fig. 140 is much used in Europe. The material excavated from the ditch is thrown into



FIG. 140. DITCH AND MOUND FENCE.

the mound and a quickset hedge planted along the top. After the lapse of some time this makes a good fence; but it requires in the interim a considerable amount of attention and repair.

In the construction of fences which depend for their support upon posts set in the ground the same considerations should control as in the construction of any other structure, viz., durability of the material, strength, and stability.

The materials employed for the posts or foundations of fences are stone blocks, wood and metal posts.

Stone Posts.—The durability of stone depends upon its chemical constitution and physical structure. If the chemical constituents are soluble in water the stone will be short-lived. If the physical structure is porous the stone will absorb water and under the action of frost will be speedily split and disintegrated. The decay of stone is more rapid at the surface of the earth, where it is exposed to the frequent alternations of wet and dry conditions. The horizontal exposed surface should be cut to such form as will readily shed water. Holes bored for the reception of posts, etc., should be filled with lead, sulphur, etc.; if not they will act as receptacles for water, allowing it to penetrate the interior of the stone and thus hasten its destruction.

Wood Posts.—In the selecting of wood for posts the character of the soil should be considered, as it exercises considerable influence upon the life of the wood. Sand and sandy loam are the least favorable to durability and clay the most favorable. The average life of the woods most commonly used is about as follows: white cedar twelve years; red cedar thirty years; white oak in sand five years, in clay fifteen years; osage orange thirty years; chestnut and tamarac twelve years. Bois d'arc or bodark is very durable; stockades built in Mexico and the Southern States over a hundred years ago are still in a good state of preservation. Well-seasoned timber will last much longer than that which is used while green. Posts obtained from trees which have been subjected to forest fires will absorb water and decay rapidly. Impregnating wood with creosote, chloride of zinc, etc., will about double the life.

Metal posts are to be had in a variety of forms. At this time there are about thirty different styles on the market. All the different shapes in which metal can be wrought have been utilized with varying degrees of success. The life of a metal post depends upon the perfectness with which it is protected from rust. Several coatings are in use, such as coal-tar, asphaltum, graphite, etc., but their lasting qualities and the amount of protection they afford to the metal in the presence of the mineral salts in the earth is a subject of much controversy.

The dimensions of posts must be sufficient to afford the required

strength—for wood 4 inches square or 5 inches in diameter will usually be sufficient; the length of the posts must be ample to allow of their being placed sufficiently deep in the ground to prevent heaving by frost. The spacing of the posts will depend upon the style of fence and ought not to exceed $16\frac{1}{2}$ feet centre to centre.

In localities subject to heavy snowfalls the posts should be spaced at short distances so as to afford strength to support the load of snow. In stapling wire fences in such localities the staples may be driven slanting upwards, so that they will pull out under the weight; then after the snow is thawed the fence may be restapled and restored to its former good condition.

Steel wire for fencing is to be had in a great variety of shapes, as plain, barbed, braided, woven, twisted, crimped, etc. The object of these various shapes is to prevent sagging and provide for the expansion and contraction of the metal under the variations of temperature. But these shapes are not always advantageous. Short bends or kinks, spirals, and coils are objectionable, as in the process of their formation the fibres of the wire are injured and the structure in which they are used is weak and liable to destruction under sudden shock or strain. With regard to the quality of the wire used it should be "medium" steel; if too soft it will stretch under strain and consequently sag and become unsightly; if too "hard" it will be liable to break under sudden shock. The size of wire used is generally No. 12, and it should have a tensile strength of at least 800 pounds.

The wire, in whatever form used, should be protected from oxidation. This is effectually secured by galvanizing, but the wire should not be galvanized before being twisted, barbed, etc., for much of the coating will be cracked and peeled off in the process of shaping, and hence the life of the wire will be lessened.

742. Height of Fences.—The height of the fence will depend upon the purpose for which it is erected. If required to act as a barrier against cattle it should not be less than 4 ft. 9 in.; if as a protection to travellers on the edge of banks, etc., 3 ft. 6 in. will be sufficient; and if for ornamental purpose of such height as may please the fancy. Barbed-wire fences are usually made four feet high; the number of wires used varies from two to five, which are generally spaced as follows:

SPACING OF BARBED WIRES.

	Inches above Ground.			
	Two Wires.	Three Wires.	Four Wires.	Five Wires.
First wire	22	15	16	8
Second "	40	30	25	16
Third "	48	35	25
Fourth "	48	35
Fifth "	48

743. Cost of Fencing.—The cost of a plain or barbed wire fence with wood posts and four strands of wire will be from \$200 to \$250 per mile; a four-strand wire fence with steel posts will cost about \$350 per mile. The cost of woven and other forms of wire with metal posts will vary from \$350 upwards per mile. Common board fence, posts set 8 feet apart, costs from \$350 to \$400 per mile.

An estimate for a mile of barbed-wire fence would be about as follows:

350 posts, including braces, at 10 cents	\$35.00
1700 lbs. barbed wire, at 6 cents	102.00
40 lbs. staples, at 6 cents	2.40
Labor	36.86
Freight, tools, superintendence.	3.07

Total.....\$179.33

TABLE

SHOWING THE AMOUNT OF NO. 12 BARB WIRE REQUIRED TO FENCE VARIOUS DISTANCES.

	1 Rod.	10 Rods.	80 Rods or 1 Mile.	160 Rods or 1 Mile.	320 Rods or 1 Mile.
	Pounds.	Pounds.	Pounds.	Pounds.	Pounds.
One Wire.....	1 $\frac{1}{8}$	10 $\frac{1}{2}$	85	170	340
Two Wires.....	2 $\frac{1}{4}$	21	170	340	680
Three "	3 $\frac{1}{2}$	31 $\frac{1}{2}$	255	510	1020
Four "	4 $\frac{1}{2}$	42	340	680	1360
Five "	5 $\frac{1}{8}$	52 $\frac{1}{2}$	425	850	1700

CHAPTER XVI.

CITY STREETS.

744. THE first work requiring the skill of the engineer is to properly lay out town sites, especially with reference to the future requirements of a large city where any such possibility exists. Few if any of our large cities were so planned. The same principles to a limited extent are applicable to all towns or cities. The topography of the site should be carefully studied and the street lines adapted to it; they should be laid out systematically with a view to convenience and comfort, also with reference to economy of construction, future sanitary improvements, grades, and drainage.

745. Arrangement of City Streets.—Generally straight lines, with frequent and regular intersecting streets, is the best method of laying out streets, especially for business parts of a city. When there is some centrally located structure, such as courthouse, city hall, market, or other prominent public building, it is very desirable to have several diagonal streets leading thereto. In the residence portions of cities, especially if on hilly ground, curves may replace straight lines with advantage by affording better grades at less cost of grading, and improving property by avoiding heavy embankments or cuttings.

746. The rectangular arrangement of streets as seen in New York and other cities is being found objectionable and a bar to convenient communication; it therefore becomes necessary to examine what other systems, if any, may be used, and determine their relative merits. The following investigation of this subject by Mr. Lewis M. Haupt, A.M.C.E., Professor of Civil Engineering, University of Pennsylvania, is very interesting, as showing what may be done in the way of opening diagonal streets:

“The systems may be divided into two classes: 1st, regular, and 2d, irregular. The first class may be subdivided into rectangular, diagonal, and circular; the second into every possible kind of dis-

tortion more or less intricate, according to the circumstances attending the growth of a city. The latter class is discarded as being unscientific, expensive, inconvenient, and poorly adapted to the requirements of a growing community.

"As people move through a city in every conceivable direction, it will be impossible to provide the shortest lines for all; but the case may be met by supposing a greater or less number of centres or points d'appui, to and from which the currents of daily life flow and ebb.

"With reference to the subdivision of the first class, it is evident that, the straight line being the shortest distance between two points, the chord will be shorter than its arc, and hence the circular system is defective. The rectangular compels a waste of distance and time, and the diagonal by itself becomes the rectangular, so that no single system fulfils all possible requirements. A combination must therefore be resorted to, and that composed of right-line elements is both the simplest and most direct. A judicious arrangement of diagonal streets with the rectangular system will doubtless be found to meet more fully than any other the requirements of the case; but it is evident that if the streets be too wide or too numerous, the building areas will be correspondingly decreased and a certain proportion of people forced beyond given limits, thus increasing their distances. On the other hand, the diagonals will in general open new building lines with more than residences enough to provide for all the displaced inhabitants.

"To illustrate the utility of such a combination, suppose a portion of a town or city to be laid out in the form of a square whose side is L feet long, and in which the blocks are l feet square and the streets w feet wide.

"Let the diagonals of the large square be opened as thoroughfares, and note their effect. The blocks or small squares extend from the middle of one street to that of its parallel, or from the building line of one block to that of the next; hence the length of a side of such a square must be $l + w$ (Fig. 141a).

"The area of the small square, including the streets, multiplied by the number of such squares will give the area L^2 of that portion of the city, and the ratio of street to property area is the same for the small as for the large squares; but the area of the small squares is $(l + w)^2 = l^2 + 2lw + w^2$, in which l^2 is the property or build-

ing area, and $2lw + w^2$ is the street area; the ratio being $\frac{2lw + w^2}{l^2}$, and the percentage of street to property area,

$$\frac{2lw + w^2}{l^2} 100. \quad \dots \quad (A)$$




FIG. 141. ARRANGEMENT OF CITY STREETS.

For any rectangle with streets of unequal widths, the general formula would be

$$\frac{bc + ad + bd}{ac} 100, \quad \dots \quad (A')$$

in which a and c are the sides of the rectangle and b and d the widths of the streets. If these quantities are equal, each to each

(A') becomes (A). The number (n) of blocks in a given square whose area is L^2 will be

$$\frac{L^2}{(l+w)^2} = n. \quad \dots \quad (B)$$

"If now two diagonals, \overline{MN} and \overline{PQ} be introduced, it is evident that where they cross the rectangular streets no additional area is taken from the private property of the city, but they will cut out of




FIG. 141a.




FIG. 141b.

each of the small squares which they cross an area whose length is $\sqrt{2}l - \frac{w}{2}$, breadth w , and whose area for one block, l^2 , is $\left(\sqrt{2}l - \frac{w}{2}\right)w$ (see Fig. 141b). For n blocks the total building area consumed from L^2 by both diagonals when n is even will be $2nw \left(\sqrt{2}l - \frac{w}{2}\right)$, and the percentage of the building area will be $\frac{2nw}{n^2 l^2} \left(\sqrt{2}l - \frac{w}{2}\right) \times 100$, which reduces to

$$\frac{w}{n l^2} (2.828l - w) 100, \quad \dots \quad (C)$$

the formula for diagonals when n is even. If n be odd, G becomes

$$\frac{w}{n l^2} (2.828l) 100 = 282.8 \frac{w}{n l}. \quad \dots \quad (C')$$

"If diagonals be opened, benefits will accrue both from the shortening of distance and the additional frontage which will be furnished, while but a small proportion of the inhabitants will be displaced. The greatest economy in distance will be in passing from *M* to *O* (Fig. 141), which by the square system is equal to *L*, and by the diagonal $L\sqrt{\frac{1}{2}}$, the ratio being $\frac{L\sqrt{\frac{1}{2}}}{L} = \frac{1.4142}{2} = \frac{70}{100}$, the numerator indicating the distance (in feet) by the diagonals, the denominator by the squares. This gives a gain of 30 per cent, which is the greatest amount possible, and from which it diminishes to zero at *P*.

"The total length of frontage on the streets in the square system is $4ln$. The diagonals give an additional length of $4n(\sqrt{2}l - w)$, and the percentage of increase is therefore

$$\frac{4\sqrt{2}l - w}{4ln} 100. \dots \dots \dots (D)$$

"The ratio of people displaced is the same as that of the area consumed by diagonals to the entire area L^2 .

"To determine these values for any particular case, and so discover whether or not the diagonals will be beneficial, let $l = 500$ feet, $w = 50$ feet, and $n = 10$.

"Formula (A) gives 21 as the percentage of *large or small* squares consumed by streets in the rectangular system.

"Formula (C) gives only 2.82 per cent of additional building area consumed by diagonals.

"Formula (D) gives 13 per cent as the increase in frontage due to diagonals, and it has been shown that the saving of distance varies from 30 per cent to nothing.

"The number of people displaced, which is only 2.82 per cent, will be abundantly provided for by the additional frontage on the diagonals, revenues will be augmented by assessments on the new buildings erected, and a large saving will be effected in time and distance for a majority of the inhabitants by this combination of systems, which is therefore found to fulfil the requirements of practice more fully than any other.

"Similar applications of the above formula will show to what extent the plans of cities already established or to be built may be




FIG. 142. ARRANGEMENT OF STREETS (PART OF WASHINGTON, D. C.)

improved by the opening of diagonals; the most economical relation of street to building area, the proper distribution of the street area, and, by extending the analysis, the ratio of pavement to carriageway may also be readily determined. All of these questions have a direct bearing on the convenience, health, and extension of our cities."

Fig. 142 shows the system adopted in laying out the streets of Washington, D. C.

747. Width of Streets.—The width of streets should be proportioned to the character of the traffic that will use them; but, as a rule, this has not been considered in the laying out of cities, and the width of the commercial thoroughfares is now found insufficient to properly accommodate the traffic.

No rule can be laid down by which to determine the best width of streets; but it may be safely said that a street which is likely to become a commercial thoroughfare should have a width of not less than 120 feet between the building lines—the carriage-way 80 feet wide, and the sidewalks 20 feet each.

In streets occupied entirely by residences a carriage-way 32 feet wide will be ample, but the width between the building lines may be as great as desired. The sidewalks may be any amount over 10 feet which the fancy may dictate. Whatever width is adopted for them, not more of it than 8 feet need be paved, the remainder being occupied with grass and trees.

Wide streets add materially to the commercial prosperity of the inhabitants of a city by relieving them of the heavy tax imposed by narrow streets on transportation through constantly recurring blockades.

Wide streets afford a good amount of breathing space, and thus add to the general health of the people. Moreover, they contribute to a city an air of spacious comfort and dignified distance, and for all time remove from it the crowded appearance which is too commonly found in all old cities and towns.

748. The maximum and minimum width of streets, with the average width of sidewalks and maximum grade, as at present established in various cities, are given in Table LXXXII.

749. Street Grades.—Following the location of streets, there is the important duty of establishing a comprehensive system of grades. If this could always be done in advance of improvements,

there would be little difficulty in obtaining the best grades for a city. Unfortunately this is seldom the case, and in adjusting the street grades of villages in process of transformation into towns the engineer encounters one of his most trying duties; he meets much opposition from the property-owners who have made improvements based upon the natural slopes, also from those who object to having a street in excavation where it passes through their lands. Each one is looking to his individual interest, and he must exercise much discretion and endeavor to fix a system of grades harmonious, convenient, and economical for the public rather than for individuals.

Every town that expects to thrive should at a very early stage in its history establish the grades of its streets to the full extent of the town plot, and in doing so keep in view the probability of future extension. In new towns this ought to be done when the town is laid out, and the grades might be made part of the original record.

750. No rule can be laid down for determining the proper grades for city streets. They will depend upon the topographical features of the site. The necessity of avoiding deep cuttings or high embankments which would seriously affect the value of adjoining property for building purposes often demands steeper grades than are permissible on country roads. There are, however, certain conditions which it is important to attain: first, that the longitudinal crown level be uniformly sustained from street to street whenever practicable, so as to avoid undulations; second, that the crown level at all intersections be extended transversely to avoid the necessity of driving over a channel, which is otherwise formed.

Table LXXXII shows the maximum grade of streets in several cities.

751. The best arrangement of intersections of streets when either or both have much inclination is a matter requiring much consideration and is one upon which much diversity of opinion exists. No hard or fast rule can be laid down; each will require special adjustment. The best and simplest method is to make the rectangular space *aaaaaaaa*, Fig. 143, level with a rise of one-half inch in 10 feet from *AAAA* to *B*, placing gulleys at *AAAA* and the catch-basins at *cccc*. When this method is not practicable, adopt such a grade (but one not exceeding $2\frac{1}{2}$ per cent) that the rectangle *AAAA*, Fig. 143, shall appear to be nearly level; but to secure this

TABLE LXXXII.
WIDTH OF CITY STREETS.

City of	Width of Streets between Building Lines.		Maximum Grade. Feet per 100 feet.	Average Width of Sidewalks. Feet.
	Maximum. Feet.	Minimum. Feet.		
New York, N. Y.....	100	60	18	15
Brooklyn, N. Y.....	100	60	12	18
Buffalo, N. Y.....	100	40	7	28
Syracuse, N. Y.....	120	33	20	
Elmira, N. Y.....	100	33	5	14
Schenectady, N. Y....	90	20	8	
Boston, Mass.....				7
Lynn, Mass.....	100	50	17.21	8
Worcester, Mass.....	100	20	20	17
Lowell, Mass.....	70	30	16	14
Cambridge, Mass.....	102	26	11.66	8
Chicago, Ill.....	150	30	2.40	25 to 4
Bloomington, Ill.....	100	30	4.80	
Jersey City, N. J.....	80	30	14	
Camden, N. J.....	100	26	8	15
Newark, N. J.....	132	40	10	10
Trenton, N. J.....	80	30	8	16 to 6
Paterson, N. J.....	120	40	17	
Terre Haute, Ind.....	99	50	5	
Richmond, Va.....	118	30	3	
Omaha, Neb.....	120	40	15	13
Nashville, Tenn.....	104	20	11	17
Parkersburg, W. Va.....	60	40		
Washington, D. C.....	160	30		
Wilmington, N. C.....	99	30	9	17
Seattle, Wash.....	120	60		16 to 8
Philadelphia, Pa.....	120	30	16	
Pittsburg, Pa.....	100	30	15½	½ width of st. 20 to 12
Erle, Pa.....	100	50		½ width of st.
Harrisburg, Pa.....	120	20	7	“ “
Providence, R. I.....	225	10	19	
Cumberland, Md.....	65	20	10	
Hartford, Conn.....	70	25	6	6 to 4
Waterbury, Conn.....	160	28	13	6
New Haven, Conn.....	100	40	12	20 to 8
Detroit, Mich.....	120	36	5	20 to 6
Grand Rapids, Mich.....	100	50	12	12 to 4
St. Paul, Minn.....	200	50		
Minneapolis, Minn.....	120	60		27
Bucyrus, Ohio.....	82½	40		16
Salt Lake City, Utah.....	132	50	15	20 to 6
Ogden, Utah.....	132	60	12.88	16 to 10
Burlington, Vt.....	99	28	10.70	
Rutland, Vt.....	99	49½	10	12 to 6
Milwaukee, Wis.....	100	60	9	25 to 12
* London, Eng.....	80	12	4	15 to 3
* Birmingham, Eng.....	80	15	9	8

* Foreign cities for comparison.

WIDTH OF CITY STREETS—*Continued.*

	Feet.
Berlin : Unter den Linden	196
Leipziger Strasse.....	72
König Strasse.....	57
Brussels: Le Boulevard Circulaire.....	220
Le Boulevard Ansbach.....	91
Le Rue Royale.....	65
Paris : Rue de Rivoli.....	88
Grands Boulevards.....	114
Avenue des Champs Élysees.....	229
Avenue Bois de Boulogne.....	898
Vienna: Ringstrasse	187
Hauptstrasse.....	

it must actually have a considerable dip in the direction of the slope of the street. If steep grades are continued across intersections, they introduce side slopes in the streets thus crossed, which are troublesome, if not dangerous, to vehicles turning the corners, especially the upper ones. Such intersections are especially objectionable in rainy weather. The storm water will fall to the lowest point, concentrating a large quantity of water at two receiving-basins, which with a broken grade could be divided between four or more basins.




FIG. 143. ADJUSTMENT OF GRADES AT STREET-INTERSECTIONS.

752. Fig. 144 shows the arrangement of intersections on steep grades proposed by Messrs. Rudolph Hering and Andrew Rosewater for the streets of Duluth, Minn. From this it will be seen that at

these intersections the grades are flattened to three per cent for the width of the roadway of the intersecting streets, and that the grade of the curbs is flattened to eight per cent for the width of the intersecting sidewalks. Grades of less amount on roadway or sidewalk are continuous. The elevation of block-corners is found by adding together the curb elevation at the points facing the block-corner, and also the sum of the widths of the two sidewalks at the corner multiplied by two and one half per cent, and dividing the whole by two. This gives an elevation equal to the average elevation of the curbs opposite the corner plus an average rise of two and one half per cent across the width of the sidewalk.




Fig. 144.

753. The instructions of the Department of Public Works of New York contain the following directions for regulating grades at street-intersections:

"In calculating the grades from the centre of the intersection to the circular corners or curb-lines, they will be established as follows: In the avenues when the ascents and descents of the cross

intersecting streets exceed 1 inch in 10 feet, the grade will be calculated at 1 inch in 10 feet to the curb-line from the centre, making 6 inches difference in the curbs on opposite sides of the avenues, and the slopes up and down the avenues will be calculated according to the grade of the avenue, let the same be more or less."

"Apexes and punch-bowls to be set into the curb-line at the same height as the centre grade."

754. Accommodation summits have to be introduced between street-intersections, first in hilly localities to avoid excessive excavation, and second when the intersecting streets are level or nearly so, for the purpose of obtaining the fall necessary for surface-drainage.

The elevation and location of these summits may be calculated as follows: Let *A* be the elevation of the highest corner, *B* the elevation of the lowest corner, *D* the distance from corner to corner, and *R* the rate of the accommodation grade. The elevation of the summit is equal to


$$\frac{D \cdot R + A + B}{2}.$$

The distance from *A* or *B* is found by subtracting the elevation of either *A* or *B* from this quotient and dividing the result by the rate of grade. Or the summits may be located mechanically by specially prepared scales. Prepare two scales divided to correspond to the rate of grade—that is, if the rate of grade be one foot per hundred feet, then one division of the scale should equal 100 feet on the map scale. These divisions may be subdivided into tenths. One scale should read from right to left, and one from left to right.

To use the scales, place them on the map so that their figures correspond with the corner elevations; then as the scales read in opposite directions there is of course some point at which the opposite readings will be the same: this point is the location of the summits, and the figures read off the scale its elevation. If the difference in elevation of the corners is such as not to require an intermediate summit for drainage, it will be apparent as soon as the scales are placed in position.

755. Sufficient fall for surface drainage may be secured without the aid of accommodation summits, by arranging the grades as shown in Fig. 145. The curb is set level between the corners, a summit is

formed in the gutter, and receiving-basins are placed at the centre and each corner.



Fig, 145;

SHOWING CROWN IN STREET GUTTER.

756. Transverse Grade.—In transverse grade the street should be level; that is, the curbs on opposite sides should be at the same level, and the street crown rise equally from each side to the centre. But in hill-side streets this condition cannot always be fulfilled, and opposite sides of the street may differ as much as five feet; in such cases the engineer will have to use his discretion as to whether he will adopt a straight slope inclining to the lower side, thus draining the whole street by the lower gutter, or adopt the three-curb method and sod the slope of the higher side.

In the improvement of old streets with the sides at different levels much difficulty will be met, especially where shade-trees have to be spared. In such cases recognized methods have to be abandoned, and the engineer will have to adopt methods of overcoming the difficulties in accordance with the condition and necessities of each particular case.

As an example of what may be done in such cases the methods adopted by Mr. J. T. Desmond, City Engineer of Haverhill, Mass., may be cited.

In Fig. 146 is shown a street 66 feet wide, with one sidewalk



Fig. 146.



Fig. 147.

5 feet higher than the other. In order to get a fair cross-section a third line of curbing was put in at the crest of the slope, and the slope between the two curbs sodded. This produces a very pleasing effect.

In Fig. 147 the same conditions exist, but only two lines of curbing are used, the slope being sodded in the same manner as in the first case.

Again, it often happens that two parallel streets are laid out with sharp descending grades, and later on the city is called upon



Fig. 148.

ARRANGEMENT OF STREETS WITH OPPOSITE SIDES AT DIFFERENT LEVELS.

to accept a new street laid out between them. The method shown in Fig. 148 is adopted.

757. Transverse Contour.—The most suitable form of transverse contour and proper rise for each kind of pavement are given in Articles 618 and 619, Chapter XII.

758. Sub-foundation Drainage of Streets.—The sub-foundation drainage of streets cannot be effected by transverse drains, because of the liability of their disturbance by the introduction of gas, water, and other pipes.

Longitudinal drains must be entirely depended upon; they may be constructed of the same materials and in the same manner as road drains. The number of these longitudinal drains must depend upon the character of the soil: if moderately retentive, a single row of tiles or a hollow invert placed under the sewer in the centre of the street will generally be sufficient, or two rows of tiles may be employed, one placed at each curb-line; if the soil be exceedingly wet and the street very wide, four or more lines may be employed. These drains may be permitted to discharge into the sewers of the transverse streets (Fig. 149.)




Fig. 149.

SECTION OF SUBURBAN STREET, SHOWING BROKEN-STONE ROADWAY, PAVED GUTTER, TILE-DRAIN, AND GRAVEL WALK.

759. Surface Drainage.—The removal of water falling on the street surface is provided for by collecting it in the gutters, from which it is discharged into the sewers or other channels by means of catch-basins placed at all street intersections and dips in the street grades.

760. Gutters.—The gutters must be of sufficient depth to retain all the water which reaches them and prevent its overflowing on the footpath. The depth should never be less than 6 inches, and very rarely need be more than 10 inches.


In streets paved with granite, wood, and brick, gutters are formed of the same material. When the street is paved with asphalt the gutter may be formed either of asphalt, recoated with bitumen, or with granite blocks or gutter stones. The width of this paving need not exceed 12 inches.

In streets where broken stone is used the gutters may be formed with gutter stones of granite blocks.

761. Catch-basins are of various forms, usually circular or rectangular, built of brick masonry coated with a plaster of Portland cement. Whichever form is adopted, they should fulfil the following conditions:

- (1) The inlet and outlet to have sufficient capacity to receive and discharge all the water reaching the basin.
- (2) Sufficient capacity below the outlet to retain all sand and road detritus, and prevent it being carried into the sewer.
- (3) Trapped so as to prevent the escape of sewer-gas. (This

EXAMPLES OF CATCH-BASINS.



SECTION.




FIG. 150. P_LAN.




FIG. 151. GUTTER BASIN.




FIG. 152. CORNER BASIN.




FIG. 153. EARTHENWARE BASIN.

requirement is frequently omitted, to the detriment of the health of the people.)

- (4) Constructed so that the pit may be easily cleaned out.
- (5) Inlet not easily choked by leaves or débris.
- (6) Offer the least possible obstruction to the traffic.
- (7) The pipe connecting the basin to the sewer should be easily freed of any obstruction.

Figs. 150 to 153 show various forms of catch-basins.

The bottom of the basins should be 6 or 8 feet below the street level, and the water level in them should be from 3 to 4 feet lower than the street surface, as a protection against freezing. The capacity and number of basins will depend upon the area of surface which they drain.

In streets having level or light longitudinal grades gullies may be formed along the line of the gutter at such intervals as may be found necessary. Catch-basins are usually placed at the curb-line of the street. A departure from this practice has been made in several cities, notably at Providence, R. I., and Rockford, Ill., where from two to six inlets are placed at the curb line of the corner and lead to a combined basin and manhole in the centre of the street. This reduces the cost of construction and of cleaning, and removes from the sidewalk the dirty operation of cleaning the basins.

761a. Catch-basins and gully-pits require to be cleaned out at frequent intervals, otherwise the odor arising from the decomposing matter contained in them will be very offensive. No rule can be laid down for the intervals at which the cleaning should be done, but they must be cleaned often enough to prevent the matter in them from putrefying. There is no uniformity of practice observed by cities in this matter; in some the cleansing is done but once a year, in others after every rain-storm, in still others at intervals of three or four months, while in a few they are cleaned out once a month.

The *methods* employed for removing the silt from the basins vary greatly. In many cities the matter is removed by ladling it out with scoops, hoes, and shovels; in a few a laborer enters the basin with an ordinary bucket, which he fills with the silt, while another laborer at the surface hauls it up and empties it into a cart or into the street-surface, to be removed later on. In this method the cleaning gang generally consists of two men and a cart, or three men and

two carts, and from six to twelve basins can be cleaned per day, depending upon the amount of material to be removed and the distance to the place of disposal.

In many cities mechanical appliances are employed for raising the buckets filled with silt. These consist either of a windlass, a tripod with a block and tackle, or a block and tackle suspended from a movable arm attached to the body of the wagon used for conveying the extracted silt.

In Wilmington, Del., the basins are furnished with metal buckets which entirely fill the space below the outlet-pipe. To clean the basin the bucket is hoisted out by a block and tackle suspended from a tripod, is emptied, and returned to its place in the basin.

The pneumatic or vacuum system of removal has been recently experimented with at Columbus, Boston, and other cities, and works very well except upon basins which have been filled with very hard material from macadamized streets. The apparatus consists of a large, air-tight, iron tank, mounted on a wagon. Two air-pumps, driven by eccentrics from the rear axle, are connected with the tank, and as the wagon is driven along the street these pumps exhaust the air in the tank and produce a vacuum. A 5-inch suction-hose, the end of which has a bell-shaped mouth, is connected with the tank by a coupling and valve. Upon arriving at the catch-basin to be cleaned, the suction-hose is inserted in the semi-liquid mass, the valve is opened, and the contents of the catch-basin are drawn into the tank. This operation is repeated at the different catch-basins until the tank is filled, when it is taken to the place of disposal. During the whole of this process the tank is hermetically sealed, thus preventing the escape of unpleasant odors.

In some cities the cleaning is done by contract, in others by the employees of the street-cleaning department. In many places the cleaning is performed in the most perfunctory manner; in others scrupulous care is exercised, the walls of the basin being washed and scrubbed with a broom, water, and a disinfectant.

The *cost* of cleaning varies greatly, ranging from twenty-five cents to five dollars per cleaning.

The material removed from the basins is disposed of in different ways. In New York it is sent out to sea; in New Orleans it is used for filling in low lands.




FIG. 153A.

Fig. 153a illustrates the type of catch-basin standard at Columbus, O. The sewer connection means of a 15-inch vitrified-pipe drain, termed a special elbow of the form shown. This elbow is used when the basin is filled to the flow-line level. The pipe, resting over a 6 1/4-inch hole enables the pipe to be removed if necessary. The interior of the basin is coated with an inch coat of cement mortar. The bill of material for a catch-basin of the dimensions shown is as follows: cubic yards; brick, 900; cement, two barrels; cast-iron cover and lid, 340 pounds; 15-inch vitrified-pipe and special elbow.

The manhole cover used with this type of

top with projecting piece at one part of the circumference. This projection forms the continuation of the curb-line, and within it is the street inlet, $22\frac{1}{2}$ inches long and $6\frac{1}{2}$ inches wide. The cover is made of a $\frac{3}{4}$ -inch top plate and $\frac{1}{2}$ -inch sides and bottom flange. The lid is 20 inches in diameter and made of $\frac{3}{8}$ -inch metal.

762. Surface Drainage at Street Intersections.—The surface waters should not be carried across street intersections if it can be possibly avoided, but cases may arise where such has to be done.




FIG. 153B. SEWER INLET WITHOUT BASIN.

Where it is necessary, it can be accomplished as shown in Figs. 154 and 155.

Waterways formed as shown in Fig. 156 should not be constructed: they are a nuisance, and an obstacle to traffic.

763. Street Lines and Monuments.—In the engineering department of every city there should be adopted and carried into effect a system of permanent street monuments, whereby the street lines may be accurately relocated at any time, even a century after the original survey was made. In the absence of such a system, it is



Fig 154. SECTION.




Fig 155. PLAN.



Fig. 156.

OBJECTIONABLE FORM OF WATERWAY AT STREET-CROSSINGS

impossible to accurately retrace the original survey. With the improvements continually in progress old landmarks are swept away, and the reproduction of former lines is largely a cut-and-try process, involving a great deal of work which is productive of only approximate results.

The remedy lies in placing at all street corners substantial stone monuments, and protecting them by special ordinance against disturbance by persons excavating in the streets.

The monuments should not be less than 4 feet long, 12 inches square on the bottom, and 6 inches square on the top; the top surface and 4 inches of each face down from the top should be hammer-dressed. The monuments should be set with the upper surface flush with the surface of the sidewalk or a few inches below, but so placed as to be easy of access. They should be set at a fixed distance from the building line—say 5 feet. If set below the level of the footway pavement, a hole may be cut in the pavement and closed with a cast-iron frame and movable cover flush with the surface of the pavement. (See Fig. 157.)

The intersections of the lines can be accurately cut upon the top surface, or a small hole may be drilled at the intersection of the lines, filled with lead, and the point marked with a centre-punch.




FIG. 157.—SHOWING MONUMENTS AND MANNER OF PLACING.

764. Monuments.—For defining the lines of country roads. The monuments to be of roughly dressed stone, about 5 feet long, 16 inches square at the base and tapering toward the top, with the

upper foot dressed to 8 inches square; the monument to be set in a pit 3 feet square and 4½ feet deep; the space around the stone to be filled with small stones, gravel, or earth, solidly packed in thin layers. The top of each stone marked with its diagonals, and its number cut on one of the faces which project above ground.

765. Street Profiles.—The following instructions of the Department of Public Works, New York, in regard to street profiles may be useful.

The drawings to be made on a horizontal scale of 40 feet and a vertical scale of 8 feet to the inch, and to be colored and figured as hereinafter indicated, with an explanatory legend.

For streets 60 feet wide and under there will be three profiles, one on each side and one intermediate through the centre of the street, to be shown in plan and elevation. For streets more than 60 feet wide, two additional profiles will be required, one through each curb- and gutter-line (to be drawn in plan only, not in elevation).

The established grade-line will be shown on the elevation only. Vertical heights above the high-water line will be given at least every 50 feet for the established grade-line and for the several lines of profile; the former on the elevation and the latter on the plan.

The plan will be drawn below the profile.

The colors used will be as follows:

Line of high-water (datum).....	Blue
Vertical height-lines.....	Black
Established grade-line.....	Red

Natural surface as follows:

South line of streets	}Orange
West line of avenues		
North line of streets	}Green
East line of avenues		
North curb of streets	}Burnt Sienna
East curb of avenues		
South curb-line of streets	}Blue
West curb-line of avenues		
Rock to be colored with.....		India ink
Earth " "	Orange
Flagging " "	Blue




FIG. 159. ROUND CORNER.




FIG. 158. TYPICAL CORNER.

When earth and rock occur the surveyor will be required to designate upon the original plan the outline of the intersection of the rock, when the same shall be developed by a plan parallel to and two feet below the established grade.

766. Increasing the Width of the Carriageway at Street-crossings.—Experience has proven the value of the London practice of widening the carriageway at street-corners and the providing of refuges or resting-places for pedestrians. Fig. 158 shows a typical street-corner, and Fig. 159 shows the widened corner and refuges.

Travel is always slower and somewhat congested at crossings, and the widening of the wheelway at these points expedites its movement; while the refuges, besides keeping the traffic on its proper side of the street, are of great convenience to pedestrians crossing the street. These refuges are usually 4 feet wide and about 12 feet long, and are elevated above the street surface; they are bordered by curb-stones, and in the centre is generally an ornamental lamp-post, indicating its position and carrying the street signs.

Another consideration in favor of these corners is the opportunity they present for ornamental façades, that add to the beauty of the city.

767. Street Statistics.—The following table shows the length of streets for each of fifty of the largest cities in the United States, with the amount paved and unpaved, the number of miles of streets lined with shade-trees, extent of grassed places or parking along the streets, the number of miles of streets to each square mile of area, the percentage of street area to the area of the city, and the number of population to each mile of streets for the year 1890.

TABLE LXXXIII.

Cities.	Streets.				Miles of Streets Lined with Shade Trees.	Grassed Places.		Miles of Streets to each square mile of Area.	Per cent of Street Area to City Area.	Number of Population to each mile of Streets.
	Length in miles.			Length (miles).		Average Width (feet).				
	Total.	Paved.	Graded and Curbed only.							
New York, N. Y.	575	358	45	62.26				14.30	16.35	2,635.31
Chicago, Ill.	3048	629	1419	30.71	1200	1300	7	12.75	15.94	537.08
Philadelphia, Pa.	1151	750	50	65.16				8.90	8.43	909.61
Brooklyn, N. Y.	653	375	3	57.43	183	300	5	24.68	32.72	1,234.88
St. Louis, Mo.	1061	422	40	39.77	50	30	10	17.29	19.65	425.80
Boston, Mass.	408	408		100.00				11.56	8.78	1,099.21
Baltimore, Md.	750	459	100	58.55	100			27.48	34.36	556.97
San Francisco, Cal.	342	92	190	26.90				22.12	28.91	874.26
Cincinnati, Ohio	496	264		52.26				19.44	18.41	610.92
Cleveland, Ohio	462	69	129	14.94				18.57	22.21	565.70
Buffalo, N. Y.	372	194		52.15	200	350	10	9.53	10.47	687.27
New Orleans, La.	625	89	261	14.24	25	30	30	16.85	19.15	357.26
Detroit, Mich.	400	147		36.75		360	15	19.43	20.97	514.69
Milwaukee, Wis.	419	72	6	17.18	349			24.65	35.01	487.99
Washington, D. C.	235	163		69.36	230	230	20	22.95	43.46	563.74
Newark, N. J.	186	48	138	25.81				10.47	11.89	977.58
Minneapolis, Minn.	800	25	4	3.13		400	4	15.48	23.48	205.92
Omaha, Neb.	508	52	41	10.24		10	6	20.73	25.92	276.48
Rochester, N. Y.	940	72	72	30.00				15.38	14.57	557.90
St. Paul, Minn.	970	40	325	4.12	50	28	36	18.86	21.44	137.27
Denver, Col.	756		756					48.31	73.95	141.13
Indianapolis, Ind.	400	234	16	58.50	234	234	6	39.72	56.42	263.59
Worcester, Mass.	195	195		100.00	150			5.73	5.43	434.13
Toledo, Ohio.	438	60	220	13.70	70	25	12	22.21	27.76	185.92
New Haven, Conn.	140	32		22.86				13.52	21.04	580.70
Lowell, Mass.	105	19	1	18.10	79			9.42	8.92	739.96
Nashville, Tenn.	251	147		58.57	50	150	20	29.74	26.16	303.46
Fall River, Mass.	106	2	79	1.89				9.68	9.17	101.87
Cambridge, Mass.	79	23		29.11				13.55	12.88	886.43
Camden, N. J.	100	31	30	31.00	50	1	30	23.04	26.18	583.13
Trenton, N. J.	100	7	50	7.00	75	5	5	25.32	28.77	574.58
Lynn, Mass.	125	82	30	65.60	20			11.75	11.13	445.88
Hartford, Conn.	130	80	50	61.54	91	91	15	8.77	11.76	409.46
Evansville, Ind.	136	33	52	24.26	6	1	12	30.77	40.79	373.21
Los Angeles, Cal.	800	88	76	10.38		80	30	28.99	32.94	62.99
Lawrence, Mass.	82	75		91.46				12.29	11.64	544.56
Hoboken, N. J.	30	17	3	56.67	9			20.41	22.42	1,454.93
Dallas, Tex.	529	25	66	4.73	15	15	2	68.88	78.27	71.96
Sioux City, Iowa	340	14	75	4.12	45	90	8	11.00	16.67	111.19
Portland, Me.	56	9	43	16.07	49	3	10	22.31	21.13	650.45
Holyoke, Mass.	50	50		100.00		12	4	12.56	14.28	712.74
Binghamton, N. Y.	80	4	70	5.00	50	50	4	7.97	7.55	437.56
Duluth, Minn.	224	35	20	15.63		23	10	69.35	66.69	147.63
Elmira, N. Y.	90	43	5	47.78	45	85	6	20.22	21.07	330.00
Davenport, Iowa	140	26	79	18.57	30	5	6	31.75	42.09	191.94
Canton, Ohio.	150	5	115	3.33	150	16	8	22.06	25.07	174.59
Taunton, Mass.	200	170	20	85.00				4.22	3.20	127.24
Lacrosse, Wis.	125	15	110	12.00	20	20	7	15.26	19.04	300.72
Newport, Ky.	30	27	3	90.00	25	2		25.00	31.25	690.60
Rockford, Ill.	120	31	50	25.83	60	96	5	18.84	23.55	194.53

CHAPTER XVII.

FOOTPATHS, CURBS, GUTTERS.

768. A FOOTPATH or walk is simply a road under a road for pedestrians instead of one for horses and the only difference that exists is in the degree of service the conditions of construction that render a road and its object are very much the same as those required.

The effects of heavy loads such as use carried are felt upon footpaths, but the destructive action of wheels is the same in either case, and the treatment to counteract these elements as far as practicable and produce perfect results should be the controlling idea in each case, and should be upon a common principle. It is not less essential that the surface should be well adapted to its object than that a road should be so, and it is annoying to find it impassable or insecure when it is needed for convenience or pleasure. In the case of economy there is the same advantage in constructing a road skilfully and durably as there is in the case of a road.

769. Width.—The width of footwalks (exclusive of the space occupied by projections and shade-trees) should be sufficiently wide to comfortably accommodate the number of people using them. In cities devoted entirely to commercial purposes the clear width should be at least one third the width of the carriageway; in suburban streets a very pleasing result may be obtained by making the walks one half the width of the roadway and reserving the greater part to grass and shade trees.

The width adopted for sidewalks in several cities is given in Table LXXXII, page 388.

770. Cross-slope.—The surface of footpaths should be so constructed that the surface-water may readily flow to the gutter.

need not be very great; $\frac{1}{8}$ inch per foot will be sufficient. A greater slope with a thin coating of ice upon it becomes dangerous to pedestrians.

771. Foundation.—As in the case of roadways so with footpaths, the foundation is of primary importance. Whatever material may be used for the surface, if the foundation is weak and yielding the surface will settle irregularly and become extremely objectionable, if not dangerous, to pedestrians.

772. Surface.—The requirements of a good covering for sidewalks are:

- (1) It must be smooth but not slippery.
- (2) It must absorb the minimum amount of water, so that it may dry rapidly after rain.
- (3) It must not be easily abraded.
- (4) It must be of a uniform quality throughout, so that it may wear evenly.
- (5) It must neither scale nor flake.
- (6) Its texture must be such that dust will not adhere to it.
- (7) It must be durable.

773. Materials.—The materials used for footpaths are as follows: stone natural and artificial, wood, asphalt, brick, tar concrete, and gravel.

774. Of the natural stones, sandstone (bluestone) and granite are extensively employed.

The bluestone when well laid forms an excellent paving material. It is of compact texture, absorbs water to a very limited extent, and hence soon dries after rain; it has sufficient hardness to resist abrasion, and wears well without becoming excessively slippery. It can be obtained in flags of almost any size and thickness. As found in the quarries, the layers of stone range from 1 inch to 3 feet in thickness, the top beds being usually the thinner. The size of the blocks in superficial area varies; frequently blocks 60 feet long by 20 feet wide and 10 inches thick are lifted from the bed. The largest slab as yet brought to tide-water was 20 × 24 feet and 10 inches thick, and there are slabs used for flagging in New York 15 by 20 feet by 8 inches.

Granite, although exceedingly durable, wears very slippery and its surface has to be frequently roughened.

775. Slabs of whatever stone must be of equal thickness

throughout their entire area; the edges must be dressed true to the square for the whole thickness (edges must not be left feathered as



FIG. 160. IMPROPER MANNER OF DRESSING THE EDGES OF CROSSING-STONES AND FLAGSTONES.

shown in Fig. 160); and they must be solidly bedded on the foundation and the joints filled with cement-mortar.

Badly set or faultily dressed flagstones are very unpleasant to walk over, especially in rainy weather; the unevenness causes pedestrians to stumble, and rocking stones squirt dirty water over their clothes.

776. Specifications for Flagstones, (New York).—Flagstones shall be of the best quality of North River bluestone, 4 feet wide, not less than 3 inches thick, and to contain not less than 12 superficial feet. The edge shall be dressed the whole depth of the stone, so as to lay close joints, and the top shall be cut evenly, so as to leave no depressions. Flagging shall be laid in four inches of sand or clean gritty earth, and the joints closed with cement-mortar.

777. Wood has been largely used in the form of planks; it is cheap in first cost, but proves very expensive from the fact that it lasts but a comparatively short time and requires constant repair to keep it from becoming dangerous.

778. Asphalt forms an excellent footway pavement; it is durable and does not wear slippery. It is largely employed for this purpose in Europe.

The proportions of materials employed in Paris are given as follows:

Bituminous rock.....	1456 pounds
Bitumen	68 "
Sand.....	784 "

This requires about 225 pounds of coal to heat it, and one workman can prepare 3 tons of material in 12 hours.

The following table gives the number of square yards that a ton of prepared rock-asphalt will spread:

TABLE LXXXIV.

Without Grit. Square yards.	With about 25 per cent of Grit. Square yards.	Thickness. Inches.
63	80	$\frac{3}{4}$
51	65	$\frac{1}{2}$
32	40	$\frac{1}{4}$
26	33	1
16	20	$1\frac{1}{2}$
$12\frac{1}{2}$	16	2

A skilled workman properly assisted can lay 140 to 180 square yards in a day.

779. The life of asphalt footways may be taken at about twelve years under ordinary traffic. The concrete will remain untouched, and what is left of the asphalt may be remelted, so that a renewal is not so costly as the first expense.

Compressed-asphalt paths have lasted ten years in some of the busiest thoroughfares of London. In Leicester, uncompressed-asphalt paths have lasted fifteen years under considerable traffic.

The thickness of the asphalt should not be less than one inch.

780. Specifications for Sheet-asphalt Footway Pavements (Washington, D.C.)

Grading.—The space over which the sidewalk is to be laid will be graded to a depth of 3 inches below the finished surface of the pavement. Soft and spongy places not affording a firm foundation will be removed and good, clean gravel substituted therefor. The bed thus prepared will be thoroughly rolled and rammed to the satisfaction of the Engineer or his authorized representative.

Tree-spaces.—A space of such dimensions as may be directed by the Engineer Commissioner (usually 2 by 4 feet) will be left around each tree. Around the edges of this space will be planted a framework of Georgia pine, 2 inches in thickness and 9 inches in depth. The plank forming the rear of the framework, and which is parallel to the curb, will be firmly nailed to the other two pieces, and will be cut in such a manner that it will bind underneath the pavement to be laid, so that the top edges will be even with the pavement when completed. In the spaces between the framework and the sides of the trench coarse sand will be placed and compacted by tamping with narrow rammers especially constructed for

this purpose. These spaces will be then filled to the sub-grade of the pavement, and the tree-spaces will be filled with earth and left in a neat and clean condition.

Base.—On the bed prepared as above specified a layer of clean broken stone, of size not exceeding $\frac{3}{4}$ inch in largest dimensions, will be spread to a depth of $2\frac{1}{2}$ inches. This will be compressed by rolling and tamping to a thickness of 2 inches. On this will be poured, at a temperature of about 250 degrees Fahr., the residuum of coal-tar distillation known in the trade as No. 4 Paving Composition. About $\frac{1}{4}$ gallon of this composition will be used for each square yard of pavement, and it will be poured on the base of broken stone in such manner as to thoroughly coat the stones on the surface and fill the interstices thereof.

Wearing Surface.—The cementing material of the wearing surface will be asphalt paving-cement prepared from the best quality of Trinidad asphalt, obtained from the so-called Pitch or Asphalt Lake in the island of Trinidad, and the residuum of petroleum distillation, mixed in the proportions of about six parts of refined asphalt and one part of residuum. With this paving-cement will be combined the old asphalt pavement from Pennsylvania Avenue or elsewhere, and crushed granular limestone quartz or other stone of a white color, in the following proportions:

Old pavement.....	69 to 76 per cent
Crushed stone.....	26 to 15 “
Asphalt cement as above specified.....	5 to 9 “
	<hr/>
	100 100 per cent

The old pavement will be furnished by the District at the property yards near the foot of New Hampshire Avenue; the other materials will be furnished by the contractor. The crushed stone in the wearing surface will vary in size from $\frac{1}{4}$ of an inch to dust.

The asphalt pavement will be broken into pieces not exceeding 4 inches in their largest dimensions, and will then be mixed with the crushed stone in the proportion of about 4 parts of asphalt pavement to one part of crushed stone. This mixture will then be heated to a temperature of about 300 degrees Fahr. in a suitable apparatus, and thoroughly mixed and made homogeneous by stirring, special care being taken not to overheat the material or

burn the asphalt. During the progress of mixing, asphalt cement will be added in the proportion of 5 per cent to 9 per cent by weight of the mixture; the exact proportion of asphalt cement thus to be added for the purpose of enriching the old pavement will be determined by the Engineer Commissioner.

The material thus prepared will be brought to the work at a temperature of 250 degrees to 275 degrees Fahr., and will be spread on the base above specified by means of hot iron rakes to a thickness of $1\frac{1}{2}$ inches, and will then be compressed by rolling and ramming to the thickness of 1 inch. A small amount of hydraulic cement will then be spread over the surface, and the rolling will be continued until the pavement is thoroughly compressed. Care shall be taken at all times not to interfere with business or travel more than is absolutely necessary for the faithful performance of the work. During the time that travel is necessarily closed at any point the contractor shall provide temporary walks, said walk to be at all times in condition for pedestrians, and easy of access from adjoining walks. The contractor shall remove all stone, plank, brick, or other material of value from points where the sidewalks are to be laid, as the work progresses, and shall haul them to the nearest property yards, or otherwise dispose of them, as the Engineer Commissioner may desire.

Curb.—Whenever ordered the curb will be reset. Curb will be redressed by the contractor whenever ordered, for which a fair price, to be fixed by the Engineer Commissioner, will be paid.

781. Extracts from Specifications for Asphalt Footway Pavements (Paris).

Form and Dimensions of Work.—Art. 7. The width of the sidewalks for each locality will be determined by the administration, its slope by the engineer. The curb between the sidewalk and the roadway will not be included in this contract.

Art. 16. The mastic pavements will be formed of a layer of pure asphaltic mastic at least $\frac{1}{8}$ inch thick, resting on a bed of hydraulic concrete 4 inches thick which comprises a covering of hydraulic mortar at least $\frac{3}{8}$ inch thick.

Art. 17. The compressed-asphalt pavements will consist of an upper layer of compressed asphalt $1\frac{1}{2}$ to $2\frac{1}{8}$ inches thick, resting on a foundation of hydraulic lime or cement concrete 4 to 6 inches thick, covered as above with mortar, or upon an old macadam road-

way picked over and covered with a thin coat of hydraulic mortar.

Art. 21. The asphaltic mastic employed either for new or repairing old paving shall be composed of naturally impregnated rock with natural bitumen of good quality, coming exclusively from mineral rocks.

The *fictional* bitumens extracted by the purification of the heavy oils or schists and by the distillation of coal, also the so-called fatty bitumens, and all other analogous products shall be rigorously proscribed.

The rock employed after being reduced to powder will be melted with a sufficient quantity of purified natural bitumen to form a mastic which, when cold, presents a homologous mass slightly elastic and which does not soften under a hot sun. This mastic shall be moulded into blocks. There may also be used blocks of bituminous mastic with a base of slates manufactured by the process of M. Seville.

Art. 22. The contractor shall be bound to employ under the orders of the engineers upon each public way the bituminous mastic above described.

The mastic shall be formed of a mixture of natural bitumen, in the proportion of one twelfth of its weight at most, and the calcareous asphalt rocks of Seyssel, Seyssel-Forens, Pyrimont or Volants, of Val de Travers or Lobsan, or others deemed equivalents by the engineers.

The mastic having a base of slate of M. Seville will be formed of a mixture of bitumen described in Art. 23 following, and of powdered red or blue slate of Ardennes, powdered chalk of Mendon or of Nanterre, and of silica from the basin of Paris, in the following proportions by weight:

Refined mineral bitumen.....	80 parts
Ground slate.....	85 "
Powdered chalk.....	10 "
Silica, ground and sifted.....	25 "
	<hr/> 100 parts

Art. 23. The bitumen shall come as much as possible from the weighings of bituminous sandstone or the asphaltic rock of Maestru, and in their default from the dry pitch of Trinidad, perfectly puri-

fied. It ought to be viscid at the ordinary temperature, never brittle or liquid; drawn into threads it should lengthen and only break in very fine points.

Art. 24. The rock employed should be calcareous, soft, with fine grain, texture fairly compact, regularly impregnated with bitumen so as not to show black and white spots; it should be of a brown color; heated to 122 to 140 degrees Fahr. it should soften and break on being torn. Care must be taken for the area in asphalt to choose only such pieces as are of the most even grain and richest impregnation. The rock of Lobsan, however, should not be employed alone in the asphalt roadways; it ought to be mixed with other rocks less fat, in proportions which will be determined by the engineer according to the composition of the other rocks. It should contain at least 7 per cent of bitumen and at the most 93 per cent of lime; its change into mastic must not require more than 9 per cent of bitumen.

Art. 25. The materials entering into the composition of the pavements are the mastics described in Art. 22; pure gravel grit and natural bitumen to assist the melting. These materials ought to be generally employed in the following proportions by weight:

Foot-pavements with a base of asphalt	{ Asphaltic mastic.....	100
	{ Bitumen.....	6
	{ Grit....	60
Foot-pavements with a base of slate....	{ Asphaltic mastic.....	100
	{ Bitumen.....	7
	{ Gravel.....	50

Art. 26. One month before the award of this contract the competitors must deposit at the office of the works in Paris samples of, 1st, a block of the mastic described above; 2d, specimens of the asphaltic rocks and the natural bitumens they intend to use; 3d, a note indicating the elements of the composition of the mastics, and proportions of the various rocks that they intend to employ in the composition of the asphaltic areas. The blocks and specimens of rocks and bitumen to have the trade-marks of the works from whence they came and the signatures of the competitors.

The necessary certificates to compete for the contract will not be delivered till after the examination and acceptance by the engineers of the specimens deposited. During all the term of this

contract the contractor can only use materials exactly similar to the specimens deposited.

Art. 27 provides for continuous inspection of the contractor's works, and the right to compel the contractor to manufacture the mastics in the depots belonging to the city.

Art. 31. The lime employed is to be hydraulic lime in powder. It must be brought onto the works in sealed bags marked with the name of the maker. Only the lime and cement designated in the specifications for the construction and repair of sewers will be allowed.

Art. 32. The broken flint must pass through a ring of $2\frac{1}{4}$ inches and be at least $\frac{3}{4}$ inch thick. It must be free from all earthy matters and washed clean.

Art. 33. The sand shall be dredged from the Seine and well cleansed from all foreign matter; it shall be screened from all grains larger than $\frac{3}{8}$ inch for the mortars or $\frac{1}{8}$ inch for grit for the mastic pavements. The grit for this last purpose shall be perfectly washed and dried before use.

Art. 34. The mortar of hydraulic lime shall be composed of 5 parts of sand and 2 parts of lime, by volume, furnished in powder; the mixture shall be directly reduced to a paste by adding the quantity of water exactly required to reduce it to the consistency of plastic clay.

The cement-mortar shall be composed of 1 part of hydraulic cement of Bourgogne or Portland cement of Boulogne and 3 parts of sand; the sand and cement shall be thoroughly mixed before the addition of any water. All mortar which shall have set shall be rejected.

Art. 35. The beton shall be composed ordinarily of 2 parts in volume of mortar and 3 of stone. The mixture, made either by rake or cylinder, must be perfectly uniform.

All beton not used at the time of making shall be rejected.

Art. 36. The bed of beton for the foundation of the sidewalks shall be well rammed and compressed, and must at least commence to set and dry before receiving mastic or asphalt. The beton shall in addition be covered with a layer of mortar $\frac{3}{8}$ inch thick.

The gravel for foundation shall pass in every direction through a ring 2 inches in diameter. It must be perfectly compressed and sprinkled with lime-grout. This foundation shall have commenced

to set before the application of the mastic, and shall be covered with a layer of mortar like the beton.

Art. 39. The ground upon which the mastic pavement is to be placed shall always be previously rammed, watered, and crowned with care. When it is thus made solid the contractor shall spread over it the foundation layer, formed according to the orders of the engineer—either a bed of beton or of sand covered by a layer of mortar, or a bed of sand impregnated with goudron $2\frac{3}{4}$ inches thick, or any other foundation prescribed by the engineer.

In all cases the pavement shall not be laid till the foundation has attained the firmness desired and becomes quite dry.

The contractor must conform to the following orders for the manufacture of the mastic to be used for pavements:

The mastic shall be prepared and cast in one or more manufactories belonging to the contractor, and which shall always remain open to the inspection of the engineers and their agents.

The contractor shall besides establish in the manufacturing depots, both of asphalt and mastic, offices exclusively for the agents of the administration set apart for the inspection of the composition of these materials. These materials shall not be admitted into the works without a carter's delivery note given by the inspector, setting forth that they have been manufactured in accordance with the specifications.

There shall only be allowed in the works blocks of mastic conforming to the samples deposited and accepted before the award, and bearing the trade-mark, or the old mastics from the walks and streets of Paris. All other bituminous matters, resinous or fatty, found in the works by the agents of the administration will subject the contractor to a deduction of \$100 for each time they are found.

To assure the execution of these conditions the contractor must not have in any manufactory, under the same penalty, any other blocks than those which should be prepared in his works, and the old mastics that have been taken up.

The use of the old mastic is authorized in the works of the city the proportion of one half with the new; the pieces of the old lewalks having been perfectly cleaned with great care, and regenerated by the addition of new purified bitumen and a sufficient

quantity of powered asphalt to render the old mastic, when melted, of the aspect and consistence of the blocks in fusion.

This mastic shall be melted in hermetically closed boilers, on wheels of a model approved by the administration, and arranged so that the material can be conveyed from the factory to the place to be used, ready to be employed.

For melting, the mastic is broken into pieces 4 inches cube, then the bitumen is melted and the mastic added little by little.

The grit must not be thrown into the boiler till the mastic is completely dissolved.

During the whole time of the operation the matter must be stirred up almost constantly, so that the combination shall be well made and the mastic not burned.

The mastic being well melted and perfectly homogeneous, it shall be run out in bands of about five feet wide, spread with a wooden float, and levelled with a strike, so as to present neither fissure nor joint. The mastic must be perfectly level, and matched exactly with the curbs, etc., against which it is laid. For this purpose the parts of the curbs, flags, etc., which will be in contact with the bitumen shall be previously warmed and goudroned.

Art. 40. Upon the soil, well shaped and rammed, shall be placed a bed of concrete, covered with a layer of mortar.

The asphaltic rock, conforming to article 24, broken down or decrepitated by heat, shall be raised to a uniform temperature of from 248 to 266 degrees Fahr., and carried to the place of employment in vehicles that will prevent as much as possible the loss of heat. It must be completely freed from the water it contains. The use of old compressed asphalt, taken from old roads, is authorized for mixture with new asphalt, in the proportion of one quarter of old compressed to three quarters of new rock, provided that the old shall be cleansed with great care before grinding and mixing with the new.

Asphalt shall not be put on the concrete foundation until it is perfectly set and dry.

The powder shall be spread with a thickness about two fifths more than the finished thickness, levelled with great care, and then rammed, at first carefully, then gradually augmenting the force by means of cast-iron *pilons* heated to the proper temperature in portable furnaces. In specially exceptional cases the compression

may also, with the written permission of the engineer, be accomplished by means of rollers.

In every case, after the pilonnage is finished, the surface shall be smoothed by means of a heated iron (*lissoir*).

The road shall not be open to traffic until it is quite cool.

Art. 43. In conformity with the contract price, stipulated hereafter, diminished by the rebate of the awarded contract, the contractor must make the necessary repairs to all asphaltic mastic foot-paths and areas, furnishing the necessary labor and materials, so that they shall be kept in proper condition. He must each year of the duration of the contract completely relay, in new material, at least the fifteenth part of the surfaces of mastic and compressed asphalt. The surfaces in mastic must be properly plane and regular, presenting neither hollows nor projections of more than $\frac{3}{8}$ inch in a circle whose radius is $3\frac{1}{4}$ feet. These surfaces must be free from fissures.

Art. 45. As the works in asphalt or mastic are accepted by the engineer they will pass into the charge of the contractor, who will receive for the maintenance the price stipulated, commencing from the first of January next following their acceptance, whatever may be the date of said acceptance.

In the last nine months of the year instalments may be paid on the contract when the engineers recognize that the conditions have been loyally carried out. The accumulated sums of these instalments must not exceed four fifths of the amount of the sums which shall be due after the time has expired. The balance of the contract price of the year will be paid in the course of the first quarter of the following year.

Art. 49. All damages in the bituminous surface, such as fissures or cracks of at least $\frac{1}{4}$ inch in width, or parting from the curbs $\frac{3}{8}$ inch in width, any lifting up or breaking away of the mastic for at least $\frac{3}{8}$ inch in depth, depressions in consequence of settlement of at least $\frac{3}{8}$ inch in depth under a straight-edge, $3\frac{1}{4}$ feet long, will subject the contractor to a deduction of 3 francs (58 cents) per day when the repairs shall not have been done within 48 hours after notice given by the engineer.

Art. 51. During the continuance of frost, and during the first month after the commencement of the thaw, there shall be no repairs to the pavements maintained by the contractor, and the in-

spection for defects shall be suspended; but the contractor shall fill with sand and gravel any holes in these pavements within 24 hours after notification by the engineer, under a penalty of 10 francs (\$1.93) for each day they remain unfilled. He may be authorized, in exceptional cases, to fill the holes with broken flint or melted bitumen, but must replace the flint or bitumen with asphalt as soon as the weather permits. It must be so arranged that the main repairs, intended to re-establish the normal outline of the roadways, are effected from May 1st to November 1st.

Art. 65. When a workman leaves one of the districts of the works under the municipal service, he must have a certificate from the contractor showing the cause for which he left.

This certificate shall be submitted at once to the engineer, who shall be at liberty to refuse the right of employing the said workman, without the contractor deriving therefrom any excuse for not furnishing, when requisite, the number of workmen required. In default of a certificate, the workman cannot be admitted, except on the written order of the engineer.

782. Compressed-asphalt Tile-pavement.—The success attending the introduction of compressed-asphalt blocks for light-traffic streets has led to the use of the same composition under the name of "compressed-asphalt tiles" for sidewalk pavements. These tiles can be made of any form and thickness required. The dimensions found most suitable are 8 × 8 inches square and 2½ inches thick. In this form they have been laid in large quantities during the last seven years and appear to have given satisfaction.

782a. Specifications for Laying Compressed-asphalt-tile Sidewalk-pavements.

(1) The tiles will be laid on a foundation of gravel and sand thoroughly compacted by ramming and rolling.

(2) The space over which the pavement is to be laid shall be excavated to the depth of ten (10) inches below the top surface of the finished pavement. Any perishable or other objectionable material found below this depth must be removed and the space filled with clean gravel or sand; the surface of the foundation so prepared shall be thoroughly compacted by ramming and rolling.

(3) The foundation for the tiles will be formed of a bed of fine bank gravel four inches in depth when compacted, screened from all pebbles measuring more than one and one-half inches. Upon

the gravel there shall be laid a bed of fine, sharp sand, washed and dried, four inches in thickness. The foundation of sand and gravel shall then be thoroughly consolidated by ramming and rolling, care being taken to preserve the surface of the sand parallel to the slope required for the finished surface of the pavement. (The hand-rammers shall weigh not less than 25 lbs., and the rollers not less than 300 lbs.)

(4) The tiles shall be laid at right angles to the street line, and their surface when finished must be even with the top of the curb and shall have the required slope.

The tiles shall be laid by the pavers standing or kneeling upon the tiles already laid, and not upon the sand-bed.

Each course of tiles must be of uniform width and depth, and so laid that all longitudinal joints shall be broken by a lap of at least two inches.

Each course shall be driven against the course preceding it by a maul so as to make tight joints.

When thus laid the tiles will be covered with clean, fine, dry sand, free from loam or earthy matter, and screened through a sieve having not less than 20 meshes to the inch.

(5) The tiles shall then be carefully rammed by placing a plank over several courses and striking the plank with a rammer weighing not less than 25 lbs.

The ramming shall be continued until the tiles reach a firm, unyielding bed and present a uniform surface with the required grade. Any lack of uniformity in the surface must be corrected by taking up the tiles and relaying them.

When the ramming is completed a thin layer of fine dry sand shall be spread over the surface and swept into the joints.

784. Brick.—Brick of suitable quality well and carefully laid on a concrete foundation makes an excellent footway pavement for residential and suburban streets of large cities, and also for the main streets of the smaller towns. The bricks should be a good quality of paving-brick (ordinary building-brick are unsuitable; they soon wear out and are easily broken). The bricks should be laid in parallel rows on their edges, with their length at right angles to the axis of the path. They should be set in cement-mortar and the joints filled flush and made as close as possible.

trees have not been planted. When so ordered a continuous tree space of 4 feet wide will be left unpaved adjacent to the curb. Edges of brick pavements when not abutting against the curb will be finished with a continuous row of brick on edge.

Quality of Brick.—Sidewalk paving-brick to be of dimensions $8\frac{1}{4}$ by 4 by $2\frac{1}{4}$ inches, hard-burned throughout, of dark red color, without flaws or cracks, and square and true on the edges. Specimens required.

Arch-bricks to be of dimensions $8\frac{1}{4}$ by 4, by $2\frac{1}{4}$ inches, hard-burned throughout, sound, and of true and regular shape. All to conform to the samples submitted with the proposals. No swelled brick or soft or salmon brick will be allowed. Specimens required.

In relaying brick sidewalks the existing sidewalks will be taken up and the bricks carefully piled and preserved. The bed will then be prepared in the same manner as prescribed for new brick walks. After the bed is prepared the old brick will be cleaned of all adhering materials so that they can be relaid with close joints, when they will be laid as prescribed for new brick pavements.

786. Artificial Stone.—Artificial stone is being extensively used as a footway-paving material both in Europe and America. Its manufacture is the subject of several patents, and numerous kinds are to be had in the market. When manufactured of first-class materials and laid in a substantial manner, with proper provision against the action of frost, artificial stone forms a durable, agreeable, and inexpensive pavement.

The varieties most extensively used in the United States are known by the names of "granolithic," "monolithic," "ferrolithic," "kosmocrete," "metalithic," etc.

The process of manufacture is practically the same for all kinds, the difference being in the materials employed; the usual ingredients are Portland cement, sand, gravel, and crushed stone.

787. Artificial stone for footway pavements is formed in two ways, viz., in blocks manufactured at a factory and brought on the ground and laid in the same manner as natural stone, or the raw materials are brought upon the work, prepared and laid in place, blocks being formed by the use of board moulds.

788. The manner of laying is practically the same for all kinds. The area to be paved is excavated to a minimum depth of 8 inches, and to such greater depths as the nature of the ground may require

to secure a solid foundation. The surface of the g is well compacted by ramming, and a layer of grav or other suitable material is spread and consolid placed the concrete wearing surface, usually 4 inc protection against the lifting effects of frost the c squares, rectangles, or other forms having areas ra 30 square feet, strips of wood being employed to which the concrete is placed. After the concr strips are removed, leaving joints about half an in the blocks. Under some patents these joints are fi under others with tarred paper, and in some cases t

789. Good artificial stone is far superior to an for footway pavements. It is of a uniform temp neous throughout, and consequently its wear is me that of natural stones. It is practically non-absor quently dries very quickly after rain.

790. The quality of the cement is an importa manufacture of artificial stone. A cement of imp cause cracking. The characteristics of good ceme in Chapter IX.

New Portland cement when spread and subject aeration will increase in bulk at least 5 per cen manufactured with such cement they will blow and increases in strength with age, and therefore stor with it will also increase in the same ratio; and has shown that slow-setting cement had an average of .0734 per cent, and quick-setting .2019 per cent twelve months.

791. The following detailed particulars for the crete footway pavements is taken from "Roads, S ments," by Q. A. Gillmore:

"Concrete footpaths should be laid upon a f compacted sand, or fine gravel, or a mixture of sand, The natural soil, if sufficiently porous to provid drainage, will answer.

"It is not usual to attempt to guard entirely effects of frost, but to provide for it by laying squares or rectangles, each containing from 12 feet, which will yield to upheaval individually like

without breaking and without producing extensive disturbance in the general surface.

"When a case arises, however, where it is deemed necessary to prevent any movement whatever, it can be done by underlaying the pavement with a bed of broken stone, or a mixture of broken stone and gravel, or with ordinary pit-gravel containing just enough of detritus and loam to bind it together. In high latitudes this bed should be 1 foot and upwards in thickness, and should be so thoroughly subdrained that it will always be free from standing water. It is formed in the usual manner of making broken-stone or gravel roads already described, and finished off on top with a layer of sand or fine gravel, about one inch in depth, for the concrete to rest upon.

"The concrete should not be less than $3\frac{1}{2}$ and need rarely exceed 4 to $4\frac{1}{2}$ inches in thickness. The upper surface to the depth of $\frac{1}{2}$ inch should be composed of hydraulic cement and sand only. Portland cement is best for this top layer. For the rest, any natural American cement of standard quality will answer. The following proportions are recommended for this bottom layer:

Rosendale or other American cement.....	1	measure
Clean, sharp sand.....	$2\frac{1}{2}$	"
Stone and gravel.....	5	"

"It is mixed from time to time as required for use, and is compacted with an iron-shod rammer in a single layer to a thickness less by $\frac{1}{2}$ inch than that of the required pavement. As soon as this is done and before the cement has had time to set, the surface is roughened by scratching, and the top layer, composed of 1 volume of Portland cement and 2 to $2\frac{1}{2}$ volumes of clean, fine sand, is spread over it to a uniform thickness of about $1\frac{1}{2}$ inches and then compacted by rather light blows with an iron-shod rammer. By this means its thickness is diminished to $\frac{1}{2}$ an inch. It is then smoothed off and polished with a mason's trowel and covered up with hay, grass, or other suitable material to protect it from the rays of the sun and prevent its drying too rapidly.

"It should be kept damp and thus protected for at least ten days, and longer if circumstances will permit; and even after it is open for travel a layer of damp sand should be kept upon it for two or three weeks, to prevent wear while tender.

"At the end of one month from the date of laying, the Portland-cement mixture forming the top surface will have attained nearly one half its ultimate strength and hardness, and may then be subjected to use by foot-passengers without injury.

"The rammers for compacting the concrete should weigh from 15 to 20 pounds, those used on the surface layer from 10 to 12 pounds. They are made by attaching rectangular blocks of hard wood shod with iron to wood handles about three feet long, and are plied in an upright position. Certain precautions are necessary in mixing and ramming the materials in order to secure the best results. Especial care should be taken to avoid the use of too much water in the manipulation. The mass of concrete, when ready for use, should appear quite incoherent and not wet and plastic, containing water, however, in such quantities that a thorough ramming with repeated though not hard blows will produce a thin film of moisture upon the surface under the rammer, without causing in the mass a gelatinous or quicksand motion."

791a. The disintegration and disfiguration of cement walks is frequently due to unskilful manipulation. While the surface mixture should be thoroughly rammed and well trowelled, yet this treatment should not be continued so long as to bring to the surface a considerable quantity of neat cement, thus leaving the layer of mortar next below without sufficient cement to bind it together. If this is done, the thin layer of cement will flake off when set, revealing a layer of almost clear sand. A similar result obtains if attempt is made to retrowel a surface once finished and partially set, but afterwards defaced. Sprinkling the surface before the cement has thoroughly set may cause blisters, which mar the work. If the surface of the setting cement is not protected from the direct rays of the sun, cracks will be produced.

792. One cubic yard of concrete laid 3 inches thick will cover 10 square yards of surface. For the wearing surface the cement and sand are mixed in equal parts.

793. Covering Capacity of Cement in Square Feet.

	Thickness in Inches.		
	1"	$\frac{3}{4}$ "	$\frac{1}{2}$ "
1 bbl. of Portland cement will cover	86	48	73
1 bbl. cement and 1 bbl. sand will cover	66	84	132
1 bbl. cement and 2 bbls. sand will cover	96	124	192

794. Wear.—As regards the wear of artificial stones, the following notes from London may be interesting: "Artificial stones have now been used by almost every Vestry and District Board in the metropolis, and from testimonials it would appear that they have given satisfaction."

A portion of Victoria stone was laid in Piccadilly in 1872, and is said to be in good condition still, having been in use nineteen years.

In 1869 the approach to Blackfriars Bridge was paved with Victoria stone, and six years later, Mr. Carr, the engineer, said, the surface was perfect and the wear decidedly less than York stone contiguous. This stone has also been laid in Holburn, where the traffic is estimated at 88,355 persons daily, and Aldgate High Street, where the traffic is estimated at 79,048 daily. Portions of the stone were taken up after five years, and the wear was found to be so slight as to be scarcely measurable.

Imperial stone has also been largely used throughout the metropolis, and appears to have given every satisfaction.

Several varieties of good stone are in the market; as examples the following may be cited:

	Cost per yard laid.	Tensile Strain in pounds per square inch.	Compressive Strain, lbs. per square inch.	Thickness in inches.	Weight in lbs per cubic ft.
Imperial	\$1.35	980	9,492	2 $\frac{5}{16}$	
Croft	1.32		9,394	2	132
Victoria	1.38-1.44	1,125	8,321	2	144
Granolithic	1.31	1,000	8,500	2	
Jones annealed....	1.30	510*		2 $\frac{1}{2}$	150
		1,500†			
York (natural)....	1.56		5,714	3	156

* 1 month old.

† 12 months old.

The following tests were made by Mr. W. Sykes, Surveyor, Fulham, London, to find the comparative wear of artificial and natural stones. The stones were of equal superficial area, all bound together with cord, so that each stone found its own bed when rubbed on York stone with sand and water.

	York.	Imperial.
Thickness before being rubbed..	2½ in.	2¾ in.
First hour.....	2¼	2¼
Second hour.	2⅞	2⅞
Third hour.....	2⅞	2⅞
Total wear.....	¾	¾

From these figures it will be seen that the three hours was for York ¼ of an inch, Imperial ¾.

This experiment is interesting as showing York was ¼ inch more than that of artificial Imperial, Victoria, and Croft wore equally, and of the same degree of hardness.

The York stone referred to above is a chiefly of silica cemented together by a matrix; it is of very unequal quality, being either exceedingly soft; it is also very absorptive, and is liable to frost.

795. Specifications for Concrete Footwalk Foundation.—The natural-soil surface shall be graded to a depth of 8 inches below the level face of the walk; perishable and objectionable material shall be removed. On the surface so graded spread a layer of broken bricks or steam ashes) to such depth as to allow thorough consolidation a thickness of 4 inches. When so prepared the concrete shall be placed; moulds and boards shall be placed at every 6 feet and adjusted to the required grade and pitch. The concrete shall be placed in layers and thoroughly rammed. After the concrete has been laid it shall be covered with the wearing coat, one inch thick, and shall be neatly trowelled to the required grade.

Traffic shall be kept off for a period of 1 week until the surface is thoroughly set.

All vault-covers, stop-cock boxes, etc., shall be placed at the required grade, and the concrete shall make no joint with their surface.

The concrete shall be composed of:

American hydraulic cement.....	1 part
Broken stone.....	7 parts
Gravel and sand....	8 "

The wearing surface will be composed of:

Portland cement.....	1 part
Sharp sand	1 "

796. Specifications for Artificial-stone Footpaths (Washington, D. C.).—The contractor shall remove all stone, plank, bricks, or other materials of value from points where the sidewalk is to be laid as the work progresses, and shall haul them to the nearest property yard, or otherwise dispose of them as the Engineer Commissioner may direct. Care shall be taken at all times not to interfere with business or travel more than is absolutely necessary for the faithful performance of the work. No more than 100 feet shall be closed to travel at any one time, nor remain closed for a longer time than three days, and free ingress and egress from the streets to all stores and hallways shall be provided for at all times; and during the time that travel is closed at any point the contractor shall provide a temporary walk, said walk to be at all times in condition, perfectly safe for pedestrians, and easy of access from adjoining walks.

The contractor shall make such cutting and filling as may be necessary to bring the foundation to the subgrade, 6 inches below the established grade of the sidewalk.

Whenever the Engineer Commissioner or inspector may deem it necessary, the foundation shall be consolidated by wetting, rolling, or ramming, to give it proper stability. Upon the foundation thus prepared there shall first be laid 3 inches of concrete, composed of one part natural hydraulic cement, two and one half parts sand, and five parts broken stone, which shall be rammed in place to the satisfaction of the Engineer Commissioner. On this concrete bed shall be laid three quarters of an inch of mortar, composed of four measures of clean, sharp sand and one of Portland cement, which shall be put in dry as possible, and rammed in place with an iron rammer weighing at least 25 pounds. Upon the foundation thus prepared shall be laid square blocks or tiles 2½ inches thick, measuring 18 inches on a side. They shall be laid so as to present a true

surface on top and conform to the exact grade. Thin grouting of pure Portland cement of the best quality shall be spread over the surface and carefully swept in. Superfluous grouting shall be cleaned off, and the surface protected with plank or otherwise until the cement has set.

Driveways crossing the footpath shall be laid with asphalt blocks, as may be directed by the Engineer. The tiles shall be $2\frac{1}{4}$ inches thick. The lower part shall be composed of one part Portland cement (equal to the current District of Columbia specifications) and three parts sharp sand, thoroughly mixed, using as small a size of sand as possible, and carefully rammed into the joints. The top one-half inch and the sides for one-half inch shall be composed of one part Portland cement, of same quality as the sand, and a clean, sharp sand.

The surface shall be finished smooth but not polished. The tiles, when being seasoned, shall be kept wet for at least twenty-four hours. No tiles shall be used on the work unless grouted with cement mortar. The tractor to be at least thirty days old. Unless otherwise directed, the edge of the sidewalk shall be finished with plaster of Paris, cement and sand of equal parts. The blocks shall be laid with the edges perpendicular to or parallel with the line of the sidewalk, as may be ordered by the Engineer Commissioner.

Cement Inspection.—No cement shall be used on the work unless approved by the Engineer Commissioner. Whenever he shall be entitled to take one-half pound of cement for test purposes. The decision of the Engineer Commissioner in all such cases, and no cement condemned by him shall be used for any purpose whatever. All cements will be tested according to the tests specified in current District of Columbia specifications.

All surplus material and refuse shall be removed from the site of the work within twenty-four hours after the completion of the work. In case of neglect on the part of the contractor to do so within the specified time, the Engineer Commissioner shall have the same removed, and the expense thereof shall be charged to the contractor and deducted from his estimates. Whenever a new sidewalk crosses the sidewalk, the plan thereof shall be approved by the Engineer Commissioner shall direct.

No material of any kind shall be used until it has been examined and approved by the Engineer Commissioner, who shall have full power to condemn the work or material not in accordance with the specifications, and to require the contractor to remove any work or material so condemned, and at his own expense to replace the said work or material to the satisfaction of the Engineer Commissioner. In case the contractor shall neglect or refuse, after written notice, to remove or replace said rejected work or material, it shall be removed and replaced, by order of the Engineer Commissioner, at the contractor's expense.

The work is to be commenced and carried on at such times and places and in such manner as the Engineer Commissioner shall direct.

The contractor will not be allowed to obstruct private driveways or approaches or to dig up or occupy the street by material more than is absolutely necessary for the prosecution of the work, special care being taken to inconvenience the public as little as possible.

When the construction of any piece of work is begun it shall be fully completed before the force is removed. In case this is not done, the Engineer Commissioner shall have the work done, and the expense thereof shall be charged to the contractor and deducted from his estimates.

If any overseer or workman employed by the contractor shall be declared by the Engineer Commissioner to be unfaithful or incompetent, or shall refuse to obey the instructions of the inspector, the contractor shall forthwith dismiss such person and not again employ him on any part of the work. The contractor will be held responsible for all injury done to the work in any way until it is accepted and measured by the engineer.

Measurement of Work.—All artificial stone-block walks, including stone and mortar foundation, will be paid for by the square yard of finished surface, in accordance with the schedule in printed form of bid, except when it is fitted around poles, lamp-posts, or scuttle-holes, in which case these spaces will not be deducted. Tree-spaces will not be deducted.

Curb.—Whenever ordered the curb will be reset. Curb will be redressed by the contractor whenever ordered, for which actual cost plus 15 per cent will be paid.

Tree-spaces.—Tree-spaces shall be left wherever necessary. These spaces shall be outlined by boards of sound Georgia pine, 2 inches thick and 9 inches wide, set on edge, with their top edge even with the pavement when completed. The plank forming the rear of this framework and which is parallel with the curb shall be firmly nailed to the other two pieces, and shall be cut in such manner that it will bind underneath the pavement when completed. The blocks shall be laid as closely to the boards as possible, and all corners and vacant spaces shall be filled with mortar similar in composition to that of which the blocks are made.

796a. Kosmocrete.—The artificial stone known by this name is extensively used in Brooklyn, N. Y.; it is formed as follows: A bottom course of dry cinders, about 12 inches thick, is laid, and upon this a layer of concrete about 4 inches thick, composed of 3 parts of granulated granite or gravel, 4 parts of one and one-half inch stone, and 1 part of Portland cement. On this concrete is worked a facing about one inch thick, composed of granulated granite, a small percentage of silicious grit, Portland cement, and carbon. The purpose of the granite and grit is to prevent the surface from becoming slippery. Cost ranges from 25 to 35 cents per square foot, depending largely upon the distance the material has to be transported, and the amount of work that has to be done preliminary to laying the pavement.

797. Tar Concrete for Footway Pavements is made in many and various ways. Pavements made according to the following specifications have proved satisfactory:

Proportions of materials:

Steam ashes.....	8 parts
Portland cement.....	1 part
Sharp sand.....	1 "
Gas-tar.....	9 parts
Water.....	70 to 80 "

Method of Mixing.—The ashes, sand, and cement are thoroughly mixed dry, then the water and tar added and mixed in the same manner as mortar. The plastic mass thus produced is passed several times through a pug mill: if this is not done, the concrete will be a failure. As the mass emerges from the mill a large proportion of the water will run from it, and means must be provided to allow it to escape freely.

The foundation is prepared in the usual manner and the concrete laid 3 to 4 inches in thickness, well rammed with hand rammers, then rolled with an iron roller weighing not less than 600 pounds—the amount of rolling to be not less than two hours for each 100 square feet. Hollows that appear during the rolling to be trimmed and filled up. After the concrete is set sprinkle a small quantity of clean, sharp sand over the surface and allow it to remain for three or four days after the path has been in use, then remove it.

The concrete should not be laid in wet or freezing weather.

798. Another method of forming tar-concrete pavements is as follows: On a dry foundation is placed a coat of rough clinkers from anthracite coal, or iron clinkers from a foundry, mixed with sand and tar in the proportions of 15 cubic feet of fine sifted ashes, $14\frac{1}{2}$ cubic feet of pit sand, and $1\frac{1}{2}$ cubic feet or 9 gallons of tar. This is laid about 3 or 4 inches thick and well rolled. Over this is placed a coating from 1 inch to $1\frac{1}{2}$ inches thick, composed of 15 cubic feet of coarse sifted ashes, 15 cubic feet of clinkers, and $1\frac{1}{2}$ cubic feet or 8 gallons of tar. It must then be well rolled and sanded, care having been taken that the materials are thoroughly mixed.

799. Footway pavements of which the binding material is coal-tar must only be reckoned as temporary. They have been extensively used in several cities, but as a rule they soon wear out and become very disagreeable. Under a hot summer sun the pavement becomes soft and sticky, the volatile oils are evaporated, and the surface becomes covered with ridges; they are difficult to repair and are never satisfactory.

800. Gravel.—For suburban streets, country roads, parks, and pleasure-grounds, gravel makes an excellent footway pavement.

The same rules that apply to the construction of gravel roadways apply to gravel footways. They must be well drained and well rolled.

Limestone chippings may with advantage be used with pit gravel. For paths formed of gravel a crowning surface looks better and is more enduring than a sloping one. (See Fig. 149.)

801. As examples of excellent rural-walk construction, the walks of Central Park, N. Y., may be cited. These walks embrace, in treatment and materials, the requirements of the generality of rural walks in this country. They are laid on every variety of ground, from level and smooth to rocky and precipitous, sometimes clamber-

ing with rustic steps and winding narrowly along rugged hillsides; sometimes gently undulating over meadows and lawns, and sometimes expanding into broad and capacious promenades. They are carried over and under roads, and over brooks, by archways and bridges of various kinds, ornamental and rustic; through gorges and ravines, and along the water edge of lakes and ponds. They are made of various widths, from 3½ to 35 feet, and adapted to nearly every circumstance of position, locality, use, and convenience that ordinarily occurs in walks for rural or park purposes.

802. The general method of constructing the walks was as follows: In the more formal walks—those having the greatest breadth and occupying ground that was originally so irregular and uneven as to require a considerable amount of excavating and filling—the preparation of the bed of the walk was the same as for the roads. Care was taken to compact the earth in the embankments, excluding all perishable and improper materials.

The bed of the walk was raised in the centre, with a moderate inclination toward the sides, and where not sufficiently firm was rolled with a hand- or horse-roller. The sub-drainage was secured by drains formed sometimes of tiles and sometimes of rubble-stone, so placed as to intercept and carry off the water from rain and springs. "Mitre drains" formed of small stones were employed where necessary.

803. One of the principal causes of the deterioration of walks, and a prolific source of trouble and expense in repairs, is the wash from water brought from the adjoining slopes. If the expense of making good the damage done in this way—sometimes by a single shower—is considered, it will be seen that a liberal and ample provision to guard against it is warranted by sound economy. No cheaper or more effective and practical method can be adopted for this object than the catch-water drains, or, as they have been termed in the Park, "sod gutters."

These are made along the uphill side of the walk, in the form of a broad grave, parallel for the most part with the walk and a few feet from it, and joined by an easy graduation of surface to the ground on each side, so as to give them as little of an artificial appearance as practicable. The bottom is made even and regular, with no depressions to lodge silt or mud, or form pools of water. When properly shaped the surface is sodded and rammed.

After the grass has taken root, the gutter will bear the passage

of a considerable volume of water for as long a time as is ordinarily required, without receiving injury. This form of gutter admits of the mowing of the grass that grows in it without difficulty, which is a great convenience. If the walk passes through a hollow, with descending ground from each way, these gutters are made on each side of the walk. When it occupies ground that is level transversely, it is raised slightly above the surface, to give an outward inclination to the turf borders and turn the water away from it.

The gutters are conducted along the walk, parallel with it, or deviating occasionally to take advantage of convenient natural depressions, until a favorable point is reached for turning off the water altogether, and disposing of it in a secure manner. Where it is practicable, the water is allowed to spread out from the termination of a gutter upon a broad surface of descending ground, and seek the general drainage courses of the district in which it is situated, that lead to a sewer inlet, a brook, or a pond. Sometimes the gutter is conducted to a sewer or road drain in the vicinity; but when facilities of this kind are not available, and it is objectionable or unsafe to discharge an accumulation of water upon a lawn or through shrubbery, special under-drains have had to be constructed. Such under-drains have been necessary, to a considerable extent, in connection with most of the main walks of the Park. They receive through grated inlets, inserted in the gutters (with accompanying silt-basins), the immediate drainage of the walks, and, through similar inlets placed in the adjoining sod gutters, the exterior drainage. Fig. 161 shows the arrangement of these drains, inlets,




FIG. 161. SECTION OF PARK WALK, SHOWING THE MANNER OF REMOVING THE SURFACE WATER.

and silt-basins. The depression on the right of the figure shows in section a sod gutter (or a natural surface channel), having an inlet

to the main and under drain through a silt-basin, which is represented under the right walk gutter. The inlets and silt-basins occur in this manner at intervals of one hundred to three hundred feet, according to circumstances, the amount of drainage, the declivity of the walks, etc. The under-drain is carried various distances along the walk, until it becomes convenient to turn it into a larger road-drain or a sewer.

Where the under-drains and silt-basins are omitted, which is the case with the narrower and more irregular walks, the drainage of the surface of the walk is conducted off to the ground beyond, or to a sod gutter, through openings in the border of the walk that are made at suitable points.

804. The footway is formed of rubble and small or roughly broken stones, deposited generally eight inches deep for a foundation, with about two inches of gravel spread over the top to receive the wear. The stones are such as are obtained from the earth excavations in grading the walk and adjoining grounds, or from blasted rock and bowlders, or field stones picked off the surface of the ground, or cobble-stones thrown out from gravel excavations, etc., as may be found convenient in any case. Blasted or quarry stones are preferable when they can be had in sufficiently small sizes, and without incurring the expense of quarrying them specially for the purpose. The sizes should be such as to admit of making up the layer of eight or ten inches deep, in two courses, or so that no single stones shall reach through the whole layer, and prevent the effectual closing of interstices. Quarry stones are better than field stones, for the reason that they are more angular and irregular in shape, and make a more open or cellular foundation to facilitate the drainage and prevent the action of frost.

805. A bed of stones laid in such a way as to permit the surrounding spaces to be filled up, either by the wash of mud along the bottom, or by the sinking of the stones in the bottom (in consequence, frequently, of defective drainage), or by the gravel or surface material working down from above, is but little better than a bed of natural stony ground, for it absorbs and retains all the water that reaches it, until it fills up and overflows at the surface, making the walk wet and spongy, and inviting all the difficulties and deteriorating results that it is a principal object in constructing walks to guard against. Walks are frequently observed that have

been made in this way—a mass of stones having been thrown together in a trench on wet ground, with considerable trouble and expense, and the unprotected interstices filled solidly with mud that has been washed in from time to time (perhaps mostly during the process of construction), until no room is left for the percolation of water from the surface, and the saturated bed is in a condition to be operated upon to the fullest extent by frost. It ought not to be a matter of surprise, although it sometimes is, with those who make such walks, that they do not give satisfaction at all commensurate with the expense and labor bestowed upon them.

806. When the layer of stones is formed of requisite depth, and some pains taken to regulate and adjust the surface by settling, breaking, or replacing stones that are too large or that project too high, and filling with smaller stones or covering the larger apertures, a coating is then spread over of quarry chips or such finer rubble or coarse gravel as may be available. In case such materials cannot be had, soft, shelly, or partially decomposed stones are selected and broken up on top of the layer, until the interstices are sufficiently closed to admit of following the process with a light film of gravelly loam or other coarse earth, which latter material, after being evenly distributed and moistened is well rolled by hand-rollers. This prepares the surface of the bed—when the work is carefully and thoroughly performed—for the reception of the final covering of gravel.

807. The perfection of the work consists, up to this point, in forming a stable and unyielding foundation, with the interstices of the main body of stones kept free and unobstructed, and a covering, to support and retain the superincumbent gravel, of the least thickness and density that will enable it to serve its purpose. A fair test is afforded of the sufficiency of the surfacing material by letting the work stand, after the rolling is done, until it has been exposed a few days to the weather: if it sinks away into the stones below, forming holes and leaving the stones naked and roughly projecting, it shows that enough material has not been added, and such spots should be well repaired; if it retains water (from rain), forming a muddy surface that does not filter away and dry out readily, it shows that more earthy material has been used than is beneficial. The proper surfacing of the bed of stones will not ordinarily add much to the average depth of the layer, just covering the highest

points of the stones, and filling over smoothly the intervening inequalities, so that the gravel, when it is applied above, will have a uniform depth and conform to the desired crowning shape of the walk.

808. If gutters are required for the walk, the foundations for them are prepared by using, in the outer edges of the stone filling, smaller stones and gravel for the better support, and to facilitate the setting of the gutter stones.

809. The gravel is deposited on the walk two or three inches deep, the coarser part being raked forward into the bottom of the layer, and such pebbles as are too large picked off. When evenly adjusted, a film of sandy or clayey loam is spread over the surface and lightly raked in to aid the binding effect, and after the whole is moderately watered or moistened, the completing process of rolling and compacting is commenced. This is done, on the principal walks, by a roller drawn by a horse; on narrow walks and those having greater acclivities, regularities, rustic steps, etc., it is done by a roller of less weight, drawn by hand, by two, three, or four men, as the case may be. As the rolling proceeds, a man follows with a rake, to correct inequalities and keep the binding material equally diffused through the gravel, and to add more of such material, from time to time, as may prove to be necessary. Judgment and expertness are required to manage this business well. Dull or unpracticed men will waste their time at it. The quantity of binding material that is judicious to use will vary sometimes with each load of gravel: if too much is used, or if it is unevenly and carelessly spread, it will produce an imperfect surface, and it will take considerable time and labor to correct after the walk is brought into use. If the gravel is fine and filled with dirt, or if the grains are of a soft, friable quality, it will not need as much foreign material added to make it bind as when it is clean and hard: it may contain such a quantity of earthy matter, however (as is frequently the case), as to make it necessary to free it from a portion of the binding substance by screening, rather than to add to it: such gravel should not be used if better can be had. All muck, top-soil, and vegetable or fertilizing matter should be carefully excluded from both the gravel and the binding material, to prevent the growth of grass in the walk. The gravel that has been used in the Central Park walks has generally been of a sharp, hard quality, and more than usually free from dirt, and it has been found that it

would bear an average intermixture of about one fifth its bulk of loamy or sandy earth to give it the requisite binding property. If more than this was added, the work of rolling and packing would be facilitated, but the surface of the walk would absorb and retain water, and become muddy after a rain; if less was added, the rolling, although it might be thoroughly done, would not suffice to make a surface that would remain firm in dry weather.

810. The effect of the proper adjustment of these points, the selection of a good quality of gravel, the judicious use of the binding material, and the raking, shaping, and rolling, is to produce a walk that is agreeable at all times: not muddy or slimy after a rain, or loosened so that the foot sinks into it when it becomes very dry, or much subject to dust.

With care and some sleight in the raking, before and after the rolling is commenced, the finer gravel and sand will be worked to the top and the coarser pebbles buried in the bottom of the layer, preventing the disagreeable feeling that is caused by walking over a coarse or unequal surface.

811. In investigating the subject of walk drainage and gutters, in the early stage of the Park work, experiments were tried in order to ascertain if some better or cheaper or less objectionable description of gutter could be devised than those in common use. Although the results attained were not such as to warrant the adoption upon the very uneven grounds of the Park of any of the kinds of gutter experimented upon, yet they may afford some hints and possess sufficient interest to be worthy of mention.

The principal kinds were as follows:

- (1) Cement or concrete gutter.
- (2) Composition gutter.
- (3) Iron gutter.
- (4) Wood gutter.

Nos. 1 and 2 were open gutters. No. 1 was composed of a concrete consisting of two parts of gravel and sand and one part of cement laid on a filling (adjoining a walk east of the Mall), of broken stone and gravel of about 9 inches in depth. The concrete was deposited 2 to 3 inches thick, and moulded by the aid of a wooden implement drawn over it into the desired form. The gravel of the walk and the side border were closed up to it on either side, and completed the process.

This gutter was comparatively cheap and easy of construction, and appeared in all respects, as regards utility, well adapted to the purpose. After exposure to the weather for a time, it became lighter in color than the gravel of the walk, owing to the cement which entered into its composition. The objection to it at the time of trial (1859) was the uncertainty of its durability, together with the general objection to all open or surface gutters—that it gave too marked and formal an outline to the walk. The sample is still in its original position. It has improved in respect to color, and has been but little affected by the changes of weather or frost or by wear.

No. 2, composition gutter, east side of "the Ramble," was made in a similar manner to No. 1 as to form and dimensions, but the materials used and its manipulation were not disclosed by the gentleman who introduced the sample and supervised its construction (Gen. Asboth). The principal defect of this gutter seemed to be the contraction of the materials, which separated on exposure into broken sections—the action of frost and other causes tending to increase it and displace the parts. It was also open to the general objection mentioned to all formal gutters.

No. 3, iron gutter, was made of light sheet-iron, in sections of U-form, with a perforated movable lid or cover. The design was to make it a concealed gutter by sinking it along the edges of the walk and covering it over with a light layer of gravel—the surface-water to percolate through the gravel and the perforations in the lid into the gutter, and thence pass off as through a pipe. This sample, as far as tried, indicated that it might be made to operate well in ordinary cases of moderate drainage and not too great inclination of the walk, but it was considered to be subject to too many contingencies for general use.

No. 4, wood gutter, was constructed upon the same principle as No. 3, with the substitution of wood for iron. It was a mere wooden trough with a perforated lid, the wood having been subjected to a process to give it greater than ordinary durability. It was apparent that it was inferior to the iron gutter (though much cheaper), and its general want of adaptability was considered as decisive against it.

A method of macadamizing gutters of the common (open) form was tried in order to obtain a gutter that would blend, better than

ordinary paved cobble-stone gutters, with the gravel of the walk, and not present the usual contrasts of color and kind of material, but it was found impracticable by ordinary means to give the materials sufficient compactness and cohesion to resist long the action of a current of water. The same process was tried for the surface of a narrow walk, on steep ground, where it was difficult to make the gravel remain during rains, and with the same results.

These experiments (although not wholly failures) serve to show that the safest and probably the most practicable means that can be adopted for the drainage of walks in general are such as have been gradually brought into use in the Park, in the manner that has been previously described.

812. General Directions for the Construction of Gravel Walks.

(1) Excavate a trench the width intended for the walk, ten to twelve inches deep, leaving the bottom even and regular and slightly crowning in the centre, unless the walk is to be quite a narrow one. If the ground is not hard and firm, pass a garden-roller a few times over it. If it is wet and heavy, lay a line of 1½-inch drain-tile (using collars) along the walk as near the centre as practicable, and at a sufficient depth to be below the reach of frost.

(2) Fill the space excavated for the walk six to nine inches deep with field or quarry stones, placing the smallest on top. Select the softest and easiest stones to break, and hammer them up on top of the stone filling until the interstices are sufficiently filled to exclude the gravel. Rotten or partially decomposed stones will answer well for this purpose, or, if this material is not convenient, use a light layer of gravelly loam or hardpan. The surface will be further improved, previous to putting on the gravel, by sprinkling it and going over it a few times with the roller. The object of the process thus far is to secure a firm, well-drained foundation for the walk, having the surface interstices of the stone filling sufficiently closed to prevent the gravel from running down and filling up the voids below, and yet leaving free vent for surface-water to percolate through.

(3) If the stone filling is well prepared in this way, and the surface made even,—no points of large stones projecting, etc.,—two inches in depth of hard fine gravel will be sufficient to complete the walk. In applying the gravel a light layer should at first be put on and raked over evenly, working the coarser gravel forward

into any interstices or inequalities of the stone filling. Moisten this layer and roll it down firmly and evenly. The second and last layer, to make the most complete and agreeable surface, should be passed through a screen the meshes of which are not more than $\frac{1}{8}$ of an inch wide, and care should be taken in applying it not to rake up the first layer, and to spread it evenly—holding the handle of the rake nearly perpendicular. If it is not screened, more pains must be taken (with a fine rake) to exclude from the surface gravel that is too coarse and unequal in size to be agreeable to the foot. Next and lastly, sprinkle and roll the whole thoroughly. The gravel should not be drenched, but only made moist or damp in order to pack well under the roller. Until the walk has had some wear, it will be necessary, after dry weather, to trim the surface anew with the back of the rake, and to repeat the rolling occasionally. Roll after a light rain, but never when the gravel is dry or when too wet.

(4) A slight intermixture of clay or loam with the gravel will serve to make it pack or “bind” more firmly when desirable, and with less use of the roller; but this should be done with moderation, and no vegetable mould should be introduced to encourage the growth of grass or weeds. It is a great advantage to procure pure gravel: its freedom from earthy or vegetable matter prevents not only vegetation from taking root, but the liability to dust in dry weather and a muddy or slippery surface in wet weather. It also prevents the action of frost. It is better, therefore, to avoid any intermixture of other substances that will defeat these objects.

(5) The surface of a walk should be a little crowned in the centre, and should be provided with outlets through the grass borders, at suitable points, to carry off sudden accumulations of water. Where the walk has much inclination, and also where the outside drainage from adjacent ground is liable to be brought to it, more frequent outlets, cross-drains, etc., must be made.

(6) If, for any considerable distance along the walk, drainage-water from sudden rains cannot be conveyed away from it securely by these means, gutters must be made. These can be made in a variety of ways, but there are no gutters that give more permanent satisfaction, at a moderate cost, than those formed neatly with small cobble-stones. Suitable stones for the purpose can generally be selected from the gravel delivered for the walk, or from the pit from which it is obtained.

(7) A system of walks, extending over a large area of ground that is not naturally adapted to easy surface drainage, must have one or more main under-drains with subordinate or branch drains entering them from various points of the system, and with inlets from the gutters of the walks, silt-basins, etc., all of which must be adapted to the local circumstances in each case by special study or survey, and no general rule can therefore be given for their treatment.

(8) A walk can be cheaply made on light, well-drained soil by simply removing the turf to the depth of three or four inches and filling the space with gravel, raking the coarse forward into the bottom and leaving the fine on top. One half of the gravel, in this case (in the bottom), may be of inferior quality.

813. Curbstones.—Curbstones are employed for the outer side of the footways to sustain the coverings and form the gutter. Their upper edges are set flush with the footwalk pavement, so that the water can flow over them into the gutters.

The disturbing forces which the curb has to resist are: (1) The pressure of the earth behind it, which is frequently augmented by piles of merchandise, building materials, etc. This pressure tends to overturn it, break it transversely, or move it bodily on its base. (2) The pressure due to the expansion of freezing earth behind and beneath it. This force is most frequent where the sidewalk is partly sodded and the ground is accordingly moist. Successive freezing and thawing of the earth behind the curb will occasion a succession of thrusts forward, which, if the curb be of faulty design, will cause it to incline several degrees from the vertical. (3) The concussions and abrasions caused by the traffic. To withstand the destructive effect of wheels, curbs are faced with iron at certain places in the streets of London, and a concrete curb with a rounded edge of steel has been patented and used to some extent in this country. Fires built in the gutters deface and seriously injure the curb. Posts and trees set too near the curb tend to break, displace, and destroy it.

The use of drain-tiles under the curb is a subject of much difference of opinion among engineers. Where the subsoil contains water naturally, or is likely to receive it from outside the curb-lines, the use of drains is of decided benefit, but great care must

be exercised in jointing the drain-tiles lest the soil shall be loosened and removed and cause the curb to drop out of alignment.

The materials employed for curbing are the natural stones, as granite, sandstone, etc., artificial stone, fire-clay, and cast iron.

The dimensions of curbstones vary considerably in different localities, and according to the width of the footpaths: the wider the path the wider should be the curb. It should, however, never be less than 8 inches deep, nor narrower than 4 inches. Depth is necessary to prevent the curb turning over towards the gutter. It should never be in less lengths than 3 feet. The top surface should be bevelled off to conform to the slope of the footpath. The front face should be hammer-dressed for a depth of about 6 inches, in order that there may be a smooth surface visible against the gutter. The back for 3 inches from the top should be also dressed, so that the flagging or other paving may butt fair against it. The end-joints should be cut truly square, the full thickness of the stone at the top, and so much below the top as will be exposed; the remaining portion of the depth and bottom should be roughly squared, and the bottom should be fairly parallel to the top.

Curbstones should be inspected before they are set, and marks showing the rejected stone should be placed on the face in such position that they will be exposed to view should the stone be placed in position. For marking the stones white-lead mixed with turpentine is the best; it is not easily washed off, is conspicuous, and is not dirty to handle.

814. Setting Curb requires care and an experienced workman, for as it is set dry, great care must be exercised to set it true to level and line. It must be well rammed and bedded or it will sink, turn slightly over or move, even months after it has been set. Curbstones carelessly set will never present a pleasing appearance.

Curbstones to be set in concrete should be first set and blocked in position on grade and line. The blocking should be done with brick, paving-stones, or other imperishable material.

The inspectors should watch this work carefully, and see that the trenches are so prepared that the full amount of concrete may be deposited and tamped solidly into place.

In tamping the concrete under and around curbstones, a

wooden tamper made of a piece of seasoned oak two inches by four inches, about five feet long, shod with quarter-inch iron, makes an excellent tool for this purpose.

The concreting of the curbs (which should be done in advance of the roadway concreting) is best performed by first filling underneath from the roadway side, then upon the face and back up to the grade of the roadway, then filling up behind the stones to the required height, removing all blocking from behind the stones as the concrete is tamped in, taking care not to disturb the alignment of the curb and to see that every space is filled solid with the concrete.

In setting curbstones it is well to keep the ends from actual contact. For this purpose strips of $\frac{3}{4}$ -inch iron can be temporarily inserted between the ends as they are set and, after the roadway concrete is laid, the joints should be filled with a thin grout composed of equal parts of Portland cement and sand. This should be done by first pressing a small amount of stiff mortar into the joints at the face and back and then pouring the grout in from the top until the joint is full. A small wire used as a probe will aid materially in securing a full joint. If these joints are not filled solid, but simply smeared over the surface with a little mortar which only penetrates a half inch or less, it will only be a question of a short time when it will drop off and leave a cavity between the stones. In order to detect defective work in filling the joints, the inspector should, after the cement has hardened, test each joint by tapping on it with a small piece of metal; the sound will reveal the presence of cavities.

815. In localities where stone is not obtainable, artificial stone, fire-clay curb, and cast iron afford excellent substitutes. Artificial stone under the name of Asbestine Building-stone is used in some of the Western cities; it is manufactured from German Portland cement, sand, and broken stone.

Fire-clay curbing is extensively used with brick pavements; some of the usual forms are shown in Figs. 162 to 166.

Cast iron is employed in some cities in France; it is cast in L-shaped sections, as shown in Fig. 167.

Curbstones, gutters, etc., are manufactured in Germany from the following :

Clay.....	91½ parts
Iron filings.....	8 “
Common salt.....	2 “
Potash.....	1½ “
Ash of elder or willow wood.....	2 “

Various colors are produced, as follows:

Violet-brown.....	by 2 parts of	pyrolusite	to 100 parts
Violet.....	“ 1 “ “	“	“ “ “
Green.....	“ 1 “ “	copper scales	“ “ “
Blue.....	“ 1 “ “	oxide of cobalt	“ “ “
Yellow.....	“ 2 “ “	oxide of antimony	“ “ “

MONOLITHIC CURB AND GUTTER.—*Parkhurst Combined Curb and Gutter.*—This curb and gutter is composed of Portland cement, trap-rock crushed and screened to different grades of fineness, and sand. It is manufactured in place on the ground, and when completed the curbing is 6 inches thick, varying as desired from 5 to 10 inches high, with a gutter 12 inches wide. It forms a monolith on each block, weakened, however, by cuts extending partially through it at intervals of about 5 feet, to allow for expansion and disturbance caused by frost or other agent.

816. Specifications for Standard Granite Curb (Washington, D. C.).—The curbing must be of good and acceptable texture and color, dressed 12 inches on the face, 3 inches on the back, and chiselled 6 inches deep on the joints, with no projections beyond the chiselled portion of the joint; the joint to be at right angles to the face and top surface; the top surface to be bevelled $\frac{1}{4}$ inch; the face and top to be plane surfaces, without depressions or irregularities. The length must not be less than 6 feet, depth not less than 20 inches nor more than 24 inches in any portion of a piece, and

thickness 6 inches. The bed of the curb must average not less than 6 inches in width, and no excessive protuberance will be allowed on the sides.

817. Special 8 by 8 Inches Granite Curb.—The curbing must be of suitable and acceptable color and texture, dressed on top and the full depth on the face, and 3 inches deep on back. The top surface will be bevelled $\frac{1}{4}$ of an inch. The face and top to be plane surfaces, without bends, twists, depressions, cups, or other irregularities. It will be 8 inches thick, not less than 8 inches nor more than 12 inches deep, and no piece less than 6 feet long. The joint will be chiselled throughout. The bed will be rough-dressed to give secure bearing.

818. Specifications for Bluestone Curb (Washington, D. C.).—The curbing must be best North River bluestone, dressed 12 inches on the face and 3 inches on back, and chiselled 6 inches deep on



FIG. 162.

FIRE-CLAY CURB.




FIG. 163.



FIG. 164.




FIG. 165.



FIG. 166.



FIG. 167.—IRON CURB.

the joints, with no projection beyond the chiselled portion of the joint; the joints to be at right angles to the face and top surface. The top surface will be bevelled $\frac{1}{4}$ of an inch; the face and top to be plane surfaces, without bends, twists, depressions, cups, or other irregularities. The length must not be less than 4 feet, depth not less than 20 inches, and not more than 24 inches in any portion of a piece, and thickness 5 inches. Each piece must have a bed not less in area than the dressed portion of the curb, and no excessive protuberance on the sides.

819. Circular Curb.—Circular curb will conform in all respects to the specifications for straight curb, except that it will be cut to the required radius. It must be cut to such lengths that three pieces will make a 90-degree curve.

820. Specifications for Curbstones (New York).—The curbstones shall be of the best quality of North River bluestone, 5 inches thick, and not less than 4 nor more than 8 feet long, and 20 inches deep, cut and smooth dressed on the front to a depth of 14 inches, bevelled on top to the slope of the sidewalk. Ends shall be accurately squared, so as to make close joints the whole depth.

821. Specifications for Setting Curb (Washington, D. C.).—The trench will be dug 24 inches deep and 18 inches wide, to permit a thorough ramming. A bed of gravel 4 inches deep will be laid in the bottom of the trench and thoroughly consolidated. On this bed the curb will be laid to level and grade with close joints and even and continuous surfaces. The ditch will then be filled with gravel, the first filling to be not more than 3 inches deep, be well rammed by rammers or bars so as to give the curb a solid bearing under its entire length. Other layers will then be rammed in the ditch to within 10 inches of the top of the curb; the layer for each ramming to be not more than 4 inches deep.

The special granite curb will be laid on a foundation of hydraulic concrete, as shown in Fig. 168.

On the gravel-bed the concrete foundation made as prescribed for the concrete base for standard asphalt-pavements will be laid. This concrete base will be laid of such depth as to permit the granite curb (of which the depth will vary generally from 3 to 12 inches) to be placed upon it and remain at the proper grade. All spaces remaining between the curb and the concrete foundation will then be carefully rammed completely full with cement mortar

or fine concrete suitable for the purpose. The necessary concrete will then be added to bring the foundation to the dimensions shown in the cut. The work of setting this curb will be done by competent stone-masons. If so desired, the contractor will be authorized to




FIG. 168.—GRANITE CURB (WASHINGTON, D. C.).




FIG. 169.—BLUESTONE CURB.

finish the foundation in front of the curb with a layer of binder, as prescribed for the intermediate course in coal-tar distillate pavements, but no extra allowance will be made for such work.

822. Specifications for Artificial Stone Curb and Gutter (Washington, D. C.).—A combination curb and gutter of artificial stone

on concrete foundation will be laid on streets, as may be ordered by the Engineer Commissioner. The curb, gutter, and foundation will conform with the dimensions given on drawings on file in Engineer Department. The concrete foundation will be composed of the same materials and will be laid in the same manner as prescribed for concrete foundations of asphalt pavements. The curb and gutter will consist of fine concrete composed of one part Portland cement, two parts clean sharp sand, and three parts clean broken stone not more than 1 inch in their largest dimensions. The exposed surfaces of both gutter and curb will be coated $1\frac{1}{2}$ inch thick with a cement composed of three parts granulated granite (the fragments being of such size as to pass through a quarter-inch screen and free from all dust), and two parts of cement.

The cement used in the manufacture of the curb and gutter must conform to the current District of Columbia specifications for slow-setting Portland cement. The work will be carried on uniformly, and the whole curb completed while in a soft and plastic state, so that it will become a homogeneous solid when set. While still plastic the curb and gutter will be saw-cut at intervals of 8 to 10 feet, as may be ordered, to allow for expansion and contraction, and to give the appearance of cut stone.

Contractors may use such methods of moulding the curb into shape as they may deem best fitted to the work. The curb and gutter when set must conform with the cross-section shown in drawing.

A conduit for electrical conductors, 4 inches wide and 4 inches high, will be left at the base of the curb if so ordered by the Engineer Commissioner. Hand-holes, to give access to this conduit, will be left at intervals of 50 feet, more or less, as may be ordered, all to be as shown on the drawings. Man-holes will be constructed near each cross-street in accordance with plans and specifications on file in Engineer Department. The exact location of each man-hole will be fixed by the Engineer Commissioner. The cost of these man- and hand-holes, and their frames and covers, must be included in the price per linear foot of the "combination curb and gutter" with electrical conduit.

The curb and gutter must be properly protected from injury while setting, and the material used for such protection must be removed within twenty-one days from the completion of work, if so ordered.

The contractor is required by law to guarantee all work for the period of five years from the date of the completion of the contract.

823. Specifications for Dressing Old Curb.—Old curb will be dressed by the contractors for street improvements whenever ordered by the engineer.

Contractors will employ competent stone-cutters to do the work, and will be allowed the actual cost of the labor employed plus 15 per cent, for tools, sharpening same, and supervision. Certified pay-rolls of men employed and amount paid will be required for each street.

824. Re-setting Curbstones.—The curbstones along the line of the work shall be readjusted and brought to the grade, and lines given by the engineer, without extra charge therefor. All curbstones on the line of the work that are cracked or broken, or otherwise damaged, shall be re-dressed so as to conform practically in form, size, and quality to the requirements of the specifications for new curbstones. New stones shall be furnished when necessary, without extra charge therefor.

825. Hollow sidewalk curbs are shown in Figs. 170, 171; they are especially designed as a conduit for electric wires or cables or for pipes. They are the invention of Mr. E. Greyson Banner, of London, England.

The principle is shown in Fig. 170 in its simplest form. The block, *a*, may be of concrete, through which the channels *cc* are




Fig. 170.




Fig. 171.

HOLLOW CURB.

moulded, and which are accessible upon the removal of the flag *b*. This flag may be continuous in the case of pipes, but for wires, etc., it may be so arranged with hand-holes at short intervals.

Fig. 171 is a modified section for use where the wires are to be kept at a distance apart, for the sake of greater insulation, each wire having a separate channel.

The curb may be formed in place or manufactured at a factory, in which case the blocks, to secure alignment, are made with projections on one end which fit into corresponding recesses on the other.

826. Gutters.—In streets covered with broken stone, a stone gutter is necessary. It may be formed of either stone slabs or paving-blocks, the latter being the better. It should be not less than 18 inches wide. If formed of paving-blocks, the blocks should be laid with their length parallel to the curb, bedded on gravel, and well grouted in with bituminous cement.




FIG. 172. PLAN SHOWING MANNER OF LAYING GUTTER-STONES.

When stone slabs are used, they should be not less than 3 feet long, 6 inches thick, and from 10 to 15 inches in width. They should be laid alternately (see Fig. 172); for if of uniform width, the continuous longitudinal joint between the gutter and the rest of the pavement will quickly wear into long deep ruts or grooves, which causes severe strains upon the running-gear of vehicles when the wheels, having once entered the rut, attempt to leave it.

The gutter should have the same slope as the roadway, and the curb should show seven inches or more above it.

In streets paved with asphalt granite blocks or bricks the same material is used for the gutters; the blocks being laid with their length parallel to the curb, instead of transversely as in the street itself.

827. Specifications for Laying Cobble Gutters and Crossings.—

The cobblestone and flagging will be furnished by the along the line of the work.

The materials necessary to be removed shall be excavated to a depth of 12 inches below the top line of the proposed gutter or crossing when fully packed. Any objectionable or unsuitable material found below that depth must be removed, and the space filled with clean sand or gravel.

All holes or inequalities shall be filled to a proper level with sand or gravel well compacted by ramming or rolling. Upon the foundation thus prepared shall be laid a bed of good bank gravel, 5 inches in thickness, thoroughly compacted by rolling or ramming. Upon this shall be spread a layer of clean, sharp sand, to serve as a bed for the paving-stones, of such depth as may be required to bring the work to grade.

The cobblestones shall be assorted as they are brought upon the ground, and no stones that are less than 4 or more than 6 inches long, or less than 2 or more than 4 inches wide, shall be used, and the several sizes must be laid so as to make an even surface when rammed. When thus laid the stone shall be immediately covered with clean, fine sand, in proper quantities, and raked until the joints become filled therewith; the stones shall then be thoroughly rammed to a firm, unyielding bed with a uniform surface and proper grade.

The foundation for the gutter and crossing-flag shall be prepared in the same manner as described for cobble, upon which the flag shall be laid with close joints and settled into place solidly in such a manner as not to fracture the flag. When gutters are laid without curb, selected stones of large size shall be laid to line in the position and at the height that the curb would be if laid. This course must be laid true to line and grade and with especial care. Gutters will generally be 4 feet wide, with 12-inch flagging in the centre.

828. Specifications for Brick Gutters.—Whenever ordered on streets to be paved with asphalt, brick gutters will be laid. The materials necessary to be removed shall be excavated to a depth of 8½ inches below the top line of the proposed gutter. Any objectionable or unsuitable material found below that depth must be removed and the space filled with clean sand or gravel. All holes or inequalities shall be filled to a proper level with sand or gravel well compacted by rolling or ramming. Upon the foundation thus prepared there will be placed a layer of hydraulic-cement concrete 4 inches in thickness. This concrete layer shall conform, in all respects except depth, with the concrete base as specified herein for standard asphalt pavements. Upon the concrete base so prepared paving-bricks shall be placed on edge with their lengths at right angles to the curb and breaking joints in the direction of the curb. The

outer edge of the gutter shall be left with alternately projecting bricks to tooth into the asphalt pavement.

The bricks must be so laid that the upper surface will be smooth and at the proper grade.

Immediately after the completion of the asphalt pavement adjacent to the gutter, hot paving-tar shall be poured into the joints of the bricks until it rises to the surface. The gutter shall then be covered with a sprinkling of sharp dry sand. If so ordered, instead of the hot paving-tar a grouting of Portland cement and sharp sand in equal proportions, mixed with a sufficiency of water to make a thin grouting, will be used. The bricks for this gutter-paving will be furnished by _____ at its property yards, and hauled thence to the site of the work by the contractor for laying them.

Bricks for gutters may be furnished by the _____ at the site of the work. A separate bid is requested for the work if bricks be so furnished.

829. Specifications for Gutter-stones.—The gutter-stones to be of _____ stone, not less than 4 feet long and 10 to 16 inches wide, and 4 inches thick throughout; to have a smooth surface free from winds, seams, or other imperfections; to be cut and squared so as to form close joints with each other and with the curb.

The stones shall be laid, at the grade furnished, on a bed of sand 2 inches thick. The joints of the stones shall break joint with the joints of the curb. The stones shall be laid narrow and wide alternately. The joints shall be filled with a bituminous-cement or Portland-cement mortar.

830. Crossing or Bridge-stones.—Street-crossings are footways provided for pedestrians; they are formed of two or more rows of stone slabs, usually with one or more rows of paving-blocks between them.

The stone used for crossings should not be less than 3 feet long, 10 inches wide, and 6 inches thick, with the top surface hammer-dressed, the ends cut to a bevel of about 15° , as shown in Fig. 174, and dressed so as to form a close joint for the full depth of the stone. The reason for bevelling the joints is to cause the traffic to travel across the joint instead of along it, and thus prevent the formation of the ruts which happens with right-angled joints. The bevelled joints must point towards the centre of the intersection, otherwise the desired result will not be obtained, and ruts will be formed.




FIG. 173. SECTION AT CROSSING, SHOWING GUTTER PAVED WITH STONE BLOCKS.




FIG. 174. PLAN OF CROSSING, SHOWING BEVELLED JOINTS.




FIG. 175. SECTION OF CROSSING SHOWING GUTTER PAVED WITH A SINGLE STONE.

Sandstone is superior to granite for this purpose.

At street-crossings the bridge-stones should be kept level with the curb so that pedestrians may step off the path onto the crossing without any drop (see Figs. 173 to 176).




FIG. 176. COVERED GUTTER.

831. Specifications for Bridge-stones (New York).—Bridge-stones to be of bluestone, equal to the best quality of North River bluestone, free from seams and imperfections. Each stone to be not less than 4 nor more than 8 feet long, except in cases where specially permitted, and 2 feet wide, and of a uniform thickness, which may vary from 6 to 8 inches, and dressed to a fall on top not varying in evenness by more than a quarter of an inch, and on the bottom bedded, with sides square and full, and ends cut to a bevel of 6 inches in 2 feet, and in special cases to such other bevel as shall be directed by the Commissioner of Public Works. The stones to be in quality and workmanship equal to the pattern at the office of the Department of Public Works, and to be cut so as to lay a joint not exceeding one fourth of one inch from top to bottom on the ends and one half inch on the sides.

The bridge-stones will be carefully inspected after they are brought on the line of the work, and all those which, in quality and dimensions, do not conform strictly to these specifications shall be rejected and must be immediately removed from the line of the work.

832. Relaying Bridge-stones.—The bridge-stones now on the street shall be relaid without extra charge therefor. If any are found defective, new stone shall be furnished therefor at the expense of the contractor. The stones so furnished must correspond in quality, dimensions, and workmanship to the pattern at the office of the Department of Public Works.

833. Prices.—The prices of the materials employed for footway pavements fluctuate widely, not only in different but in the same localities; therefore the following prices simply exhibit the extreme range:

	Cents.
Bluestone flagging 8' thick, per square foot.....	35 to 95
Granite stone flagging 6' thick, per square foot.....	40 " 110
Cement concrete " "	12 " 20
Artificial stone " "	18½ " 30
Brick " "	9 " 22½
Granite, straight, per linear foot.....	85 " 125
" circular, " "	100 " 137
Bluestone curb, straight, per linear foot.....	35 " 91
" " circular " "	45 " 110
Sandstone curb, straight, " "	35 " 75
" " circular, " "	60 " 100
Brick gutters, per square foot.....	20 " 38
Granite " " "	40 " 50
Granite bridge-stone per linear foot.....	70 " 234
Bluestone " " "	60 " 115

CHAPTER XVIII.

RECONSTRUCTION AND IMPROVEMENT OF COUNTRY ROADS.

834. THE improvement of existing roads may be divided into three branches:

- (1) Rectification of alignment and grades.
- (2) Drainage.
- (3) Improvement of the surface.

The first of these consists in the application of the principles which have been laid down for the location, etc., of new roads, and will include straightening the course by extinguishing unnecessary curves and bends; improving the grade by either avoiding or cutting down hills and embanking valleys; increasing the width where requisite, and rendering it uniform throughout.

The second consists in applying the principles laid down for the drainage of new roads, and in constructing the works necessary to give them effect.

The third consists in improving the surface in the best possible manner, either by the forming of an artificial pavement or, if sufficient funds for this purpose are not available, by adopting such local materials as will make a comparatively fair surface.

835. Improving Clay Roads.—Clay soils can only be made into fair wheelways by means of thorough drainage effected by any of the methods described in Chapter XIV.

The narrower the roadway the more effective will be the drainage.

If sand, gravel, ashes, coal-dust, furnace-slag, or shells can be obtained, a coating of any one of them, 4 inches thick, well compacted by rolling, will form an improvement; if none of these materials can be obtained, the clay itself may be utilized by being first burned, then spread and rolled.

The manner of preparing and using the clay is as follows: In summer weather, or during the hot season, the soil in the proposed road should be cut out to a depth of two feet into large spits and laid roughly one upon the other, and left in that condition for about ten days. By this time the sun's rays will have evaporated the moisture held by soils of this nature. So soon as the spits are dry they are submitted to the action of fire in the following manner: A circle is formed fifteen feet in diameter, surrounded by a wall made of the roughest and largest spits, two feet high. In the inclosure thus formed straw or other light combustible material is laid; fagots or small pieces of wood are placed on these, and over them are placed other spits, so as to form a cone or pyramid, the whole structure to be about 8 feet high. Fire is then applied to several parts at once, due care being taken to see that the spits sink evenly until the whole mass is well alight. After being well banked the mass is left for a day or two, and as soon as it attains a good red appearance is drawn down, the wall broken, the spits are thrown on top, and others added as required from day to day, until all the earth dug has been submitted to the same process. In a length of 100 yards of road 20 feet wide thus served, it would take about six fires to burn the 12,000 cubic feet contained therein. The cost of labor would probably be twenty or twenty-five cents per cubic yard. The burnt earth is then, after cooling, relaid upon the road, and now, being of a thoroughly porous nature, settles into a good, dry, solid layer.

Before applying any of the above-mentioned materials to a clay surface all mud and perishable material must be removed. In fact, all the weather-worn clay should be removed to a depth of 18 inches or more, and the surface thus exposed thoroughly consolidated by rolling.

836. In the maintenance of clay roads neither sods nor turf should be used to fill holes or ruts; for, though at first deceptively tough, they soon decay and form the softest mud. Neither should the ruts be filled with field-stones: they will not wear uniformly with the rest of the road, but will produce hard ridges.

Trees and close hedges should not be allowed within 200 feet of a clay road. It requires all the sun and wind possible to keep its surface in a dry and hard condition.

837. Sand Roads.—The aim in the improvement of sand roads is to have the wheelway as narrow and well-defined as possible, so as to have all the vehicles run in the same track. An abundant growth of vegetation should be encouraged on each side of the wheelway, for by this means the shearing of the sand is in a great measure avoided. Ditching beyond a slight depth to carry away the rain-water is not desirable, for it tends to hasten the drying of the sands, which is to be avoided. Where possible the roads should be overhung with trees, the leaves and twigs of which catching on the wheelway will serve still further to diminish the effect of the wheels in moving the sands about. If clay can be obtained, a coating 6 inches thick will be found a most effective and economical improvement. A coating of 4 inches of loose straw will in a few days' travel grind into the sand and become as hard and firm as a dry clay road.

838. The maintaining of smooth surfaces on all classes of earth roads will be greatly assisted and cheapened by the frequent use of a roller (either steam or horse) and any one of the various forms of road grading and scraping machines. In repairing an earth road the plough should not be used. It breaks up the surface which has been compacted by time and travel.

839. Improper Use of Scraping-machines.—The scraping-machine should not be employed to drag the soft mud out of the ditches and place it in the centre of the road. The use of the scraper is to remove from the road-surface the weather and traffic-worn material which no longer possesses coherence, and which, no matter how well rounded up and rolled, will be converted into mud after the first shower of rain. This material, along with that removed from the side ditches, must be deposited in such places where it cannot be washed back on the road-surface. As it consists chiefly of alluvial and vegetable matter mixed with animal excreta, it is useful for fertilizing purposes and may be disposed of to the neighboring farmers; but it must not be left in heaps on the roadside, to be removed by them at their leisure.

840. Cost of Constructing Earth Roads.—The following prices are taken from the bids received for the construction of wagon-roads through the Yellowstone National Park. The specifications were: clearing, 30 feet wide; roadway, 18 feet wide and 6 inches higher at the middle than the edges; on each side a berme of 1

foot, with a ditch on the outer side 5 feet wide at top, 2 feet at bottom, and 18 inches deep. The roadway to be covered with 9 inches of clay or earth.

PRICE PER MILE.

Highest, \$4382.

Lowest, \$2529.

841. Cost of maintaining earth roads ranges from \$50 to \$80 per annum per mile.

842. Value of Improvements.—The improvement of roads is chiefly an economical question relating to the waste of effort and the saving of expenditure. Good roads reduce the resistance to locomotion, and this means reduction of the effort required to move a given load. Any effort costs something, and so the smallest effort costs the least, and therefore the smoothest road saves the most money to every man who traverses it with a vehicle.

843. Before undertaking any improvement it is generally required to know the cost of the proposed improvement and the benefits it will produce. In the improvement of roads the amount of money that may be profitably expended for any proposed improvement may be calculated with sufficient accuracy as follows. First obtain the following data:

- (1) The quantity and quality of the traffic using the road.
- (2) The cost of haulage.
- (3) Plan and profile of the road.
- (4) Character and cost of the proposed improvement.

844. From the data so obtained ascertain the total annual traffic and the total annual cost of hauling it. Next, calculate the annual cost of hauling the given tonnage over the improved road, which may be obtained from the data given in Chapter X. Then the difference between the two costs will represent the annual interest on the sum that may be expended in making the improvement. For example, if the annual cost of haulage over the given road is \$10,000 and the cost for hauling the same over the improved road will be \$7000, the difference, \$3000, with money at 6% per annum, represents the sum of \$50,000 that may be expended in carrying out the improvement.

845. For the purpose of ascertaining the amount of money that may be profitably expended in improvements, each part of a given road must be separately investigated as above directed,

because the amount that may be expended varies with the amount of traffic; and as the quantity of traffic using different portions of a road varies, the data obtained close to a town cannot be taken as correct for distant portions, nor the data obtained for distant portions as correct for portions close to towns.

846. The defects of existing roads may be stated as follows:

- (1) Unnecessary ascents and descents.
- (2) Unnecessary length.
- (3) Imperfect surface.

The money benefit accruing from the elimination of any one or all of these defects may be approximately calculated as follows:

847. Profit of Eliminating Grades.—Take for example the elimination of a 5% grade 1 mile long from an earth-road. The observations on this grade show that the daily traffic over it is 224 teams, each dragging an average load of 800 pounds, equivalent to 24,000 tons per annum; that the time occupied in traversing it is half an hour; that the value of a team's labor is 30 cents per hour. Therefore the cost of haulage on this grade is $33\frac{1}{10}$ cents per ton-mile, or \$8064 per annum for the total tonnage using it.

From an examination of the ground we find that the grade can be reduced to 2% by constructing a new piece of road 2 miles long, and that the cost of the change will be \$18,000.

From the resistance to traction opposed by the new road-surface plus the effect of gravity we find that a team will haul a load, on the reduced grade, of 1200 pounds, and that the time occupied in travelling the two miles will be one hour. Therefore the cost per ton-mile will be 28 cents, or \$6720 per annum for the total tonnage. To this add the annual cost of maintaining the extra mile of new road, say \$200; this gives \$6920 as the cost per annum, which subtracted from the original cost of \$8064 leaves \$1144; which sum, with money at 6%, represents a capital of \$19,066, a sum sufficient to make the proposed change.

848. The money loss caused by grades may be approximately ascertained as follows: Ascertain the cost of hauling a ton on level portions of the same road and on the grade; take the difference and multiply it by the annual tonnage: the product represents the annual loss. For example, the cost per ton-mile on a level is 22.50 cents, on a 5% grade 33.60 cents; difference 11.10 cents = loss per ton, or an annual loss on a traffic of 30,000 tons of \$3330, which is

the interest at 6% on \$55,000; which sum the community could borrow for the purpose of reducing the grade to a level, pay the interest and be no worse off financially, and have a good road besides.

849. Profit of Decreasing Length.—The Profit arising from the elimination of any unnecessary length may be stated as follows:

- (1) Saving in time.
- (2) Reduction in wear and tear of horses and equipment.
- (3) Saving the cost of maintenance of such unnecessary portion.
- (4) Reduction in the cost per ton-mile of haulage.
- (5) Saving by the return of the land previously occupied by the road to other and perhaps more remunerative uses.
- (6) The decrease in the working time of the horses will permit of a slight increase in the load.

The saving in the above items will vary directly as the distance saved.

As an example take a level road 5 miles long and, neglecting the saving in time and rental value of the land saved, and increase of load, what will be the effect of decreasing its length one mile?

- (1) Saving of the annual maintenance of 1 mile.
- (2) Reduction of the time required in travelling over the road, thus permitting persons who make several daily trips to make an extra trip per day at the same cost for driver and horse-feed and with no extra fatigue to the horses.
- (3) Saving in wear and tear of horses shoes, harness, and vehicles.
- (4) Saving in the ton-mile cost for haulage.

Assuming observation of the traffic to show that 100 teams drawing average net loads of 2500 pounds use the road daily, and that the cost per ton-mile is 20 cents, therefore the annual tonnage = 33,480 tons, and the total annual cost of haulage per ton-mile = \$6696.

Summing up the items, we have:

Saving of maintenance 1 mile.....	\$50.00
33,480 ton-miles, at 20 cents.....	\$6696.00
	<hr/>
	6746.00

Which is equivalent to the interest at 6% on \$112,433, which sum could be borrowed to make the improvement.

850. Profit of Improving the Surface.—The benefits accruing from this improvement are a general reduction in the cost of haulage and wear and tear. The smooth, hard road-surface enables the same power to haul a greater load with the same and even less fatigue than it can on a rough surface.

The less the resistance to traction the greater the load, and the greater the load the sooner will the produce be marketed. Besides the wear and tear on a smooth surface is not one third that on a rough surface.

Assuming that it is required to know how much may be profitably expended in improving the surface of a level earth road one mile long, and that the observations show that it is used by 50 teams per day, each dragging when the road is in good condition a net load of one ton, and when in bad condition a net load of 1200 pounds, and that the cost per ton-mile when the road is in good condition is 18 cents, and when in bad condition 39 cents; that the road is in good condition for one half the year, and in bad condition for the other half; that the cost of paving and improving the road will be \$7500 per mile,—then we have:

150 days, at 50 tons =	7500 tons, at 18 cents.....	= \$1850.00
150 " " 27 " =	4050 " " 39 "	= 1579.50
	11,550 "	
Cost of maintaining the earth road.....		50.00
		<u>\$2979.50</u>

$\$2979.50 \div 11,550 = 25.81$ cents, average cost per ton-mile for haulage.

On a broken-stone road in its average condition and at all times throughout the year a team of horses will draw a net load of 3 tons at a speed of 3 miles per hour. If the cost of horses' labor, drivers' time, etc., be taken at 30 cents per hour, the cost per ton-mile will be 10 cents, or for the 11,550 tons annual traffic \$1155; to which add for annual maintenance of one mile of road \$350. The annual cost will therefore be \$1605, which deducted from the former cost of \$2979.50 leaves \$1375, which, with money at 6% is equivalent to the annual interest on \$22,916, which sum may be expended in improving the road-surface one mile long.

The annual loss occasioned by the waste of motive power on

unimproved road-surface is clearly shown by the above calculations. In the best condition of the earth road it required 50 teams to move 50 tons; on the improved surface but 17 teams are required to perform a like work, and the labor of the teams formerly required may be more profitably employed at other work. On the earth road in its worst condition it required two teams to move one ton; on the improved surface but one team is required to move three tons.

851. Any calculations made to ascertain the benefits accruing to a community from improved roads must necessarily fall far short of the truth, since no account can be taken of the saving in wear and tear of horses and vehicles, of the saving in time caused by the increased size of the loads, which thus decrease the number of days on which hauling must be done, thus allowing the time to be more profitably employed, or of the enhancement of the value of the land in consequence of the improved roads, or of the social advantages arising from their improvement.

CHAPTER XIX.

MAINTENANCE.—REPAIRING ; CLEANSING ; WATERING.

852. Maintenance.—The maintenance of a roadway is the keeping of it, as nearly as practicable, in the same condition as it was when originally made; the *repair* of a roadway is the work rendered necessary to bring it up to its original condition after it has become deteriorated by neglect to maintain it. Thus there is a wide distinction between the two operations, and when the comparison of costs is instituted errors are frequently caused by setting the repairs of one road against the maintenance of another or *vice versa*.

853. Necessity for Maintenance.—No matter how well made a structure may be, or how carefully the materials used have been inspected, the use of it will exhibit defects which it is almost impossible to guard against, such as variableness in the quality of the material and slighting on the part of the workmen. Moreover, every material, whether natural or artificial, is continually undergoing a process of deterioration by the action of the elements; this decay is hastened or retarded in proportion to the means employed and care bestowed to arrest it. The materials employed for pavements are not only subjected to the destroying action of the elements, but also to abrasion and concussion, which by themselves are powerful destroying agents. In view of these facts the continual presence of workmen engaged in repairing pavements must not in all cases be considered as evidence of defective construction or improper materials, but as an honest endeavor by those in charge of the highways to preserve the surface in good travelling condition.

854. The essential requisite to the preservation of a good surface is eternal vigilance on the part of the roadway keepers. If a depression appears in consequence of settlement, defective material, or other causes, it must be at once eliminated; if not, it will be

quickly deepened and enlarged by each succeeding vehicle, and will thus become an obstacle to safe travelling.

855. Good Maintenance comprises:

(1) Constant daily attention to repair the ravages of traffic and the elements. The character and quantity of these repairs will vary with the character of the pavement and the manner of its construction. With granite blocks laid on a concrete foundation they will be the least, with broken stone they will be the greatest; the other materials, as wood, asphalt, and brick, lying between.

(2) Cleansing, i.e., removing the detritus caused by wear, horse-droppings, and other refuse finding its way into the streets.

(3) Watering to lay the dust.

856. Systems of Maintenance.—Three systems of maintaining pavements are in vogue:

(1) By contract, at a fixed price per square yard per annum for a fixed period. Under this method asphalt pavements are maintained in both the United States and Europe. Wood pavements are also maintained under this system in Europe, but rarely in America. The form of contract under which this system is carried out in Europe is given in Articles 214 and 265. The advantage of this system is that of having some one admittedly responsible for the condition of the pavement. Its defects are (a) the difficulty of determining the exact condition the pavement is in at the expiration of the contract. (b) It is an extremely costly system.

(2) By independent contracts for the labor and materials, the tools and supervision being furnished by the city.

(3) By men in the employment of the city, materials, etc., being purchased in the open market. This is the system adopted by the city of Liverpool, and the excellence of that city's pavements needs no comment.

857. Maintenance of Country Roads.—When a country highway is finished and thrown open to traffic, it cannot be left to take care of itself; if it is, it will soon deteriorate and become bad. It is to the thorough appreciation of this fact that the excellence of the European roads is due. Upon its completion a system of maintenance must be instituted. Three systems are in vogue: (a) By contract with private parties. (b) Personal service by the rural population. (c) By men permanently employed for the purpose by the community.

(a) The contract system is unsatisfactory, from the difficulty of getting a proper observance of the terms of the contract from the contractor or his employers.

In Austria during the last century experiments were made with the letting of the maintenance of the state roads to private parties, which experiments proving unsatisfactory, caused the government to take the work in hand, and it has adhered to this practice up to the present day, with a short interruption in the years 1858–1861, during which time the keeping of the roads was again let by contract, and again gave unsatisfactory results.

(b) The personal-service or labor-tax system is not applicable to the maintenance of improved roads. In fact, it is not applicable to any class of roads; it is unsound in principle, unjust in its operation, wasteful in its practice, and unsatisfactory in its results.

(c) By men permanently employed for the purpose by the community. This system has been adopted by France, Germany, and nearly all European countries. Its advantages are many. The men so employed become familiar with the peculiarities of their sections and with the best way to deal with them, and good men soon learn to take an interest in the road which it is their business to keep in order. "It is in vain to expect the same skill or industry from men employed by the job, or having no interest in the goodness of the road, or in making the most of the means at their disposal."

858. The maintenance or keeping of the road in proper order consists of:

(1) The daily removal of the detritus either in the form of dust or mud, the horse-droppings and other rubbish.

(2) The filling of ruts or depressions.

(3) The cleansing out of the ditches, catch-basins, and water-courses.

(4) Watering the surface in dry weather.

The disintegrating action of the weather and the friction of the traffic produces dust; this dust renders the road heavy for traffic and annoys passengers and horses. If rain falls, the dust is converted into mud. A well-swept road produces no mud after a rain, at least not for several days. However, if the humidity continues, the road-surface becomes at first sticky and finally is covered with mud. Mud makes the tracks of wheels apparent; other vehicles

follow in them, and after a while ruts are formed which injure the road. Thus it is essential that the dust and mud be removed from the road-surface. The dust may be removed by sweeping, the mud by scraping. These sweepings and scrapings should not be left on the sides of the road to be redistributed by the first wind, but should be immediately removed: they might be utilized by the farmers as an adjunct to their manure-pile.

(1) The best time for sweeping is early in the morning before the dew has dried; besides, there is less inconvenience to the traffic at that time.

The removal of dust and mud may be effected either by brooms and hand-scrapers or by mechanical sweepers and scrapers drawn by horses. In the rural districts the former will be most suitable, while in the vicinity of towns the latter will be most economical.

(2) Daily attention must be given to the making of slight repairs such as filling ruts and depressions; for, however well the materials may be laid and rolled, the traffic will search out the places which are weak or have escaped the full pressure of the roller.

(a) All ruts should be at once filled. If there are three parallel, the centre rut should be first filled. The traffic is thus slightly diverted, as a horse will avoid new metal.

(b) Depressions or hollows should be filled at once. The surface of the road should never be allowed to lose its regular section.

(c) If the surface of the road where these patches are to be placed is very hard, it must be loosened up with the pick.

(d) Water lodging in a depression should not be let off by digging a trench with the pick-axe to the side of the roadway. The depression should be filled up.

(e) All loose stones should be picked off at once and stored for use in filling hollows. If allowed to remain, they are not only dangerous to horses, but are liable to be crushed or to be forced through the skin of the roadway, thus causing damage.

(3) At all seasons of the year the gutters should be kept free from mud and rubbish of all sorts, and anything that impedes the free discharge of the rain-water from the road must be removed.

The ditches and culverts should be well cleaned out in advance of the spring and fall rains. In northern localities, where snow lies for some time, the outlets of all ditches and culverts should be

opened and cleaned out before the spring thaw sets in. In the fall all weeds and grass in the ditches should be cut, and the culverts and water-outlets left in good shape for the winter.

All bridges should be examined at least twice a year.

All structures such as bridges, culverts, and drains should be numbered, the numbers being legibly painted on some prominent part; and a book should be kept in which the dates and condition at periodical inspections are entered.

Retaining-walls should be examined and repaired at least once a year.

Guard-stones should be reset immediately they become displaced.

Parapets, mile-stones, and guide-posts should be periodically examined, repaired, and reset.

(4) Watering to lay the dust is essential in summer and occasionally in winter. In summer, during the dry hot weather, the road-surface becomes extremely brittle and then should be watered, the dust and refuse having been first removed.

Sometimes, in winter especially, after frost the road gets very sticky and picks up freely under passing wheels. It should then also be watered and all slush and mud removed. When the dust is regularly removed from a road it does not require so much watering in dry weather as it otherwise would.

A road should never be watered unless it really needs it, as too much water is injurious and it increases the wear from traffic.

The most common method of watering a road is that of carrying the water in barrels mounted on wheels or vehicles specially constructed for the purpose and distributing it therefrom through a perforated pipe.

858a. The Errors Commonly Committed in the Maintenance of Broken-stone Roads are:

(1) *The Unskilful Application of Materials.*—This means using more material than is legitimately required, and the applying it in an improper manner. Roads always wear out in a succession of small round holes or long straight lines. The usual unskilful method of repair is to put a square patch on a round hole. This means that at least a third too much material is used, with a bumpy or uneven surface as the result; or the long lines are filled up too full, and the overplus means so much stone wasted. In

coating a large surface it is the aim of an unskilful roadman to spread all the stone he can, "to make a good show." The result is the material is heaped on, often three stones thick, or else scattered about as if sprinkled on the surface. Material thus improperly placed will not be consolidated in the position it was originally intended for; it will be rolled about by each passing vehicle; it thus loses its size, its shape, its angles (so necessary for proper consolidation), and annoys every one using the road. The material so wasted makes the cost of maintenance 15 to 20 per cent greater than is necessary. The misapplication of the material also produces an extremely uneven contour, which necessitates a great amount of new material being again applied later to remedy the unevenness that could be easily obviated if the material at first had been properly applied.

No material should be placed on the road-surface until the latter is properly prepared to receive it. If ruts have formed, only just sufficient stone should be used to fill the ruts to the level of the adjoining road-surface (it is far better to underfill a rut than overfill it). Material can always be added without much expense, but ruts filled too full not only cause needless inconvenience, but material is used wrongfully, and becomes absorbed where it is not required, adding a large expense. If the road is regularly coated and maintained, there is no reason why ruts should form. If the manual labor is efficient, no ruts will form—if directly a road is tracking, which is the real preliminary for ruts, steps are taken to turn the traffic. This is easily done if the surface is kept clean and free from detritus. When a road shows signs of wearing out small holes successively appear, and these should at once be attended to. The correct process is to open the edge of these wearing holes about 3 inches over the exact edge by picking up the road-surface with a sharp pickaxe, then fill with fine stone run out to a thin V-point, and cover with sharp sand or road-scrappings. In dry weather the materials should be moistened with water.

In coating large surfaces the material should not be applied more than two stones thick at one time; otherwise the bottom layer will not be consolidated, the top layer *will* be, and when a secondary settling takes place this will collapse and an uneven surface will result. In patching or coating a hill it is practically

impossible to make a patch lie firm unless the road is cross-scored. The extra labor for this is but a very minor expense compared with the loss of value of material where it remains kicking about without being consolidated. Where roads are continually in ruts, and there is no special reason for such to show, it will usually be found useless to attempt any remedy other than the taking up of the rutted portion, strengthening the foundation, and relaying the material. This seems expensive, but it will be found to be the most economical, and a lastingly good road will result.

(2) *Use of Improper Materials.*—Well-made roads are frequently ruined by the use of local materials whose first cost is cheap, but excessively dear in the end, by want of substance and unsuitability for the purpose required.

(3) *Neglect of Repairs.*—By neglecting to make repairs and restore worn-out material the road becomes so “thin” that it collapses under the traffic. The neglect of applying new material is termed “starving” the road. The remedy is a most expensive one, for the whole of the “starving” has to be made good at once, instead of being spread out in proper maintenance over a period of years.

(4) *Insufficient and Unskilful Manual Labor.*—Manual labor must of necessity be employed for caring for the road, and upon its efficiency and skill will depend the condition of the road. This, being the easiest portion of road maintenance to abolish for “saving,” and the most constant source of apparent expenditure, is generally the first to suffer when “economy” takes the place of *efficient* and economical management; but there is no more wasteful system, leading to bad roads, than thus starving roads. Manual labor should be arranged so as to allow each workman to be properly instructed and superintended. Without this, the manual-labor difficulty will be found to be one long series of annoyance and disappointment. Until a workman thoroughly appreciates that *he* is responsible for a good road, and not responsible for making a “show,” he is no good as a roadman. “Here’s a hole, put a shovelful of stones into it,” is not road-repairing.

The ever-changing “system” of management invariably results in bad roads. No roads can be effectually maintained where the head or *personnel* is constantly changing. Each change usually has

the same unsatisfactory ending; the roads will be surfeited with material, more often bad because it is cheap, or else starved of necessary material or labor because the initial outlay is great or appears so.

859. Amount of Water Required.—Mr. E. P. North found the amount of water necessary to keep macadam roads in the vicinity of New York from becoming dusty to be at the rate of 71.3 cubic feet per 1000 square yards applied twice in a day, or say 143 cubic feet per day. In very hot or beezy weather this was not quite enough.

On the telford roads in New York 25 cubic feet applied four times a day are necessary per 100 square yards, or about 100 cubic feet per day.

One water-cart holding 79 cubic feet waters 35,000 square yards four times a day, keeping it free from dust except during windy weather.

860. Cost of Maintenance.—The cost of maintenance is very variable, being principally dependent upon the degree of perfection with which the road has been constructed, but largely influenced by the employment of a sufficient number of skilled laborers to maintain the surface in proper condition under skilled supervision.

The cost of maintaining the roads of France varies from \$60 to \$500 per mile, with an average of \$150, of which about half is for labor and half for materials.

The following table gives the cost per annum per square yard for the maintenance of macadamized streets in different localities:

Bristol, Eng.....	8 to 24 cents
Charing Cross, London*.....	100 "
Glasgow, Scotland.....	17 "
Leeds, Eng.....	20 to 26 "
Liverpool, Eng ...	24 " 36 "
Manchester, Eng	12 " 40 "
Paris, France.....	19 " 258 "
Toronto, Can.....	24 "
Belgium	4 " 10 "
Germany	20 " 80 "

* Now paved.

The annual expenditure necessary to keep a given highway in proper repair may be ascertained very closely by combining the different factors of cost. These factors are:

I. *The average number of cubic yards of stone per mile* which will be necessary to keep the road in proper repair, or, in other words, the quantity of stone which will be required to replace the annual wear caused by traffic and the weather, and removed in the form of mud and dust. This quantity depends upon the following subsidiary factors:

1. Width of road.
2. Nature of foundation, drainage, and thickness of crust.
4. Situation of the road.
5. Quality of the stone to be applied.

One cubic yard of stone broken to pass through a 2-inch gauge will cover 30 square yards of road, one stone thick, and will give $\frac{1}{2}$ inch thickness of consolidated material. The quantity of material required to cover a mile of road is evidently directly proportional to the width of the road. On a road 16 feet wide, having a sufficient thickness of crust composed of good sound stone, having a good foundation, the road being well drained and freely accessible to sun and wind, the traffic being equal to 100 tons per day—not of an extraordinary nature, and carried on broad-tired wheels—the wear should be about one-eighth of an inch per annum. Such a road would require about 54 cubic yards of good sound broken stone per annum to keep it in repair.

II. *The cost of the material.* If this is procured by contract, its cost will be positive, but if procured by day's labor under the supervision of the authorities, its cost will depend upon the following subsidiary factors:

1. Cost of quarrying, including labor, supplies, use of tools, and royalty or interest on cost of quarry.

The cost of quarrying varies with the nature of the stone and character of the quarry. An average price, including all items of cost, is about 60 cents.

2. Cost of breaking, including labor, supplies, interest, and depreciation of plant.

The cost of breaking varies with the stone and ranges from 30 to 80 cents per cubic yard.

3. Cost of hauling from quarry to depots at the roadside.

This cost varies with the distance and character of the roads, and ranges between 20 and 50 cents per cubic yard per mile.

4. Cost of stacking at the roadside.

This may be taken at 5 cents per cubic yard.

5. Cost of loosening the stones in the heaps (a considerable item in frosty weather or when the stones have lain for some time).

6. Cost of hauling stones from depots to the portion of the road where they are to be used.

7. Cost of preparing the road-surface to receive the stone.

8. Cost of spreading the stone.

The combined cost of the items 5, 6, 7, and 8 varies between 20 and 50 cents per cubic yard. As it consists of manual labor performed by the same men it is difficult to affix a specific value to each item.

III. *The cost of compacting the stone.* This item is very variable; it includes the wages of roller attendants, two sweepers, team labor for hauling water, coal, oil, brushes, etc., interest and depreciation about 20 per cent of the cost of the roller plant. An average is about 28 cents per cubic yard.

IV. *Cost of cleaning and scraping.* This depends upon the width, nature, and situation of the road, the nature of the traffic, and the quality of the stone. Much diversity of opinions exists as to the frequency and methods of cleaning, and scraping, but it is generally conceded that a road should be scraped as soon as the thickness of the mud reaches one-fourth of an inch. But scraping is not the best or cheapest form of cleaning a road. Mud is but the refuse of a road with water added. If this refuse is removed when the road is dry, and in consequence dusty, a hand or machine broom can remove nearly three times as much dust as can be scraped off in the form of mud, and the surface of the road will not be injured or torn up. One sweeping will generally clean a road perfectly: whereas when a scraper is employed it must be gone over three or four times before the surface is clean; but under certain conditions of the atmosphere the surface of the road is too sticky to allow of

sweeping, and at such times it is impossible to do without a scraper. Its use should be as limited as possible, for it will permanently damage a road more quickly than any other method by pulling up the compacted stone.

V. *The cost of cleaning up the sides of the road, ditches, etc., and keeping open watercourses.* This depends upon the frequency with which it will have to be done; usually three times a year is sufficient, and an average price is \$15 per cleaning per mile.

VI. *The cost of sprinkling.* This depends upon the frequency of sprinkling and accessibility of water, and is made up of team labor for hauling the sprinkling-cart, wages of driver, cost of water, interest, and depreciation of the sprinkling-plant. The average number of days on which sprinkling is needed is 180; number of daily sprinklings, once per day per mile; average cost, 70 cents per mile.

To these items must be added a certain sum (about \$5) per mile for repair and replacing of tools, etc., and about 5 per cent on the total cost to cover the administrative charges.

Combining these factors in the following manner will give the probable cost of maintenance per mile of a given road:

Let N = average number of cubic yards of stone spread per mile;

A = cost per cubic yard of stone in depots;

L = cost of preparing road-surface and spreading stone;

R = cost per cubic yard of rolling;

C = average number of times sides will require cleaning;

c = cost of cleaning sides, etc., per mile;

S = average number of times road will require cleaning;

s = cost of cleaning per mile;

W = average number of times road will require sprinkling;

- w = cost of sprinkling per mile;
 D = annual depreciation and renewal of hand tools;
 I = cost of administration, say 5 per cent of total cost;
 X = cost of maintenance per mile per annum.

Then

$$X = N(A + L + R) + Cc + Ss + Ww + D + I.$$

If the stone is quarried by day's labor, its cost will be

$$A = q + b + h + p,$$

in which q = cost of quarrying;

b = cost of breaking;

h = cost of hauling;

p = cost of stacking.

861. Repair.—When the thickness of the covering is so reduced that it is necessary to re-cover it with stone, let it be done in sections as large as convenient. The stone should be spread and rolled in the same manner as directed for building. As a rule, in re-coating, the thickness need not be more than two or three stones. The periods at which re-coating will be required depend upon the quantity of the traffic, and will vary from three to five years.

862. Organization of Road Force.—For the proper care of a roadway an adequate amount of skilled laborers permanently employed is necessary. This labor should be employed by the community, and be under the direct orders and supervision of the county engineer. The force should be arranged as follows: county engineer, inspectors (assistant engineers), chief foreman, foremen, laborers.

The number of men required will depend upon the amount of the traffic. With light traffic one laborer will be required to every 4 miles; with heavy traffic and a wide road one man will be required to every mile. In the spring and fall extra help will be required.

the extra men should be directed by the permanent roadman on each section, whose knowledge of his section will enable him to employ them to the best advantage.

Chief Foreman.—There will be required one chief foreman for every 100 miles of road. His duties shall be to superintend the entire road management under direct orders from the County Engineer, received either from himself or his assistants. He shall have no power to engage or discharge any foreman without first reporting to the engineer, but shall have full authority over the laborers. He shall set out and direct all work for the foremen, shall OK the foremen's requisitions for tools, supplies, horse-labor, etc. He shall under no circumstances purchase tools, materials, or employ special labor unless the requisition therefor is signed by the engineer, in cases to avert an accident or to save expense alone excepted. He shall walk the district in his charge as far as practicable, and carefully take and keep notes of work required to be done, inspect all bridges and structures. He shall examine the foremen's book and see that all accounts are properly entered.

He shall keep an order and tool account, a material, team, and general expenditure book, also a careful diary of his day's doings. He shall work the same hours as the workmen, and do his utmost to skilfully manage and check all extravagance, filling up any spare time in doing necessary work. In the absence of any foreman he shall take his place and direct the work until new arrangements can be made. He will have charge of the steam road-roller and be responsible for the economical working of the same.

Foreman.—The best men obtainable should be employed for this work. They should have about ten miles of ordinary country road to superintend, varying, of course, very much with the traffic; they should live as near as is practicable to the centre of their sections. They should not be changed from one section to another, but be retained permanently in the same section.

Each foreman should be supplied with a blank diary, in which he should write up every day the work he is engaged upon; each page so written to be initialed by the chief foreman. This diary should always be in his possession while on the road, and should always be ready for examination by the inspector or engineer, who

will note in it the date of examination. The foreman will also be supplied with a time-book in which to keep his own and his men's time; also with an account-book in which he will note the reception and weight of all material, keep an account of all tools, extra labor, team-hire, blacksmith and all other accounts of his section.

The foreman shall take all necessary instructions from the chief foreman, and in his absence all orders from the inspector or engineer must be promptly carried out. They shall work themselves and see that the work is properly carried out on their section. They shall have no power to discharge or engage any workman without first reporting the matter to the chief foreman.

Tools.—Every foreman should be supplied with the following tools for the use of the men under him and himself: shovels, pick-axes, spades, hoes, rakes, rammers, wheelbarrows, brush-hooks, axes, scrapers, brooms, stone-sledges, stone-hammers, straight-edge, level, line.

The tools should be repaired by the nearest blacksmith, under contract for a year or more at schedule rates, and before any tools are repaired the foreman shall give a written order to the smith and preserve a duplicate himself.

Whether the county shall purchase a stone-crusher or not will depend upon circumstances, whether stone is to be had in the county or not, or whether it can be purchased cheaper.

Roller.—The proper maintenance of a road cannot be carried out without the employment of a roller. If the extent of the road will not warrant the purchase of a steam-roller, a horse-roller should be secured. Whichever kind of roller is used, its weight should not be less than 4 tons and need not exceed 10 tons; the weight per inch of width is more important than the gross weight of the machine.

Team-labor and Materials.—All team-labor and materials should be supplied under contract. The chief foreman of the section will keep the time of all horse-labor and give time-checks for the same. If stone is purchased, it should be bought by weight, and each load delivered should be weighed on a public weighing machine, and the weight-check delivered to the foreman receiving

the material, who in turn will deliver to the carter a receipt in the form furnished for the purpose.

Accounts.—Accounts of all kinds should be sent to the County Engineer direct as soon as the work or contract is complete, and no account should under any circumstances be passed unless accompanied by the necessary order for the work being carried out.

Requisitions for tools, etc., should be sent in by the foreman at a fixed date in each month, and a date be fixed for their issuance.

Snow.—When snow has fallen heavily or is drifting, the road-guard must shovel it off the road so as to keep a track open. If he is unable to do this with the assistance of hired laborers, he must make requisition for extra help. If, on account of continued drifting, the road cannot be kept open, the travel may be temporarily led over the adjoining fields, care being taken to mark the location of the temporary road by poles and wisps of straw or tree-branches. When the weather permits sleighing for some time, loose stones and gravel liable to cause accidents are to be removed, and bare spots are to be covered with snow.

When thaw sets in, all snow and ice on the roads must be speedily removed.

County Engineer.—The County Engineer with the aid of his assistants will take direct management of all the roads, set out all work and give directions to the chief foreman, and, in general, superintend the carrying out of all work, make plans and prepare estimates for all materials, keep all accounts and perform all incidental duties.

Storage and Delivery of Broken Stone.—Depots or spaces for the storage of the broken stone should be provided along the sides of the road; these depots should be close enough together for the roadmen to wheel out the stone to the intervening portions of the road.

The contractor should be required to deliver the broken stone at each of these depots at such times and in such quantities as the engineer may direct. The stone heaped up at the depots should not be allowed to encroach upon the road or interfere with the gutters; one or two cubic yards will be a sufficient quantity to have at each depot. A convenient size for the stone-heaps will be 6 feet long, 3 feet wide, and $1\frac{1}{2}$ feet high. Such a heap will contain 1 cubic

yard, and the quantity so stored can be ascertained by measurement at any time.

863. Records.—It is very desirable that those in charge of roads should adopt some form of record, showing plainly the cost of materials, of labor, and of any miscellaneous expenditures connected with the maintenance of roads. Comparisons of the total cost of different roads, and of the proportion of expenditure for materials and labor, and for other things, would be facilitated, and a step would be taken towards gathering statistics relating to road-maintenance which are at present wanting in both America and England.

864. Instructions to Roadmen (published by the Road Improvement Association of No. 57 Basinghall Street, London, E. C.) will be found useful to roadmen, and are therefore submitted *in extenso*:

(1) Never allow a hollow, a rut, or a puddle to remain on a road, but fill it up at once with chips from the stone-heap.

(2) Always use chips for patching, and for all repairs during the summer months.

(3) Never put fresh stones on the road if by cross-picking and a thorough use of the rake the surface can be made smooth and kept at the proper strength and section.

(4) Remember that the rake is the most useful tool in your collection, and that it should be kept close at hand the whole year round.

(5) Do not spread large patches of stone over the whole width of the road, but coat the middle or horse track first, and when this has worn in, coat each of the sides in turn.

(6) Always arrange that the bulk of the stones may be laid down before Christmas.

(7) In moderately dry weather and on hard roads, always pick up the old surface into ridges six inches apart, and remove all large and projecting stones before applying a new coating.

(8) Never spread stones more than one stone deep, but add a second layer when the first has worn in, if one coat be not enough.

(9) Use a steel-pronged fork to load the barrels at the stone-heap, so that the siftings may be available for "binding" and for summer repairs.

(10) Never shoot stones on the road, and crack them where they lie, or a smooth surface will be out of question.

(11) Go over the whole of the new coating every day or two with the rake, and never leave the stones in ridges.

(12) Remove all large stones, blocks of wood, and other obstructions (used for diverting the traffic) at nightfall, or the consequences may be serious.

(13) Never put a stone upon a road for repairing purposes that will not pass freely in every direction through a 2-inch ring, and remember that still smaller stones should be used for patching and for all slight repairs.

(14) Recollect that hard stone should be broken to a finer gauge than soft, but that the 2-inch gauge is the largest that should be employed under any circumstances where no steam roller is employed.

(15) Never be without your ring-gauge. It should be to the roadman what the compass is to the mariner.

(16) If you have no ring-gauge, remember MacAdam's advice that any stone you cannot put easily into your mouth should be broken smaller.

(17) Use chips, if possible, for binding newly-laid stones together, and remember that road-sweepings, horse-droppings, sods of grass, and other rubbish, when used for this purpose, will ruin the best road ever constructed.

(18) Remember that water-worn or rounded stones should never be used upon steep gradients, or they will fail to bind together.

(19) Never allow dust or mud to lie on the surface of the road, for either of these will double the cost of maintenance.

(20) Recollect that dust becomes mud at the first shower, and that mud forms a wet blanket which will keep a road in a filthy condition for weeks at a time, instead of allowing it to dry in a few hours.

(21) See that all sweepings and scrapings are put into heaps and carted away immediately:

(22) Remember that the middle of the road should always be a little higher than the sides, so that the rain may run into the side gutters at once.

(23) Never allow the water-tables, gutters, and ditches to clog up, but keep them clear the whole year through.

(24) Always be upon your road in wet weather, and at once fill up with "chips" any hollows or ruts where the rain may lie.

(25) When the main coatings of stone have worn in, go over the whole road, and, gathering together all the loose stones, return them to the stone-heap for use in the winter to follow; for loose stones are a source of danger and annoyance and should never be allowed to lie on any road.

865. The French System of Highway Maintenance.—The system of highway maintenance adopted by the French, whose roads are unexcelled by any is as follows:

The roads are divided into national, departmental, military, and vicinal or country cross-roads.

The national roads are maintained entirely at the expense of the public treasury; the departments provide for the second class of roads, and also partly for the military roads; the local cross-roads are maintained by the communes, or when of higher importance by the departments.

The national roads aggregate upwards of 23,180 miles in length, of which 1632 miles are paved like a street. These roads average in width 16 metres or 52 feet 6 inches, of which 19.68 feet is for the wheelway, 19.68 feet for the sidewalks, and 13.12 feet for the ditches and embankment slopes. The department roads are not quite so wide, their average width being 39 feet. The aggregate length of the latter is about 29,167 miles. The military roads number 28, and are about 932 miles long in all. They are chiefly in the west of France, laid out after the last insurrection of Vendée. The sum of about \$6,800,000 is yearly expended in making new roads or repairing old ones, and \$32,000,000 is expended for maintenance and inspection.

The cross-roads are managed by a special branch of the department of the Minister of the Interior, a branch which employs about 3000 inspectors and 42,000 workmen, specially charged with the duty of keeping these roads in repair. In 1872 these cross-roads aggregated 338,273 miles in length and covered a surface of about 915,000 acres. To the very considerable sum which the communes must apply to the extension and repair of these country roads, the government used to add a yearly grant of \$2,300,000; but since 1873 this sum has been reduced to \$1,150,000 annually.

The care of the national roads is a large part of the duties of the "Engineers of Bridges and Roads" (*Ingénieurs des Ponts et Chaussées*) and belongs to the portfolio of the Minister of Public Works.

In each department there is appointed by the Minister of Public Works an engineer-in-chief, who has the direction and responsibility of the work of maintenance of such portion of the national roads as lie within that department. He is also placed in charge of some other work in that department; either of railroads, canal or river improvements, or the care of the seaports, if such lie in that department.

Sometimes he is also in charge of the departmental roads, and in a few cases of the county roads as well. Under him are several Engineers-in-ordinary (*Ingénieurs ordinaires*), who are employed only in a certain section of the department; each one having charge of the work in an *arrondissement*.

There they direct the repairs according to the general plans of their chief, but at the same time they are allowed considerable latitude to display their ability or originality and follow out their own ideas in the details of the work. Their duties require them to visit carefully at least four times a year, oftener if necessary, every road confided to their care.

The next grade below the engineers-in-ordinary is that of Conductor or Assistant Engineer.

The conductor has a subdivision comprising a length such that he may be able to inspect it in detail at least twice each month and still have sufficient time to attend to the other requirements of the service with which the chief is charged, i.e., of bridges, railroads, canals, seaports, etc.

The supervision comprises usually from 25 to 50 miles of road, according to the distribution and the complexity of their maintenance, and of other details connected with them. The conductor makes semi-monthly inspections of the roads under his charge, and, further, he makes his tour of inspection on foot.

He gives orders to the foremen of the different gangs at work along the roads. He keeps a record of their work, to see that they do a proper amount. If any have been guilty of neglect, he may recommend to his chief that they be punished.

Following each regular inspection he forwards a written report

to the engineer in charge of that division. He keeps the accounts for his division. He is consulted by the engineer in case of the receipt of any petition or other affairs upon which his accurate knowledge of the division would make him capable of giving information or advice.

If any surveys are to be made, he makes them. He also inspects all road material, all of which is furnished by contract, and has immediate charge of the construction of all new work.

The engineer can give no order to the laborers without giving it through the conductor.

In districts where there is much to do he is aided by a second assistant engineer.

This is the grade held by the younger engineers, who have charge of the drafting and clerical work in the chief-engineer's office, and also assist in the outdoor work when there is a press of it.

It is from the ranks of these latter that by promotion the corps of assistant engineers or conductors is kept up to the required number. Their promotion is made on their successfully passing examinations for that purpose.

Under the conductor comes the road laborer or cantonnier. The road laborers are divided into squads of five or six. Each one is in charge of an overseer, chosen from one of their number.

Each of the road laborers has charge of a length of road varying from $1\frac{1}{2}$ to $2\frac{1}{2}$ miles, depending upon the condition of the road, the amount of circulation, and the method of maintenance, which would depend upon the nature of its construction.

When there happens to be much work to be done at once, a few laborers by the day are hired to assist, but they are reduced to the least possible number.

If there is to be work that will require extra laborers for a considerable length of time, they organize another road gang, so that the work will be done by regular hands.

886. Regulations for Cantonniers (Road Laborers).

Definition of the Work of Cantonniers.—The cantonniers are charged with the manual labor connected with the daily maintenance of the roads, over a definite length of road, called a canton.

They must obey, in everything relating to their work, the engineers, foremen, and other agents of the administration of roads and bridges.

Nomination of Cantonniers.—The cantonniers are nominated prefect, from a list submitted to the chief engineer, containing three times, or at least twice, the number of candidates required to fill the vacancies. They are dismissed by the prefect on the advice of the chief engineer.

Conditions of Admission.—To be nominated a cantonnier it is necessary (1) to have fulfilled the laws relating to service in the army, and to be not more than 45 years old; (2) not to be subject to any infirmity which may hinder daily and diligent labor; (3) to have worked on the construction or repair of roads; (4) to have a certificate of good conduct from the mayor of the commune or the subprefect of the arrondissement.

Candidates who can read and write will be preferred.

Chief Cantonnier.—The cantons of the roads in a department shall be grouped in districts containing at least six cantons. The six cantonniers will constitute a brigade; one of them shall be chief cantonnier; he must be able to read and write, and shall be chosen from the cantonniers distinguished for zeal, good conduct, and intelligence.

The chief cantonniers shall have a shorter length than other cantonniers, so that they may be able to attend to special duties allotted to them. They shall accompany the foremen in their rounds, and note the orders which may be given by the cantonniers of their brigade, and see that the orders are carried out. They shall accordingly go over the whole extent of their district at least once a week, varying the days and hours of their visits, to satisfy themselves of the presence of the cantonniers, and to direct them in their work; they shall report to those under whose orders they are more particularly placed, and shall furnish to the engineers all the information that may be required of them.

They may be temporarily employed in superintending and keeping account of the works of re-dressing the paved causeways, and in directing itinerant gangs of workmen.

Distinctive Marks of Cantonniers.—Cantonniers shall wear a blue jacket and a leather hat, round which shall be a band of copper 0.28 m. long and 0.055 m. broad, with the word "cantonnier" cut out in it. The chief cantonniers shall wear besides on the left arm an armet of the prescribed pattern.

There shall be given besides to each man a mark consisting of

a staff 2 metres long, divided in decimetres, shod with iron, and furnished at the top with a strong iron plate 0.24 m. wide and 0.16 m. high, on each side of which shall be shown in letters 0.08 m. high the number of the canton. This mark must always be set up on the road at less than 100 metres from where the cantonnier is at work.

The Work of the Cantonniers.—The work of the cantonniers consists in maintaining and repairing the roads daily and constantly, so that they may be dry, clean, and smooth, safe in times of hard frost, and of a satisfactory appearance at all seasons.

To effect this, they must, subject to the orders and instructions which may be given them in case of need:

(1) Insure the flowing off of water by cleansing the gutters, pipes, etc., by making small drains for the purpose wherever they may be necessary, taking care that these drains should never be made in the body of the road.

(2) At suitable times open and maintain the ditches, regulate the sides, throwing the surplus earth on the neighboring ground, if there is no objection, or putting it together to facilitate its measurement or removal.

(3) Remove as soon as possible with a scraper or shovel all liquid or soft mud from the whole breadth of the road, even if there be neither hollows nor ruts, and collect the mud in regular heaps on the sides to be measured, if there is room for it there.

(4) Spread the mud, when dry, on the sides which have lost their shape or have a slope of more than 1 in 25 from the road, and throw the surplus on the neighboring fields, if not objected to.

(5) At the approach of winter redouble attention to all that is prescribed in the two preceding paragraphs, to prevent lumps of frozen mud.

(6) In dry weather remove the dust and deposit it on the sides.

(7) Clear away the snow from the whole breadth of the road, or at least from the middle, particularly at places where it accumulates and obstructs the traffic; throw it immediately on the neighboring fields if possible, or collect it in heaps on the sides, so as to show drivers of vehicles where the road is.

(8) Break and remove ice from the road, and scatter sand and rubble, especially at the sides and at sharp turnings.

(9) Also break the ice in the ditches and remove it where it accumulates, so as to threaten flooding of the road in the thaw.

(10) In the time of thaw assist the flowing off of the water and remove pieces of ice, mud, and dirt, so that the effects of the thaw may prejudice the traffic and road as little as possible.

(11) Collect, break, and stack in separate heaps and in a particular shape all loose stones, and those projecting or only just showing if too large, and those near in the neighboring fields which can be used for the purposes of the road. Break the materials intended for maintenance, if the breaking is not done by the contractor.

(12) Cut or dig up thistles or other weeds, especially before their flowering season.

(13) Clear away loose stones for the road and everything which may hinder the traffic.

(14) Clean and clear away earth, plants, and extraneous matters from the plinths, string-courses, and parapets of bridges, etc.

(15) Look after the preservation of mile-stones, sign-posts, and bench-marks on the road.

(16) Cultivate and look after plantations belonging to the State, see to their preservation and to that of plantations of private owners, straighten provisionally all young trees bent by the wind, and do generally all that the welfare of the road demands, conformable to more particular instructions given by the engineers of the district for carrying out the above general orders.

Employment of Materials.—On roads in a state of repair the road laborers shall conform to the following rules for employment of materials.

The materials shall be made use of as they are required, always choosing damp weather for their employment, avoiding wholesale coating and throwing down stones at random.

To proceed regularly, care should be taken to observe in time of rain the hollows and tracks of vehicles, which perceptibly alter the shape of the road.

These worn parts should be cleaned and picked, particularly at the edges, but only to the depth necessary to insure the binding of the materials. The materials arising from the picking should be cleared of earth and broken if necessary before being used.

The filling up of the hollows or wheel-tracks should be effected

with the débris and with the necessary quantity of new material received through the engineer. It must be carefully beaten so as to incorporate it with the lower layer, and then made to conform to the contour of the road. The parts thus restored should be maintained with particular care until they are completely consolidated.

With respect to roads which are not in a good state of repair, but which nevertheless are open for traffic, one should endeavor to keep them in as good a condition as possible by employing, with the care which has just been indicated, the materials available.

All large or projecting stones should be taken out, as they cause damage, and they should be broken to a proper size before being used again.

The coatings more or less extensive to be made on worn roads will be prescribed by the engineer, who will also decide on the materials to be used. The hollows and ruts to be filled up must first be cleared of mud and earth, and their surface then picked to a depth of from 4 to 5 centimetres ($1\frac{1}{2}$ to 2 inches). The materials should not be spread except in layers of from 5 to 6 centimeters (2 to $2\frac{1}{2}$ inches), which should be carefully beaten and consolidated.

Task-work to be performed.—To stimulate and maintain the activity of the cantonniers, the engineers, inspectors, and foremen shall assign them work to be performed in a given time, whenever local circumstances permit it. A summary of information on these tasks shall be entered in that part of the cantonnier's book reserved for the instructions of the service.

Work thus prescribed shall be one of the principal objects of supervision by the immediate head of the cantonniers, as well as by the mayors and road commissioners.

Determination of Working Hours.—From the 1st of May to the 1st of September the cantonniers shall be on the roads, without quitting them, from 5 o'clock in the morning to 7 o'clock in the evening. The rest of the year they shall be there from sunrise to sunset. They shall take their meals on the road at hours fixed by the chief engineer. The total duration of meals shall not exceed two hours, but during great heat it may be prolonged to three hours.

Removal of Cantonniers.—Cantonniers may be removed either singly or in brigades, when the needs of the service imperatively

require it, to points indicated to them. These displacements shall not take place except under an express order from the engineer.

Compulsory Attendance of Cantonniers in time of Rain, Snow, etc.—Rain, snow, or other inclemency of the weather shall not be a pretext for the absence of cantonniers; they must in such times redouble their zeal to prevent damage and keep the road in good condition for the whole extent of their cantons. They are, however, authorized to make themselves fixed or portable shelters which shall not interfere with the public way or adjoining property, but which must be in sight of the road and less than 10 metres off, so that the presence of the workmen can always be ascertained.

Gratuitous Assistance to Travellers.—Cantonniers must render gratuitous aid and assistance to drivers and travellers, but only in case of accidents.

Surveillance over Breaches of Highway Law.—To prevent as much as possible breaches of highway law, the cantonniers shall warn travellers and occupiers of the adjoining lands who may be disposed to commit them. They shall consequently keep an eye on repairs, building, deposits, encroachments, and planting which may take place without leave on the highway. They shall report any such breaches to the surveyor, either when he makes his rounds, or at once by letter or by message through the chief cantonnier.

Tools with which Cantonniers must be provided.—Every cantonnier shall be provided, at his own expense, with a wheelbarrow, an iron shovel, a wooden shovel, a road-pick, an iron road-scraper, a wooden road-scraper, an iron rake, an iron crowbar, an iron sledge-hammer, and a line 20 metres long.

The head cantonniers must besides be provided with three boning rods (rods in the form of a T much employed in European countries to range in grades, etc.), with a level graduated to indicate gradients, and with a double metre measure.

Tools of a Particular Kind to be furnished by the Administration.—Each cantonnier shall be entrusted with an iron ring 6 centimetres (2½ inches) in diameter, so that he may ascertain if the stones which he has to spread on the road have been broken according to the specifications.

Providing Tools in advance to Cantonniers.—Cantonniers who have no means of procuring them can have any tools they require

supplied in advance. The repayment of the cost of these tools will be insured by the administration by stoppages, which, except in cases of dismissal, shall not exceed one sixth of the monthly salary.

Keeping Tools in Repair.—Cantonniers shall keep their tools in a good state of repair. If they become negligent in this respect, they will be repaired by the administration, and the expenses will be repaid in the same manner as for new tools.

Tools must not be taken to be repaired during working hours. Excuses for absence based upon the necessity of getting tools repaired will never be accepted.

Cantonniers' Books.—Every cantonnier will be provided with a book suitably ruled and headed, in which he will make notes on the work and conduct of the laborers, any orders and instructions given them, and information of the work which has been assigned to them. It must be presented by them to the agents charged with the supervision of the road, every time they are required to do so, under penalty of the stoppage of a day's pay for every time they neglect to produce it, or three days' pay in the case of having lost it.

Means of Verifying the Absence of Cantonniers.—The absence and negligences of cantonniers will be verified by the engineers and the agents of the administration employed under their orders, who will make a note of them in the books just spoken of. Absence can also be verified by gendarmes on their rounds, by mayors of the parishes in which the cantons are situated, and by road commissioners.

Leave of Absence at Harvest-time.—At harvest-time, when the road is in good condition, cantonniers can obtain leave of absence from the engineer-in-ordinary, when authorized by the engineer-in-chief. They will receive no salary while on leave of absence, at the expiration of which they must return punctually to their posts or they will be immediately superseded.

Surrender of Book and of Distinctive Badges on Dismissal of a Cantonnier.—When a cantonnier is dismissed, he must surrender to the engineer his book, his staff, his ring, and the distinctive badges which he wears on his arm and cap. Failing to do this, double the value of these articles will be retained from that which is due to him for salary at the time of his dismissal.

Classification and Salary of Cantonniers.—Cantonniers of

each department will be divided into three classes of equal number, whose salary, for each class, will be fixed by the prefect, on the proposal of the chief engineer.

The classification will be made each year by the chief engineer, on the report of the engineer-in-ordinary, and according to the services of the cantonniers during the preceding year.

The chief cantonniers will be divided into two classes, likewise of equal number.

Their salaries will be fixed, like those of the ordinary cantonniers, by the prefect, on the proposal of the chief engineer.

The cantonniers receive from \$10 to \$20 per month, and the chief cantonniers receive 20% more.

Indemnity for Removal.—Cantonniers who leave their cantons by order of the engineer will receive an indemnity of one fifth more than their salary, and three fifths for every day they sleep out.

No indemnity for removal will be allowed to head cantonniers except when they go out of the district of their brigade. In this case, the indemnity to which they are entitled will be regulated in the same way as those which are paid to ordinary cantonniers.

Annual Gratuities.—Every year, on the report of the engineer-in-chief, the prefect may grant to the most deserving cantonnier in each district of the engineer-in-ordinary, a gratuity, which shall not exceed a month's salary.

A similar gratuity may also be awarded to that one of the chief cantonniers of the department who shall have rendered the best service.

Fines on Account of Absence.—Every cantonnier who shall not be found at his post by one of the agents having a right of supervision on the road, shall be subject to a fine of three days' pay for the first time, of six days in case of a second offence, and be dismissed the third time.

Those who, without being absent, shall not have done enough work during the month, or who have neglected the duty entrusted to them, will be fined enough to pay for repairing any damage resulting from their negligence.

A part of these fines may be granted by the engineer-in-chief, on the report of the engineer in ordinary, for the benefit of those cantonniers who by their zeal and work have deserved encouragement.

867. The system described above, while employed throughout France for the maintenance of the national roads, is applied to all the other roads in but 27 of the 87 departments.

In three departments the engineer-in-chief has, it is true, the direction of the work, but has under him a different corps of engineers or commissioners to superintend the work upon the county or vicinal roads.

In 57 of the departments a commissioner appointed by the Minister of the Interior has charge of the county or vicinal roads. His corps comprises commissioners or trustees in the arrondissements and cantons who are appointed by the prefect of the department.

The ordinary vicinal roads are in the charge of the mayors of the communes. The direct agents are inspectors, who are charged with the duty of watching this work, and are responsible for its proper execution.

Inspectors.—The chief inspector is under the direct authority of the prefect, and he has charge of all the vicinal roads of the department, and all the sub-inspectors are under his orders. He executes the laws and regulations prescribed, and the inspectors of arrondissements have similar power in their own districts. The chief inspector may, when he deems fit, order that certain operations shall be carried out under agents directly under his control.

Under the law of 1836, the appointment of inspectors of all grades lay with the prefect, who might, if he so chose, transfer the control of the roads to the government corps of engineers. This right of option was taken from the prefect by the law of 1866, which included among the duties and privileges of the Council General of the department the right to designate to what parties should be confided the execution of work upon vicinal roads. The laws of 1871 confirmed this right and extended it to departmental roads, so that to-day the nomination, organization, and control of the staff in charge of department roads of all classes is the exclusive right of the prefectural authority, without restriction.

The inspectors are divided, ordinarily, into inspector-in-chief, inspectors of arrondissements, and inspectors of cantons. They shall be French citizens and must be at least 21 years of age.

The law of 1836 prescribes that in each department there shall be a commissioner whose duty it shall be to examine candidates for the position; and when a vacancy occurs, it is the duty of the pre-

fect to announce the date of such examinations in his department, and send this notice to the prefects of adjoining departments. The Minister of the Interior is also notified of all such vacancies and changes.

The duties of the inspectors employed on the vicinal roads are to study the projects, arrange the plans, estimate the cost, and watch the execution of all road work, under the authority of the prefects and the mayors. Their pay is fixed by the Council General; and they are never to be remunerated by a percentage on work performed.

The Laborers.—The workmen for all main department highways and roads common to several communes are appointed by the prefect. The mayors of the communes name those employed on the ordinary vicinal roads; but as this appointment implies a fixed charge upon the commune, his action must be sanctioned by a vote of the municipal council.

Day's Work of Proprietors.—France has a system of working out road taxes, but it is carried out as follows: For work of this nature two periods are generally fixed in each year, ranging from one month to six weeks in length, each. The mayors of the communes fix the dates, and so arrange it that any work commenced can be finished in the specified time. And in connection with the inspector of the canton, the mayor also divides the workmen among the several roads and fixes the hours for beginning and ending work at each place. Five days before the date fixed the mayor sends to each laborer working under this system a notice requiring him to report at a certain day and hour, upon a certain road, for such work as may be there assigned to him. In case of sickness the laborer must make this fact known to the mayor within twenty-four hours after receiving his notice; and while the mayor may postpone the service required, this cannot be extended beyond the current year. As an unnecessary number of workmen at any one place leads to confusion and embarrassment, it is the duty of the mayor to detail at one time and on any one piece of work only a sufficient number of laborers to best accomplish a specified task without loss of time. If this labor is to be expended on a vicinal road of common interest to several communes, the prefect of the department designates the time and location of such work.

Each workman under this system carries to the place designated

such common tools as the mayor's notice may direct. Tools with which the farmers are not ordinarily supplied are furnished by each commune from the fund appropriated to public works. All beasts of burden must be harnessed, and all vehicles must have a driver, and the time of this driver is received as a full acquittance for the time of one man. Farmers may substitute for themselves, or members of their family, other men hired and paid for by themselves. These substitutes must be able-bodied men not less than 18 nor more than 60 years of age.

The length of the day's work is fixed in each department by a general rule issued by the prefect, and it varies according to the seasons of the year. This day's work cannot be divided, but must be furnished entirely by the laborer. In case of legitimate interruption by reason of bad weather, the laborers are bound to complete it at the earliest date possible. If the laborer fails to report at the hour indicated, or in any way fails to complete his legal day's work, the lost time must be paid for in money, and this fine can be legally recovered by the municipal receiver of taxes.

Works carried out on vicinal roads under the labor-tax system are under the direction and control of the mayor of the commune in which such roads lie. This functionary is assisted by the inspector in organizing his force and commencing work, and each day's work is preceded by a roll-call, compared with the list furnished by the mayor. If any laborer breaks any of the rules fixed for the conduct of the work, comes unprovided with the tools called for in his official notice, or in any way does not conscientiously perform the duty assigned him, he can be sent from the work, and the value of his services, or the proportionate part thereof, collected in money. At the end of each day's work the superintendent of works credits each laborer upon his official notice with the number of days and class of work done, and at the same time discharges the original requisition for labor. After the work is completed this accredited notice is signed by the mayor, and sent by him to the municipal receiver, and the latter makes the proper entry upon his books or register of *prestataires*.

In case a commune neglects or refuses to vote the number of days' work necessary on its roads in the proper time for performance, and the sub-prefect advises the prefect of this fact, it shall be the duty of the latter official to serve a special notice upon the

mayor of the defaulting commune demanding that he execute the required work within the specified time. This same notice also notifies the farmers that unless the work is well done in the time fixed, its value will be required from them, in money. This notice must be made public by the mayor; or in case of his refusal by a special agent of the prefect. All work of this character is done under the supervision of an inspector appointed by the prefect or sub-prefect, and the certificate of execution is delivered by the mayor on the certificate of this inspector. If the mayor refuses to do this, the certificate of the inspector himself is valid.

Task-work by Proprietors.—Task-work has certain advantages over work by the day, for the laborers are free to select their own time, and by more active exertions they can shorten their hours of labor. When the municipal council of a commune has arranged a basis upon which it can convert day's work into task-work, and this schedule has received the approval of the prefect, the mayor of the commune may decide, so far as the smaller roads are concerned, whether work in his commune shall be done by one system or the other, as he may deem best. This decision is binding upon all the *prestataires* who have declared their intention of working out their taxes. The prefect of the department may in a similar manner decide as to the execution of work upon the main highways and roads of common interest to several communes.

When such task-work is to be done, the requisition states the class and amount of work and the date by which it must be completed. The character of work required is further indicted upon the ground by the inspector of the canton, and it is carried out under his direction. The party assigned to a task is responsible for its proper execution; and upon the receipt of the measurement and certificate of the inspector that it is properly done and within the given time, the mayor accredits the farmer with his task. Work improperly done must be done over again, and within a time fixed by the mayor.

Contract Work.—The mayors, with the authority of the prefect for vicinal roads, and the prefect for the main highways and smaller roads common to several communes, may let by contract the construction and repair of these roads. But under the law of 1836, the proprietors, even when the work is converted into tasks, cannot be credited for taxes with work done under the control and for the

account of a contractor. Nevertheless, when work on any department road is let by contract, the conditions of the contract oblige the contractor to receive in return for services the day work or tasks of the proprietors according to a conversion tariff approved by the Council General of the department in the first case, and by the municipal council with the approval of the prefect in the second case.

In cases where the department supplies this labor in lieu of taxes from the laborer and cash paid to the contract or, the department by its agents makes the requisitions and superintends the execution exclusively; the contractors having nothing to do with the disposition of the men. But if the prestataires do not carry out their obligations, the contractors may call upon the mayor or the inspectors to compel the fulfilment of these obligations.

Cash Work.—In theory all work for which money is paid should be executed under a public contract. Nevertheless, with the authority of the prefect certain work may be let by private agreement under the following conditions:

- (1) For work or supplies when the value does not exceed \$600.
- (2) For work when the conditions forbid the delay of a public letting.

- (3) That which by its nature requires special skill and experience on the part of the contractor.

- (4) That which cannot be let by contract after two several attempts to do so. Work may also, with the authority of the prefect, be economically carried out either directly under the control of the inspectors, or by way of indirect taxes, in cases of urgency or when other methods of execution have been recognized as impossible or less advantageous. Under these conditions the work should, if possible, be accomplished by the task system.

All projects must be approved by the prefect, and all specifications for work must contain the clause that the contracts are subject to the general conditions imposed upon contractors for vicinal roads as annexed to the general instructions issued on December 6, 1870.

The provisional or final acceptance of work performed upon main highways or roads common to several communes lies with the inspector of the arrondissement, assisted by the inspector of the canton, and made in the presence of the contractor. The accept-

ance of vicinal roads lies with the mayor in the presence of the inspector of the canton, two members of the municipal council, and the contractor. The contractor is always summoned on these occasions, but his absence is no obstacle to the action of the officials.

All difficulties arising from disagreement as to work performed on vicinal roads, or from damage caused by these works, and not arising from a material expropriation of lands, can be adjusted by the council of the prefecture, with appeal to the council of state.

Commissioners of Supervision.—In some departments, the prefects have thought it proper to delegate a portion of the care of inspection required by the many details of work on vicinal roads to a commission appointed by the prefect and made up from members of the General Council, the councils of the arrondissements, the mayors, and certain proprietors particularly interested in the good condition of the roads. Where a road passes through two arrondissements and is too long to be easily watched by one commissioner, it may be divided, and its several parts supervised by distinct commissioners. Each commission names its own president and secretary and fixes the day and place of meeting. When the prefect or sub-prefect attends a meeting, he is the president for the time being.

When the prefect thinks best, these commissioners may be consulted upon projects recommended by the inspectors for new works, and upon a basis of a division of expenses between the communes. They may also designate several of their number to take part in the acceptance of work done by contract. Within the first three months of the year, these commissioners send to the sub-prefects their observations upon the state of the roads and point out the localities most urgently needing repair. In this report they also name the workmen who have most faithfully performed their duty, as well as those who have been careless or slow in the performance of their work.

The Police of the Roads.—No one without previous authority can perform any act upon a road that in any way interferes with its function as a public way or interrupts travel. And it is specially forbidden to make any trenches or openings; to deposit stones, earth, or rubbish upon it; to take away any sand, gravel, or other material; to spread anything over the road; to divert water channels so as

to cause washing of the road; to interrupt in any way the flow of water in the ditches, even temporarily; to construct or repair any building, wall, etc., bordering upon the road; to open ditches, plant trees or hedges along said road, or to dig wells or cisterns nearer to the road than provided in the regulations. To perform any of these intended acts, authority must first be formally requested. For all vicinal roads this authority is granted by the mayor with the advice of the inspector; and in no case can the mayors give a verbal authorization. For main highways and other more important roads the authority comes from the prefect, upon the report of the inspectors, or from the subprefect under similar advice. Every authorization expressly reserves the rights of third parties, and stipulates that the roads must be restored to their normal good condition.

Ditches and Slopes.—In giving to the department commissioners or to the Council General the right to give to vicinal roads the necessary width, the law of 1871 accorded them the right to include all the land required for proper ditches and slopes. These ditches must be cleaned as often as necessary, and the expense of so doing is charged to the commune; the ditches being a legal part of the road, and protected against encroachment in the same manner as the road proper. If the authorities have not opened a ditch along the whole length of a road, as sometimes happens, the bordering proprietors may do so by first having the lines and levels given them by the proper parties; without this authority they are expressly forbidden to touch the ditches. The care of ditches opened for their own protection and convenience lies in the hands of the proprietors.

Rural Roads.—Outside of the vicinal roads properly so called, there are in all communes a certain number of minor roads or means of communication which, while of little importance, perhaps, must yet be carefully maintained, as they may lead to a public fountain, a watering-place for cattle, or to common pasturage. Such roads are termed rural roads in the law of 1839, but they are really public roads in the sense that their use is open to all, that they cannot be claimed as private property by the owners of adjoining soil, and that they are legally under the care of the public authorities and are maintained in the same manner as are other roads of the commune.

The method adopted is to map every road and every public path in the commune, and expose this plan for one month at the office of the mayor of the commune. Any objections made to the correctness of the plot or claims of private ownership of roads shown are submitted to the municipal council, which is to sift out those having a basis of fact. And this same official body renders an opinion upon the degree of utility of the roads shown, and the possibility of suppressing certain ones so that the soil may be sold for the benefit of the commune. The map with the report of the municipal council is then submitted to the prefect of the department, who examines it to see that no vicinal roads have been included under the head of "rural." The opposition to the official dedication of a certain road may be founded upon a claim of property, or upon the fact that it is not public. The property claim is decided in the courts of justice; the second case must be decided by the administrative power, that is, the prefect.

When a minor road of this kind is definitely classified as a "rural road" it is public property, and the administrative authority itself cannot restrain travel on it except in case of absolute necessity. If a commune wishes to enlarge such a road, it can do so only by an amicable agreement with the owner of the necessary land, unless the prefect officially classes it among the vicinal roads. If a rural road is suppressed, the soil can be sold for the benefit of the commune; but in such case the proprietors bordering on such a road can either demand that the use of it be continued to them, or that the commune provide some other passage or pay them an indemnity.

868. Street Cleansing.—Although circumstances legitimately determine the intervals at which streets shall be cleaned, nevertheless clean, well-swept streets not only add materially to the prosperous appearance of a town, but they also have a very marked influence upon the health and morals of its inhabitants; wet and muddy, badly-formed, ill-drained streets cause dampness in the subsoil of the dwelling-houses in the vicinity and a humidity of the atmosphere, both of which tend to produce a low standard of health in their neighborhood, irrespective of the wet surface through which pedestrians have to wade whenever they are obliged to cross such streets.

Dusty streets, too, are very injurious from the gritty silicate-loaded air arising from them. Such an atmosphere when inhaled is known to produce disease of the lungs, even when free from the dust arising from horse-droppings or other organic impurities.

869. The dirt-producing causes common to all roadways are:

(1) Detritus produced by the attrition of the paving material, horseshoes, wheel-tires, and shoe-leather. This cause cannot be eliminated.

(2) The horse-droppings, which add an offensive element to the body of street dirt, are, if collected at once, valuable as manure. This is done by the street orderly boys in London. If properly cared for, it would undoubtedly afford an income greater than the cost of collecting it.

(3) Dirt forced up through the joints of block pavements. Under modern specifications the joints of block pavements are intended to be closed with a water-proof material. This of course would give full protection against this source of dirt, but in the majority of block pavements it is doubtful if this requirement is ever faithfully performed. A few months generally suffices to dislodge the imperfect filling, and the material of the substratum quickly shows itself on the surface of the pavement.

(4) House and shop refuse carelessly swept into the streets is an ever-present source of street dirt. London imposes and enforces a fine of not less than \$25 and not exceeding \$200 upon any person sweeping or throwing any refuse, dirt, ashes, dust, decayed fruit, or offensive matters of any kind upon the foot or carriage ways. Also any person refusing to have the dust or ashes removed by the scavengers or obstructing them in the performance of their duties is liable to a penalty not exceeding \$25. Again, the method of removing house-refuse is a prolific source of street dirt. The receptacles containing it are brought out and are placed on the edge of the curb long before the cart makes its appearance or can be reasonably expected to do so.

870. The result of these receptacles, filled with heterogeneous collections of house-refuse, being left unprotected in the public streets is that their contents are quickly strewn about the surface of the street, by their being upset accidentally or purposely; and the appearance of the street, which has probably been carefully

swept and garnished during the night or early in the morning, quickly assumes, especially in a high wind, a very offensive character, and probably has to be re-swept and cleansed before the ordinary traffic of the day commences.

871. With good pavements the amount of refuse to be removed is reduced to a minimum. With pavements the wear of which is practically nothing, the dirt consists principally of manure, which has a ready sale. The reduction in the amount of unsalable refuse is an object to be sought for; its collection and disposal is an expensive item. This reduction can only be effected by the adoption of impermeable pavements.

In Berlin and Liverpool the average quantity of refuse collected by sweeping has been continuously decreasing in spite of increased traffic and area, this reduction being due to good pavements.

872. **Composition of Street Dust.**—The following analysis of street dust is given by Mr. H. G. Hanks, State Mineralogist of California. The samples, examined under the microscope, contained vegetable fibre, principally horse-manure and the decaying débris of Oregon pine and redwood planking, bits of coke and coal, glass, horse-hair, quartz sand, some blue particles the nature of which could not be determined, and a dark-colored, finely-divided, half-dried mud which was pleasant neither to the sense of sight or smell. A portion mixed with distilled water and placed in a bottle swarmed with life in forty-eight hours.

Professor Tyndall has also shown that dusty air is alive with the germs of the bacteria of putrefaction, whilst the pure fresh air which he gathered on a mountain peak in the Alps is devoid of such germs, and is absolutely powerless to produce any organisms. Persons living in streets that are improperly swept or watered are unable to open doors or windows with impunity by reason of the dust.

Dr. Letherby, in 1867, analyzed dry mud from the streets of the city of London—dried by exposure for many hours to a temperature of from 266 to 300 degrees Fahr. At the same time he analyzed, for comparison, well-dried, fresh horse-dung and common farm-yard dung. The results of the analyses of the mud from stone pavements are given in Table LXXXV.

TABLE LXXXV.

COMPOSITION OF MUD FROM STONE-PAVED STREETS, HORSE-DUNG AND FARM-YARD DUNG.

(Dried at 300 degrees Fahr.)

Constituents.	Fresh Horse-dung. Per cent.	Farm-yard Dung. Per cent.	Mud from Stone-paved Streets.		
			Maximum organic (dry weather). Per cent.	Minimum organic (wet weather). Per cent.	Average. Per cent.
Organic.....	82.7	69.9	58.2	20.5	47.2
Mineral.....	17.8	30.1	41.8	79.5	52.8
	100.0	100.0	100.0	100.0	100.0

The higher proportion of mineral matter in wet weather proves that in such weather the abrasion of stone and iron is greatest. Dr. Letherby estimated that the average proportions of stone, iron, and dung in the muds were:

Horse-dung.....	57 per cent
Abraded stone.....	80 "
Abraded iron.....	18 "
	<u>100 per cent</u>

The mud was so finely comminuted that it floated freely away in a stream of water.

In the mud of wood pavements, the proportion of organic matter in the dried mud was larger than in the mud of stone pavements. It amounted to about 60 per cent.

The amount of moisture in the street mud varied according to the state of the weather.

Stone Pavements.	Moisture.
In the driest weather.....	rarely less than 35 per cent
In ordinary weather.....	" " 48½ "
In wet weather.....	" " 70 to 90 "

873. The detritus of the material of a granite pavement constitutes but a very small proportion of the total quantity of mud-

forming dust. Colonel Haywood exemplified this proportion in an interesting manner, taking the instance of the granite pavement of London bridge,—3-inch Aberdeen granite sets,—which was removed in 1851, after having been down nine years. The average loss of granite over an area of 3950 square yards, he estimated, was equal to 2 inches of vertical wear. The total volume of granite worn away was therefore about $219\frac{1}{2}$ cubic yards, assuming that the surface was a continuous mass of granite, though there was of course a considerable superficial area of joints. Assuming that the granite worn off was reduced to the state of fine powder, it was increased in bulk probably one half, and its volume had been $(219\frac{1}{2} \times 1\frac{1}{2} =)329\frac{1}{2}$ cubic yards. Adding 5% for the loss upon stones removed and replaced from time to time, the total quantity worn off and reduced to powder and carried away, mixed with the dust of the street and mud, would only have amounted to 345.7 cubic yards for nine years, equivalent to a wear of .105 cubic yard—about a tenth of a cubic yard—per day. Whereas the quantity of dust removed daily in dry calm weather was from 3 to $3\frac{1}{2}$ cubic yards—over thirty times as much as the granite detritus. So much for horse-droppings and shoe-leather, which must have constituted twenty-nine thirtieths of the total accumulation, independent of the contributions of house-refuse, in the inhabited streets. Table No. LXXXVI shows the number of cubic yards of street-refuse collected in a few cities.

TABLE LXXXVI.

AMOUNT OF REFUSE COLLECTED FROM CITY STREETS.

City.	Street Mileage.	Refuse removed. Cubic yards.
Baltimore.....	780	180,000
Boston.....	73	70,499
Brooklyn.....	365	259,398
Buffalo.....	225	100,000
Chicago.....	660	150,000
New York.....	841	535,709
Philadelphia.....	700	266,831
Washington.....	125	127,623
St. Louis.....	440	200,000

874. The relative amount of dirt produced by the different pavements, if swept daily, appears to be about as follows:

Pavement.	Cubic Yards per 1000 Yards of Surface.
Asphalt.....	.007 to .04
Wood (impervious joints).....	.04 " .07
" (open joints).....	.07 " .20
Granite (impervious joints).....	.015 " .024
" (open joints).....	.07 " .25
Macadam.....	.10 " .35

These figures are only approximations and will vary with the amount of traffic, state of the weather, and character of the pavement of intersecting streets: if these are productive of dirt, a large quantity will be dragged by the vehicles on to the good pavement, which is thus debited with a large quantity of material which does not rightfully belong to it.

The care exercised in the removal of the ashes and garbage by the occupiers of the buildings on the street will also influence the amount of dirt to be removed.

875. Methods employed for Cleansing.

- (1) By hand during the day.
- (2) By hand during the night.
- (3) By hand and machinery during the night, supplemented by a street orderly or patrol system during the day.

Of the above methods each locality will have to decide upon the one which is best suited to its requirements. For large cities the third method is the most suitable:

876. Systems of Executing the Work.

- (1) By contract; the contractor furnishing all the tools and labor.
- (2) By contract for the labor only, the city furnishing the tools and machinery.
- (3) By contract for the horses and removal and disposal of the refuse, the city furnishing the labor and machinery.
- (4) By the city, with its own staff and machinery.

Cleansing by contract has generally proved unsatisfactory, from the difficulty of obtaining a proper observance of the terms of the

contract by the contractor and his employés, and it has been found that the work can be more carefully and systematically carried out by the civic authority with its own officers and staff. It is, perhaps, true that the work may be done under the contract system at less actual cost to the taxpayers, but all public work should be done in the best manner possible irrespective of cost, thoroughly, but without extravagance; and the result of such work, especially where it affects the cleanliness and the appearance of a town, soon fully repays any moderate extra cost that may thus have been incurred, irrespective of the enormous benefit that is conferred upon any community by the reduction of disease and the death rate by a proper attention to such necessary sanitary work.

The semi-military organization introduced by the late Col. Waring in the street-cleaning department of New York City has proved eminently successful. He employed as superintendents men especially fitted by either military or technical training to carry out the duties assigned to them; he organized the laborers into a brigade of self-respecting and efficient workmen, clothed them with a conspicuous white uniform, which most of them keep surprisingly clean in spite of the work they do. The men are in responsible charge of work; if they shirk it, the fact is recorded against them, while good work is also noticed and reported. Each sweeper is furnished with a small wheeled iron framework, to which he attaches a bag of coarse cloth, a broom with a scraper on the back, a watering-can, a short shovel, and a scraper when he has asphalt to look after; with these tools he is expected to keep a definite area of pavement clean. The sweepings, instead of being left in heaps along the gutter to be blown about by the wind and scattered by wagon-wheels, are shovelled up and placed in the bag carried on the truck-frame; when one bag is filled it is tied up and placed on the curb, and another placed in position on the truck-frame. These bags are collected by wagons.

The work is done under the supervision of foremen, inspectors, and other officers, who report how each man is doing his duty. In case the men wish to make complaints, they must first state their case to a committee of forty-one drivers and sweepers; if the committee

cannot decide the case, it goes to a committee of five drivers and five officers of the department; and in case this committee does not come to a decision, it is settled by the Commissioner of Street Cleaning.

877. Cost of Cleaning.—The average cost of cleaning the different pavements appears to be as follows:

Asphalt.....	.003	cent per square yard per cleaning
Stone block.....	.005	" " " " " "
Wood.....	.007	" " " " " "
Brick.....	.0034	" " " " " "
Broken stone.....	.0106	" " " " " "

The average cost of supervision varies from .011 cent to 34 cents per mile.

The cost per mile of street cleansed varies as follows:

Omaha, Neb.	\$16.00
St. Louis, Mo.	17.00
Boston, Mass.	20.00
San Francisco, Cal.	20.75
Brooklyn, N. Y.	22.75
Cleveland, Ohio.	22.90 to 70.00

The amount annually expended per head of population in street cleaning is shown in the following table. It varies from 5 cents in Buffalo and 8 cents in Chicago to 71 cents in New York and 92 cents in Cincinnati.

The average of eleven bids for street cleaning recently received in Buffalo, N. Y., was for asphalt 37 cents per 10,000 square feet per cleaning, for stone block 55 cents per 10,000 square feet per cleaning.

TABLE LXXXVII.

AVERAGE ANNUAL COST PER HEAD OF POPULATION FOR STREET
MAINTENANCE.

Cities.	Average Cost per Head of Population.	
	Construction and Repairs of Streets.	Street Cleaning.
Baltimore, Md.....	\$0.28	\$0.25
Boston, Mass.....	1.84	0.80
Brooklyn, N. Y.....	0.49	0.20
Cambridge, Mass.....	0.64	0.36
Camden, N. J.....	0.38	0.19
Canton, Ohio.....	1.22	...
Chicago, Ill.....	3.18	0.08
Cincinnati, Ohio.....	2.88	0.62
Cleveland, Ohio.....	1.84	0.19
Dallas, Texas.....	0.47	...
Davenport, Iowa.....	1.12	0.19
Detroit, Mich.....	1.63	0.16
Duluth, Minn.....	15.00	0.15
Elmira, N. Y.....	0.40	0.07
Evansville, Ind.....	0.66	0.15
Fall River, Mass.....	0.89	...
Hartford, Conn.....	0.88	0.11
Hoboken, N. J.....	0.46	0.05
Lacrosse, Wis.....	0.81	...
Lawrence, Mass.....	0.74	0.07
Lowell, Mass.....	1.27	...
Lynn, Mass.....	0.72	0.18
Minneapolis, Minn.....	1.21	...
Nashville, Tenn.....	1.71	...
Newark, N. J.....	0.11	0.16
New Haven, Conn.....	1.68	0.06
New Orleans, La.....	0.14	0.10
Newport, Ky.....	0.60	0.16
New York, N. Y.....	0.68	0.71
Omaha, Neb.....	4.15	0.16
Philadelphia, Pa.....	0.61	0.27
Rochester, N. Y.....	1.06	0.15
Rockford, Ill.....	0.51	0.08
St. Louis, Mo.....	1.85	0.28
St. Paul, Minn.....	5.69	0.28
San Francisco, Cal.....	3.21	0.20
Sioux City, Iowa.....	20.05	0.16
Springfield, Mass.....	...	0.28
Taunton, Mass.....	1.41	...
Toledo, Ohio.....	4.08	0.10
Trenton, N. J.....	0.17	0.03
Washington, D. C.....	2.50	0.81
Worcester, Mass.....	1.65	0.08
New York (1896).....	...	1.29
Columbus (1897).....	...	0.16

878. The method of cleaning employed in Berlin, which is said to be the cleanest city in Europe, is as follows:

The men are city employés.

The sweeping-machines are city property, but the horses are hired by contract.

The removal of sweepings is also done by contract; the contractors for this work being obliged to maintain suitable dumping-places, in return for which they receive for their free use the street sweepings. These sweepings are of some value, the contractors often realizing over \$20,000 per annum from them.

The contractors are bound under all circumstances to supply enough wagons to remove each day all street waste. The number of wagons required varies with the weather. In dry weather often hardly half so many wagons are needed as in wet weather. They are required to remove the rubbish as soon as it is swept up, and only in cases of bad weather are the sweepings allowed to stand more than one hour before being carted away. If these regulations are broken, the contractors forfeit a certain amount to the city.

The streets are cleaned during the night.

The number of men employed by the city is about 600, and the number of sweeping-machines in use in 1889 was 42.

The area cleaned in 1889 was 3,361,312 square yards.

The average daily amount cleaned by each man was 5716 square yards.

The area swept by a machine ranges from 6545 square yards on bad pavements to 10,315 square yards per hour on asphalt pavement.

The total expenses of the street-cleaning department in 1888 and 1889 were \$481,493.48, made up of the following items:

Wages.....	\$193,261.44
Uniforms.....	2,769.12
Tools, materials, etc.....	44,819.76
Carting away.....	182,487.12
Sprinkling.....	53,110.56
Depots for supplies.....	1,221.12
Public closets.....	1,279.44
Miscellaneous.....	2,544.48
	<hr/>
	\$481,493.04

Of this sum the street-car companies paid for cleaning and sprinkling the parts of the street occupied by their tracks the sum of \$24,135.58.

The quantity of refuse removed from the streets was as follows: In 1882-83, 95,493 wagon-loads; in 1888-89, 97,969 wagon-loads. The number of loads, therefore, varied very little in spite of the considerable increase of area cleaned. In fact in the year 1888-89 the number was about 16,000 less than in 1878, when it amounted to 113,994 wagon-loads. This was due to the constant increase of good, impervious pavements.

The wages of the laborers employed in the street-cleaning department vary between 36 and 83 cents per day, in addition to which they receive uniforms free. The salaries of inspectors range from \$357 to \$636 per year; they also receive their uniforms free.

New employés after 1½ years service are advanced to a higher grade.

The men are paid for Sundays and holidays, and in case of sickness receive half-pay. Old workmen are pensioned after 10 to 15 years' service at \$100 per year, and for 30 years or more \$150. With relative allowance between, the number of pensioners in 1889 was 11. Assistance is also rendered to sick employés. In 1889 about \$100 was expended for this purpose.

879. In Paris street sweeping is performed by 2200 men, 950 women, and 30 boys. They begin work at 3 A.M. in the summer and at 4 A.M. in the winter and continue without interruption till 11, when the work for women ceases; the men continue for 10 hours and are paid by the day from 65 to 74 cents. The women are paid 6 cents per hour and cannot earn more than 45 cents a day. All are obliged to provide their own brooms. The roadmen in charge of the sweepers are paid from \$21 to \$25 a month. Those receiving the lower salaries are obliged each month to contribute the odd dollar to a reserve fund that is deposited to the credit of each workman until he quits his employment. The plant consists of upwards of 200 mechanical sweepers.

The amount of refuse removed daily averages 2300 cubic yards and requires the daily use of 520 carts and 980 horses. The refuse is disposed of by public tender to contractors for a term of four years.

880. The cleansing of the city of London is carried out under the department of the commissioners of sewers. The force employed consists of about 500 men, women, and children. The work begins at 8 p.m. and is concluded at 9 a.m. The street orderly boys begin work at 7.30 a.m. They number about 150, and their duty is to remove every particle of dirt, especially horse-droppings, in the area assigned to them before it has been ground by the wheels. Bins at the street curb receive the gatherings. Not only the more important streets, but minor ones, courts and alleys, are looked after by the orderly boys. These boys are lodged and fed by the city, a certain deduction for the purpose being made from their wages. As they reach manhood they are promoted to other positions, and when they attain old age, after faithful service, they are pensioned.

The courts and alleys inhabited by the poorer classes are cleaned daily, and from May to October are washed with jet and hose usually twice a week.

881. Baltimore, Md.—Population, 443,547. Street mileage cleaned (1891), 780. Total expenses of street-cleaning department, \$283,070.54.

Distribution of expenses:

Collecting garbage.....	\$189,062.16
Cleaning streets and removing dirt.....	118,423.00
Dumps.....	4,689.40
Tools.....	2,404.50
Superintendence.....	9,991.49
Removing garbage from city (contract).....	8,500.00
	<hr/>
	\$283,070.54

The equipment consists of 150 garbage carts, 61 street-dirt carts, 136 scrapers and sweepers. Work executed by city employés. The wages paid range from \$10 to \$18 per week. The sale of street dirt and refuse realized \$912.76.

882. Boston.—Henry B. Wood, Executive Engineer of the street commissioners of the city of Boston, in a recent communication to the daily press says: That modern hygiene calls for constant attention to the immediate removal of all kinds of street refuse from public highways and places before fermentation takes

place, or disease-laden gases or dust, particles emanating therefrom can be disseminated. A mere occasional attempt to clear up what street litter we cannot climb over is not sufficient; indeed, the pavement must now be swept so clean that it is passable at any point for pedestrians. He continues:

"The number of miles of streets cleaned is 7273.24, at an average cost of less than \$20 per mile, and the number of loads of street dirt removed is 77,000. The entire force of men employed has been about 300. Some streets have been swept every day, in sweeping weather; some three times a week. Each day's work has been so assigned that the computed area covered per week has been figured up to about 590,000 square yards to a district.

"For a paved district of said area a good working gang is composed of one foreman, one sub-foreman, two sweeping-machine drivers, two water-cart drivers, sixteen sweepers, six teamsters, six helpers, and one dump inspector, allowing a trifle over one sweeper to a mile of gutter-stroke. Such a force costs about \$23,000 for a full year. Eighty-one per cent of the streets are either gravel or macadam, and the cost of cleaning averages about \$65 per mile for each cleaning.

"The introduction of the push-cart patrol system as an important adjunct to the regular street-sweeping force has found approval in the tidy appearance of the business thoroughfares. It is found that, even after a street has been once thoroughly swept, in less than two hours' time the sweeping of the sidewalks and the throwing away of waste material into the street will so disfigure its surface that it appears as though the street-cleaning force had neglected it in its daily rounds. To obviate this difficulty the push-cart patrol comes in, collecting and removing this refuse matter continually throughout the day."

In 1894 the average force employed was 303 men, using 3 three-horse machines, 19 double and 21 single sweeping-machines, 11 water-carts, 90 street-carts, 100 horses, 14 asphalt-scrapers, and about 33 extra teams. The number of cart-loads of sweepings removed was 95,478, of which 30,766 loads were dumped at sea; 10,433 miles of streets were cleaned and 2176 miles of paved gutters on macadamized streets. The average cost per mile, including supervision, labor, yard and stable expenses, was \$15.61. The gross expenditure divided by the total mileage of streets in the city shows

that the cost per mile per season was \$679. The operation of the push-cart patrol system was considered most satisfactory, and an extension of their routes is thought advisable. They alone took up 50,280 barrel loads during the year. The cost of snow removal during the year was \$78,382.

883. Brooklyn, N. Y.—Population, 806,343. Street mileage cleaned, 380. Expenses of street-cleaning department, \$239,875; supervision, \$36,000. Work done by contract. Cost per mile, \$22.75; cost per capita, 30 cents.

884. Cleveland, Ohio.—Population, 261,456. Street mileage cleaned, 680. Expenses of cleaning department (1891), \$116,099.51. Work done by contract. Dry-weather cleaning, \$22.90 per mile; spring cleaning and scraping, \$45.80 per mile; wet-weather cleaning, \$70 per mile. Cost per capita, 42 cents.

885. Detroit Mich.—The streets are cleaned when and as often as necessary. The work is done by day's labor, with the aid of sweeping-machines. This work is principally performed by aged persons who cannot do a full day's labor and cannot obtain work elsewhere. The purpose in employing labor of this character is to preserve the independence of the men and keep them from becoming paupers. Eight hours constitutes a day's work, and \$1.50 per day is paid. The hours and per diem allowance are fixed by the common council.

886. In New York the street cleaning is executed by the municipal authority under the direction of a special bureau, part of the labor being furnished by men in its employ and part by contract; the carts are also furnished by contract.

The total number of men employed ranges from 1500 to 2000, and the number of carts is between 300 and 400. The amount of sweeping collected per annum is about 550,000 cubic yards. The number of sweeping-machines employed is about 60. The number of miles of street swept each day is about 60, tri-weekly about 200, and bi-weekly about 70. The refuse is deposited at sea, and it costs 18 cents per cubic yard to place it on the scows.

The cost of cleaning the above street mileage, equal to an area of about 314,179,328 square yards, is about \$1,279,647 per annum.

887. Philadelphia, Pa.—Population, 1,046,252. Street mileage cleaned, 756. Work done by contract. Expense of street-cleaning department, \$552,000; supervision, \$11,920. Ashes are removed

weekly, garbage daily. Amount of refuse removed in 1891: garbage, 84,065 loads; street dirt, 290,680 loads; ashes, 573,999 loads; dead animals, 14,795. Number of men employed, 400; number of machines, 17. The average number of miles cleaned per man was 118.

888. St. Louis, Mo.—Streets paved with granite and wood swept by contract at 50 cents per 10,000 square feet per sweep. Asphalt pavements, 39 cents per 10,000 square feet per sweep. The macadam and Telford cleaned by hand labor, under the supervision of the street department.

889. St. Paul, Minn.—Population, 133,156. Street mileage cleaned, 349.

Total cost of cleaning by city force in 1891:

	Labor.	Materials.
Unpaved streets.....	\$35,470.11	\$119.11
Paved streets.....	20,296.27	1,121.32
Total.....	\$55,766.38	\$1,240.43

Cost of cleaning 30,000 square yards of asphalt pavement by hand under contract, \$49.75 per week.

Paved streets are scraped with hoes in the spring at a cost of about \$35 per mile, and are afterwards kept clean with sweeping-machines at a cost of about \$9 per mile.

890. Washington, D. C.—The cleaning of the streets is at present performed by contract, the rate in 1899 being 23½ cts. for hand and 21½ cts. for machine per 1000 square yards for each sweeping. The improved alleys are cleaned under another contract (1899) at 39 cts. The remainder of the work is done by hired labor, supplemented to some extent by men from the District workhouse. The extent of streets swept by the contractor is 3,102,026 square yards, equal to 126.37 miles.

The remaining streets within the city, which are cleaned by hired labor and the chain-gangs, are as follows:

Pavement.	Square yards.	Length, miles.
Macadam.....	270,320	8.0
Gravel.....	591,418	29.4
Total.....	861,738	37.4
Unimproved.....	1,272,695	71.9

The contractor uses ten four-horse sweepers, five of the Wright and five of the Filbert pattern. The sweeping is done by night, except when the contrary is specifically authorized.

The amount of material removed from the streets averages $1\frac{1}{2}$ cubic yards per sweeping to every 3000 square yards of area swept. Before sweeping the route is sprinkled by the contractor at his own expense. The average force employed by the contractor, besides the 10 large sweepers, consists of 4 sprinkling-carts, from 40 to 50 broom, hoe, and shovel men, and between 30 and 35 carts. The maximum force here named will clean 900,000 square yards of pavement in 12 hours. The total cost of the cleaning is divided between the government and the city, the cost per capita being about 21 cents per year.

891. Street Orderly or Patrol System.—This system comprises a staff of men or boys usually the latter, equipped with a bag or scoop and a brush. Each boy is assigned to a definite area, from which he removes all horse-droppings and refuse as it falls and before it has time to be ground up by the wheels. The pans are of sheet-iron formed as shown in Fig. 281. The bags are of canvas and are shaped like an old-fashioned carpet-bag; one of the lips is provided with a metal edge over which the refuse is swept. The brush is generally made of a bundle of birch twigs.

The refuse so collected is disposed of in different ways.

In London cast-iron boxes are fixed at the curb into which the boys empty the scoops when filled; the receptacles are in turn emptied by shovels into carts at stated intervals.

The bag is claimed to be better than the scoop; it holds more than the scoop, and therefore requires less running to the receptacles to be emptied, and it covers up the refuse; but the emptying process is always troublesome and can hardly be conducted without considerable dirt being scattered in emptying.

In Paris the refuse is collected in a similar manner, but instead of sidewalk receptacles they have a light wrought-iron vehicle proportioned to carry four full bags, two inside and two suspended from hooks on the outside. This system fills the bags at once, allows them to be stored without offence or dirt anywhere, and the final removal is expeditious and cleanly. Fig. 278 shows the hand-cart used by the street patrol in New York and several American cities.

892. Street cleansing is effected either by hand sweeping and scraping or by mechanical sweepers. As to which is the most economical, much depends upon the value of labor, and also upon the condition of the roads to be dealt with. On pavements covered with ruts and depressions machine brooms are not effective, but in point of time and as a general rule the value of a horse rotary-brush sweeping-machine is undoubted; the only time at which such a machine fails to do effective work is on the occasions when the mud to be removed (owing to a peculiar condition of the atmosphere) has attained a semi-solidity, and is of a stiff and sticky consistency, when it either adheres to and clogs the brushes of the machine, or is flattened by them onto the road instead of being removed. In such a condition of the street the scraping-machine must be employed, but care must be exercised in its use, as there is always danger of injuring the pavement.

893. Cost of Street Sweeping.—City Engineer Rundlett has kept a careful account of sweeping the paved streets of St. Paul, by hand and by machines. The average cost by hand in May was \$25.00; June, \$20.18; July, \$18.57. Total average per mile by hand, \$20.00; by machine, \$9.24.

In cleaning the streets of St. Louis the bids for cleaning asphalt pavements are 25 per cent below those based on granite block.

In Washington the street cleaning in 1899 cost 23½ cts. for hand, 21½ cts. for machine, and 39 cts. for alleys per thousand yards, cleaned once.

894. The amount of surface which one man can sweep per hour depends upon the condition of the pavement, dry, wet, or muddy. The following figures are approximate:

Asphalt, dry.....	1200	square yards per hour.
" wet and muddy.....	1000	" " " "
Granite block, dry.....	1000	" " " "
" wet and muddy.....	750	" " " "
Macadam, dry.....	700	" " " "
" wet and muddy.....	350	" " " "

895. The amount of surface cleaned by a mechanical sweeper will depend upon the width of the machine broom, the power of the horses, gradient, and condition of the surface. The wider the stroke of the broom the less will be the cost of sweeping. As the

width of stroke differs in different machines, the area swept by each in a given time will vary with that width.

The average speed of the mechanical sweepers is one and a half miles per hour.

896. The cost of operating a machine sweeper is about 50 cents per hour. With a machine having a stroke of $5\frac{1}{2}$ feet it will require six strokes of the machine to sweep a 30-foot roadway; therefore, to clean one mile of roadway 30 feet wide, such a machine must travel six miles, and will require about four hours and, at 50 cents an hour, cost \$2.00. With a machine having a stroke of 8 feet, but four miles' travel of the machine will be required.

897. Brooms.—The hand brooms used are made of steel wire, rattan, bass and birch. As the strength and durability of these brooms is of some importance as affecting the ultimate cost of street sweeping, care should be exercised in their selection.

Steel wire lasts longer than any other, but is only suitable for block pavements. Bass and birch are weak and speedily wear out. Rattan is most suitable for asphalt and Macadam pavements. Rubber squilgees or mops are most efficient for cleansing asphalt pavements.

898. Carts and Wagons.—The carts and wagons employed in the removal of street dirt should be provided with covers. The employment of wooden carts for this work is not economical; the rough usage which they receive renders their life but a short one, and they are constantly requiring repair. Iron or steel should be substituted. Such carts are to be purchased in the market and have many points to recommend them.

899. The methods employed for the final disposing of the street refuse are many and varied. In the seaboard cities and those situated on rivers it is generally placed on barges, carried to sea or other deep water and deposited. In others it is used for filling in low lands (a practice which cannot be too strongly condemned). In a few localities it is destroyed by fire. This is the superior method and quite successful, and is gaining in favor in situations where difficulties are encountered in disposing of the refuse, the only objection raised against it being the offensive odor. This odor is not so bad as people imagine; it approximates that of burning leather and can be entirely avoided by suitable devices and chimneys of sufficient height. As a rule, people are prejudiced against crematories being located near their residences.

The cost of a plant for a town having a population of 100,000 would be about \$100,000. The cost of cremating the refuse ranges from 20 to 40 cents per ton, depending upon the amount of combustible the refuse contains.

900. Removal of Snow.—An important feature of maintenance is that involved in the removal of snow. Good management implies that it shall be speedily removed and not left to interrupt travel.

901. In American cities no provision is made beforehand for the extra assistance required for its removal, and all that can be done is to collect as many teams and men as possible at the moment; the result is that much valuable time is wasted in this operation. In European cities, this extra labor is engaged in advance. In Paris a contract is made each year with the general omnibus company to supply carts and horses at any time needed. In London also, contingent contracts provide for any additional number of teams required at a moment's notice.

902. The organization and arrangements for the removal of snow in the cities of Milan and Turin, Italy, are the most complete of any city, and a description of their methods may be interesting.

The system adopted in Milan is as follows: The city is divided into districts of varying extent according to their importance; each district is allotted to a contractor, who has to find the carts, horses, and laborers, while the city furnishes the necessary implements, spades, shovels, brooms, scrapers, barrows, etc., with proper stipulations as to their care. The contracts are made annually, and generally the same persons are anxious to secure them. The form of the contract is rigid, and the contractors, who are drawn from the trades most affected by winter—paviors, bricklayers, masons, quarrymen, etc.,—are held to a rigid responsibility. Payment is only made for work which is well done; slovenly and careless execution goes for nothing. The supervision of each district is under an engineer aided by assistants and the police.

Payment is made per inch depth of snow fallen. The average depth of the snowfall in each district is determined from the depth of the snow caught on a number of stone posts fixed in open spaces and clear of shelter from buildings. Each post is capped with a flat slab set horizontally. The depth of the snow on these slabs is meas-

ured by the engineer of the district in presence of two of the contractors of his section.

The average cost of removing the snow per inch of depth per square yard is .006 cent. Ordinarily the removal of the snow from the more active thoroughfares is finished within ten hours of the cessation of the storm, and from the rest within 24 hours, exclusive of night.

The snow is dumped into the navigable canals and water-courses intersecting the city, and latterly into the new sewers in the central portions of the city, which are promptly flushed whenever it snows.

The number of men engaged in the removal of snow in addition to the regular street-cleaning force, ranges from 2000 to 3000, according to the severity of the storm. The implements are housed in different storehouses throughout the city. The whole expense of removing and disposing of the snow during the remarkable winter of 1874-75, when more than 40 inches of snow fell, was about \$44,000. In the case of each storm the work of removal was done within 24 hours.

903. In Turin much the same method is practised, work being paid for by the exact measure of snow fallen. The street-car companies are obliged to bear their share of the expense, paying for a width of 9 feet 10 inches for single and 18 feet 8 inches for double tracks.

904. Many schemes for the disposal of snow have been experimented with, such as dumping it into the sewers, melting it by the application of steam, hot air, etc., as also with salt; but the only successful scheme so far is by cartage, depositing it in adjacent streams, or where this is objectionable, as in the case of navigable rivers, it may be heaped up in vacant lots or in the squares and parks, provided no damage is done to the grass or paths.

905. Dumping the snow down the manholes into the sewers has been tried in London and other cities, but has generally failed through the snow consolidating. An experiment with this method in the city of Cologne gave the following results. A number of shafts were opened into the crown of the main sewer that empties into the Rhine, each shaft being from 2 to 5 feet square. At one of these places the sewer was of oval section, 6 feet \times 4 feet, and the fall was 1:600. It was possible to dump the snow directly from the carts, each of which held about two cubic yards, into the sewer

without stopping the flow there. At another place where the sewer was 4 feet \times 2.3 feet and the same fall prevailed, this process was not possible although a strong stream of water was thrown on the mass from the water service-pipes. The large mass suddenly thrown into the sewer acted as a dam and had to be removed. But at this same shaft when the same amount of snow was regularly thrown into it by four laborers no stoppages occurred. A few hundred feet below the place all the snow was found to be melted. Several hundred loads of snow were removed through these two shafts alone in a few hours.

The cost of melting snow by the application of hot air or steam far exceeds that of shovelling and carting away.

906. In order to grapple with this question of the removal of snow when no provision has been made beforehand, the following suggestions may be of use:

"It is useless to attempt to cart it away while falling, but try to make clear crossings for the foot-passengers and to keep the traffic open. If there should be a high wind at the time, and the snow drifts in consequence, cut through the drifts so as to allow the vehicular traffic to continue. Directly the snow ceases to fall put on all available hands to clear the channel-gutters and street-gratings, in preparation for a sudden thaw, when, if these precautions were not taken, serious flooding and great damage to property might ensue; for the same reason cart away all the snow you can at the bottom of the gradients and in the valleys, and also from very narrow streets and passages, etc. In the wider streets use the snow-plough, or with gangs of men (in the snow season there is generally plenty of labor obtainable) shovel the snow into a long narrow heap on each side of the street, taking care to leave the channel gutters and gratings quite clear, and a sufficient space between the heaps for at least two lines of traffic. Passages must also be cut at frequent intervals through the heaps, in order to allow foot-passengers to cross the street, and also to let the water reach the channel-gutters as soon as the snow begins to melt."

907. With regard to the removal of snow from the footpaths, it is highly desirable that this should be effected by the occupiers of the premises adjacent to the street, as otherwise it adds immensely to the work of the local authority. The following interesting remarks by the superintendent of the scavenging department of Liverpool will be no doubt read with great interest:

"The only way to compass the removal of snow from the footwalks of the principal thoroughfares within a comparatively short time is by sprinkling them with salt such as is commonly used for agricultural purposes. It is certain that, unaided by the salt, a sufficient number of men cannot be procured for the emergency of clearing snow from the footways of the most important thoroughfares. It has been stated by medical authorities that the application of salt to snow is detrimental to the health of people who have to walk through the 'slush' produced by the mixture, and that the excessive cooling of the air surrounding the places where the application has been made is injurious to delicate persons. It therefore seems that the application of salt to snow should not be undertaken during the daytime, but should be commenced not before 11 P.M., nor continued after 6 A.M., and that only such an area of footwalks should be so treated on any one night as the available staff of men can clear by an early hour the following morning.

"To sweep snow from the footwalks whilst the fall of snow continues, and especially during business hours, appears to be wasteful and futile, and to apply salt during the same periods may be held to be injurious to health.

"That the snow of an ordinary fall can be removed from the footwalks by an application of salt an hour or so before they are scraped is an ascertained fact, except at least when a moderately severe frost has preceded, accompanied, or followed the snowfall, or when the snow has drifted into extensive accumulations. Were it not for the danger to health by excessive cooling of the air, and for the expense attending the operation, all the impervious pavements could be cleared of snow (unless the fall was a heavy one) in a comparatively short time by a liberal application of salt and the employment of the horse sweeping-machines as soon as the snow has become sufficiently softened to admit of their use.

In Paris the use of salt for melting the snow is carried to a considerable extent. Pure fine salt for this purpose is delivered at the railway stations at about \$6 per gross ton—the state and city taxes, which amount to \$32, being remitted. It was first used on a large scale in 1880. It produces a dark-colored slush with a temperature of about 10° F., which will not freeze unless the temperature falls below this degree. When it does not interfere too much with traffic in the streets it is often left in place for several days, because

it does not freeze and is to a considerable extent a prevention of slipping. If it becomes too thick, it is removed with scrapers or with sweeping-machines.

The action of the salt is more rapid the more rapid the traffic; on streets of great travel the snow of the salted surface is reduced to mud in two hours.

No account is taken of the effect of the salt and snow mixture on the health of the people.

The salt is spread from wheelbarrows by the shovel, and does not need to be very uniform. If the snow (packed) is six or eight inches deep, a surface layer is first melted and removed, and the lower layer is salted in turn.

Amount of Salt Required.—It is estimated that to melt packed snow to a depth of $1\frac{1}{2}$ to 2 inches about 5 ounces of salt are required per square yard.

The application of salt on broken-stone roads in winter will not prevent the freezing of the ground, but will increase the mud-producing action of the water formed by the melted snow, thus causing their condition to be much worse than if the snow were allowed to remain in its solid form.

In the United States the bad effect upon horses' feet of the cold produced by the use of salt has been the cause of much complaint, and the Society for the Prevention of Cruelty to Animals has taken up the matter of regulating its use.

A mixture of salt and snow produces a temperature in the mixture of 0° F.

Sea-water sprinkled on snow causes the latter to melt rapidly. It will not freeze except at a temperature many degrees below that required to freeze fresh water.

908. Weight of Snow.—Experiments made show that a cubic yard of fresh-fallen snow may weigh as much as 814 pounds or as little as 71, or a range of from 2.63 pounds to 30.14 pounds per cubic foot.

"Snow readily compresses under traffic, and when removed in carts and dumped elsewhere it may be assumed that on an average four cubic yards of snow measured as it has fallen is equal to one cubic yard when placed on the apparatus." This computation, however, does not make any allowance for the snow thrown

from off the roofs, etc., and it of course greatly consolidates whilst travelling in the cart.

909. The removal of light falls of snow from country roads may be effected by the ordinary snow-plough forming it into a long narrow heap on each side, but taking care to leave the gutters unobstructed. Heavy drifts must be cut through with the shovel.

In some localities it may not be desirable to remove the snow, sleighs being used in place of wagons. In such cases care must be taken when a thaw sets in to have ditches and water-courses clear.

910. Street Washing.—Cleansing the pavements by washing them with a stream of water from the fire-hydrants is practised in both Paris and London. In the former city it forms part of the daily routine, but in the latter it is only used periodically, and more especially in the courts and alleys. Disinfectants are also used in Paris in this connection. During 1890 this method was experimented with in New York. The results were not satisfactory; the muddy water collected in puddles in the hollows of the pavement, and the amount of mud and silt carried into the sewers threatened to soon choke them up.

This method is specially applicable to impervious pavements, such as asphalt and stone blocks and brick with water-proof joints. Wood pavements when they become covered with sticky mud are more easily cleansed by washing.

In washing asphalt pavements sufficient water must be used to convert the dust and dirt into a fluid mud; if a quantity insufficient to produce this result is applied, the dirt is converted into a pasty condition, with the result that the surface becomes dangerous for horses. This pasty mud is also difficult to remove either with brooms or other practicable appliances; horse-manure when it dries sticks to the asphalt and cannot be removed in dry weather unless it be previously soaked and scraped off. After washing, the sludge formed should be removed by the use of rubber squilgees; their use will also hasten the drying of the surface.

In many cities, especially such as suffer from periodical droughts, objection is raised to the large quantity of water required for street washing. In many German cities this objection is overcome by scraping the asphalt pavements with rubber squilgees while they are covered with the water from the sprinkling-carts; the operation is repeated four or more times a day. The result is considered

satisfactory, and a considerable saving in the cost of keeping the catch-basins clean is effected, as well as the saving in the cost of the water.

911. Street Sprinkling.—Streets are sprinkled with water for the purpose of laying the dust and cooling the air.

Two methods of applying the water are practised: (1) by hose attached to the fire-hydrants, and (2) by specially constructed carts.

The carts are preferable to the hose method; with the latter there is less regular distribution of the water, and in some localities there may be pressure enough to cause injury to the pavements. Again, the hydrants are generally located so far apart that long lengths of hose are required, and the constant rubbing soon wears them out. To obviate this metal pipe is employed in Paris; the pipes are usually in lengths of $6\frac{1}{2}$ feet, mounted on two-wheeled trucks, and connected by flexible joints.

Carts cause less interruption to traffic, require less time and fewer men; moreover, when there is a scarcity of water they may be filled from wells or rivers.

912. Systems.—Three systems are practised for carrying out the work of sprinkling: (1) by the municipality, with its own equipment and men; (2) by contract, the contractor furnishing the labor and equipment; (3) by contract for the labor, the city furnishing the carts. The first system is generally the most satisfactory.

913. Quantity of water required.—The quantity of water required will vary greatly, depending upon the character of the pavement and the temperature. The average number of gallons used in the United States per 100 square yards is 250; in Paris about 120 gallons per square yard; in London about 150 gallons.

914. Frequency of Sprinkling.—The frequency of sprinkling will depend upon local circumstances. In Berlin all the streets are sprinkled twice a day from April 1st to October 1st, and the principal thoroughfares and squares are sprinkled three and four times per day in this period. For this work the contractor receives on an average \$1.68 per day for each wagon. About 150 sprinkling-carts are used, each holding about 950 gallons. The street-car companies share the expense of sprinkling the streets occupied by their tracks.

In American cities the frequency of sprinkling the streets varies

with the locality and the seasons of the year. The general practice appears to be about as follows:

Paved streets are sprinkled twice a day during the months of March, April, and November, three times a day during May and October, and four times a day during June, July, August, and September.

Unpaved, macadamized, and gravelled, streets are sprinkled twice a day during the months of March, April, May, October, and November, and three times a day during June, July, August, and September.

It is not usual to sprinkle the streets on Sunday, but in some few localities boulevards and driveways used on that day are sprinkled once or twice.

Street sprinkling in San Francisco, Cal., presents some unusual problems, due largely to the clouds of dust brought from the Western Addition hills and the smooth bituminous rock pavements on some of the streets. The difficulties to be overcome, as related to a single street, are stated by Superintendent King as follows:

"One of the main problems to be solved was the best method of sprinkling Market Street from Second to Van Ness Avenue. The difficulties to contend with here are: (1) a smooth pavement which was easily rendered slippery; (2) the strong westerly and northerly winds blowing down the cross streets from the Western Addition strike the buildings on the south side and blow all the dirt from the south side of the street over to the north side; and (3) the winds prevailing in the afternoon are so strong that when the street is sprinkled with a fine enough spray to lay the dust and still not make the pavement slippery, the water is so rapidly evaporated that the pavement is dry and dusty before the cart can complete its trip and return. After several days' experimenting, it was found that the proper way to sprinkle this street is to sprinkle heavily between the car-tracks, to sprinkle the north side of the street with a heavy spray next to the gutter and a light spray outside, and to leave a strip about 10 feet wide next to the outer rail of the car-tracks unsprinkled. The south side of the street is not sprinkled at all. Dust blowing across or down the street is caught and held by the wet pavement and gutter on the north side, and

heavily loaded teams have a dry strip outside of the car-tracks upon which they can travel without slipping."

915. Cost of Sprinkling.—The cost of sprinkling is variable, depending upon the time occupied in travelling to and from the points where the water is obtained and where it is used. The range appears to be from 4 mills to 7 cents per 1000 square yards sprinkled.

In Indianapolis the average cost for sprinkling per lineal foot of street is 16.26 cents, and the average number of gallons of water used per square foot is 6.81.

In St. Paul, Minn., during 1894, the price for street-sprinkling varied from \$12.00 to \$14.20 per mile per week. The sprinkling began April 26 and ended October 31. The cost per foot front to the property owners is from 4.75 to 5.3 cents for the entire season. These prices include the payment of \$5.28 per mile per week to the water department for the water used. The average amount of water used was for July and August 15,100 gallons per mile per day. The average for the four months was 11,580 gallons per mile per day.

916. Sea-water and deliquescent salts (as the chloride of calcium) have been used for street-sprinkling. The surface is kept moist, but at the expense of the moisture in the air, and it is said that horses' hoofs are injured by the chemicals.

In some cities during very hot weather disinfectants are mixed with the water used for sprinkling. The disinfectant usually employed is a mixture of manganate of soda one pound, sulphuric acid half a pint, and water one gallon to every one hundred gallons of water used for sprinkling.

Experiments with salt water have been made in San Francisco. Mr. L. M. King, who superintended the experiment, says:

"Salt water binds the dirt together between the paving-stones, so that when dry there is no loose dirt to be raised by the wind. The salt which is deposited on the street absorbs moisture from the air during the night, so that during the early morning the street is thoroughly moist and has the appearance of having been freshly sprinkled. This effectually prevents dust being raised by the wind or street-sweepers before the regular sprinkling-carts can get over the ground during the morning. It is more healthful than fresh water, for the reason that salt water will destroy many disease-germs now contained in the dirt on our streets."

It is claimed by those cities which use salt water that one load is equal to three of fresh water.

916a. Sanding Pavements.—In all European cities sand is used very freely to prevent the slipping of horses on the pavements, especially on asphalt and wood. The spreading the sand and removal of the ground-up sand add materially to the work of the cleaning department.

Quantity and Manner of Applying Sand.—In Birmingham the sand is spread from a cart with a shovel, and the men who do this work are so expert that they can make an effective covering of the whole street (30 to 45 feet wide) with the use of only one load to the mile.

On Fifth Avenue, New York, the contractor was restricted to the use of four loads to the block or eighty loads to the mile.

CHAPTER XX.

TREES.

917. OPINIONS differ as to the desirability of trees on roads and streets. Some claim that they do more harm than good; that they impede the circulation of the air, and that, as far the shade they afford, people who do not like sunshine have only to keep on the shady side of the way; that they deprive the road-surface of the drying action of the sun and air, and that in wet weather the constant dropping of water from their branches keeps the road in a muddy state. Others claim that trees, especially in streets, temper the heat and serve as a protection against dust, that the evaporation from their leaves tends to keep the surrounding air cool and moist; that the perpetual vibration of their foliage and swaying of their branches, whilst admitting a sufficient amount of light, serve to protect the eyes from the noonday glare; that they act as disinfectants by drawing up and absorbing the organic matters contained in the filth from which the streets of a town are never free and which, infiltrating the ground, are a frequent cause of fevers and infection; and it is asserted that on soil roads some varieties of trees both drain the road and help to hold its earthen surface together by their root-fibres.

“Those who have observed woodland roads closely know they are dry except when below the general grade of the land or actually swamped with water. At any point of temperature a tree, even in winter and without any leaves upon it, is evaporating moisture from its twigs, branches, and trunk. It must freeze very deep to prevent all root-action, and whatever moisture roadside trees may draw from the roadbed will, by so much, prevent the tendency to muddiness in any loam road well filled with tree-roots.”

“Beside the draining and drying effect of tree-roots, the fibres

given to the soil by some kinds of trees (well known to ploughmen in all countries) have a most salutary effect in holding the earth together. If the soil be rich, the whole substance of the raised and rounded roadbed may be completely filled with horizontal stitches, as the housewife darns and runs the heels of stockings, thus trebling their ability to resist friction. Roots in the surface-soil are better than brush to hold up travel when they are alive and pumping water out of the ground. If we are looking for economy, nothing can be cheaper than the way a maple, elm, cottonwood, or white pine will fill the surface of an earth road with fibre. The chestnut, hickory, ash, black walnut, and beech may all be thought of in this connection, but only the close student of nature and the variety of trees adapted to different soils and situations will succeed in this branch of road-making. Yet the nation has many thousand miles of muddy highway where no other improvement seems possible."

"There is a use for the overhanging branches of trees in winter. They shade the road and permit it to freeze or remain solid when, but for the shadow, the road would be softening in the sun. The branches work in this way to prevent and protect the road from being cut in pieces. The traveller and his weary team, swamped in thawed earthen roads, are glad to reach the frozen track on the north side of a bit of woodland. And the man who would cut away roadside shades so as to let all our earth roads thaw out and settle together is very much mistaken."

Trees also serve to make the border of the road discernible at night as well as after snowdrifts, thereby warning the travellers against embankments and other dangers along the sides of the road.

918. In France, as far back as the middle of the sixteenth century, trees were planted along the royal roads. This practice has been more or less continuously followed.

During several periods it was stopped by those in authority, they being of the opinion that trees were more of a damage than a benefit. But now trees are planted along all roads having a width greater than 10 metres (32.8 feet). They are placed at distances varying from 5 to 10 metres (16.4 to 32.8 feet), in single rows upon the narrow roads, and in double rows upon the wider.

919. "The roads of Belgium are flanked on either side by two and sometimes four rows of shade-trees, which add much to the beauty of the country through which they run."

920. Financial Value of Trees.—Take two streets in all respects alike, except that one has trees well selected, set at suitable distances apart and well cared for, the other with no trees or with trees carelessly set and neglected, as frequently happens. A person wishing to purchase a residence will undoubtedly select the street having the fine trees, although he may have to pay more than many times the cost of the trees. Thus from a financial standpoint trees pay.

921. In Saxony a considerable revenue is derived from fruit-trees planted on the roadsides. The trees are cared for by the roadmen in so far as professional knowledge is not required; they remove insects, clear the tree-frames of rubbish, and water them.

In sections where fruit-trees cannot be cultivated on account of climatic causes, or where they would be liable to wanton damage and plundering of the fruit, forest-trees are planted.

The state-road fruit-trees are leased to the highest bidders, and the money received is covered into the state treasury. The lessees of the fruit-trees are held to a strict account for any damage done the trees. Ladders must be used to gather the fruit, and any battering of the trees with clubs or poles to get the fruit down is prohibited and is punishable by fine.

922. Selection of Trees.—Trees should be selected with reference to the climate, locality, quality of soil, extent of space, and circumstances of surroundings in general.

Large-growing varieties should be selected for places of great extent, smaller varieties for places of less extent. A low compact tree is not suitable for street planting.

The qualities necessary in a good street tree are that it must be hardy, must not be affected by a long-continued drought, heat must not wither it nor make it look rusty; it must be able to withstand dust, smoke, soot, foul air, and the insidious attacks of insects, and be able to recover from any malicious or accidental injury it may receive.

The tree must be of rapid growth and develop a straight, clean stem with shady foliage. It must be graceful either in full leaf or when bare, as in winter; its roots must not require too much room, and they must be able to withstand the effects of pollution or rough treatment.

As to what variety to select very little can be said; a large quantity of suitable trees exists from which one may select as local conditions or fancy may dictate.

923. Precautions to be taken in the Selection.—Whatever variety of tree is selected, the following precautions should be taken to insure its flourishing:

(1) The young tree should have been well nourished in the nursery; it should not be planted on the street until its stem is over 8 feet in height and about 3 inches in diameter. The stem should be clean and straight, and the whole tree symmetrical.

(2) The ground where a tree is to be set should be examined to see whether it is suitable for tree-growth. If it is not, the poor material should be removed and good soil substituted. The amount to be removed depends upon circumstances and can be determined by examination. A tree to flourish must have plenty of good ground in which to grow; it should be good to the depth of at least 3 feet, and an equal distance in all directions from the trunk when practicable. The amount of good soil is of greater importance than the shape it is in. The further the tree is planted from the curb the better, so as not only to give it a larger body of soil, but to lessen the risk of killing the tree by the pollution of the ground with gas from defective pipes and also excess of moisture from the gutters.

924. Distance Apart to plant Trees generally appears to be a matter of choice, but this should not be so. Trees should be placed so far from one another that at maturity they will not meet. Such distances will enable them to develop in their natural beauty. To determine the proper distance apart measure the spread of full-grown trees of the same variety as those to be planted; it will vary from 30 to 50 feet. The trees should alternate on opposite sides of the street.

925. Trees at Street-intersections.—Where streets cross at right angles or nearly so, two trees of large-growing varieties may be placed on each corner, far enough from the corner of the curb not to interfere with the catch-basin when there is one. Each tree should be placed on the tree line of one street and the fence line of the other; this will require eight trees to every intersection. The trees so planted should form a handsome mass of foliage and afford an agreeable shade where most needed. At some intersec-

tions it may not be possible to plant all the eight trees, but as many as can should be placed.

926. Protection of Trees.—Each tree should be protected with a light iron railing to prevent mischievous persons from cutting their names on or otherwise injuring the trunk.

Where it is necessary that the footpath be entirely paved the space around each tree may be arranged as shown in Fig. 177. A light stone curb is placed around the tree in a circle the diameter of which should be about 4 feet, and the curb should project above the pavement about 3 to 6 inches; this prevents people from walking on the earth, keeps the ground from becoming hard, and permits air and water to enter to the roots. Or a cast-iron grating 4 feet square may be employed for the same purpose.




FIG. 177. PROTECTION OF TREES IN WALKS.

927. Specifications for Protection of Trees.—The contractor when directed shall protect from injury trees upon the line of the work, and the grading around them must be carefully done. The grass sodding on the sidewalks must also be protected as much as possible.

CHAPTER XXI.

STAKING OUT THE WORK.

928. THE staking out of the work consists in placing stakes in the ground to direct the workmen and define the limits of the work.

The centre line of the proposed road is marked by stakes set (usually) at distances apart of 100 feet on the straight portions, and at 15, 25, or 30 or 50 feet on curves, depending upon their sharpness; on the stakes the cut or fill at that point is marked.

929. The staking out of straight lines and simple curves of less than 100 feet radius presents no great difficulty; curves of greater radius, compound or reverse, will require to be set out by the same formula and methods as are employed for setting out the curves on railroads. For detailed instructions, etc., any one of the many railroad-engineer's pocket-books may be used, such as Henck's, Trautwine's, or Shunk's.

930. Side Slopes.—The setting of the slope stakes on ground that is level or nearly so at right angles to the centre line is a simple matter, the position of the stake being found by adding together the half-width of the roadway, and the base of the triangle obtained by multiplying the depth by the ratio of the slope. When the natural surface of the ground is inclined, the setting of the slope stakes is less simple. The ordinary method employed is a tentative process of combined levelling and calculation, which is nothing better than a rule of thumb. The manner of procedure is as follows: Suppose it is desired to set the stakes *D* and *E*, Fig. 178. The depth of the cutting at *C* is ascertained, and a point is taken on the surface where it is assumed the slope will cut; its height above *AB* is obtained; this height is multiplied by the ratio of the slope, and the half-width *AC* or *CB* added: if this agrees with the distance of the assumed point, that point may be taken as

correct; if not, a second trial must be made. A difference of 6 inches will be of no practical importance.




FIG. 178. MANNER OF SETTING SLOPE STAKES.

The guessing may be aided by taking levels at the points *F* and *G*, and performing the calculations as outlined above.

A more accurate and sometimes a more expeditious method is as follows:

Take a cross-section book, and on each page plot the cross-section of the ground at each station, and draw the slope lines; the exact distances can then be obtained at a glance by counting the spaces between the centre line and the point where the side slope intersects the natural surface.

Slope stakes are required at every centre stake along the line, and also where the ground is very rough at intermediate distances.

931. Setting out Culverts.—The length of a culvert which passes under an embankment is less than the distance between the bottom of the opposite side slopes, and may thus be found: From the height of the embankment *H*, Fig. 179, take the above ground height of the culvert *h*; the remainder will be the height, *h*₁, of the embankment: then the required length *ab* is equal to the top width of the embankment *cd*, plus the width of the base of the slopes on the top of the culvert. Thus if *CD* equal 30 feet, and *h*₁ equal 5 feet, the ratio of the slopes 1½ to 1, the length *ab* will be

$$30 + (5 \times 3) = 30 + 15 = 45 \text{ feet.}$$

932. When the natural surface of the ground is horizontal, the length of any structure passing under an embankment will lie






FIG. 179.

half on each side of the centre line. When the natural surface is inclined, the ends of the structure will be at different distances



Fig, 180.



Fig, 181.

from the centre line, according to the slopes of the ground. This is seen in Figs. 180 and 181, the first of which represents the section, and the second the plan, of an embankment. The lines *SS*

and OO , representing the ends of a culvert passing beneath the embankment, are seen to be at different distances from the centre line. The position of the points S and O may be found by first getting from the tables of side width the points A and D , and measuring in from these points the distances AS and DO , depending upon the slopes AB and AD . In the case of the upper end the distance of SS from A will be less than if the natural surface was level; at the lower end the distance from D to O will be greater. Having found the distances of SS and OO from the centre line, we get the position and length of the wing walls of the culvert by drawing a line from S to any desired angle to intersect the slope AA ; and upon the lower side of the embankment we get, in the same manner, the lines DD , OD , the latter being of course longer than the wings upon the upper side AS , AS .

933. Setting out Bridge Work.—In laying out the abutments for bridges there are numerous cases to be considered,—as whether the bridge is on the square or on the skew, upon a level or a gradient, upon a curve or a straight line, and whether the natural surface is horizontal or inclined; the position and form of abutments and wing walls depending so much upon the various conditions affecting each particular case, that any attempt to lay down general rules for each work would be of little use.

934. Staking out Drains.—The method of setting grade marks for drains is as follows:

At every 50 feet along the line of the trench place a board a couple of feet wider than the width of the trench, bed it firmly in the earth and mark the centre line on it; then ascertain the level of the boards, calculate depth of cutting at each one, and mark it plainly on each board. To transfer the grade line to the bottom of the trench, procure a measuring-rod (say 6 feet long), subtract the depth of cutting from the length of the rod, and to the board that straddles the ditch nail a piece of board upright, the height of which above the horizontal board is equal to the difference found. This operation being performed at each board, a line stretched from the upright pieces will be parallel to the grade line, and six feet above the bottom of the trench.

935. Vertical Curves.—As stated in Article 610, the apex or meeting point of grades require to be rounded off by vertical curves, thus slightly changing the grade at and near the point of

intersection. A vertical curve rarely need extend more than 200 feet each way from that point (Fig. 182).

Let AB , BC , be two grades in profile, intersecting at station B , and let A and C be the adjacent stations. It is required to join the grades by a vertical curve extending from A to C . Suppose a




FIG. 182.

chord drawn from A to C . The elevation of the middle point of the chord will be a mean of the elevations of grade at A and C , and one half of the difference between this and the elevation of grade at B will be the middle ordinate of the curve. Hence we have

$$M = \frac{1}{2} \left(\frac{\text{grade } A + \text{grade } C}{2} - \text{grade } B \right),$$

in which M equals the correction in grade for the point B . The correction for any other point is proportional to the square of its distance from A or C . Thus the correction at $A + 25$ is $\frac{1}{16} M$; at $A + 50$ it is $\frac{1}{4} M$; at $A + 75$ it is $\frac{9}{16} M$; and the same for corresponding points on the other side of B . The corrections in the case shown are subtractive, since M is negative. They are additive when M is positive, and the curve concave upward.

936. Staking out Contour of Street Foundations.—In order to insure the proper transverse form of street pavements, stakes should be driven across the street, the tops of which shall correspond to the intended contour. The stakes should be placed longitudinally of the street at distances not exceeding 16 feet, and transversely at distances not exceeding 10 feet. After the stakes are placed ridges of concrete may be formed along the street, as shown in Fig. 183. After the ridges or small banks of concrete are

so placed the filling of the interspaces may be proceeded with, and a straight-edge resting on the ridges will guide the workmen in keeping the concrete to the proper form; or the stakes may be placed as directed above and a thin slat nailed to their tops, the concrete filled in and made flush with the top of the slat, a straight-edge 17 feet long, its ends resting on the slats, being used for this




FIG. 183. MANNER OF FORMING CONTOUR OF STREETS.

purpose. After the concrete is thoroughly set the slats may be removed and the space they occupied plastered over with cement.

937. Setting Stakes for Curb.—Stakes for setting curb should be placed on the front line of the curb, with their tops at the required grade. Their distance apart should not exceed 50 feet, and on circular work will require to be closer. At street corners three stakes should be driven, one at the intersection point of the meeting curbs and one at each tangent point (Fig. 184).




FIG. 184. SHOWING MANNER OF SETTING STAKES FOR CURBS.

938. In placing the stakes for any structure they should be placed so far outside of the work that they will remain undisturbed during the construction of the work. They must be so placed that lines stretched from any two of them will define the corner and

face of the structure (Fig. 185). Stakes for defining the boundaries of an excavation may be placed at the angles thereof.




FIG. 185. MANNER OF SETTING STAKES FOR STRUCTURES.

939. Two stakes, at a sufficient distance apart upon the land, will fix any line upon the water; and two sets of stakes, upon different lines upon the shore, will by their intersection fix any point upon the water with accuracy sufficient for many purposes. For exact work, however, a transit should be employed to fix a line; and two angular instruments, in well-chosen positions, will determine any point.

940. Bench Marks.—A permanent bench or reference mark for levels should be established with care, in the immediate neighborhood of any proposed structure, from which the elevations of the various parts may be obtained. Such bench marks should also be fixed at the commencement of long cuttings, and generally at intervals of from 500 to 1000 feet along the works, a list of such elevations being entered in the engineer's note-book.

CHAPTER XXII.

SPECIFICATIONS AND CONTRACTS.

941. Specifications.—A specification or detailed description of the various works to be carried out is always attached to a contract, and is prepared before estimates are called for. The prominent points in connection with specifications are as follows:

- (1) Description of the work.
- (2) Extent of the work.
- (3) Quality of the materials.
- (4) Testing of the materials.
- (5) Delivery of materials.
- (6) Character of the workmanship.
- (7) Manner of executing the work.
- (8) Time of commencement.
- (9) Time of completion.
- (10) Manner and times of payment.
- (11) Penalties for infraction.
- (12) Such general instructions and stipulations as may be found necessary in each case.

Attention to these points and a clear and accurate description of each detail (leaving nothing to be imagined) will not only materially contribute to the rapid and efficient execution of the work, but will avoid all future misunderstandings.

942. Concerning Tests of Materials.—While proper tests should always be stipulated, yet if they are carried to an extreme degree, as frequently happens, they defeat their own object. When it becomes impossible to carry out certain unreasonable demands, the alternative is to evade them as much as possible; and it must always be borne in mind that the more stringent the demand, the greater the difficulty in enforcing it.

943. Contracts.—A good, clear, and comprehensive contract is a difficult thing to write, but it should be "common-sense" from beginning to end, and should be the joint production of both engineering and legal ability, neither sacrificing the one feature to the other.

GENERAL SPECIFICATIONS.

The following specifications, in conjunction with those given throughout the work, will aid in preparing specifications for the different works connected with highways.

944. Clearing.—The land will be cleared to the width of feet on each side of the centre line, and on each section must be entirely completed before grading is commenced.

The clearing must be done in such manner that all useful timber may be saved. Trees of large dimensions shall be trimmed and put into the most profitable shape for the market; when so trimmed they shall be piled in such places along the line of the road as the engineer may designate.

Brushwood, stumps, tree limbs, etc., must not be cast upon the adjacent land, but shall be formed into piles and burned; stumps and other material that will not burn, must be removed from the work and disposed of by the contractor. All brush or trees accidentally or otherwise thrown upon the adjacent lands must be taken off and disposed of as above described. The land when cleared must be left in a clean condition, and the contractor will be held responsible for all damage to crops, fences, fruit-trees, and timber of adjacent owners.

945. Close Cutting.—Where embankments are to be formed more than one foot in height, the stumps shall be chopped close to the ground.

946. Grubbing.—Where excavations do not exceed 2 feet in depth, or embankments one foot in height, all stumps shall be grubbed out. The catch-water drains, side ditches, and off-take drains shall be grubbed wherever required.

947. Grading.—Grading will include all excavations and embankments required to form the roadway, all excavations and embankments required for altering the level of intersecting roads. Excavations for the foundations of all structures, excavations for all trenches and ditches, excavations required for the altering of

the channels of streams, etc., and all other excavations and embankments that may be required for the full completion of the road.

The grading shall be executed in accordance with the lines and grades given by the engineer. The portions which are above grade are to be excavated, and such and so much of the excavated material as may be suitable for the purpose, and as may be necessary, shall be filled in those parts which are below the grade lines. The material excavated, not so used for filling, shall be placed in spoil-banks at such points as the engineer designates, or it may be removed from the line of the work by the contractor for his own use and benefit, if so directed.

Where embankments are to be formed of a height less than 3 feet, all top-soil and vegetable matter must be excavated to such depth as the engineer may direct. The material so excavated will be piled up outside of the embankment lines, and afterwards used to cover the slopes of embankments and cuttings; the surplus that remains after completing this work shall be removed and placed in spoil-banks at such places as will be designated by the engineer, or it may be removed by the contractor for his own use and benefit. In places where the embankments exceed 3 feet in height the perishable matter shall be removed, but no excavation done unless specially ordered by the engineer.

All sloping ground covered with pasture shall be deeply ploughed over the base of the embankments before the latter are commenced. On slopes which have been covered with timber the slope shall be cut into steps before the embankment is commenced.

948. Formation of Embankments.—Embankments of a height less than 3 feet shall be made by horses and carts. Embankments of greater height may be formed by tipping from dump-cars travelling on a track.

The embankments will be formed to such height above the sub-grade as the engineer may direct, to provide for shrinkage, compressions, washing, and settlement, and they must be maintained to the required height, width, and shape until accepted. Whenever embankments are made from side ditches, the width of the berm to be left at the foot of the slopes will be given by the engineer.

In the formation of embankments no mud, muck, vegetable

matter, tree stumps, or other materials which the engineer may deem unsuitable, will be allowed to be used. Such material must be removed from the line of the work and disposed of as the engineer may direct.

After completion, the slopes of all cuttings and embankments will be covered to a depth of 6 inches with the loam and vegetable soil previously reserved for this purpose, or such shall be obtained from such places as the engineer may direct.

The slopes of embankments will generally be $1\frac{1}{2}$ to 1, of earth excavations 2 to 1, of rock excavations 1 to 1; and no allowance for excavations outside the limits of these slopes will be made unless specially ordered by the engineer.

The widths, slopes, and other dimensions may be varied at any time by the engineer to suit circumstances.

In the event of slips occurring in excavations, the contractor will remove the débris and reslope the work. If the slips occur through carelessness on the part of the contractor, no allowance for the removal or reshaping will be made; but if they occur through unavoidable causes, he will be paid for it as loose rock or as earth, according to the class to which it may appear to the engineer to belong.

Rock shall be excavated to a depth of two feet below the sub-grade level and the space refilled with stone broken to a size not exceeding $2\frac{1}{2}$ inches.

In the event of work being proceeded with in winter, no snow or ice will be placed in embankments or allowed to be covered up in them, and all frozen earth must be excluded from the heart of the embankment.

949. Earth-work Measurement and Classification.—All earth-work shall be measured in excavation, and will be classified under the following heads, viz., earth, loose rock, solid rock.

Earth will include clay, sand, gravel, loam, decomposed rock, and slate, stones and boulders containing less than one cubic foot, and all other matters of an earthy nature, however compact they may be.

Loose rock will include all boulders and detached masses of rock measuring more than one cubic foot and less than one cubic yard; also hardpan, compact gravel, sandstone, and all other materials of a rock nature (except solid rock) which may be

loosened with the pick, although blasting may be resorted to in order to expedite the work.

Solid rock will include all rock found in place in ledges, and in masses or boulders measuring more than one cubic yard, and which can only be removed by blasting, which fact will be determined by the engineer.

950. Drains.—At such places as may be designated by the engineer, drains will be formed in the following manner: the trenches will be opened to the width and several depths given by the engineer. In the trenches so opened drains of tiles will be constructed, as directed by the engineer.

The tiles furnished shall be the best quality of clay or terracotta, manufactured expressly for drainage purposes; they shall be in lengths of not less than one foot, and shall be of uniform diameter throughout. A pipe of larger diameter, broken in half, will be used for collars; the pipes will be laid true to grade and the trenches filled in with round field stones. The stones must not be thrown in, but shall be laid in carefully by hand, the largest stones being used to wedge the pipes in place; on top of the stone filling place good sods, with the grass side down. Silt-basins will be constructed of brick, of the forms and dimensions shown on plans, at the points designated by the engineer.

951. Catch-water Ditches.—Catch-water ditches will be excavated at the top of the slope of all excavations on the up-hill side only; they shall be excavated not closer than 6 feet to the edge of the slope; they shall be excavated on the lines and to the grades given by the engineer.

952. Off-take Ditches.—These ditches will be excavated wherever directed by the engineer, and will have such form and dimensions as he may direct.

The contractor shall also excavate and form all other drains and ditches which the engineer may deem necessary for the proper drainage of the road.

953. Rip-rap.—In cases where slopes require protection from the action of water, the protection works will be constructed of brush or stones, and will be carefully performed in such manner and of such dimensions as the engineer may direct.

954. Retaining, Breast, Slope, and Parapet Walls.—These walls

will be constructed at such places and in such manner as may be directed by the engineer.

955. Culverts formed of earthenware, cast-iron pipe, stone laid dry or in mortar, will be constructed wherever directed by the engineer. Their form and dimensions shall correspond with the detailed plans prepared therefor.

MASONRY.

Stone masonry will be classified as follows:

956. First-class Masonry shall be built of sound stone, of a quality to be approved by the engineer; it will consist of large rectangular stones, with the beds dressed parallel throughout, and the vertical sides hammer-dressed so as to form quarter-inch joints; the stones will be left quarry-faced except when otherwise ordered; rock-faced stones to have a one-inch chisel-draught cut on all four edges of the face, and no face projection greater than 3 inches.

The rise of the courses of first-class masonry will not be less than 12 inches, and may range up to 24 inches, the thinnest courses being invariably placed towards the top of the work; the stones in adjacent courses shall break joints by at least one foot.

Headers shall be built in every course not further apart than 6 feet; they will have a length in the face of the wall of not less than 24 inches, and they must run back at least $2\frac{1}{2}$ times their height; when they will not allow this proportion, they must pass through from front to back. Stretchers shall have a minimum length in the face of the wall of 30 inches, and their breadth of bed shall be at least $1\frac{1}{2}$ times their height. First-class masonry will be laid in Portland cement mortar, and each course must be thoroughly grouted before the next course is started. Each stone shall be cleaned and dampened before being set. Improperly dressed stones must be recut before placing in the wall, as no hammering will be allowed after the stones are set.

First-class masonry will include all dimension stone, such as coping, cap-stones, bridge seats, and parapets, abutments, and piers of large bridges.

957. Second-class Masonry will include retaining-walls, abutments, wing walls and parapets of minor bridges, and head walls on box culverts. It will consist of broken range-work, built of such stone as may be approved by the engineer; the stones shall be dressed

to horizontal beds and vertical joints; the face shall be "rock face," with edges pitched to line, with no face projections exceeding 2 inches. At least one third of the stones must be headers evenly distributed through the wall; the mortar joints shall not exceed one half-inch in thickness. All vertical joints must be broken by at least 6 inches. No stone will be allowed in the face of the wall which has a less area than 72 square inches. Quoin stones shall have a chisel-draught one inch wide cut on each side of the angle.

The backing and foundation will be of large sound stones, roughly squared, no stone to measure less than 2 cubic feet. The broadest bed will be laid underneath, and must have a good bearing on the stones below. The stones shall be laid in full mortar beds, well bonded with each other and with the face stone, and with all spaces filled with small stones and spalls, well grouted.

No stone shall be cut on the wall, and stones once bedded shall not be removed unless directed by the engineer.

The foundation course shall be of large stones not less than 12 inches in thickness and 8 feet area of bed, and when the wall is 4 feet or less in thickness shall extend from front to back.

The mortar employed for second-class masonry will be of Rosendale cement, in the proportion of 1 of cement to 2 of sand. Portland cement will be used wherever directed by the engineer.

958. Third-class Masonry.—Masonry of this class will generally be used for box culverts, retaining and slope walls, and for backing for first-class masonry. It shall consist of sound stones laid on their natural beds, and roughly squared where used for face work.

The walls shall be carried up in courses ranging from 15 to 18 inches in height; each course shall be well bonded, having a header at every 3 feet. Not more than one third of the stones shall be less than 9 inches thick, or contain less than two cubic feet, and no stone shall be less than 6 inches thick. The stones shall be laid in Rosendale cement mortar, and each course well grouted.

959. Fourth-class Masonry will consist of stone laid dry, and will be used for box culverts, retaining, slope, breast, and parapet walls, and paving of box and arch culverts.

960. First-class Arch-culverts shall be built in accordance with the specifications for first-class masonry, with the exception of the arch sheeting and ring-stones. The ring-stones shall be so dressed that when laid their beds will radiate truly from the centre of the circle. The ring-stones and sheeting shall not be of less thickness

than 10 inches on the soffit, and shall be dressed the full depth of the bed, so as to form joints not exceeding three eighths of an inch; each stone must break joints with its fellow by at least 10 inches. Arch stones to be full bedded in mortar, and each course afterwards thoroughly grouted. The face stones to be rock-face, with a one-inch chisel-draught around the edges.

961. Second-class Arch-culverts.—Arch-culverts of 8 feet span and under shall be constructed of suitable flat bedded stones, ranging, according to the span, from 16 to 24 inches deep, and with a minimum length of from 16 to 24 inches, and 5 to 6 inches in thickness on the soffit. They must invariably extend through the entire thickness of the arch; each stone to be well and closely fitted so as to give half-inch joints, and to break joints with its fellow 9 to 7 inches. The whole to be laid in thin cement mortars, and each course well grouted immediately after being laid.

The face-stones of the arch to be as nearly uniform in depth as possible, of large size, and neatly incorporated with the perpendicular face of the masonry. The keystones to be 10 or 12 inches on the soffit, to have a chisel-draught around their edges, and to project beyond the face of the wall 2 or 3 inches. The side and wing walls will be of second-class masonry.

The extrados of all arches shall be flushed with cement mortar three inches thick, levelled up and rounded to a moderately even and smooth surface.

962. Centring.—Centres of arches must in all cases be well formed, of ample strength, securely placed in position, and in every respect conform to the requirements of the engineer. The ribs must not be placed further apart than 3 feet in any case. The lagging shall be 3 inches thick; the supports of centres shall be substantial and well constructed, and they must be provided with proper wedges for easing centres when required. Centres shall not be struck without permission from the engineer.

963. Wing Walls will generally be of first-class masonry, laid up in steps, each step covered with a hammer-dressed coping.

964. Parapets of masonry structures will be of first-class masonry, covered with hammer-dressed coping.

965. Laying Masonry in Freezing Weather.—No masonry is to be built in freezing weather, except by permission of the engineer. If such permission is given the mortar shall be made by either of the following methods:

Make a mortar of one part of hydraulic lime and three parts of sand, mix thoroughly, and allow it to stand in a heap covered with stable manure until used, to prevent freezing.

Mix mortar for use with ordinary cement in the proportions of one to three. Both mortars to be saturated with brine in the final mixing. Or,

Dissolve one pound of rock salt in 18 gallons of water when the temperature is at 32 degrees Fahr., and add one ounce of salt for every degree lower of temperature, or enough salt, whatever the temperature may be, to prevent the mortar freezing.

No masonry laid in freezing weather to be pointed until spring.

966. Pointing.—All outside joints of first- and second-class masonry shall be raked out to a depth of one inch, and neatly pointed with a mortar made of one part Portland cement and one part of sand.

967. Grouting.—Each course of masonry as laid shall be grouted with a mixture of two parts of cement to 3 parts of sand, no more water being used than that necessary to give the required fluidity.

968. Brick Masonry.—The bricks used shall be of the best quality, hard-burned entirely through, regular and uniform in shape and size. Soft or underburned bricks will not be allowed in the work. The bricks shall be laid in cement mortar made as directed. Every brick shall be laid in a full bed of mortar on bottom, sides, and ends, which for each brick is to be performed at one operation. In no case is the joint to be made by working in mortar after the brick is laid. The joints shall not exceed $\frac{3}{8}$ of an inch, and none shall be less than $\frac{1}{4}$ of an inch, and shall be neatly struck or flush-pointed. Every sixth course to be headers. No "bats" shall be used except in the backing of walls, where a moderate proportion (to be determined by the engineer) may be used, but nothing smaller than half-bricks will be allowed.

The bricks will be inspected and culled on delivery, and those condemned must be at once removed.

The bricks must be thoroughly wet just before laying.

In forming arches the bricks must be laid in concentric rings, each longitudinal line of bricks breaking joints with the adjoining lines in the same ring and in the ring under it.

969. Dry Walls.—Retaining, slope, parapet, and breast walls of

dry stone will be constructed where directed. The stones for this class of work must be sound, flat, bedded stones. No round or cobble stones will be allowed. Not more than one third of the stones shall be less than one foot thick, and no stone shall be less than six inches thick or have a bed area of less than four feet. The stones shall be set horizontally on their largest bed, and so well bedded and fitted as to require neither spalls nor wedges to keep them in place. All walls shall be covered with a hammer-dressed coping of the dimensions shown on the plans.

970. Dry Box-culverts.—The bottom shall be paved with good sound stone closely set on edge under the walls as well as the waterway. The side walls shall be built of large well-shaped stones well bonded and joints well broken. No stone shall have a less area of face than one square foot. There shall be one header to every three stretchers, and the header must pass entirely through the wall. The covering-stones must be entirely sound and wide enough to extend at least two thirds across either wall.

The end walls of box-culverts shall be laid up in second-class masonry and finished off in accordance with the plans. The coping must be of proper and uniform thickness, neatly hammer-dressed on top and face.

971. Pipe-culverts.—Culverts of salt-glazed earthenware or cast-iron pipe shall be constructed at such points as the engineer may designate. The ends of said pipes will be carried by head walls of either brick or stone masonry covered with stone coping. The form and dimensions of these structures shall correspond to the plans prepared therefor.

The earthenware pipe shall be of the quality known as culvert-pipe. It shall be sound and well burned throughout, free from cracks, flaws, fire-checks, and other imperfections, and shall be of uniform thickness throughout and shall have not less than the following weights:

Internal diameter.	Weight per foot.
6 inches.....	15 pounds
9 "	28 "
12 "	40 "
15 "	60 "
18 "	80 "
20 "	90 "
24 "	180 "

The joints shall be closed with cement-mortar.

Cast-iron pipe shall be used wherever directed by the engineer, and shall be obtained from a foundry approved by him. It shall be of the diameters and thickness ordered, will be laid in the same manner as earthenware pipe, and the joints calked with lead if so ordered.

972. Cement.—All cement furnished must be of some well and favorably known brand, and shall be approved by the engineer. It shall be delivered in barrels or equally tight and safe receptacles, and after delivery must be protected from the weather by storing in a tight building or by suitable covering. The packages shall not be laid directly on the ground, but shall be laid on boards raised a few inches from it. To insure its good quality it shall be subjected to the following tests, and every cask or lot of cement rejected by the engineer shall be conspicuously marked "condemned," and shall be removed from the site of the works; and, after rejection, should any of the cement so rejected be found to have been used, the work where it has been used shall be taken down and replaced with cement of the proper quality without extra compensation.

The supply of cement must be so gauged that a sufficient quantity will be kept on hand to allow ample time for the tests to be made without delay to the work of construction.

973. Cement Tests.—The Rosendale cement must stand a tensile strain of 50 pounds per square inch of sectional area on specimens mixed to a stiff paste and allowed to set thirty minutes in air and twenty-four hours under water, and of 90 pounds on specimens allowed to set seven days under water, and shall be ninety per cent fine when tried with a sieve having 2500 meshes to the square inch. It must take not less than twenty-five minutes to bear the light wire, that is, a weight of four ounces on a wire one twelfth of an inch in diameter.

Portland cement shall be tested in the same manner and the requirements for fineness will be the same, but specimen briquettes will be required to resist without fracture a tensile strain of at least 175 lbs. per square inch at the expiration of three days, and at the expiration of seven days to show an increase of at least 50 per cent over the strength at three days, but it must bear a minimum strain of 350 lbs. per square inch at the end of seven days.

974. Sand.—The sand used for making mortar shall be sharp,

clean, and free from loam and vegetable matter. If sand of the required quality cannot be found in natural beds on the line of the work, it shall be furnished by the contractor. The sand shall be screened and washed if so ordered by the engineer.

975. Water.—The water employed for mortar shall be fresh and clean, free from mud or other objectionable matter. Sea-water may be used if permission is given by the engineer.

976. Mortar shall be composed of two parts of sand and one part of cement, mixed thoroughly dry and tempered to the required consistency.

When Used.—It shall be used as soon as made, and any mortar that may have taken a "set" while unused shall be wasted.

Variation in Proportion.—No variation from the above proportions will be permitted unless to make the mortar richer when required in special cases.

Tempering.—The thorough mixing and incorporation of the materials will be insisted upon. The dry cement and sand shall be turned over and mixed with shovels by skilled workmen not less than ten (10) times before the water is added; after adding the water, the paste shall be again turned over and mixed by skilled workmen not less than six (6) times before it is used.

Boxes.—Tight mortar boxes will be provided, and no mortar shall be made except in such boxes.

977. Concrete, how Composed.—Concrete shall consist of angular fragments of sound, durable stone or hard-burnt brick, which shall be cleaned and thoroughly freed from dust and dirt, and broken so as to pass in any direction through a ring two (2) inches in diameter, and of hydraulic cement and sand, in the following proportions by volume:

Cement	1 part
Broken stone.....	5 parts
Sand.....	2 "

Mixing.—These materials shall be intimately incorporated on the mixing-board or in a mechanical mixer, and after proper tempering shall be deposited carefully in place and thoroughly rammed until the surface is floated.

Period of Repose.—The concrete so laid shall be left without disturbance or shock for at least twenty-four (24) hours.

Variation in Proportions.—The above proportions shall be varied without extra compensation upon the order of the engineer and to his entire satisfaction.

Expeditious Operation.—The whole operation of mixing and laying each batch of concrete shall be performed as expeditiously as possible, with the use of a sufficient number of skilled men.

978. Foundation Excavation.—Foundation-pits shall be excavated to such depths as the engineer may deem proper for the safety and permanence of the structure to be erected.

979. Artificial Foundations.—Foundations of piles, timber, plank, and concrete shall be prepared of such dimensions and in such manner as the engineer may direct, and the materials used shall conform in quality, etc., to the requirements stated for the respective kinds.

980. Timber.—The timber furnished shall be sound, straight-grained, well seasoned, and free from sap, large knots, shakes, and wanes. Knotty timber will not be allowed in the work where such would impair its strength.

981. Piles.—The piles shall be of sound, straight-grained timber from which the bark has been removed; they shall measure not less than 8 inches in diameter at the small end, nor be less than 28 feet long. They may be driven with any approved form of pile-driver or by the "hydraulic jet;" if they are driven by this latter method, they shall be constantly loaded with a weight of 2000 lbs. They shall be driven, by whichever method adopted, until they do not move more than one-half inch under the blow of a hammer weighing 2000 lbs. and falling 30 feet.

982. Cofferdams.—Where cofferdams are required for foundations, they shall be constructed in the manner directed by the engineer, and all pumping, bailing, and draining shall be performed as required and directed by the engineer.

983. Wrought-iron.—All wrought-iron work furnished to be of the specified form and dimensions. The wrought-iron used shall be the best refined iron; it shall be tough, close-grained, highly fibrous, and when broken shall show a blue-gray fracture. It shall bear a high welding heat, and a cold bar must bend through 90 degrees without sign of fracture; the tensile strength to be not less than 50,000 lbs. per square inch of sectional area when tested in large and long lengths. The reduction of breaking area shall average 25

per cent, and the elongation of the bar before rupture shall be at least 15 per cent. Iron subjected to compressive strain to have an elastic limit of not less than 25,000 lbs. per square inch.

984. Cast-iron.—All cast-iron work to be of the specified form and dimensions; the iron to be gray iron, of uniform color and structure, with medium grain, sharp bright fracture, tough texture, and a low percentage of graphite. It shall be clean and free from sand, scoria, cold-shuts, blow-holes, blisters, or other injurious defects. Sample pieces 1 inch square, cast from the same heat of metal in sand-moulds, shall be capable of sustaining, on a clear span of 4 feet 8 inches, a central load of 500 pounds when tested in a rough bar. A blow from a 4-pound hand hammer shall produce an indentation on a rectangular edge of the casting without flaking the metal.

GENERAL STIPULATIONS APPLICABLE TO ALL CONTRACTS.

The following stipulations are applicable to all classes of work and should be inserted in all specifications, being varied, of course, to suit each particular case.

985. Interpretation of Specifications.—In case of ambiguity of expression in the specifications, or doubt as to the correct interpretation of the same, the matter shall be submitted to the engineer, whose decision shall be final.

986. Omissions in Specifications.—Any work or materials that may have been accidentally omitted in the description of the work, but which is clearly implied, shall be furnished by the contractor the same as if it had been specifically stated.

987. Engineer defined.—Wherever the word "engineer" is used it refers to the chief engineer or his authorized assistants, by whom all explanations and directions necessary for the satisfactory prosecution and completion of the work described in these specifications will be given.

988. Contractor defined.—Wherever the word "contractor" is used it refers to and means the party or parties who shall have duly entered into contract with the _____ of _____ to perform the work; their duly authorized agents or legal representatives.

989. Notice to Contractor.—Any written notice to the contractor which may be requisite under these specifications may be served on

said contractor either personally or by mail, or by leaving the same at his last known place of residence.

990. Preservation of Engineer's Marks, etc.—All engineer's marks and stakes after location shall be carefully preserved without disturbance until permission for their removal or erasure shall be given, and every facility must be furnished for the staking out, etc., of all work to be done under these specifications.

991. Dismissal of Incompetent Persons.—Any incompetent person or persons who may be employed on the work shall be removed on the requisition of the engineer; and no person so removed shall thereafter be employed upon any portion of the work.

992. Spirituous Liquors.—Contractors are not to give or sell or suffer any one to give or sell or keep any ardent spirits on any part of the work or in any boarding-house or building under his control.

993. Quality of Materials.—All materials furnished and used under these specifications must be of the best quality of their respective kinds, free from any and all defects which in the judgment of the engineer may render them unfit for use. Rejected material must be at once removed from the works or conspicuously marked "condemned." If condemned material is used in any part of the work, the same shall be removed and replaced with materials of the quality required by these specifications.

994. Samples.—Before any materials are used, samples thereof shall be furnished the engineer by the contractor. Said samples, if approved, shall remain in the engineer's office and be used as the standard with which all like materials furnished under these specifications must agree.

995. Deviations from Plans and Specifications.—No deviations from the specifications or detailed plans will be allowed, unless a written permission shall have been previously obtained from the engineer.

996. Right reserved to alter Details.—The engineer, during the progress of the work, may, by giving written notice to the contractor, alter any of the details of construction in any manner that may be found expedient or suitable; such alterations shall not invalidate the contract, and the contractor must adopt and execute the same as if they were part of the original contract, and at the completion of the work an allowance will be made for such alterations, etc., either for or against the contractor as the case may be, and the value of such alterations will be estimated by the engineer

from the schedule of prices attached to the contract, or should it not apply, the equitable amount will be estimated by the engineer.

997. Inspectors.—The work under these specifications is to be prosecuted at and from as many different points on the line of the work as the engineer may from time to time determine, and at each of said points inspectors may be placed on the day designated for the commencement of the work thereat. Whenever any work is in progress at or from one or more points at a time, an inspector may be appointed by the engineer to supervise each subdivision of the same, viz., for the inspection of the material, excavation, preparation for the foundation, the laying of the pavement, etc.

998. Defective Work.—The contractor will be held responsible for the faithful execution of the work in accordance with the specifications. Any defective work that may be discovered by the engineer or his appointees before the final acceptance, or before final payment shall have been made, shall be removed and replaced by work and materials which shall conform to the spirit of the specifications; the fact that the inspector or other person in charge may have overlooked such defective work shall not constitute an acceptance of the same.

999. Measurements.—The different classes of work will be measured as follows:

Clearing and grubbing by the acre.

Excavation in all classes of earth, rock, etc., and in all situations, including ditches, foundations, altering the channel of water-courses, borrow-pits, etc., by the cubic yard; the measurement shall invariably be made in excavation. If any case should arise where this may be found impossible, then the engineer shall determine the quantities, making all proper allowances, of which he will be the judge.

Overhaul.—The contract price of excavation shall be taken to include the whole cost of hauling, except only extreme cases which may involve a haul of more than eight hundred (800) feet. For every hundred feet over eight hundred (800) and up to twenty-five hundred (2500) the contractor will be allowed at the rate of one cent per cubic yard; that is to say, in the event of the haul being in any case 2500 feet, seventeen cents (17) per yard will be added to the schedule rate, and will be the maximum allowance for overhaul in any case.

The price stipulated for excavation of the several denominations, together with the price of overhaul in extreme cases, shall be the total price for excavating, loading, removing, depositing, and shaping all the material. In a word, the rates and prices stipulated in the contract must be understood to cover every contingency,—the furnishing of all labor, material, power, and plant, the cost of finishing up cuttings and embankments, the dressing and draining of borrow-pits, and the dressing of slopes to the required angle, and the completing of everything connected with the grading in a creditable and workmanlike manner, in accordance with the directions and to the satisfaction of the engineer.

Masonry of all kinds and classes (stone and brick) by the cubic yard in place.

Timber, lumber and plank, of all kinds and for all purposes, by the foot, board measure, in place.

Piles by the lineal foot in place.

Culvert and Drain-pipe of all classes by the lineal foot in place.

Stone, Brick, and Pole Drains by the lineal foot in place.

Concrete by the cubic yard in place.

Curbing by the lineal foot in place.

Gutters by the square foot in place.

Crossing or Bridge Stones by the square foot in place.

Catch-basins by number as completed, including all appurtenances and connections.

Bridges by the lineal foot in place.

Pavements.—All classes of pavements will be measured by the square yard in place; and the area occupied by the rails of street railways will be deducted, but the space occupied by manhole heads and catch-basins, when not exceeding one square yard each, will be included.

The several measurements will be made and computed by the engineer, and his final return of the several amounts shall be the only valid account of the work done and materials furnished. All previous estimates upon which partial payments may have been made are merely approximate, and subject to the correction of the final return.

1000. Partial Payments.—Monthly estimates shall be made during the progress of the work, and payments to the amount of 80

per cent thereof will be made, the retained percentage not being due or payable until the final completion of the work. These monthly estimates do not constitute an acceptance of the work, the final estimate and formal acceptance constituting the only valid acceptance of the whole or any part of the work.

1001. Commencement of the Work.—The work to be done under these specifications shall be commenced on such day and at such place or places as the engineer may direct. Failure to so commence without a good and valid reason therefor will be authority for the _____ to declare the contract forfeited, and the said _____ may proceed with the execution of the work in such manner as may be deemed proper.

1002. Time of Completion.—The work shall be prosecuted in such manner as to complete it in accordance with the specifications on or before the expiration of _____ working days. Should the execution of the work be delayed in consequence of any act or omission on the part of the _____, the condition of the weather, or by any circumstances so unusual that they could not be foreseen previous to or avoided during the construction of the work (all of which shall be determined by the engineer, who shall certify the same in writing), the time during which the work was so suspended shall be excluded, and the time extended by a corresponding number of days.

But neither an extension of time for any reason beyond the date fixed for the completion of the work, nor the acceptance of any part of the work comprised in these specifications subsequent to the said date, shall be deemed to be a waiver by the said _____ of the right to abrogate the contract for abandonment or delay in the manner herein provided.

1003. Progress of Work and Forfeiture of Contract.—The _____ reserves the right to declare the contract forfeited, if at any time it should appear to the engineer that the work or any part thereof is being unnecessarily delayed, or that the contractor is wilfully violating any of the conditions of the contract, or is executing the same in bad faith, or if the said work be not fully completed within the time named for its completion; he shall have power to notify the contractor to discontinue all work or any part thereof, by a written notice to be served upon the contractor either personally or by leaving said notice at his residence or with his _____.

agent in charge of the work. And thereupon the contractor shall discontinue said work or such part thereof, and the engineer shall thereupon have the power to place such and so many persons as he may deem advisable, by contract or otherwise, to complete the work, or such part thereof, and to use such materials as he may find upon the line of said work, and to procure other materials for the completion of the same, and to charge the expense of said labor and materials to the aforesaid contractor; and the expense so charged shall be deducted and paid by the _____, out of such moneys as may be then due, or may at any time thereafter become due said contractor on account of work performed under these specifications; and in case such expense is less than the sum which would have been payable if the same had been completed by the said contractor, he shall forfeit all claim to the difference; and in case such expense shall exceed said sum, he shall pay the amount of such excess to the _____.

1004. Damages for Non-completion.—The contractor shall pay to the _____, as damages for non-completion of the work within the time stipulated for its completion, the sum of \$100 for each and every day which may exceed the said stipulated time for its completion, which said sum of \$100 per day is hereby, in view of the difficulty of estimating such damages, agreed upon, fixed, and determined by the contractor and the _____ as the liquidated damages that the _____ will suffer by reason of such default, and not by way of penalty; and the _____ is hereby authorized to deduct said sum of \$100 per day from the moneys which may be due or become due said contractor for work under these specifications.

1005. Evidence of the Payment of Claims.—In case of any legal claims being filed with the _____ against the contractor for labor or materials furnished under these specifications, the said _____ shall retain the whole or so much of such moneys as may be due or to become due the contractor as may be considered necessary to meet the lawful claims of such persons, until the liabilities shall be fully discharged and such notice withdrawn.

1006. Protection of Persons and Property.—The contractor shall during the progress of the work use all proper precautions by good and sufficient barriers, guards, temporary bridges, etc., for the prevention of accidents, and at night he will put up and keep suitable and sufficient lights, and he will indemnify and save harmless the

against and from all suits and actions, of every name and description, brought against it, and all costs and damages to which the said may be put for or on account or by reason of any injury or alleged injury to the person or property of another, resulting from negligence or carelessness of the contractor, his agents or employees, in the performance of the work, or in guarding the same, or from any improper materials used in its prosecution, or by or on account of any act or omission of the contractor, his agents or employees; and the shall retain the whole or so much of the moneys due or to become due by reason of the work under these specifications as may be considered necessary, until all such suits or claims for damages as aforesaid shall have been settled and satisfactory evidence to that effect is furnished.

1007. Bond for Faithful Performance of the Work.—The contractor shall execute with his sufficient sureties a bond in the sum of thousand dollars for the faithful performance of the work in accordance with the requirements of the specifications.

1008. Power to Suspend Work.—The prosecution of the work may be suspended for such periods as the engineer may from time to time determine. No claim or demand shall be made by the contractor for damages by reason of such suspensions in the work, but the period of such suspensions will be excluded in computing the time limited for the completion of the work. During such suspensions all materials delivered upon but not placed in the work shall be neatly piled or removed so as to not obstruct public travel. The wages of watchmen retained for the public protection during the period of suspension will be allowed.

1009. Loss and Damage.—All loss and damage arising out of the nature of the work to be done under these specifications, or from any unforeseen obstructions or difficulties which may be encountered in the prosecution of the same, or from the action of the elements, or from incumbrances on the line of the work, shall be sustained by the contractor.

1010. Miscellaneous Work.—If any work or service be required to be done which in the opinion of the engineer does not come within the class of work to be measured under the contract, he shall be at liberty to direct the contractor to perform the same by day's labor, and the contractor when required by him shall furnish such force and materials and perform such work in the manner

directed, and he shall be paid the reasonable and actual wages of the men as ascertained by the timekeeper and the actual value of all materials furnished, together with fifteen per cent of the total amount for the use of tools and profit. The engineer shall be at liberty to discharge any inefficient or unsuitable workmen who may be placed on such work, and the work so performed will be subject to his approval before payment is made therefor.

1011. Cleaning up.—All surplus materials, earth, sand, rubbish, and stones, are to be removed from the line of the work as rapidly as the work progresses. At any time within one month after the completion of the work, if so required by the engineer, all material shall be swept into heaps and removed from the line of the work; and unless this be done by the contractor within forty-eight hours after being notified so to do to the satisfaction of the engineer, the same shall be removed by the _____, and the amount of the expense thereof shall be deducted out of any moneys due or to become due to the contractor under these specifications.

1012. Personal Attention.—The contractor shall give his personal attention to the faithful prosecution of the work, shall not sublet the same or any part thereof without the consent of the _____, nor will he assign by power of attorney or otherwise any of the moneys payable under these specifications.

1013. Payment of Workmen.—The contractor shall punctually pay the workmen who shall be employed on the work comprised in these specifications, in cash current, and not in what is denominated "store" pay.

1014. Prices.—The prices stated by the contractor in his tender and stipulated in the contract must be understood to cover every contingency, the furnishing of all labor, materials, power, and plant which may be required for the performing and completing of the work described in these specifications (and for maintaining the same in good order for a period of six months).

1015. Payments, when Made.—The contractor shall not be entitled to demand or receive payment for any portion of the work done or materials furnished under these specifications until the same shall be fully completed in the manner set forth, and such completion duly certified by the engineer in charge of the work, and until each and every of the stipulations herein before mentioned are complied with, and the work completed to the satisfac-

tion of the _____ and accepted by _____, whereupon the _____ will pay in cash, on the expiration of _____ days from the time of acceptance, the whole of the moneys accruing to the contractor under these specifications, excepting such sum or sums of money as may be retained under any of the provisions herein contained, and such sums as may have been paid in the form of partial payments upon the monthly estimates of the engineer.

FORMS OF SPECIFICATIONS.

The following forms of specifications may be of assistance in preparing specifications for different works.

1016. Specifications for the Construction of a Highway from _____ to _____ in the town of _____, county of _____.

The following specifications are intended to cover the methods of construction and the furnishing of all the labor and materials necessary for the proper and workmanlike completion of the above-named highways in accordance with the plans on file in the office of the engineer, and in accordance with such instructions relating thereto as may from time to time be given by said engineer, or his assistants and inspectors.

Description of the Work.—The character and approximate amounts of work to be done are as follows:

Earth excavation.....	cubic yards
Loose rock excavation.....	" "
Solid " ".....	" "
Embankment to be furnished from.....	" "
Borrow-pits.....	" "
Blind stone drains.....	lineal feet
Tile drains, 8 inches in diameter.....	" "
" " 6 " " ".....	" "
Earthenware pipe-culverts, 12" diameter.....	" "
" " " 18" ".....	" "
" " " 24" ".....	" "
Dry box-culverts.....	cubic yards
" " " , third-class masonry.....	" "
Dry retaining-walls.....	" "
Rip-rap.....	" "
Catch- and silt-basins, number of.....	
Paved gutters.....	lineal feet

[Here insert the clauses suitable for each class of work in the schedule.]

1017. Specifications for Bulkhead (Fig. 138, p. 495).

The bulkhead will be formed as follows:

The piles will be of sound straight-grained spruce or other approved timber; they shall measure not less than 6 inches in diameter at the small end and not less than 12 inches nor more than 15 inches at the large end when cut off. The piles shall have the bark removed, be accurately pointed, and when required the heads shall be properly banded to prevent splitting or brooming while being driven; if found necessary, the points shall also be protected with wrought-iron shoes. The piles will be spaced 6 feet from center to center, and shall be driven with a batter of $1\frac{1}{4}$ inches per foot. They may be driven by the hydraulic "jet" or by an ordinary pile-driver; if by the jet, they shall be loaded with a weight of 2000 pounds. By whichever method driven, they shall reach a total penetration into the soil and sand of not less than 15 feet below low-water mark. Piles injured in driving shall be drawn out and replaced by sound ones at the contractor's expense. Piles found too short shall be drawn out and replaced by longer ones.

Lengthening.—Lengthening by using a follower or blocking will not be allowed. Any pile found too short must be drawn out and a longer one substituted. When the piles shall have reached the required depth, their tops shall be sawed off evenly at the established grade.

Pile-cap.—And thereon a pile-cap of yellow-pine timber ten (10) by twelve (12) inches will be laid, fastened to each pile with one one- (1-) inch drift-bolt eighteen (18) inches long. On the water face and thirty (30) inches below the top of the pile-cap there will be placed a

Brace Stick of yellow-pine timber five (5) by ten (10) inches, bolted to every second pile with one one- (1-) inch bolt eighteen (18) inches long. On the water face at mean high-water mark there will be placed a

Chafing-stick of yellow-pine timber five (5) by ten (10) inches, bolted to every pile with one one- (1-) inch bolt. On the land side of the piles at both mean high- and low-water marks there will be placed longitudinally

Wale-sticks of yellow-pine timber five (5) by ten (10) inches, bolted to every pile with one one- (1-) inch bolt.

Sheet-piling.—On the land side of the wale-sticks sheet-piling

of tongued and grooved yellow-pine plank, three (3) inches thick and not less than eight (8) inches wide, will be driven to a depth of not less than ten (10) feet below low-water mark. Each plank will be spiked to both wale-sticks with two six- (6-) inch cut spikes; the tops will be sawed off level with the upper wale-stick.

Anchor-piles.—On the land side and opposite every third pile and eighteen (18) feet distant therefrom an anchor-pile not less than six (6) inches in diameter and ten (10) feet long will be driven to the angle shown on plan, to a penetration of not less than seven (7) feet. At the back of the anchor-piles there will be placed loosely upon the ground a brace-stick of yellow-pine timber five (5) inches by ten (10) inches.

Tension-rods.—Tension-rods made from one and one quarter ($1\frac{1}{4}$) inch iron will extend from front to rear brace-stick, passing through both sticks and piles; the rods will be screwed on both ends and will have under each nut on the water face an iron washer four (4) inches in diameter, cast to the required angle.

Bolt-holes.—All bolt-holes will be bored with an augur one eighth ($\frac{1}{8}$) of an inch smaller than the diameter of the bolt they are to receive.

Fender-piles.—Fender-piles eighteen (18) inches in diameter at the butt and 30 feet long will be driven at every twenty (20) feet along the water face.

Lengths of Timber.—The pile-cap, braces, and chafing-sticks shall be in lengths of not less than eighteen (18) feet; they shall be arranged so as to bring the

Joints on a pile. All joints shall be made by a twelve (12) inch half-lap splice fastened with two seven eighths ($\frac{7}{8}$) inch by fifteen (15) inch bolts. All bolt-heads in pile-cap will be countersunk flush with the top. Iron washers will be placed under all bolt-heads and nuts.

1018. Specifications for Grading, Macadamizing, Curbing, and Flagging Avenue, from to .

Grading.—The entire width of the avenue is to be regulated and graded to sub-grade, fifteen (15) inches below finished grade, in accordance with the grades and cross-section shown in plans. Such portions as are above the grade lines shall be excavated, and as such are below shall be filled in.

Slopes.—Slopes in both embankment and excavation shall be

one and one half (1½) horizontal to one (1) vertical unless otherwise ordered.

If the material taken from the excavations is unsuitable or insufficient to make the embankments, the deficiency shall be supplied by the contractor. The material so furnished shall be good clean earth, sand, gravel, or broken rock and earth. If broken rock is furnished, the proportion of earth and rock shall not be less than 1 to 1, and the materials shall be so distributed that no voids shall be left.

Any perishable matter that may be found at sub-grade level shall be removed and the space filled in with good material.

The sub-grade surface shall be truly shaped and trimmed to the required cross-section, then rolled with a roller weighing not less than 300 pounds per inch of run. The rolling will be continued until the surface has become firm and hard: in no case shall it be less than 5 hours per 1000 square yards. Such parts as cannot be reached by the roller shall be tamped with hand rammers. Water shall be applied by sprinkling in advance of the roller, but an excess must not be used; generally 25 gallons per 1000 square yards will be sufficient.

On the sub-grade surface prepared as above described a layer of bank gravel will be spread to a depth of nine inches and rolled continuously until the depth is reduced to seven inches; on the foundation so prepared the broken stone will be placed. Its finished thickness will be eight inches. The stones will be spread in two layers: the first layer will be spread to a depth of five and a half inches and rolled till the depth is reduced to five inches; water will be applied in advance of the roller, but not in excess. When the broken stone is so compacted a layer one inch thick of clean sand, or sand containing not more than 15 per cent of loam, will be spread over the surface, and the rolling continued until the stones cease to sink or creep in front of the roller, and the thickness of the layer of broken stone is 4 inches or thereabouts. When the first layer has been finished to the satisfaction of the engineer, the second layer will be spread to the same depth and treated in the same manner as the first layer. The rolling of this surface will be continued until all settlement has ceased.

In quality the stone must conform to the sample in the office of the engineer.

In form it shall be as nearly cubical as practicable, and in size shall not exceed in any dimension two and a half inches, but may range from this size down to quarter-inch chips; but the proportion of stones below one and a half inches shall not exceed 20 per cent of the whole quantity. The stone will not be screened, but shall be delivered as it comes from the breakers; care, however, being taken that clay does not become intermixed with the stone.

Gutters.—For a width of two feet on each side of the carriage-way adjoining the curb a gutter of granite blocks will be laid. Each block shall measure not less than six nor more than nine inches in length, in width not less than three nor more than five inches in depth, not less than seven nor more than eight inches; the blocks to be split and dressed so as to form, when laid, close joints on sides and ends.

The blocks will be laid in courses parallel to the curb. Each course shall be formed with blocks of a uniform width and depth, and laid so that all the longitudinal joints shall be broken by a lap of at least two inches.

The blocks will be laid on the gravel foundation and set stone to stone, both on sides and ends. When thus laid, their surface shall be covered with a layer of clean sharp sand, which shall be swept with brooms until all the joints are filled. Into the sand joints thus made there will be poured a hot mixture of coal pitch and creosote. The whole surface of the blocks will then be covered with one half-inch of sharp sand, which shall be left undisturbed until ordered removed by the engineer.

Curbing.—The curbstones shall be of bluestone, equal in quality to the best North River bluestone. The curbstones shall be not less than three feet in length, five inches thick, twenty inches deep, and matched width throughout. The top of the stone shall be cut to a bevel of one inch; the front shall be cut smooth and to a fair line, to a depth of fourteen inches. The ends from top to bottom shall be truly squared, so as to form close and even joints, and the front so laid as to present a fair and unbroken line. Curbstones shall be back filled, and backed up with at least one foot of clean, gritty earth, free from clay and loam.

Circular Corners.—The curbstones at the corners of intersecting streets shall be cut on a curve, with true and even joints, and

shall be of the same description as the curb before described, and be laid in the same manner.

Flagging.—All the flagging to be of bluestone equal in quality to the best North River bluestone, even on its face, and to measure not less than two feet wide, to contain not less than eight superficial feet, and to be in no place less than three inches thick. To be laid with close joints, in regular courses of four feet wide. Each stone shall be chisel-dressed on the four edges a distance of one inch down from the top and square with the face thereof, and free from drill-holes.

Flagging shall be bedded in four inches of clean, gritty earth or steam ashes, free from clay and loam, and the work brought to an even surface; the joints of the flagging shall be closed up with cement mortar, and be left clean on the surface; the whole space of the sidewalks to be regulated before laying the flagging.

Catch-basins.—Catch-basins will be constructed at the points indicated on the plans or wherever the engineer may direct.

They will be of brick masonry, built with care, of the form and dimensions shown on the plan. They will be made perfectly watertight by plastering the interior with neat Portland-cement mortar one half-inch thick. The exterior shall be coated with cement mortar one inch in thickness. Each basin will be connected by a nine-inch cement or earthenware pipe-shoot connected to a twelve-inch cement or earthenware pipe. This pipe will be laid on the lines and grades given by the engineer, and connected to the sewer or other outlet.

Each basin will be fitted and furnished with a cast-iron head and grating of the form and dimensions shown on plan.

(Here insert such clauses for general specifications and stipulations as are suitable.)

1019. Specifications for the Supply of Broken Stone.—The stone shall be fully equal to the sample in the engineer's office, otherwise it will be rejected.

It shall be broken in as nearly cubical form as practicable, each cube to have a square face and sharp edges, and shall not exceed in any dimension two inches, but the stones may range from this size down to quarter-inch chips; but the proportion of stones below one and a half inches shall not exceed 20 per cent of the whole quantity.

The broken stones shall not be screened, but will be delivered as

they come from the breakers; care, however, being taken that clay does not become intermixed with them.

The stone when delivered must be clean and free from clay or other dirt.

The stone shall be supplied on the order of the engineer in such quantities as he may specify, and must be delivered within the time specified in the order. Failure to so deliver the stone without good and sufficient reason will be a valid excuse for the forfeiture of the contract.

ADDITIONAL CLAUSES REQUIRED IN SPECIFICATIONS FOR
REPAIRING, ETC.

1020. Indemnification for Patent Claims.—The contractor shall indemnify and save harmless the against and from all suits and actions of every nature and description arising out of the claim or claims of any person or persons claiming to be patentees of any process connected with the work herein provided for, or of any materials used upon said work.

1021. Indemnity Bond.—The contractor shall execute with two sufficient sureties a bond in the sum of thousand dollars, for the indemnification of the against and from all such suits and actions aforesaid.

1022. Right to Construct Sewers, etc.—The right to construct sewers or any work in connection therewith, lay water, gas, or other mains and make house connections therewith, in advance of the pavement, is expressly reserved by the ; and the said may suspend the work on the pavement on any part of the line for the purpose above stated, without other compensation to the contractor for such suspension than extending the time for completing the work as much as it may, in the opinion of the engineer, have been delayed by such suspension. And the contractor shall not interfere with or place any impediment in the way of any person or persons who may be engaged in the construction of such works.

1023. Old Materials.—All old materials which it may become necessary to remove, and where no instructions for their disposal is previously given, shall be considered as the property of the contractor, and the same shall be immediately removed by him from the line of the work.

1024. Security retained for Repairs.—The shall retain out of the moneys payable to the contractor on completion of the work the sum of ten cents per square yard of pavement laid under these specifications, which sum of ten cents with interest shall be paid upon the expiration of the guaranty period; provided that the work at that time is in good order, or as soon thereafter as the work shall have been placed in good order, to the satisfaction of the engineer.

During the guaranty period should any part of the work require repairs, the engineer shall notify the contractor to make such repairs, and in case of neglect or failure to make said repairs within forty-eight hours after service of notice the shall have the right to purchase such materials as may be deemed necessary, and to employ such persons as may be deemed proper, and to undertake and complete such repairs, and to pay the expense thereof out of the said sum of ten cents per square yard retained for that purpose, and such part of said sum as shall remain after the expenses of said repairs have been deducted will be paid in the manner hereinbefore described.

1025. Alteration of Manhole Covers, Stopcock Boxes, etc.—All the frames and heads of sewer manholes, stopcock boxes for water and gas, are to be adjusted (either raised or lowered) to the level of the pavement.

1026. Heads of Specifications for Repaving.

Specifications for Regulating and Paving with Pave-
ment the Carriageway of street to
avenue from

- (1) Description of the work.
- (2) Removal of old materials.
- (3) Excavation.
- (4) Adjustment of manhole heads, etc.
- (5) Adjustment of curb.
- (6) Adjustment of bridge stone.
- (7) Furnishing new curb.
- (8) Furnishing new bridge stones.
- (9) Preparation of roadbed.
- (10) Foundation, character of.
- (11) Concrete.
- (12) Concrete, manufacture and laying.

-
- (13) Pavement, character and quality.
 - (14) Manner of laying.
 - (15) Cleaning up.
 - (16) Quality of material.
 - (17) Inspectors.
 - (18) Right to construct sewers.
 - (19) Commencement of work.
 - (20) Time of completion.
 - (21) Suspension of work.
 - (22) Extension of time.
 - (23) Damages for non-completion.
 - (24) Personal attention of contractor.
 - (25) Contractor's representatives.
 - (26) Defective work.
 - (27) Improper prosecution of the work.
 - (28) Accidents or damages to persons or property to be paid for by the contractor.
 - (29) Incompetent workmen.
 - (30) Power to annul contract for violation of stipulations.
 - (31) Payment of claims for labor and materials.
 - (32) Measurements.
 - (33) Engineer's estimates.
 - (34) Payments, when made.
 - (35) Percentage retained.
 - (36) Prices.
 - (37) Interpretation of specifications.
 - (38) Engineer defined.
 - (39) Contractor defined.
 - (40) Preservation of engineer marks, etc.
 - (41) Indemnification of patent claims.
 - (42) Indemnity bond.
 - (43) Security retained for repairs.

1027. Specifications for Street cleaning should Contain the following Conditions.—The mode of cleaning shall be to first clean the gutters of all solid matter, and then sweep from the sides towards the centre; dirt collections not to be placed within 5 feet of the gutters.

Whenever the sweeping of streets would cause the dust to rise, they shall be first sprinkled by sprinkling-wagons to be approved

by the of the of ; and the sprinkling shall be so done that the dust will not be turned into mud.

All hand sweepings shall be done with push-brooms, and all sweeping by machinery with machines approved by the of .

All parts of streets covered with sheet asphalt shall be swept by machinery six times each week, between the hours of 10 P.M. and 6 A.M., and a sufficient number of men with bass brooms shall be kept employed to keep them constantly clean between the hours of 7 A.M. and 6 P.M.

All accumulations of sweepings, and of mud or rubbish removed from inlets or gutters, shall be removed within three hours from the time such heaps are made, in carts tightly built in such a manner that the contents can be removed without spilling or leaking, and the place where they had been collected shall be swept clean.

All gutters kept wet by the flow of filthy water or sewage shall be thoroughly scraped, brushed, and flushed at least twice a week from May 1st to November 1st, and for this work each contractor will be required to keep at least 100 feet of hose in each district, and brushes or brooms especially made for work of this kind shall be used in cleaning the gutters.

All solid matter must be removed from the gutters and inlets before they are flushed.

All street crossings, inlets, gutters approaching the same, and all gutters necessary to drain crossings within 100 feet of inlets, and streets in front of fire-plugs, for a radius of 5 feet, must be kept clean of dirt, mud, ice, and snow.

1028. Instructions to Bidders.—*Proposals for* [insert description and location of the work]. In pursuance of the following ordinance [insert ordinance].

Sealed proposals for the above work, indorsed with the above title, also with the names of the person or persons making the same and the date of presentation, will be received at the office of

until o'clock .M., day of , 189 , at which place and hour the bids will be publicly opened by and read, and the award of the contract will be made to the lowest responsible bidder with adequate security as soon thereafter as practicable. The person or persons to whom the contract may be awarded will be required to attend at the office of with the sureties offered by him or them, and execute the contract within

five days from the date of the service of a notice to the effect that the contract has been so awarded, and that the adequacy and sufficiency of the security offered has been approved by the ; in case of failure or neglect so to do, he or they will be considered as having abandoned it, and as in default to the ; and thereupon the work will be readvertised and relet, and so on until the contract be accepted and executed. The work is to be commenced at such time as the engineer may designate.

The price must be written in the bid, and also stated in figures, and all proposals will be considered as informal which do not contain bids for all the items for which prices are herein called for, or which contain prices for items not called for, or which contain erasures, alterations, or other irregularities.

Permission will not be given for the withdrawal of any bid or estimate, and the right is expressly reserved by the to reject all bids if it shall be deemed for the public interest so to do. No bid will be accepted from or contract awarded to any person who is in arrears to the upon debt or contract, or who is a defaulter, as surety or otherwise, upon any obligations to the .

Bidders are required to state in their estimates, under oath, their names and places of residence, the names of all persons interested with them therein, and if no other person be so interested, they shall distinctly state the fact; also that it is made without any connection with any other person making a bid or estimate for the same work, and that it is in all respects fair and without collusion or fraud; and also that no member of or other officer of the

is directly or indirectly interested therein, or in the supplies or work to which it relates, or in any portion of the profits thereof. Where more than one person is interested, it is requisite that the verification be made and subscribed by all the parties interested.

Each estimate shall be accompanied by the consent, in writing, of two householders or freeholders in the , with their respective places of residence, to the effect that if the contract be awarded to the person making the estimate, they will, upon its being so awarded, become bound as his sureties for its faithful performance; and that if he shall omit or refuse to execute the same, they will pay to the any difference between the sum to which he would be entitled upon its completion, and that which the said

may be obliged to pay to the person to whom the contract shall be awarded at any subsequent letting; the amount in each case to be calculated upon the estimated amount of the work by which the bids are tested. The consent above mentioned shall be accompanied by the oath or affirmation, in writing, of each of the persons signing the same, that he is a householder or freeholder in the and is worth the amount of the security required for the completion of the contract and stated in the proposals, over and above all his debts of every nature and over and above his liabilities as bail, surety, and otherwise, and that he has offered himself as surety in good faith and with an intention to execute the bond required by law. The adequacy and sufficiency of the security offered will be determined by the of the

In case a proposal is submitted by or in behalf of any corporation it must be signed in the name of such corporation by some duly authorized officer or agent thereof, who shall also subscribe his own name and office. If practicable, the seal of the corporation should also be affixed.

The successful bidder will be strictly held to the time bid for completion of the work, and to the conditions of the specifications.

The engineer's estimate of the nature and extent of the work to be done and materials to be furnished is as follows: [Insert estimate.]

As the above quantities, though stated with as much accuracy as is possible in advance, are approximate only, bidders are required to submit their estimate upon the following express conditions, which shall apply to and become part of every estimate received:

1. The items and quantities stated in the above schedule are merely approximate and may be altered in part or wholly changed during the progress of the work. They are intended only to indicate the general character of the work and shall not be made a basis of any claim for extra compensation of profits in case the quantities of the final estimate shall vary from them, nor be regarded as having any relation or bearing whatever upon the quantities of the final estimate.

2. Bidders must satisfy themselves by personal examination of the site of the proposed work as to the difficulties to be encountered and such other matters which can in any way influence their estimates, and no information derived from the drawings or specifica-

tions or from the engineer or any of his assistants will relieve the contractor from any risks or from fulfilling the terms of the specifications and contract.

3. The contractor will be required to complete the entire work to the satisfaction of the _____ and in substantial accordance with the specifications.

No estimate will be received or considered unless accompanied by either a certified check upon one of the National or State banks of the _____ drawn to the order of the _____, or money to the amount of five per centum of the amount of the security required for the faithful performance of the contract. Such check or money must not be inclosed in the sealed envelope containing the estimate, but must be handed to the officer or clerk of the department who has charge of the estimate box, and no estimate can be deposited in said box until such check or money has been examined by said officer or clerk and found to be correct. All such deposits, except that of the successful bidder, will be returned to the persons making the same within three days after the contract is awarded. If the successful bidder shall refuse or neglect, within five days after notice that the contract has been awarded to him, to execute the same, the amount of the deposit made by him shall be forfeited to and retained by the _____ as liquidated damages for such neglect or refusal; but if he shall execute the contract within the time aforesaid, the amount of his deposit will be returned to him.

Bidders are particularly cautioned that in no case will they be permitted to use materials either in quantity or quality different from those described in the specifications. [And also, that a provision in the specifications and contract requires the maintenance of the pavement in good condition for the period of _____ from the final completion and acceptance thereof.]

The amount of security is _____ thousand dollars for the faithful performance of the contract, and also for the indemnification of the _____ for infringement of patents the amount is _____ thousand dollars. The contractor must notify the engineer in writing _____ hours before commencing the work. The plans can be seen and blank forms of proposals and further information can be obtained on application at the office of _____

1029. Form of Proposal.

		NO.	BID OR ESTIMATE.	
For [insert description of work]			, made by	, resid-
ing at	, and	residing at	, and	resid-
ing at	, and	residing at	, composing the firm	
of				

1. declare that the only person interested in this proposal; and no other person other than herein above named has any interest in this proposal, or in the contract proposed to be taken.

2. further declare that this proposal is made without connection with any other person or persons making a proposal for the same purpose, and is in all respects fair, and without collusion or fraud.

3. further declares that no member of the or other officer is directly or indirectly interested in this proposal, or in the supplies or work to which it relates, or in any portion of the profits thereof.

4. further declares that the names of the persons affixed to the consent hereto annexed were written by said persons respectively, and that said persons are householders or freeholders in the

5. have examined the proposals for estimates for the above work, dated the day of , 189 , and published in the , and the form of contract for the work (including the plans and specifications for the work), and have also visited and examined the site and location and made the investigations recommended in the instructions to bidders, and will contract to furnish the material and perform and complete the work mentioned in said proposals for estimates and approved form of contract on the following terms, viz.: For clearing, grubbing and close cutting, per acre, the sum of . For earth excavations for all classes, per cubic yard, the sum of . For loose rock excavation, per cubic yard, the sum of . For solid rock excavation, per cubic yard, the sum of . For 12-inch culvert pipe, per linear foot, the sum of . For 24-inch culvert pipe, per linear foot, the sum of . For concrete, per cubic yard, the sum of . For each receiving basin, complete, with iron head and grating, the sum of

For brick masonry, per cubic yard, the sum of .

For yellow-pine timber, including fastenings, per 1000 feet-board measure, the sum of . For spruce and other plank,

including fastenings, per 1000 feet board measure, the sum of .

. For riprap, per cubic yard, the sum of . For dry stone masonry, per cubic yard, the sum of .

The above prices include the furnishing of all the materials, tools, plant, and labor, and every risk and contingency necessary for the completion of the work in accordance and with specifications and plans.

Time within which . will complete the whole work according to specifications . days.

.....

CITY OF , COUNTY OF , ss.:

.....
 being duly sworn, say, each for himself, that the several matters stated in the above estimate are in all respects true.

Subscribed and sworn to this . day of , A.D. 189 , before me,

.....

Commissioner of Deeds.

1030. Form of Agreement (to be executed in triplicate).

This agreement made and entered into this . day of , one thousand eight hundred and ., by and between the [insert name of city, town, or county] of , hereinafter called the party of the first part, and [name of contractor], of the [insert place of residence], hereinafter called the party of the second part,

Witnesseth: That the said party of the second part has agreed, and by these presents does for himself, his heirs, executors, administrators, and assigns, covenant, promise, and agree with the said parties of the first part, for the considerations hereinafter mentioned

and contained, and under the penalty expressed in a bond bearing even date with these presents, and hereunto annexed, that he, the said party of the second part, his heirs, executors, administrators, or assigns, shall and will furnish and provide, at his own or their own cost and expense, all the necessary materials, appliances, tools, plant, and labor which are or may be necessary for the proper and substantial construction and completion of the [insert description of work], in accordance with the general plans on file in the office of the said party of the first part, and in strict conformity in every part and particular with the following specifications, and in accordance with such detail plans and instructions relating thereto as may from time to time be given by the chief engineer or his duly appointed assistants; and further agrees that the said parties of the first part shall be, and are hereby, authorized by their chief engineer, or such other person or persons, or in such other manner, as they may deem proper, to inspect the material to be furnished and the work to be done under this agreement, and to see that the same correspond with the specifications and conditions hereinafter set forth.

The party of the second part admits and agrees that the amounts and quantities of materials to be furnished and work to be done, as stated in the proposals for estimates for the said work, are approximate only; that he is satisfied with the foregoing estimate in determining the price according to which he agrees to do the work required by this contract in accordance therewith, and that he shall not and will not dispute or complain of such statement, nor assert that there was any misunderstanding in regard to the nature or amount of the materials to be furnished or work to be done; and he covenants and agrees that he will complete the entire work to the satisfaction of the and in substantial accordance with said specifications and the plan therein mentioned, and that he will not ask, demand, sue for, or recover for the entire work any extra compensation beyond the amount payable for the several classes of work in this contract enumerated, which shall be actually performed, at the price therefor herein agreed upon and fixed.

The parties hereto also declare that this contract is made with reference to the proposals for estimates for the above-described work, hereto annexed, and the estimate of the contractor now on file

in the _____, which are to be taken as part and parcel of these presents [here insert specifications and general stipulations].

Commencement.—The said party of the second part hereby further agrees to commence the work comprised under this agreement on such day and at such place or places as the engineer may designate. Failure to so commence will be authority for the party of the first part to declare this agreement forfeited, and the said party of the first part may proceed with the execution of the work in such manner as they may deem proper.

Time of Completion.—The party of the second part agrees to prosecute the work in such manner as to complete the same in accordance with this agreement on or before the expiration of two hundred (200) days after the date of commencement, and it is further agreed that in the computation of said time, the length of time (expressed in days and parts of a day) during which the work or any part thereof has been delayed in consequence of the condition of the weather, or by any difficult circumstances so unusual that they could not be foreseen previous to, or avoided during, the construction of the work, or by any act or omission of the parties of the first part (all of which shall be determined by the chief engineer, who shall certify to the same in writing), and also Sundays and holidays on which no work is done, and days on which the prosecution of the work is suspended by order of the party of the first part, shall be excluded.

But if the construction of said work should require material or work in greater or lesser quantities or amounts than those mentioned and set forth in the engineer's estimate, then the said time shall be increased or diminished as much as the said engineer, by a certificate in writing, shall deem just and reasonable, and fairly proportioned to the amount of said increase or diminution.

But neither an extension of time for any reason beyond the date fixed herein for the completion of the work, nor the doing and acceptance of any part of the work called for by this agreement, subsequent to the said date, shall be deemed to be a waiver by the said party of the first part of the right to abrogate this contract for abandonment or delay in the manner provided for in Article 80 of this agreement.

Damages for Non-completion.—And the said party of the second part hereby further agrees, that the said parties of the first part

shall be and are hereby authorized to deduct and retain out of the moneys which may be due or become due to the said party of the second part under this agreement as damages for the non-completion of the work aforesaid within the time hereinbefore stipulated for its completion, the sum of dollars for each and every day which may exceed the said stipulated time for its completion; which said sum of dollars per day is hereby, in view of the difficulty of estimating such damages agreed upon, fixed and determined by the parties hereto as the liquidated damages that the parties of the first part will suffer by reason of such default, and not by way of penalty.

Improper Prosecution of Work.—The said party of the second part further agrees that if at any time it should appear to the engineer that the works are being delayed, or are not being prosecuted with due diligence, or with such speed as would be necessary for their completion within the time specified, or that the works are being prosecuted in an improper or unworkmanlike manner, the said engineer shall notify the contractor in writing, specifying the causes of complaint, and upon the party of the second part failing to rectify such matters within seven days after the receipt of said notice, the engineer shall notify the party of the first part of such failure; and it is further agreed, that in the event of such failure the party of the first part may, without further notice, suspend the contractor from all work under this agreement; and it is further agreed, that the said party of the second part shall immediately respect said suspension, and shall stop work, and cease to have any rights to possession of the ground; and the said party of the first part shall thereupon have the power to carry on and complete the work herein described, by contract or otherwise, employing such plant, tools, and materials as may be on the ground, and procuring such others as may be wanting, for the proper completion of the work, and to charge the expense of such labor and materials to the aforesaid party of the second part, and the expense so charged shall be deducted and paid out of such moneys as may be then due, or may at any time thereafter become due, to the said party of the second part under or by virtue of this agreement, or any part thereof; any excess of cost over and above the amount accruing as above stated shall be charged against the party of the second part and his sureties, who will each and severally be held liable there-

for; and in case the cost of completion shall be less than the sum which would have been payable under this contract if the same had been completed by the party of the second part, he shall be entitled to receive the difference.

Engineer's Returns.—The said party of the second part further agrees that the return of the engineer shall be the account by which the amount of material furnished and work done in terms of this contract shall be computed; provided, however, that nothing herein contained be construed to affect the right of the party of the first part to reject and contest any return or certificate of the engineer or inspectors having charge of the work, should such return or certificate be in their opinion not in accordance with the facts of the case or the requirements of this agreement, or otherwise improperly given.

Damage to Property.—And it is hereby further agreed, that in case any damage or injury shall or may result to buildings, water-pipes, hydrants, gate-boxes, sewer-basins, man-holes, sewers, or other works through or by reason of any negligence, carelessness, or want of skill on part of said party of the second part, the said party of the second part shall restore the same to their former good condition; failing to do so, said party of the second part shall pay such amount as shall or may be sufficient to cover the expense and damage occasioned by such negligence, carelessness, or unskilfulness.

Gas-pipes.—And the said party of the second part further agrees to do everything necessary to support and sustain the gas-pipes laid in or across said streets, which may be liable to any injury from digging the trenches for the work hereinbefore mentioned, and to have a sufficient quantity of timber and plank constantly on the ground, and to use the same as required for bracing and sheet-piling the sides of the excavation.

Notice to Gas Companies.—And the said party of the second part further agrees to give notice in writing, at least twenty-four hours before breaking ground for the purpose of constructing the work hereinbefore mentioned, to such and all such gas companies as have, or may during the progress of the work have, any gas-pipes which may be affected by such excavations as may become necessary.

And it is further agreed, that the said party of the second part

shall not cause any hindrance to or interfere with such gas company or companies in protecting their pipes, nor in removing or otherwise protecting and replacing the main and service pipes, lamp-posts and lamps, where necessary; but that the said party of the second part will suffer the said company or companies to take all such measures as may become necessary for the purpose aforesaid.

Penalty of Damage to Gas-pipes.—And it is hereby further agreed, that in case any damage or injury shall or may result to the said pipes, lamp-posts, lamps, or other works of any gas company, through or by reason of any negligence, carelessness, or want of skill on the part of the said party of the second part, his agents or servants, the said party of the second part shall become liable to pay such amount as shall or may be sufficient to cover the expense and damage occasioned by such negligence, carelessness, or unskillfulness; and such amount shall be charged against the said party of the second part, and may be deducted from any sum or sums due or to become due or payable to said party of the second part on account of this contract.

Water-pipes.—The party of the second part hereby further agrees to sustain in their places, without injury, all the main and service water-pipes which may be affected in any manner by the work under this agreement, including any such protective measures as may be required in cold weather to prevent them from freezing; or failing to do so, the said shall be and he is hereby authorized to replace and recalk and repair the same immediately in each block, as the work progresses, and the cost thereof shall be charged to the said party of the second part, and the cost so charged to the said party of the second part shall be retained and deducted, and the parties of the first part are hereby authorized to retain and deduct said cost out of the moneys which may be due or become due to the said party of the second part under this agreement.

Transfer of Contract.—The party of the second part further agrees not to transfer or sublet any part of the work referred to in this agreement, without the previous written consent of the engineer; any such transfer or subletting without said consent will be null and void, and will be sufficient cause for the annulment of

the contract; nor shall any of the moneys payable under this contract be assigned by power of attorney or otherwise.

Loss or Damage.—And it is further agreed that all loss or damage arising out of the nature of the work to be done, or from any unforeseen or unusual obstructions or difficulties which may be encountered in the prosecution of the same, or from the action of the elements, or from injury to persons or property of another, resulting from negligence in the performance and guarding of the same, which must be protected when necessary with barriers, and at night with red lights, or from any improper materials used in prosecution or by or on account of any act or omission of his own, or his agents, will be sustained by the contractor, and he shall save harmless the party of the first part from any and all liabilities and claims for such, and the said party of the first part shall have the right to retain any moneys that may be due or become due, until evidence has been furnished that all such suits or claims for damages as aforesaid have been satisfactorily settled.

Public Protection.—It is further agreed that the contractor will enclose every opening he may make in the public highway with sufficient barriers, and must maintain red lights at the same at night, and must take all necessary precautions to guard effectually against accidents to persons, horses, vehicles, or property of any kind, and all work shall be done in such manner and at such times as to interfere as little as possible with public travel and convenience; and the contractor shall conduct his work for this object as the engineer may from time to time direct.

Work not Provided for in Contract.—The said party of the second part further agrees, that if, before the completion of the work contemplated herein, it shall become necessary to do any other or further work on or about this regulating, etc., than is provided for in this contract, or to construct any sewer or sewers or appurtenances thereof, on the line of this work, the said party of the second part will not in any way interfere with or molest such other person or persons as the may employ to do such work, and will suspend each part of the work herein specified, or will carry on the same in such manner as may be ordered by the said , to afford all reasonable facilities for doing such work, and no other damage or claim by the said party of the second part hereof shall be allowed except such extension of the time specified

Security to be retained for Repairs.—And the said party of the second part hereby further agrees that the said parties of the first part shall be and are hereby authorized to retain, out of the moneys payable to him under this agreement, the certain sum of twenty-five cents per linear foot of the work done under this agreement, and to expend the same, in the manner provided for, in making such repairs to the work done under this agreement as the said

may deem necessary, except curbing and flagging, which will be finally accepted upon the completion of the work. And it is further agreed that if, at any time during the period of six months from the date of the acceptance by said of the work under this agreement, the said work or any part thereof (excepting only such part or parts of the work as after the completion thereof may have been disturbed in the construction or repairs of sewers or drains, or in laying or repairing gas or water main or service pipes, or railroad-pier foundations) shall in the opinion of the said require repairs, the said shall notify the said party of the second part to make the repairs so required, the said party of the second part shall immediately commence and complete the same to the satisfaction of said ; and in case of failure or neglect, on his part, to do so within forty-eight hours from the date of the service of the aforesaid notice, then the said shall have the right to purchase such materials as he shall deem necessary, and to employ such person or persons as he may deem proper, and to undertake and complete the said repairs, and to pay the expense thereof out of the said certain sum retained for that purpose by the said parties of the first part, as before mentioned. And the parties of the first part hereby agree, upon the expiration of the said period of six months, provided that the said work at that time be in good order, or as soon thereafter as the said work shall have been put in good order to the satisfaction of the said , to pay to the said party of the second part the whole of the sum last aforesaid or such part thereof as may remain after the expense of making such repairs, in the manner aforesaid, shall have been paid therefrom. And it is hereby further agreed, between the parties hereto, that if the termination of the said period of six months after the completion and acceptance of the work done

under this agreement shall fall within the months of December, January, February, and March, then in that case the said months of December, January, February, and March, or such part thereof as the may determine, shall not be included in the computation of the said period of six months.

Prices.—And the party of the second part hereby further agrees to receive the prices set forth in the following schedule as full compensation for furnishing all materials and labor, and the doing of all work, including all loss or damage arising out of the nature of the work, or from the action of the elements, or from any unforeseen obstructions or difficulties, which may be encountered in the prosecution of the same; also all expenses incurred by or in consequence of the suspension or discontinuance of said work which may be required in building and constructing, and in all respects completing the aforesaid [insert description of work], including all appurtenances and accessories, to the satisfaction of the engineer and the hereinbefore mentioned authorities, and in the manner and under the conditions hereinbefore specified, to wit: [insert schedule of prices].

Manner of Payment.—And the said party of the second part further agrees that he shall not be entitled to demand or receive payment for any of the aforesaid work or material until the same shall be fully completed in the manner set forth in this agreement, and such completion duly certified by the chief engineer, and until each and every one of the stipulations hereinbefore mentioned are complied with.

Whereupon the parties of the first part will pay, and hereby bind themselves and their successors to pay, to the said party of the second part, on account, ninety (90) per cent of the monthly estimate of the whole amount of money accruing to the said party of the second part, and the reserved ten (10) per cent upon the formal acceptance of the work by the party of the first part.

In witness whereof, the ha hereunto set hand and seal on behalf of the said parties of the first part, and the said party of the second part hath also hereunto set hand and seal, the day and year first above written; and said commissioner and party hereto of the second part hath executed this agreement in triplicate, one part of which is to remain with

the said , one other to be filed with the , and the third to be delivered to the said party hereto of the second part.

Signed and sealed in presence of

.....
.....

Contractor.

STATE OF , CITY OF , COUNTY OF , ss.:
On this day of , 189 , before me personally came

to me known, and known to me to be the , the person described in and who executed the foregoing instrument, and he acknowledged to me that he executed the same as such , for the purposes therein mentioned.

.....
Commissioner of Deeds,
..... County.

STATE OF , CITY OF , COUNTY OF , ss.:
On this day of 189 , before me personally came

to me known, and known to me to be the person described in and who executed the foregoing instrument, and he acknowledged to me that he executed the same for the purposes therein mentioned.

.....
Commissioner of Deeds,
..... County.

1031. Form of Bond.

Know all men by these presents, that we,

of the , are held and firmly bound unto the of the in the sum of thousand dollars lawful money of the United States of America, to be paid to the said , or to their certain attorney, successors, or assigns; for which payment, well and truly to be made, we bind ourselves, and our several and respective heirs, executors, and administrators, jointly and severally, firmly by these presents.

Sealed with our seals. Dated this day of , one
thousand eight hundred and

Whereas, the above bounden

by an instrument in writing under hand and seal ,
bearing even date with these presents, ha contracted with the
said to furnish all the materials and labor, and in a good,
firm, and substantial manner construct [description of work]:

Now, therefore, the condition of the above obligation is such, that
if the said above bounden

or executors, administrators, or assigns, shall well and
truly, in a good, sufficient, and workmanlike manner, perform the
work mentioned in the aforesaid agreement, in accordance with the
terms and provisions therein stipulated, and in each and every re-
spect comply with the conditions and covenants therein contained,
then this obligation to be void; otherwise to remain in full force
and virtue.

Signed and sealed in presence of
.....
.....
.....
.....

STATE OF , CITY OF , COUNTY OF , ss.:
On this day of , 189 , before me personally came

to me personally known, and known to me to be the same persons
described in and who executed the foregoing obligation, and sev-
erally acknowledged that they executed the same.

.....
Commissioner of Deeds,
..... County.

STATE OF , CITY OF , COUNTY OF , ss.:
I , of said , being duly sworn, do depose and say,
that I am a holder in the of and in

Subscribed and sworn to this)
day of , 189 , before me,)

Accidents.—During the time the horses and vehicles are employed by the _____ the attendants shall under no circumstances leave them. The contractor shall be responsible in

case of accident owing to neglect, carelessness, or inattention on the part of the attendants.

1031b. Specifications for Sprinkling.—Amount of Work.—The work to be done consists in sprinkling, in the manner prescribed herein, the roadways from curb-line to curb-line of the following-named avenues, streets, and public places of the city of
The total length of streets to be sprinkled under these specifications is estimated at _____ *miles*.

The number of times and hours of sprinkling shall be as follows:

1. All streets, avenues, public places, and parts thereof shall be sprinkled _____ times a day during the entire season: provided, that only _____ sprinklings during the season shall be required on Sundays.

2. When a street is sprinkled three times a day, the first sprinkling shall be completed before 8 o'clock A.M., the second sprinkling shall be between 10 o'clock A.M. and 1 o'clock P.M., and the third sprinkling shall be between 2 o'clock P.M. and 6 o'clock P.M.

3. When four sprinklings a day are required, the first sprinkling shall be completed before 8 A.M., the second shall be between 8 A.M. and 11 A.M., the third shall be between 12 noon and 3 P.M., and the fourth shall be between 3 P.M. and 6 P.M.

4. All streets shall be sprinkled in regular rotation. The starting-point in the morning shall be the starting-point for all the following sprinklings during the day.

5. The quantity of water to be delivered on the street will be determined from time to time by the Street Commissioner.

6. The sprinkling shall be done with two-horse wagons which carry a tank holding not less than 600 gallons, and shall have attached two sprinklers. The wagons must be provided with springs (fore and aft), and must have tires not less than three inches in width. The wagons must also be numbered consecutively, and have the name of the contractor in letters not less than three inches in height painted on the rear end of the tank.

7. The sprinklers must be so arranged that the spray of water can be readily stopped by the driver on either side of the wagon. The sprinklers shall be constructed so as to deliver and properly spread the water, and be provided with suitable controlling devices

for regulating the quantity of water discharged, said devices to be so arranged as to be operated by the driver from the seat or foot-board; the spray of water thrown must be uniform throughout its entire width.

The sprinklers must be kept in good condition and repair, Wagons with broken or choked sprinklers, defective gear, and leaking tanks or valves shall not be used.

8. All wagons shall be periodically inspected, and any found unfit for use shall be ordered off the street, and sprinkling done by rejected wagons will not be paid for.

9. Sprinkling must be done with judgment and care, and the street-crossings must be kept as nearly dry as possible.

10. If the contractor fails or neglects to sprinkle any street or avenue the number of times required by this contract except in case of rain, or if he should flood the street or avenue, then two-thirtieths of his monthly pay for said street or avenue will be deducted for each day on which such omission or flooding occurs.

11. As to whether the contractor has given the streets the number of sprinklings and the quantity of water required, and as to whether rain has obviated the necessity of sprinkling, shall be determined by the Street Commissioner.

12. The contractor shall use particular care not to waste any water in filling the tanks; and also in closing the hydrants as soon as the tank has been filled. A deduction of two dollars shall be made on the next monthly estimate for every hydrant which is left wholly or partly open when not in use for filling the tank. Any hydrant found damaged or out of order must be immediately reported to the Street Commissioner. Hydrants damaged by the contractor shall be repaired by the Water Commissioner, who will report the cost to the Street Commissioner, who will charge it to the contractor and deduct it from his monthly estimate.

1031c. Form of Monthly Certificate.

CERTIFICATE NO.

\$ _____ City of _____, 19 _____

To.....

THIS IS TO CERTIFY that under the terms of the contract
dated _____, for work upon _____

Mr. _____, contractor, is entitled to the following payment, amounting to _____ Dollars.

The above estimate is based on _____ Am't of this certificate \$ _____

Previously paid \$ _____

Total paid to date \$ _____

.....
Engineer in charge.

1031d. Affidavit of Contractor.

State of _____, City of _____, ss :

_____, being duly sworn according to law, on his oath saith that he is the contractor mentioned in a certain agreement made with the Mayor and Common Council of _____ for the improving and paving of _____ from _____ to _____ in said city, and that the work thereon has been completed and finished according to the terms and conditions of said agreement in every particular.

And deponent further saith that all the laborers and workmen employed by him on said work, and all and every person or persons who have furnished materials, have been paid, and that he does not now owe anything for materials furnished or to any laborers or workmen or other persons for work or labor done or performed by them on said work.

And deponent further saith that there has been no damage done or injury sustained by any person or persons either to themselves or their property, which was caused by reason of any act, omission, carelessness, or want of skill on the part of this deponent or his agents in the prosecution of the work aforesaid, and that no notice has been served upon him or any claims or demand has been made upon him for damages thereunder, and deponent knows of no claim or demand that any person or persons have or can have against him or said city for any damage caused or injury done to themselves or their property during the construction of the aforesaid work.

Sworn and subscribed to before _____
me this _____ day of _____, 19 _____, }

1031e. Certificate of Acceptance.

TO THE MAYOR AND COMMON COUNCIL OF THE CITY OF :

I do hereby certify that of from
to , contractor, has been completed to my satisfaction
and in accordance with the specifications and contract.

.....

Engineer in charge.

1031f. Certificate of Final Acceptance.

TO THE MAYOR AND COMMON COUNCIL OF THE CITY OF :

, 19

I do hereby certify that the year(s) during which period
the pavement of from to ,
M , contractor, was required to be kept in repair, expired
on , 19

As the proper repairs have been made, and the work is now in
a condition satisfactory to me and in accordance with the speci-
fications and contract, the ten per cent retained is now due and
payable, for which amount I have given a certificate this day.

.....

Engineer in charge.

1031g. General Specifications for Steel Highway Bridges.
(*American Bridge Co.*) *Classification.*—Bridges under these speci-
fications are divided into six classes, viz.: Class A, for city traffic.
Class B, for suburban or interurban traffic with heavy electric cars.
Class C, for country roads with light electric cars or heavy highway
traffic. Class D, for country roads with ordinary highway traffic.
Class E, for heavy electric street railways only. Class E, for
light electric street railways only.

Material.—All structures to be of rolled steel, except the floor-
ing and wheel-guards of Classes A, B, C, E, and E, and the
stringers, flooring, and wheel-guards of Class D, which may be of
timber. Cast iron or cast steel will be permitted only in machinery
of movable bridges and in special cases for shoes and bearings.

Type of Bridges.—The following types of bridges are recommended: For spans up to 25 feet, rolled beams. For spans from 25 to 40 feet, rolled beams or plate girders. For spans from 40 to 80 feet, plate or lattice girders. For spans from 80 to 140 feet, lattice girders. For spans over 140 feet, lattice girders or pin-connected trusses.

Spacing of Trusses.—The width between centres of trusses shall in no case be less than one-twentieth of the span between centres of end pins or shoes.

Floor-beams.—All floor-beams in through bridges shall be riveted to the main girders.

Stringers.—Steel stringers shall preferably be riveted to the web of the floor-beams.

Solid Floor.—For bridges of Classes A and B a solid floor, consisting of stone, asphalt, etc., on a concrete bed, is recommended. For this case the flooring will consist of buckle-plates or corrugated sections, and the concrete bed shall be at least 3 inches thick for the roadway, and 2 inches thick for the footwalk, over the highest point to be covered, not counting rivet or bolt-heads.

Buckle-plates.—Buckle-plates shall not be less than $\frac{5}{8}$ inch thick for the roadway and $\frac{1}{2}$ inch thick for the footwalk.

Dead Load.—In determining the weight of the structure for the purpose of calculating strains, the weight of timber shall be assumed at 4 pounds per foot B. M., the weight of concrete and asphaltum at 130 pounds, of paving brick at 150 pounds, and of granite stone at 160 pounds per cubic foot.

The rails, fastenings, splices, and guard timbers of street-railway tracks, resting on cross-ties, shall be assumed as weighing 100 pounds per lineal foot of track.

Live Load.—The bridges of the different classes shall be designed to carry, in addition to their own weight and that of the floor, a moving load, either uniform or concentrated, or both, as specified below, placed so as to give the greatest strain in each part of the structure.

Class A, City Bridges.—For the floor and its supports, on each street-car track or any part of the roadway, a concentrated load of 24 tons on two axles 10 feet centres and 5 feet gauge (assumed to occupy a width of 12 feet), and upon the remaining portion of

the floor, including foot-walks, a load of 100 pounds per square foot.

For the trusses, for spans up to 100 feet, 1,800 pounds per lineal foot of each car track (assumed to occupy 12 feet in width), and 100 pounds per square foot for the remaining floor surface; for spans of 200 feet and over, 1,200 pounds for each lineal foot of track and 80 pounds per square foot of floor; proportionally for intermediate spans.

Class B, Suburban or Interurban Bridges.—For the floor and its supports, on any part of the roadway, a concentrated load of 12 tons on two axles 10 feet centres and 5 feet gauge (assumed to occupy a width of 12 feet), or on each street-car track a concentrated load of 24 tons on two axles 10 feet centres; and upon the remaining portion of the floor, including foot-walks, a load of 100 pounds per square foot.

For the trusses, for spans up to 100 feet, 1,800 pounds per lineal foot of each car track and 80 pounds per square foot for the remaining floor surface; for spans of 200 feet and over, 1,200 pounds for each lineal foot of track and 60 pounds per square foot of floor; proportionally for intermediate spans.

Class C, Heavy Country Highway Bridges.—For the floor and its supports, on any part of the roadway, a concentrated load of 12 tons on two axles 10 feet centres and 5 feet gauge (assumed to occupy a width of 12 feet), or on each street-car track a concentrated load of 18 tons on two axles 10 feet centres; and upon the remaining portion of the floor, including foot-walks, a load of 100 pounds per square foot.

For the trusses, same as for Class B, except load on car tracks for spans up to 100 feet will be 1,200 pounds, and for spans of 200 feet and over, 1,000 pounds.

Class D, Ordinary Country Highway Bridges.—For the floor and its supports, a load of 80 pounds per square foot of total floor surface, or 6 tons on two axles 10 feet centres and 5 feet gauge.

For the trusses a load of 80 pounds per square foot of total floor surface for spans up to 75 feet, and 55 pounds for spans of 200 feet and over; proportionally for intermediate spans.

Class E, Bridges for Heavy Electric Street Railways Only.—For the floor and its supports, on each track a load of 24 tons on two axles 10 feet centres.

For the trusses, a load of 1,800 pounds per lineal foot of each car track for spans up to 100 feet, and a load of 1,200 pounds for spans of 200 feet and over; proportionally for intermediate spans.

Class E₁, Bridges for Light Electric Street Railways Only.—For the floor and its supports, on each track a load of 18 tons on two axles 10 feet centres.

For the trusses, a load of 1,206 pounds per lineal foot of each car track for spans up to 100 feet, and a load of 1,000 pounds for spans of 200 feet and over; proportionally for intermediate spans.

Impact.—To compensate for the effect of impact and vibration, 25 per cent of the maximum strains resulting from the above-mentioned live load shall be added thereto.

Wind Pressure.—The wind pressure shall be assumed acting in either direction horizontally. First, at 30 pounds per square foot on the exposed surface of all trusses and the floor as seen in elevation, in addition to a horizontal live load of 150 pounds per lineal foot of the span moving across the bridge. Second, at 50 pounds per square foot on the exposed surface of all trusses and the floor system. The greatest result shall be assumed in proportioning the parts.

Momentum of Street Cars.—For longitudinal bracing of structures carrying street railroads, the momentum produced by suddenly stopping the train shall be considered; the coefficient of friction of wheels sliding upon the rails being assumed as 0.2.

Centrifugal Force.—When the structure carrying a street railroad is on a curve, the additional effects due to the centrifugal force shall be considered.

Permissible Tensile Strains.—All parts of the structure shall be so proportioned that the sum of the maximum loads, together with the impact, shall not cause the tensile strain to exceed:

On soft steel 15,000 pounds per square inch.

On medium steel 17,000 pounds per square inch.

Permissible Compressive Strains.—For compression members, these permissible strains of 15,000 and 17,000 pounds per square inch shall be reduced in proportion to the ratio of the length to the least radius of gyration of the section by the following formulæ:

$$\text{For soft steel, } p = \frac{15,000}{1 + (1^2 \div 13,500r^2)}$$

$$\text{For medium steel, } p = \frac{17,000}{1 + (1' \div 11,000r^2)}$$

where p = permissible working strain per square inch in compression, l = length of pieces in inches, centre to centre of connection, and r = least radius of gyration of the section in inches.

No compression member, however, shall have a length exceeding 120 times its least radius of gyration, excepting those for wind-bracing, which may have a length not exceeding 140 times the least radius of gyration.

Reversal of Strains.—The reversal of strain in members of bridges of Classes A, B, C, and D need not be considered, but the members shall be proportioned for the strain giving the larger section.

For bridges of Classes E, and E, members subject to alternate strains of tension and compression in immediate succession (as counter stresses in web members or chords in continuous trusses) shall be so proportioned that the total sectional area is equal to the sum of areas required for each strain.

Combined Strains.—In case the maximum strains due to wind, added to the maximum strains due to vertical loading (including impact), shall exceed the following limits: on soft steel, 19,000 pounds per square inch, on medium steel, 21,000 pounds per square inch, properly reduced for compression, addition must be made to such sections until these limits are not exceeded.

Shearing and Bearing Strains.—The shearing strain on rivets, bolts, or pins, per square inch of section, shall not exceed 11,000 pounds for soft steel, and 12,000 pounds for medium steel; and the pressure upon the bearing surface of the projected semi-intrados (diameter \times thickness) of the rivet, bolt, or pin hole, shall not exceed 22,000 pounds per square inch for soft steel, and 24,000 pounds for medium steel.

Plate Girders.—Plate girders shall be proportioned on the assumption that one-eighth of the gross area of the web is available as flange area. The compressed flange shall have the same sectional area as the tension flange; but the unsupported length of flange shall not exceed twenty times its width.

The shearing strain in web plates shall not exceed 9,000 pounds per square inch for soft steel and 10,000 pounds per square inch for medium steel.

Floor Timber.—The fibre strain on floor timber from dead and live load without impact shall not exceed 1,200 pounds per square inch on yellow pine and white oak, and 1,000 pounds per square inch on white pine and spruce.

Spacing of Rivets.—The distance from the edge of any piece to the centre of a rivet hole must not be less than $1\frac{1}{2}$ times the diameter of the rivet, nor exceed eight times the thickness of the plate; and the distance between centres of rivet holes shall not be less than three diameters of the rivet.

Tie Plates.—All segments of compression members connected by latticing only, shall have tie plates placed as near the ends as practicable. They shall have a length of not less than the greatest depth or width of the member, and a thickness of not less than one-fiftieth of the distance between the rivets connecting them to the compressed members.

Lacing.—Single lattice bars shall have a thickness of not less than one-fortieth, and double bars connected by a rivet at the intersection of not less than one-sixtieth of the distance between the rivets connecting them to the member; and their width shall be in accordance with American Bridge Company's standards, generally:

For 15-inch channels, or built sections with $3\frac{1}{2}$ - and 4-inch angles: $2\frac{1}{2}$ inches ($\frac{3}{8}$ -inch rivets).

For 12-, 10-, and 9-inch channels, or built sections with 3-inch angles: $2\frac{1}{2}$ inches ($\frac{3}{8}$ -inch rivets).

For 8- and 7-inch channels, or built sections with $2\frac{1}{2}$ -inch angles: 2 inches ($\frac{3}{8}$ -inch rivets).

For 6- and 5-inch channels, or built sections with 2-inch angles: $1\frac{1}{2}$ inches ($\frac{1}{2}$ -inch rivets).

Planing and Reaming.—In medium steel over $\frac{3}{4}$ inch thick, all sheared edges shall be planed and all holes shall be drilled or reamed to a diameter of $\frac{1}{8}$ inch larger than the punched holes, so as to remove all the sheared surface of the metal.

Process of Manufacture.—All steel must be made by the open-hearth process, and if by acid process, shall contain not more than 0.08 per cent of phosphorus, and if by basic process, not more than 0.05 per cent of phosphorus, and must be uniform in character for each specified kind.

Physical Properties.—Steel shall be made of three grades : Rivet, soft, and medium.

Rivet steel shall have: Ultimate strength, 48,000 to 58,000 pounds per square inch. Elastic limit, not less than one half the ultimate strength. Elongation, 26 per cent. Bending test, 180 degrees flat on itself, without fracture on outside of bent portion.

Soft steel shall have : Ultimate strength, 52,000 to 62,000 pounds per square inch. Elastic limit, not less than one half the ultimate strength. Elongation, 25 per cent. Bending test, 180 degrees flat on itself, without fracture on outside of bent portion.

Medium steel shall have: Ultimate strength, 60,000 to 70,000 pounds per square inch. Elastic limit, not less than one half the ultimate strength. Elongation, 22 per cent. Bending test, 180 degrees to a diameter equal to thickness of piece tested, without fracture on outside of bent portion.

Pins.—Pins up to 7 inches diameter shall be rolled. Pins exceeding 7 inches diameter shall be forged under a steel hammer striking a blow of at least 5 tons. The blooms to be used for this purpose shall have at least three times the sectional area of the finished pins.

Steel Castings.—Steel castings shall be made of open-hearth steel containing from 0.25 to 0.40 per cent carbon and not over 0.08 per cent of phosphorus, and shall be practically free from blow-holes.

Timber.—The timber shall be strictly first-class spruce, white pine, Douglas fir, Southern yellow pine, or white oak bridge timber; sawed true and out of wind, full size, free from wind shakes, large or loose knots, decayed or sap wood, worm-holes, or other defects impairing its strength or durability.

CHAPTER XXIII.

TOOLS AND MACHINERY EMPLOYED IN THE CONSTRUCTION OF HIGHWAYS.

THE implements employed in the construction of highways and pavements are many and varied. A brief description of the principal ones, and the range in price, is given in the following pages. The prices stated are only approximate and will vary, depending upon the quantity required and the condition of the market.

1032. Tools for Clearing and Grubbing.



FIG. 186.—BUSH-HOOKS.



FIG. 187.—AXE MATTOCK.



FIG. 188.—PICK MATTOCK.

Axes.....	price per dozen	\$12.00 to \$15.50
Bush-hooks, handled.....	" " "	17.00
Grub-hoes.....	" " "	11.00 to 17.00
Mattocks.....	" " "	15.50 " 18.00
Stump-pulling machines.....	each	150.00 " 250.00
Cross-cut saws.....	per foot	0.68

1033. Tools for Grading.—PICKS are made of various styles, according to the class of material in which they are to be used. Fig. 189 shows the form usually employed in street work. Fig. 190 shows the form generally used for clay or gravel excavation.

The eye of the pick is generally formed of wrought iron, pointed with steel.

The weight of picks ranges from 4 to 9 lbs., and cost per dozen \$8.50 to \$25.



FIG. 189.—GRADING-PICK.



FIG. 190.—CLAY-PICK.

SHOVELS are made in two forms, square- and round-pointed, usually of pressed steel. They cost from \$7 to \$13 per dozen for the square-pointed and from \$7.25 to \$13.50 for the round-pointed.



FIG. 191.—SHOVELS.

PLOUGHS are extensively employed in grading, special forms being manufactured for the purpose. They are known as "grading-ploughs," "road-ploughs," "breaking-ploughs," "township-ploughs," etc. They vary in form according to the kind of work they are intended for, viz., loosening earth, gravel, hardpan, and some of the softer rocks.

These ploughs are made of great strength, selected white oak, rock elm, wrought steel and iron being generally used in their construction.

The cost of operating ploughs ranges from 2 to 5 cents per cubic yard, depending upon the compactness of the soil.

The quantity of material loosened will vary from 2 to 5 cubic yards per hour.

Fig. 192 shows the form usually adopted for loosening earth. This plough does not turn the soil, but cuts a furrow about 10 inches




FIG. 192.—GRADING-PLOUGH.

wide and of such a depth as it may be regulated for up to 11 inches.

In light soils the ploughs are operated by two or four horses; in heavy soils as many as eight are employed.

Grading-ploughs vary in weight from 100 to 325 lbs., in price from \$22 to \$65.

Fig. 193 illustrates a plough specially designed for tearing up macadam, gravel, or similar material. The point is a straight bar of cast steel drawn down to a point, and can be easily repaired. Price about \$40.



FIG. 193.—HARDPAN-PLOUGH.

SCRAPERS are generally used to move the material loosened by ploughing; they are made of either iron or steel, and in a variety of forms, and are known by various names, as "drag," "buck," "pole," and "wheeled."

The drag-scrapers are usually employed on short hauls, the wheeled on long hauls.

Figs. 194 and 195 illustrate the usual form of drag-scrapers.



FIG. 194.—DRAG-SCRAFER.

Drag-scrapers are made in three sizes. The smallest, for one horse, has a capacity of 3 cubic feet; the others, for two horses, have a capacity of 5 to $7\frac{1}{2}$ cubic feet. The smallest weighs about 90 lbs., and the larger ones from 94 to 102 lbs.




FIG. 195.—DRAG-SCRAPER WITH RUNNERS.

The price is variable, iron being the cheapest and steel the dearest; the range appears to be from \$10 to \$18.

A recent improvement in drag-scrapers is the furnishing them with runners or a double bottom. These devices prolong the life of the scraper. Fig. 195 shows a drag-scraper furnished with steel runners.

Buck-scrapers are made in two sizes—two-horse, carrying $7\frac{1}{2}$ cubic feet; four-horse, 12 cubic feet.

Pole-scraper Fig. 196 is designed for use in making and levelling earth roads and for cutting and cleaning ditches; it is also well adapted for moving earth short distances at a minimum cost.




FIG. 196—POLE-SCRAPER.

SIZE AND PRICE.

48 in. wide, weight 123 lbs.....	\$14
86 " " " 113 "	18

Wheeled scrapers consist of a metal box, usually steel, mounted on wheels, and furnished with levers for raising, lowering, and dumping. They are operated in the same manner as drag scrapers, except that all the movements are made by means of the levers, and without stopping the team. By their use the excessive resistance to traction of the drag-scraper is avoided. Various sizes are made, ranging in capacity from 10 to 17 cubic feet. In weight they range from 350 to 700 lbs.; in price from \$40 to \$75.

Figs. 197 to 199 show the three positions of the scrapers when in use.




FIG. 197.—POSITION WHEN LOADING.



FIG. 198.—POSITION WHEN CARRYING.




FIG. 199.—POSITION WHEN UNLOADED.

WHEELBARROWS.—The wheelbarrow Fig. 200 is constructed of wood and is the one most commonly employed for earthwork. Its capacity ranges from 2 to $2\frac{1}{2}$ cubic feet. Weight about 50 lbs. Price about \$20 per dozen.

The barrow Fig. 201 has a pressed-steel tray, oak frame, and steel wheel, and will be found more durable in the maintenance department than the all-wood barrow. Capacity from $3\frac{1}{2}$ to 5 cubic feet, depending on size of tray. Price from \$5.50 to \$7.50.

The barrow Fig. 202 is constructed with tubular iron frames and steel tray, and is adaptable to the heaviest work, such as moving heavy broken stone, etc., or it may be employed with advantage in the cleaning department. Capacity from 3 to 4 cubic feet. Weight from 70 to 82 lbs. Price from \$10.75 to \$13.50.



FIG. 200.



FIG. 201



FIG. 202.

The maximum distance to which earth can be wheeled economically in barrows is about 200 feet.

The wheeling should be performed upon planks, whose steepest inclination should not exceed 1 in 12. The power required to move a barrow on a plank is about $\frac{1}{8}$ part of the weight; on hard dry earth, about $\frac{1}{4}$ part of the weight.

The time occupied in loading a barrow will vary with the character of the material and the proportion of wheelers to shovellers. Approximately, a shoveller takes about as long to fill a barrow with earth as a wheeler takes to wheel a full barrow a distance of about

100 or 120 feet on a horizontal plank and return with the empty barrow.

CARTS.—The cart usually employed for hauling earth, etc., is shown in Fig. 203. The average capacity is 22 cubic feet, and the average weight is 800 lbs. Price about \$75.

These carts are usually furnished with broad tires, and the body is so balanced that the load is evenly divided above the axle.

The time required to load a cart varies with the material. One shoveller will require about as follows : clay, seven minutes ; loam, six minutes ; sand, five minutes.




FIG. 203.—EARTH-CART.

DUMP-CARS.—These cars are made to dump in several different ways, viz., single or double side, single or double end, and rotary or universal dumpers.

Dump-cars may be operated singly or in trains, as the magnitude of the work may demand. They may be moved by horses or small locomotives. They are made in various sizes, depending upon the gauge of the track on which they are run. A common gauge is 20 inches, but varies from that up to the standard railroad gauge of 56½ inches.

The principal dimensions, capacity, prices, etc., of single-side dumping-cars are given in the following table. Those made by different manufacturers vary, but not materially, from these stated.



FIG. 204 —SIDE DUMPING-CAR.



FIG. 205.—ROTARY DUMPING-CAR.

DIMENSIONS, CAPACITY, PRICES, ETC., OF DUMP-CARS.

Gauge. Inches.	Dimensions.								Capacity, Cubic Yards.	Price.
	Length over All.	Wheel- base.	Length of Body.	Width.	Depth.	Top of Body above Rail.	Diameter of Wheels.	Diameter of Axles.	Weight.	
20	ft. in.	ft. in.	ft. in.	ft. in.	in.	ft. in.	in.	in.	lbs.	
30	" 5	" 3	" 5	" 5	" 16	" 4	" 16	"	1300	\$64
36	" "	" "	" "	" "	" "	" "	" "	"	1400	67
36 to 56½	8 4	3 5	6 0	6 0	24 to 30	"	20	"	1450	70
									2000	2½ to 3 100 to 110

TRACK AND TRACK FASTENINGS.—The rails used on construction range from 12 to 25 lbs. per yard. The price varies considerably with the condition of the market.

The number of tons of rails required per mile is as follows:

Weight per yard.	Tons of 2240 lbs. per mile.	
12 lbs.	18 tons	1920 lbs.
16 "	25 "	320 "
20 "	31 "	960 "
25 "	39 "	640 "
28 "	44 "	000 "

The number of cross-ties per mile is as follows:

Centre to Centre.	No. of Ties
1½ feet.	3.520
1¾ "	3.017
2 "	2.640
2¼ "	2.348
2½ "	2.118

The number of splice-joints per mile is as follows (two bars and four bolts and nuts to each joint):

Rails 20 feet long.	528 joints
" 24 " "	440 "
" 26 " "	406 "
" 28 " "	378 "
" 30 " "	352 "

The size of spikes used and the number required per mile is as follows (four spikes per tie):

Weight of Rail.	Size, measured under head.	Ties, 2 ft. C. to C., require Kegs	Average Number per Keg of 300 lbs.
24 to 35 lbs.	4" × ½"	17½	600
20 to 30 "	4 × ⅞	14½	720
16 to 25 "	4 × ¾	10½	1000
16 to 20 "	3½ × ¾	9	1190
16 to 20 "	3 × ¾	8½	1240
12 to 16 "	2½ × ¾	7½	1342

DUMP-WAGONS, Figs. 206 and 207.—The use of these wagons for moving excavated earth, etc., and for transporting materials such as sand, gravel, etc., materially shortens the time required for

unloading the ordinary form of contractor's wagon; having no reach or pole connecting the rear axle with the centre bearing of the front axle, they may be cramped short and the load deposited just




FIG. 206.—DUMP-WAGON




FIG. 207.—DUMP-WAGON DUMPED.

where required. They are operated by the driver, and the capacity ranges from 35 to 45 cubic feet.

MECHANICAL GRADERS.—Within the last few years several machines have been devised for the purpose of handling earth more




FIG. 208.—ROAD-GRADER.

expeditiously and economically than can be done by hand; they are called by various names, such as “road machines,” “graders,” “road-hones,” etc. Their general form is shown in Figs. 208 to 210.




FIG. 209.—ROAD-GRADER.

Briefly described, they consist of a large blade made entirely of steel or of iron, or wood shod with steel, which is so arranged by mechanism attached to the frame from which it is suspended that

it can be adjusted and fixed in any direction by the operator. In their action they combine the work of excavating and transporting the earth. They have been chiefly employed in the forming and maintenance of earth roads, but may be also advantageously used in preparing the subgrade surface of roads for the reception of broken stone or other improved covering.

A large variety of such machines are on the market, and the price ranges from \$100 to \$300.




FIG. 210.—ROAD-GRADER.

Besides the above-described machines, there is another known as the "New Era" grader, shown in Fig. 211. This machine excavates the material from side ditches, and automatically places it in the embankment, or it can be used in a cutting, in which situation it will excavate and automatically load the material into carts or wagons. Fig. 212 shows the machine at work.

Briefly described, the machine consists of a plough which loosens and raises the earth, depositing it upon a transverse carrying-belt, which conveys it from excavation to embankment. This carrier is built in four sections, bolting together, so it can be used to deliver earth at 14, 17, 19, or 22 feet from the plough. The carrier-belt is of heavy 3-ply rubber 3 feet wide.

The plough and carrier are supported by a strong trussed framework resting on heavy steel axles and broad wheels. The large rear wheels are ratcheted upon the axle, and connected with strong

gearing which propels the carrying-belt at right angles to the direction in which the machine is moving.




FIG. 211.—NEW ERA GRADER.




FIG. 212.—NEW ERA GRADER AT WORK.

The wheels and trusses are low and broad, occupying a space 8 feet wide and 14 feet long, exclusive of the side carrier. This enables it to work on hillsides where any wheeled implement can be

used. Notwithstanding its large size it is so flexible that it may be turned around on a 16-foot embankment. Pilot-wheels and levers enable the operator to raise or lower the plough or carrier at pleasure.

As a motive power 12 horses—8 driven in front, 4 abreast, and 4 in the rear on a push-cart—are usually employed.

When the teams are started, the operator lowers the plough and throws the belting into gear, and as the plough raises and turns the earth to the side the belt receives and delivers it at the distance for which the carrier is adjusted, forming either excavation or embankment.

When it becomes necessary to deliver the excavated earth beyond the capacity of the machine (22 feet or $7\frac{1}{2}$ feet above the plough), the earth is loaded upon wagons, then conveyed to any distance. Arranging the carrier at 19 feet, wagons are driven under the carrier and loaded with $1\frac{1}{4}$ to $1\frac{1}{2}$ yards of earth in from 20 to 30 seconds. When one wagon turns out with its load, another drives under the carrier, and the machine thus loads 600 to 800 wagons per day.

The makers claim that with six teams and three men it is capable of excavating and placing in embankment from 1000 to 1500 cubic yards of earth in ten hours, or of loading from 600 to 800 wagons in the same time, and that the cost of this handling is from $1\frac{1}{4}$ to $2\frac{1}{2}$ cents per cubic yard.

POINTS TO BE CONSIDERED IN SELECTING A ROAD MACHINE.
—In the selection of a road machine the following points should be carefully considered:

- (1) Thoroughness and simplicity of its mechanical construction.
- (2) Material and workmanship used in its construction.
- (3) Ease of operation.
- (4) Lightness of draft.
- (5) Adaptability for doing general road-work, ditching, etc.
- (6) Safety to the operator.

CARE OF ROAD MACHINES.—The road machine when not in use should be stored in a dry house and thoroughly cleaned, its blade brushed free from all accumulations of mud, wiped thoroughly dry, and well covered with grease or crude oil. The axles, journals, and wearing parts should be kept well oiled when in use,

and the blade should be kept sharp and in good condition at all times. An extra blade should be kept on hand to avoid stopping the machine while the dulled one is being sharpened.

SURFACE-GRADERS.—The surface-grader, Fig. 213, is used for removing earth previously loosened by a plough. It is operated by one horse. The load may be retained and carried a considerable




FIG. 213.—SURFACE-GRADER.

distance, or it may be spread gradually, as the operator desires. It is also employed to level off and trim the surface after scrapers.

The blade is of steel, $\frac{1}{4}$ inch thick, 15 inches wide, and 30 inches long. The beam and other parts are of oak and iron. Weight about 60 lbs. Price about \$9.




FIG. 214.—ROAD-LEVELLER.

The road-leveller, Fig. 214, is used for trimming and smoothing the surface of earth roads. It is largely employed in the spring when the frost leaves the ground.

The blade is of steel, $\frac{1}{4}$ inch thick by 4 inches by 72 inches, and is provided with a seat for the driver. It is operated by a team of horses. Weight about 150 lbs. Price about \$12.

1034. **Draining-tools.**—The tools employed for digging the ditches and shaping the bottom to fit the drain-tiles are shown in Fig. 215. They are convenient to use, and expedite the work by avoiding unnecessary excavation. For cost of drains, etc., see Art. 688, *et seq.*




FIG. 215.—DRAINING-TOOLS.

The tools are used as follows: Nos. 3, 4, and 5 are used for digging the ditch; Nos. 6 and 7 for cleaning and rounding the bottom of the ditch for round tile. No. 2 is used for shovelling out loose earth and levelling the bottom of the ditch; No. 1 is used for the same purpose when the ditch is intended for "sole" tile.

1035. Tools for Rock Excavation—HAND DRILLING.—The tools employed for hand drilling are illustrated in Fig. 216, in which Fig. A represents the first or shortest drill, usually eighteen inches in length, with cutting head about one and three quarter inches wide and weight about four pounds. The second drill is shown by Fig. B; it is about twenty-seven inches long, one and eleven sixteenth inches wide on the cutting edge, and weighs about six pounds. The third or longest drill is shown at C; it is usually forty inches in length, cutting edge one and five eighth inches wide, and weighs about nine pounds.

The scraper is shown by Fig. D. It is used to remove the sludge from the bottom of the hole, and consists of an iron rod one half inch in diameter, one end of which is flattened out in a circular form and turned up at right angles to the stem. The other end is made to terminate in a spiral hook or *drag-twist*, the use of which is to withdraw the absorbent material used to dry the hole before inserting the explosive.

The *bull* or *claying-iron* is shown by Fig. E. It is used for forcing clay into seamy rock and thus prevent the entrance of water into the blast-hole. It consists of a round bar of iron, called the stock or shaft, a little smaller in diameter than the bore-hole, and a thicker portion, called the head or poll, terminating in a striking-face. While this tool is not an essential part of a drilling outfit, yet it is a very serviceable one, and should always be at hand in wet ground when loose gunpowder is employed.

Fig. F represents the *tamping-iron* or rammer. It consists of a bar of copper or phosphor bronze, the tamping end of which is grooved to receive the fuse lying against the side of the bore-hole. The use of rammers made of iron is dangerous, as sparks produced by the striking of the iron against silicious substances may cause ignition of the charge.

Fig. G represents an auxiliary implement called the *beche*. It is used for extracting a broken drill. It consists of an iron rod having a diameter slightly less than that of the bore-hole, and is made hollow at one end. The form of the aperture is slightly conical, so that it may pass over the broken stock of the drill, and when hammered down may grasp the stock in its higher portion with sufficient firmness to allow of the two being drawn out together.




FIG. 216.—HAND-DRILLING TOOLS.

Fig. H represents the sledge or striking-hammer; its form and weight are variable, the latter is usually about five pounds.

Fig. I represents the hand hammer; its weight varies from two to four pounds. The distinction between a hammer and a sledge is founded on dimensions only; the hammer, being intended for use in *one* hand, is made comparatively light and is furnished with a short handle, while the sledge, being intended for use in *both* hands, is furnished with a much longer handle and is made heavier.

Hand drills are used in sets of different lengths. The sets may be intended for use by one man or by two. In the former case the sets are described as "single-hand" sets, and they contain a hammer for striking the drills; in the latter case the sets are called "double-hand," and they contain a sledge instead of a hammer for striking. It may appear at first sight that there is a waste of power in employing two men, for that two men cannot bore as fast as one. This rate of speed can, however, be obtained, and is due less to the greater effectiveness of the stroke than to the fact that two men can, by repeatedly changing places with each other, keep up almost without intermission a succession of blows for an indefinite length of time, whereas with the single set the man is continually obliged to cease for rest.

The making and sharpening of the drills is an extremely important part of the blacksmith's labor and requires judgment and intelligence. A smith will, with the assistance of a striker, sharpen and temper about thirty single-hand drills of medium size in an hour, or twenty double-hand drills of medium size in the same time. Of course much will depend on the degree of bluntness in the cutting edge; but assuming the drills to be sent up only moderately blunted, this may be taken as a fair average of the work of two men.

PRICES OF HAND-DRILLING TOOLS.

Drill-steel.....	per pound	\$0.25
Striking-hammers, 3 to 5 pounds.....	" "	.86
" " 5 pounds and over.....	" "	.90
Spoons.....	each	2.00
Wedges.....	per pound	.12½
Plug and feathers.....	" "	.80
Crowbars	" "	.10
Stone-sledges.....	" "	.80
Blacksmith outfit.....	from	\$50 upwards

STEAM DRILLING.—A steam-drilling outfit comprises a steam drill; a set of drill-steels; a set of blacksmith's tools for sharpening the drills; a sand-pump; a band for centring piston; extra drill parts; a portable steam boiler; steam hose, etc.




FIG. 217.—STEAM DRILL.

Steam drills vary in size, price, etc., as shown in the following table:

SPECIFICATIONS OF THE LITTLE GIANT DRILL

Name and number	Kid Drill for Block Hoisting	No. 1	Nos. 2 and 2-A	Nos. 3 and 3-A	Nos. 3 1/4 and 3 1/4-A	Nos. 4 and 4-A	No. 5	No. 7
Dimensions :								
Diameter of cylinder, in inches	1 1/2	2 1/4	2 1/4	3 1/2	3 1/4	3 3/4	4 1/2	5 1/2
Length of stroke, in inches . .	3 3/4	5 1/4	6 1/4	6 1/4	6 1/4	7 1/4	7 1/4	8 1/2 (extended)
Length of feed, in inches . . .	10	15	18	24	24	30	36	30
Usual depth of hole drilled, feet	1 1/2	4	6 to 10	10 to 15	15	20	20 to 30	...
Usual diam. bottom of hole, ins.	1	1 1/2	1 1/2	1 1/2	1 1/4	2	2 1/4	...
Depth drilled in ten hours, feet	...	50	60	70	70	70	70	...
Diameter of steel, in inches . .	3/4	3/4	1	1 1/4	1 1/4	1 1/4	1 1/2	1 1/4
Diameter of hose, in inches . .	3/4	3/4	3/4	1	1	1 1/4	1 1/2	1 1/2
Diam. steam pipe, 150 ft. long, ins.	3/4	1	1 1/4	1 1/4	1 1/4	2	2	2 1/2
Size of boiler required to run drill by steam, in horse-power	3	5	7	10	10	12	15	20 to 23
Weights :								
Drill, unmounted, in pounds . .	95	150	200†	265†	290	390§	560	860 (including shaft)
Adjustable tripod, no weights, lbs.	70	70	145	175	175	354	400	...
Set tripod weights (3 to set), lbs.	108	210	288	336	336	510	570	...
Drill m'ted on tripod with w'ts, lbs.	273	430	633	776	801	1254	1470	...
Drifting column, 6 ft. high, lbs.	...	185	319	319	319	405
Shipping measurements (outside):								
Of box for drill alone, in inches	42x13x10	42x13x11	45x13x11	48x14x11	48x14x13	58x16x13	61x19x14	80x25x15
Of box for tripod, in inches . .	36x 8x 6	36x 8x 6	40x 8x 8	45x10x10	45x10x10	51x14x14
Of box for six lengths of hose, ins.	34x34x24	34x34x24	34x34x24	34x34x24	34x34x24	34x34x24
Prices :								
Of drill complete, unmounted . .	\$125 00	\$185 00	\$200 00	\$250 00	\$275 00	\$350 00	\$400 00	...
Adjustable tripod and w'ts, complete	25 00*	30 00	50 00	50 00	50 00	60 00	65 00	...
Of column 6 feet high	50 00	50 00	50 00	50 00	60 00
Of drill with tripod and weights }	150 00	{ 215 00 }	250 00	300 00	325 00	410 00	465 00	...
or column, complete }		{ 235 00 }						

* Plain tripod. † Weight of 2-A drill is 275 pounds. § Weight of 4-A drill is 470 pounds.

PRICES OF STEAM-DRILLING TOOLS.

Steam drill	\$185.00 to \$490.00
Steam boiler	\$280.00 to ———
Steam hose... ..	54 to 97 cents per foot
Drill-steels, per set ..	\$25.00 to \$115.00
Blacksmith's swages for dressing drills.....	\$15.00
Forge and hand tools.....	\$50.00 upward
Sand-pumps, each.....	\$3.00
Giant blasting-powder, per pound..	.15 to 60 cents
Leading-wires, per foot ..	1 cent upward
Magneto-electro blasting apparatus, each... ..	\$25.00 to \$50.00
Derricks, each.....	\$100.00 upward

PORTABLE BOILERS for operating steam drills.—Fig. 218 shows a convenient arrangement of a steam boiler for operating rock-




FIG. 218.—PORTABLE BOILER.

drills. A water-tank occupies one end of the frame and fuel can be carried on the other end. Price from \$400 upwards.

1036. Tools Employed in the Construction of Broken-stone Roads
—STONE-HAMMERS.—The hammers generally used for breaking stone are three, viz.:

Sledges, 5 pounds and over	80 cents per pound
Hand hammers, 3 to 5 pounds.	36 " " "
" " 1½ to 2 "	45 " " "

THE RING-GAUGE, for testing the size of the stone and through which the largest stone should in all positions freely pass. The diameter is usually 2½ inches, can be made by any blacksmith at a cost of 25 cents.

THE STRAIGHT-EDGE, Fig. 219, is used for obtaining the proper transverse form of roads. It consists of a horizontal bar having in the centre of its length a plummet for ascertaining when the straight-edge is level. Gauges formed of upright pieces of wood marked off in inches are placed at every four feet; these upright pieces have a slot cut in them so as to allow of their being moved either up or down and adjusted to the desired depths below the horizontal line. These upright pieces are secured to the straight-edge, as shown in the section, by a small bolt passing through the slot in the upright and the straight-edge, the bolt being furnished with a thumbscrew, by tightening which the gauges are fixed in place when adjusted to the required depths.




FIG. 219.—STRAIGHT-EDGE.

LINES.—Linen, in rolls 100 feet long; price per dozen rolls \$9.

REEL AND STAKE.—Price per dozen \$6 to \$9.50.

STONE-FORKS.—The broken stone can be more easily and quickly taken up and thrown upon the roadway by the use of forks than by shovels. The price of forks ranges from \$18 to \$25 per dozen.




FIG. 220.—ROADBED-ROLLER.

ROADBED-ROLLER, Fig. 220.—This is a very efficient form of roller for compacting embankments and the subgrade surface of highways. The roller is 5 feet long with nineteen sections, ten




FIG. 221.—SPRINKLING-CART.

of 35 inches in diameter and nine of 32 inches in diameter, set alternately. The sections act dependently on the axle. Weight about $2\frac{1}{2}$ tons. Price \$265.

SPRINKLING-CARTS.—Fig. 221 shows a convenient form of sprinkling-cart for use either on construction or sprinkling suburban streets and country roads. Capacity about 150 gallons. Price about \$100.

RAKES used for spreading the stone should be about twelve inches long and have prongs from two to three inches in length, spaced three quarters of an inch apart, and have handles about six feet long. The price of such rakes is from \$12 to \$15 per dozen.

STONE-CRUSHERS.—The leading styles of stone-crushers are illustrated in Figs. 222 to 232. The dimensions, capacity, weights, etc., are given in the tables on pages 631, 632, and 633.

The amount of the product in a given time will vary according to the character of the rock to be broken as well as to the size to which it is broken; the smaller the size the less the amount broken and the greater the power required.

In getting an engine to drive a stone-crusher it is advisable to provide one of greater power than is stated in the tables, for no close estimate can be made to cover all varieties of rock, and it is more economical to use 10 H. P. from a 12 or 15 H. P. engine than from a 10 H. P. engine.

For cost of crushing stone and cost of operating crushing-plants see Art. 365 *et seq.*, and Table XXXIX.

PORTABLE CRUSHERS.—Any one of the crushers described can be had in portable form. Some are made portable by mounting on low-wheeled trucks, others by attaching travelling-wheels directly to the frame of the machine, and others by attaching a pair of wheels to one end to act as a front truck, using the fly- or balance-wheels of the machine as rear travelling-wheels. When the balance-wheels are used for this purpose, it is necessary to have independent belt-wheels. If the balance-wheels are used for belt-wheels, it will be necessary to have either a metal or wood covering which can be easily placed and removed, for the face of the balance-wheels will become too roughened to be used directly for belting. Fig. 233 shows one of the many forms of portable crushers.

BRENNAN CRUSHER.

Size or Receiving Capacity	Approximate Product per Hour in Tons to Macadam Size.	Approximate Weight.	Proper Speed.	Horse-power Required.	Prices.
5 x 20	8 to 10	7,000	300	8
7 x 20	12 " 15	10,000	300	12 to 15
8 x 12	8 " 10	8,000	280	8
8 x 25	15 " 20	13,000	280	15 to 20
10 x 25	20 " 30	16,000	280	20 " 30
12 x 27	30 " 40	32,000	280	30 " 40
20 x 48	60 " 100	72,000	240	80

GATES CRUSHER.

• Size.	Dimensions of Each Receiving Opening, about. Inches.	Dimensions of Three Receiving Openings Combined, about. Inches.	Weight of Breaker. Pounds.	Capacity per Hour in Tons of 2000 lbs. Passing 24-in. Ring, according to Character of Rock or Ore.	Revolutions of Driving pulley.	Height from Bottom Frame to Top of Hopper.	Space Occupied by Breaker. Inches.		Diameter of Hopper. Inches.	Size Engine Recommended to Drive Breaker, Elevator, and Screen. Indicated Horse-power.	Prices Subject to Change without Notice.
							Width of Frame.	Length of Frame.			
00	2 x 4	2 x 12	500	700	24	17	26	13	1 to 1½	\$ 125
0	4 x 10	4 x 30	3,300	2 to 4	500	50	30	73	28	4 " 5	400
1	5 x 12	5 x 36	5,600	4 " 8	475	55	31	76	42½	8 " 10	600
2	6 x 14	6 x 42	7,800	6 " 12	450	61	39	90	46½	12 " 15	800
3	7 x 15	7 x 45	13,800	10 " 20	425	75	48	103	54½	20 " 25	1200
4	8 x 18	8 x 54	21,500	15 " 30	400	91	54	114	79½	25 " 30	1000
5	10 x 20	10 x 60	27,000	25 " 40	375	101	63	123	88	30 " 40	2500
6	11 x 24	11 x 72	40,500	30 " 60	350	114	73	139	103	40 " 60	3500
7	14 x 30	14 x 90	65,800	50 " 125	350	144	84	145	120	75 " 125	6000
8	18 x 42	18 x 126	89,000	100 " 150	350	156	90	164	132	100 " 150	7000

FORSTER CRUSHER.

No.	Opening in Jaws.	Speed.	Horse-power.	Total Weight.	Capacity per Hour Varies according to Matter Crushed.	Floor-space Required	Price.	Cost Extra Sets Dies, per Set.
1	4 x 0	350	1	1,800 lbs.	1 to 2 tons	4½ x 3½	\$ 190	\$10
2	5 x 15	300	3	4,500 "	4 " 7 "	6 x 4½	390	25
3	7 x 18	300	5	7,400 "	5 " 8 "	7 x 5½	570	35
5	12 x 24	250	8	17,000 "	10 " 14 "	11 x 7½	1000	90

FARREL CRUSHER.

No.	Size or Receiving Capacity.	Approximate Capacity in Tons, per day of 10 Hours, to Sizes Stated.						Extreme Dimensions.			Revolutions of Pulley.	Horse-power Required.	Total Weight.	Price.			
		tons.		in.		tons.		in.		Length.					Breadth.	Height.	
6 $\frac{1}{2}$	15 \times 9	100 to	2 $\frac{1}{2}$	80 to	2	55 to	1 $\frac{1}{2}$	7	0	5	3	5	3	275	12	15,000	\$ 750
7	16 \times 10	120 " "	2 $\frac{1}{2}$	100 " "	2	75 " "	1 $\frac{1}{2}$	7	2	5	6	5	3	275	15	16,300	375
8	20 \times 10	175 " "	3	150 " "	2 $\frac{1}{2}$	125 " "	2	7	8	5	10	5	1	275	20	18,800	1050
*9	24 \times 15	250 " "	3	200 " "	2 $\frac{1}{2}$	175 " "	2	7	10	7	2	5	9	275	25	26,000	1575
*10	30 \times 13	300 " "	3	275 " "	2 $\frac{1}{2}$	225 " "	2	8	6	8	2	6	4	275	30	37,600	2250
*11	30 \times 15	400 " "	4 $\frac{1}{2}$	350 " "	3 $\frac{1}{2}$	8	6	8	2	6	4	275	30	37,600	2250
*12	36 \times 20	800 " "	8	600 " "	6	500 to	5	9	10	8	8	6	10	275	40	50,000	2875
*13	36 \times 24	1000 " "	10	800 " "	8	500 to	9	10	8	8	6	10	275	40	50,000	2875

* These sizes have two driving-pulleys.

CHAMPION CRUSHER.

No.	Size or Receiving Capacity of Jaws.	Product per Hour in Tons when Machine is Closed to 2 Inches.	Weight, Approximated.	Speed, Revolutions.	Driving-pulleys, Diameter and Face.	Horse-power Required.	Price.
	inches.	tons.	lbs.		inches.		
3	7 \times 13	7 to 13	5,000	180	44 \times 8	12	\$ 600
4	9 \times 15	12 " 18	8,000	160	50 \times 8	15	800
5	11 \times 26	24 " 36	16,000	150	60 \times 10	25	1500

CLIMAX CRUSHER.

	No. 1.	No. 2.	No. 3.	No. 4.
Size of top opening of jaws in inches.....	7 \times 13	9 \times 16	10 $\frac{1}{2}$ \times 22	12 \times 28
Product per hour in tons when machine closes to 2 inches.....	7 to 12	10 to 15	15 to 30	25 to 40
Weight, approximate.....	5,000	8,500	15,000	20,000
Weight, with two-wheeled trucks and elevator.....	6,000	10,000
Weight, mounted on 4 wheels, with 10-foot elevator.....	7,300	11,000
Speed, revolutions.....	325	300	290	275
Driving pulleys, diameter and face, inches	28 \times 8	32 \times 9	38 \times 10	42 \times 12
Horse-power required.....	10	12	25	35
Floor-space required, length.....	5 ft.	6 ft.	7 ft.	8 ft. 1 in.
Floor-space required, width.....	4 ft. 4 in.	5 ft. 1 in.	5 ft. 6 in.	6 ft.
Extreme height of machine.....	2 ft. 7 in.	3 ft. 10 in.	4 ft. 7 in.	4 ft. 10 in.
Size of elevator best suited.....	No. 1	No. 2	No. 3	No. 3
Diameter of screen best suited, in inches..	30	30	36	36

WESTERN CRUSHER.

No.	Size or Receiving Capacity of Jaws.	Product per Hour.	Weight, Approximated.	Speed, Revolutions.	Diameter and Face of Driving-pulleys.	Horse-power Required.
	inches.	tons.	lbs.		inches.	
5	7 × 13	10 to 12	5,000	200	40 × 6½	8 to 10
10	9 × 15½	12 " 20	8,000	200	44 × 8	10 " 13
15	10 × 23	18 " 25	14,000	200	44 × 10½	15 " 20

AUSTIN CRUSHER.

No.	Jaw-opening in Inches.	Size Engine Required.	Speed, Revols.	Weight of Crusher.	Capacity per Hour, Tons.	Floor-space Required.	Price, Not Mounted.	Price, Mounted on Four-wheel Trucks.	Price of Extra Dies, per Pair.
3	8 × 15	10 H. P.	300	6000 lbs.	10 to 14	2½ × 7 ft.	\$600.00	\$ 725.00	\$40.00
4	10 × 18	15 "	300	8000 "	15 " 20	3 × 8 "	900.00	1050.00	50.00

Elevator, 14 ft. long, \$175; for each additional foot add \$5. Revolving screen, 2-section, \$200; 3-section, \$250. Each section is 2½ ft. long by 2 ft. in diameter, made of steel, and turns on anti-friction rollers.

BLAKE CRUSHER.

Size or Receiving Capacity.	Product per Hour in Cubic Yards.	Weight of Heaviest Piece.	Total Weight.	Extreme Dimensions.			Proper Speed, Revolutions.	Horse-power Required.	Price, f.o.b. Pittsburg.
				Length.	Breadth.	Height.			
Inches.		lbs.	lbs.	ft. in.	ft. in.	ft. in.			
10 × 4	3	1,695	4,000	3 11	3 3	3 9	250	4	\$ 275
10 × 7	5	4,339	8,000	5 3½	5 3	4 5	250	6	450
15 × 7	7	6,500	15,000	6 5	5 0	5 11	250	9	750
20 × 12	10-12	10,000	21,000	7 6	6 0	6 3	250	15	1000
20 × 15	Coarse or Preliminary Breaker.	2,450	32,600	9 3	6 0	6 7	150	12
24 × 18		9,425	37,500	9 10	5 0	6 10	125	12



FIG. 222.—THE BRENNAN CRUSHER. EXTERIOR VIEW.




FIG. 223.—THE BRENNAN CRUSHER SECTIONAL VIEW.



FIG. 224.—THE GATES CRUSHER. EXTERIOR VIEW.




FIG. 225.—THE GATES CRUSHER. SECTIONAL VIEW.




FIG. 226.—THE FARREL CRUSHER. SECTIONAL VIEW.




FIG. 227.—THE CHAMPION CRUSHER. SECTIONAL VIEW.




FIG. 228.—CLIMAX CRUSHER. SECTIONAL VIEW.




FIG. 229.—THE WESTERN CRUSHER. SECTIONAL VIEW.




FIG. 230.—THE AUSTIN CRUSHER. SECTIONAL VIEW.




FIG. 231.—THE BLAKE CRUSHER. SECTIONAL VIEW.

SCREENS.—Nearly all specifications for broken stone call for it to be screened, either to separate it into different sizes or to remove the tailings; for either purpose revolving screens made of steel plate perforated with holes of the required size are employed. They can be run in several ways, as shown in Figs. 237 to 241.



FIG. 232.—THE FORSTER CRUSHER. SECTIONAL VIEW.



FIG. 233.—GATES PORTABLE CRUSHER.

Fig. 234 shows a three-section screen; the first section has holes one inch in diameter, the second section holes one and one half inches in diameter, and the third section holes two and one half inches in diameter. Holes of any other dimensions may be used, depending upon the sizes desired. Dust-jackets are also used in connection with the screens, thus separating the dust from the crushed stone. The following table contains the usual dimensions, weight, price, etc., of steel-plate screens:

No.	Diam-eter.	Length, with three sections.	Revolu-tions of Pulley.	Size Pulley, Diameter Face.	Weight, Lbs.	Price for three sections complete.	Price for two sections complete.
	inches.	ft. in.		inches.			
1	24	10 6	90	30 × 6½	2200	\$275	\$225
2	30	12 6	90	36 × 8	3550	385	325
3	36	12 6	80	36 × 8	3900	450	375
4	42	12 6	70	36 × 8½	4500	550	450
5	48	15 6	60	42 × 9	5500	700	575
6	54	15 6	60	48 × 10	950	800




FIG. 234.—REVOLVING STONE-SCREEN.




FIG. 235.—SEMI-PORTABLE ENGINE AND BOILER.

ENGINES AND BOILERS FOR DRIVING ROCK-CRUSHERS are usually of the portable or semi-portable type. Fig. 235 shows a compact combination of the semi-portable form, and Fig. 236 shows the portable type.




FIG. 236.—PORTABLE BOILER AND ENGINE.

SPECIFICATIONS OF PORTABLE BOILERS AND ENGINES ON WHEELS. FIG. 236.

No. of size	0	1	2	3	4	5	6	7	8
Horse-power.....	6	8	10	12	15	20	25	30	35
Diam. of cylinder, in..	5	5	6	7	8	8	9	10	10
Length of stroke, in..	8	8	9	10	10	12	12	12	15
Usual no. revolutions.	185	240	190	160	160	170	170	170	150
Diam. of pulleys, in..	14&32	14&32	16&36	20&44	20&44	30&48	32&54	32&54	36&60
Face of pulleys, in..	8½&8½	8½&8½	8½&9½	10½&10½	10½&10½	8½&12½	10½&12½	10½&12½	10½&14
Diam. of boiler, in....	26	28	30	32	32	34	36	36	40
Length of furnace, in..	84	86	88	88	44	52	52	52	52
Height of furnace, in..	80	82	81	85	38	38	40	40	44
Width of furnace, in..	21	23	24	26	26	28	30	30	34
No. of 3-inch tubes....	17	20	22	26	26	30	34	34	40
Length of tubes, in....	54	66	72	72	78	90	96	102	102
Shipping wt. complete	4800	5000	5700	6000	7100	8100	9600	10,500	11,300
Price.....	\$700	\$724	\$788	\$880	\$981	\$1043	\$1083	\$1,277	\$1,351

STONE-CRUSHING PLANTS.—Complete crushing-plants include a stone-crusher, engine, boiler, shafting, pulleys, and belting. These plants may be divided into two classes, viz., *stationary* and *portable*. In arranging either class of plant care must be taken to save unnecessary handling of the stone; to this end the crusher must be

placed (1) so as to receive the stone directly from the carts or other conveyance used to transport it from the quarry, and (2) so as to deliver the broken stone into the vehicles which are to haul it away without handling.




FIG. 287.—CRUSHING-PLANT FOR HILLSIDE LOCATION.




FIG. 288.—CRUSHING-PLANT FOR LEVEL GROUND.

In Figs. 237 to 240 a few illustrations are presented showing simple methods of arranging plants. Fig. 237 shows a fixed plant for hillside location, with road graded for delivery of stone to the crusher, and chute for delivery of broken stone to the carts.

Fig. 238 shows a fixed plant for location on level ground, with road graded for delivery of stone to crusher, and elevator for raising crushed stone to chute for delivery into carts.

Fig. 239 shows a plant for temporary use, with platform for receiving the stone to be crushed, three-section screen, and platform




FIG. 239.—TEMPORARY CRUSHING-PLANT.




FIG. 240.—PORTABLE CRUSHING-PLANT.

for receiving the crushed and screened stone, from which it can be shovelled into the carts or an elevator can be attached.

Fig. 240 shows a portable plant with elevator and screen.

Fig. 241 shows a portable plant with crusher elevated sufficiently to allow of a screen being used without the employment of an elevator.




FIG. 241.—CRUSHER MOUNTED ON WHEELS.

STONE-DISTRIBUTING CARTS.—The cart shown in Fig. 242 is specially designed for distributing broken stone for building or repairing roads. The cart is mounted on four wheels, so arranged that it can be turned in a short space. The bottom of the cart slopes downward to the back, and the tail-board is hinged at its upper edge and is furnished with two adjusting chains by which the opening or swing of the lower edge is regulated. Steel wings are attached to the sides of the cart at the tail-board for the purpose of spreading the stone the full width between the wheels. The cart is tilted by a rack and pinion operated by the driver, and may be fixed at any desired angle. As the stone flows from the rear of the cart it is levelled by a scraper attached to the bottom of the tail-board; this scraper is pivoted at the centre and can be adjusted so as to spread the stone to any required thickness and over any desired width equal to or less than the gauge of the cart, and thicker on one side than on the other.

The carts are built in two sizes, to be hauled by two or three horses, respectively, the horses being harnessed abreast. The two-

horse size is five feet wide and has a capacity of one and one half cubic yards, and weighs empty 2250 pounds. The three-horse size is seven feet six inches wide and has a capacity of two and one half cubic yards, and weighs empty 2750 pounds.

The price of the two-horse cart is \$175, and of the three-horse size \$200.




FIG. 242.—STONE-DISTRIBUTING CART.

HORSE ROLLERS.—The following figures show a few selections from the large variety of horse rollers in the market. The principal dimensions, weights, and prices are given on pages 647 and 648.



FIG 243.—ENTERPRISE ROLLER.

For the advantages of rolling, form of rollers, amount of rolling, etc., see Articles 396, 397, and 400.

THE ENTERPRISE ROLLER, Fig. 243.—This roller is made in two forms, “reversible” and “non-reversible.” Both styles are made in sizes of 3, 4, 5, and 6 tons, the diameter of the rolling cylinders being respectively 54, 56, 58, and 60 inches, and a width of 54 inches, which is common to all weights. The non-reversible roller is equipped with a ballast-box which will hold a weight of 2 tons, so that a 4-ton roller can be increased to 6, and a 6-ton to 8 tons. Price about \$100 per ton.

Pope's reversible roller, Fig. 244, is made in sizes ranging from 5 to 10 tons. The diameter of the 5-ton roller is 5 feet, and width




FIG. 244.—POPE'S REVERSIBLE ROLLER.

5 feet. The diameter of the 10-ton roller is 7½ feet, and width 5 feet. Price \$100 per ton.

The Champion reversible roller, Fig 245, is constructed in two sections which revolve independently on the axle. The diameter of the rolls and width of the rolling face are the same, viz., 5 feet. This roller is made in four weights, viz., 2½, 3½, 4½, and 5½ tons, and each is supplied with two steel boxes, each of which will hold about a ton of pig iron, thus converting each roller from a light- to a medium- or heavy-weight roller, as desired. Price 2½ tons \$350; for each additional ton add \$50.

The Austin roller, Fig 246, is made in weights of $3\frac{1}{2}$, 4, and $4\frac{1}{2}$ tons. The rolls are $4\frac{1}{2}$ feet in diameter, and width 5 feet.




FIG. 245.—CHAMPION REVERSIBLE ROLLER.




FIG. 246.—AUSTIN REVERSIBLE ROLLER.

STEAM ROLLERS.—There is a large variety of steam rollers in the market from which to select. The leading types are shown in Figs. 247 to 151, and the principal dimensions, etc., are given in the following tables.

For the advantages of rolling, cost of maintaining steam rollers, and amount of rolling required, etc., see Articles 396, 398, 403, and 404.

THE SPRINGFIELD ROLLER. FIG. 247.

	25,000 lbs.	30,000 lbs.	35,000 lbs.
Front rolls, diameter.....	48 inches	48 inches	48 inches
Front rolls, width.....	40 inches	44 inches	48 inches
Beveled driving-wheels, diameter...	76 inches	76 inches	76 inches
Beveled driving-wheels, width.....	20 inches	22 inches	24 inches
Extreme width of machine.....	70 inches	78 inches	86 inches
Compression per square inch.....	550 pounds	600 pounds	650 pounds
Coal capacity.....	450 pounds	500 pounds	550 pounds
Water capacity.....	280 gallons	315 gallons	350 gallons
Maximum grade ascended with 120 pounds steam on loose metalling...	22 per cent.	22 per cent.	22 per cent.

THE PITTS ROLLER. FIG. 248.

	10-ton.	12½-ton.	15-ton.
Front roll, diameter.....	44 inches	46 inches	48 inches
Front roll, width.....	47 inches	51 inches	52½ inches
Driving-wheels, diameter..	69 inches	69 inches	72 inches
Driving-wheels, width.....	18 inches	20 inches	22 inches
Extreme width of machine	78 inches	89 inches	94 inches
Wheels, base.....	117 inches	128 inches	133 inches
Coal capacity ..	400 pounds	500 pounds	500 pounds
Water capacity	225 gallons	275 gallons	320 gallons
Coal consumption per day varies according to work and grades from	400 to 900 lbs.	600 to 1000 lbs.	800 to 1200 lbs.
Travelling speed per hour with fast gear.....	2.92 miles per hour	2½ to 2⅞ miles	2⅞ miles
Travelling speed per hour with slow gear.	2.21 miles per hour	2 miles	1.85 miles

THE HARRISBURG ROLLER. FIG. 249.

	10-ton.	12-ton.	15-ton.
Driving-wheels, width.....	18 inches	20 inches	22 inches
Pressure per inch of width.....	466 pounds	500 pounds	566 pounds
Coal capacity.....	400 pounds	500 pounds	600 pounds
Water capacity.....	130 gallons	155 gallons	180 gallons
Maximum grade ascended with 120 pounds of steam.....	20 per ct.	20 per ct.	20 per ct.

THE AVELING & PORTER ROLLER. FIG. 250.

	10-ton.	15-ton.	20-ton.
Front roll, diameter.....	45 inches	48 inches	54 inches
Driving-wheels, diameter.....	66 inches	72 inches	78 inches
Extreme width of machine....	78 inches	87 inches	96 inches
Pressure per inch of width.....	450 pounds approx.	550 pounds approx.	650 pounds approx.
Coal capacity.....	400 pounds	450 pounds	500 pounds
Water capacity.....	150 gallons	200 gallons	250 gallons
Maximum grade ascended with 100 pounds of steam on bin of loose metalling.....	17 per ct.	17 per ct.	17 per ct.

THE COLUMBIAN ROLLER. FIG. 251.

	27,000 lbs.	32,500 lbs.	38,000 lbs.
Front roll, diameter.....	48 inches	48 inches	52 inches
Driving-wheels, diameter.....	70 inches	72 inches	74 inches
Driving-wheels, width.....	20 inches	22 inches	24 inches
Extreme width of machine....	81 inches	87 inches	95 inches
Coal capacity }	sufficient	for 5	hours
Water capacity }			
Compression of drivers per square inch.....	507 pounds	575 pounds	605 pounds
Grade ascended.....	14 to 20	feet per	100

THE RUSSELL ROLLER. FIG. 247a.

	10-ton.	12½-ton.	15-ton.
Front rolls, diameter.....	50 inches	52 inches	54 inches
Front rolls, width.....	46 inches	48 inches	50 inches
Driving-wheels, diameter.....	70 inches	72 inches	74 inches
Driving-wheels, width.....	20 inches	22 inches	24 inches
Extreme width of machine....	78 inches	79 inches	87 inches
Coal capacity.....	450 pounds	500 pounds	600 pounds
Water capacity of tanks.....	285 gallons	365 gallons	415 gallons




FIG. 247.—THE SPRINGFIELD.




FIG. 247a.—THE RUSSELL ROLLER.

SCARIFIERS.—This is the name given to the tools or mechanical devices used for picking or breaking up of broken-stone roads preparatory to the applying of new metal. In England these tools are extensively employed. There are, broadly speaking, two types, the one fashioned on the form of ploughs and harrows, and the other based on the principle of the rock-drill and ore-stamping mill. Each type is arranged to be operated by attaching to the steam-roller or by a traction engine, and is provided with regulating devices which adjust the depth of penetration. It is considered that a suitably constructed scarifier will perform the work more expeditiously and thoroughly than it can be performed by hand, and at one-half the cost.

Steam-rollers are usually furnished with spikes to fit in sockets on the hind rollers, which are intended to be used for breaking up roads, but they do not usually perform this operation in a satisfactory manner.

The scarifiers employed in the United States are generally of the plough type, and are drawn by four to eight horses. The shoe is usually reversible and adjustable, and provided with a sharp and a blunt point. It is found that in some work the sharp point is the better; in other work the blunt one is more suitable.

When using scarifiers it is essential to have the road thoroughly soaked with water.




FIG. 248.—THE PITTS.




FIG. 249.—THE HARRISBURG.




FIG. 250.—THE AVELING & PORTER.




FIG. 251.—THE COLUMBIAN.

1037. The Tools employed for the Maintenance of Broken-stone Roads are:

Shovels.....	per dozen	\$ 7.00 to \$13.50
Picks.....	" "	10.75 " 22.50
Spades.....	" "	13.25 " 14.50
Hoes.....	" "	13.50
Rakes.....	" "	14.00 to 16.00
Hand rammers.....	each	1.15 " 12.00
Wheelbarrows.....	per dozen	20.00 " 52.50
Brush-hooks.....	" "	17.00
Axes.....	" "	12.00 to 15.50
Scrapers.....	each	8.00 " 12.00
Brooms.....	per dozen	8.50 " 9.00
Stone-sledges.....	per pound	.30
Stone-hammers.....	" "	.45 to .30
Grass-shears.....	each	1.63 " 2.63
Turfing-axes.....	"	1.75
Sod-lifters.....	"	2.75
Straight-edges.....	"	12.00
Drain-cleaners.....	per dozen	9.00 to 11.00
Levels.....	" "	48.00
Lines.....	" "	9.00

1038. Tools Employed in the Construction of Block Pavements—

HAND HAMMERS.—Cobblestone-hammer, Fig. 252, price \$2.50 each.

Square-block hammer, Fig. 253, price each \$2.50.

Brick-hammer, Fig. 254, price each \$1.50.



FIG. 252.



FIG. 253.




FIG. 254.

Pavers' crowbars, per pound 12 cents.

Sand-screens, from \$6 to \$12 each.

Brooms, rattan and wire, \$4 to \$8 per dozen.

HAND RAMMERS.—Hand rammers are of different forms, as shown in Figs. 255 to 259.

Fig. 255, used for cobblestones, is of wood, generally locust, banded with iron, weighs about 40 lbs.; price \$4 to \$7.50.

Fig. 256, used for Belgian blocks, is of wood and steel, weighs about 45 lbs.; price \$9.

Fig. 257, used for granite blocks, is made of iron, with cast-steel face, locust plug, and hickory handles, weighs from 45 to 55 lbs.; price \$9 to \$12.



FIG. 255.



FIG. 256.




FIG. 257.



FIG. 258.



FIG. 259.

Fig. 258, used for brick, is made of wood, shod with cast iron or steel, weighs about 27 lbs.; price \$3.

Fig. 259 is used for miscellaneous work, as tamping in trenches and next to curbs, weighs about 20 lbs.; price \$1.15 to \$3.

1039. Tools Employed for Asphalt Pavements.—The tools used in laying asphalt pavements comprise iron rakes, hand rammers and




FIG. 260.—ASPHALT-RAMMERS.




FIG. 261.—SMOOTHING-IRON.

smoothing-irons, hand rollers, either with or without a fire-pot, and steam rollers, either with or without provision for heating the front roll.

The tamping- and smoothing-irons are shown in Figs. 260 and 261. They are of cast iron, with wood handles. They are used hot, being heated in the portable fire-box shown in Fig. 263. They cost about \$20 per dozen.



FIG. 262.—FIRE-POT ROLLER.



FIG. 263.—PORTABLE FIRE-BOX.

Fig. 262 shows a hand roller, with fire-pot; it is of cast iron, with a smooth-turned face, usually 3 feet in diameter and 3 feet wide. The weight varies from 400 to 1000 lbs., and the price is about 10 cents per pound.

The steam rollers used for compressing and smoothing asphalt and plastic pavements are different in construction, appearance

and weight from those employed for compacting broken stone. The difference is due to the different character of the work re-




FIG. 264.—ASPHALT-ROLLER.




FIG. 265.—ASPHALT-ROLLER.

quired: In compacting broken stone the solidification is mechanical and is effected by the weight or pressure of the machine; in

the case of asphalt and plastic pavements the solidification is effected by chemical action, the roller being only required to bring the constituents into more intimate contact and to produce a smooth surface.

Figs. 264 and 265 illustrate the form of roller used for asphalt and plastic pavements; the weight is usually five tons, but they are made in sizes ranging from three to fifteen tons; the rear drum or roller is usually made with solid heads, so that it can be filled with water or sand and thus increase its weight.

There are several of these rollers on the market to select from; they all agree in the principle of construction, differing only in minor details and dimensions.



FIG. 266.—ASPHALT-MIXING MACHINE.

The principal dimensions of a five-ton roller are as follows :

Front roll or steering-wheel.....	30 to 32 inches diameter
Rear roll or driving-wheel.....	48 " "
Width of front roll.....	40 " "
" " rear ".....	40 " "
Extreme length.....	14 feet
" height.....	.7 to 8 feet
Water capacity.....	80 to 100 gallons
Coal " 	200 pounds

The price for a five-ton roller and heavier is about \$400 per ton.

ASPHALT-MIXERS.—The general form of the machines employed for mixing the materials for asphaltic cement pavements is shown in Fig. 266. The cut shows an engine attached to the machine, but this can be omitted and the power applied by belting, using either spur or bevel gearing to suit location.

The machines are made in various lengths and diameters and with and without steam-jackets.

A steam-jacketed mixer 30 inches diameter and 8 feet long, with a capacity of about 5 cubic yards per hour, costs about \$325.

SURFACE-HEATER FOR REPAIRING ASPHALT PAVEMENTS.—Fig. 267 shows the Perkins surface-heater for repairing asphalt and mastic pavements. It consists of a metal tank mounted on wheels, and at the rear of this a series of burners surrounded by a wire netting packed with asbestos cement. The tank, which has a capacity of about half a barrel, contains gasoline. An air-pump at



FIG. 267.—SURFACE-HEATER.

the head of the tank is used to force the gasoline to the burners. The purpose of the asbestos packing is to conserve and diffuse the heat. Each burner can be turned on and off at will, and when all are in use the tank will keep them running for about five hours. The machine complete weighs about 700 pounds.

The method of operation is to place the heater over the space to be repaired and turn on the heat. In a very short time the

entire surface of the pavement under the hood is softened, so that the top can be removed with a hoe. Only sufficient of the old material is taken off to secure a clean, fresh surface, which, being hot, the new material welds perfectly with it.

CONCRETE-MIXING MACHINES.—Where large quantities of concrete are required, as in the foundations of improved pavements, concrete can be prepared more expeditiously and economically by the use of mechanical mixers and the ingredients will be more thoroughly mixed than by hand. Thorough incorporation of the ingredients is an essential element in the quality of a concrete; when mixed by hand, the incorporation is rarely complete, because it depends upon the proper manipulation of the hoe and shovel. The manipulation, although extremely simple, is rarely properly performed by the ordinary laborer unless constantly watched by the overseer. Several varieties of concrete-mixing machines are in the market. A con-




FIG. 268.—CONCRETE-MIXING MACHINE.

venient portable type is illustrated in Figs. 268 and 269. The capacity of the mixers ranges from five to twenty cubic yards per

hour, depending upon size, regularity with which the materials are supplied, speed, etc. In price they range for machines without engines from \$425 to \$600 ; with engines, from \$950 to \$1250.

For the advantages of concrete, cost, etc., see Articles 457 *et seq.*




FIG. 269.—CONCRETE-MIXING MACHINE.

SAND-DRYERS.—Revolving cylinders connected to a furnace are employed for drying the sand used, for the cushion coat of block pavements, for mixing with asphaltic cement, and for heating the gravel used to fill the joints in block pavements. They are made in various forms and sizes; the one shown in Fig. 270 is 15 feet long and 3 feet in diameter and has a capacity of 5 cubic yards per hour. Price \$600.

Revolving cylinders mounted on wheels, 9 feet long and 2 feet in diameter, cost about \$250.

Rectangular dryers mounted on wheels, 9 feet long, 4 feet wide, and 4 feet deep, cost about \$150.

Pans 6 feet long, 5 feet wide, and 6 inches deep cost about \$20.




FIG. 270.—SAND-DRYER.




FIG. 271.—PORTABLE HEATER FOR ASPHALT OR PAVING-CEMENT.

HEATING-KETTLES are employed for heating the paving-cement used for filling the joints in block pavements, and for heating the asphalt paving mixture for asphalt pavements when it has to be conveyed long distances from the factory. They are made in various forms and sizes. Circular ones are usually about 3 feet 6 inches in diameter and 3 feet 6 inches high, with the melting-chamber 20 to 24 inches deep, and cost about \$60. The rectangular ones range from 4 to 8 feet in length and from 3 to 4 feet in width and from 2 to 4 feet deep at centre of heating-chamber; they range in price from \$75 to \$500. The most approved form is shown in Fig. 271. It is constructed with double bottom, similar




FIG. 272.—SWEEPING MACHINE.

to a double boiler, so that the heating-surface extends the full length and well up on the sides. The melting-chamber is made of soft steel. Capacity about 600 gallons; weight with tongue, double-tree, and neck-yoke 3320 lbs.

1040. Tools for Cleansing—HAND TOOLS.—Brooms for street sweeping are made of steel wire or rattan; their size is generally 16 inches long by 4 inches wide; wire lasts longer than rattan, but is only suitable for block pavements.

Price, steel...	per dozen	\$12.00 to \$18.00
" rattan	" "	8.50 " 9.00

SQUILGEES, or rubber scrapers, are used for cleaning asphalt pavements. Price per dozen \$7.50 to \$9.

MECHANICAL SWEEPERS.—A variety of these machines are in the market, and in various sizes, to be used with one or four horses. Figs. 272 to 276 show a few of the many forms.

The sweeper shown in Fig. 272 is known as the "Pride of New York." The broom is 8 feet 6 inches long, and sweeps a track 7



FIG. 273.—SWEEPING MACHINE.




FIG. 274.—SWEEPING MACHINE.

feet 10 inches; it weighs complete 1900 lbs., and is operated by two horses, and costs about \$400. Smaller machines of the type are also manufactured, to be operated by one horse; the one-horse machine sweeps a track 5 feet 6 inches wide, weighs 1400 lbs., and costs about \$300.

Fig. 273 shows the "Austin Sweeper." It is made of steel throughout. The broom is 8 feet in length and is made of tempered flat steel wires or rattan, and sweeps 6 feet wide. It is operated by two horses.

The sweeper shown in Fig. 274 is known as the "Barnard Castle." It is made in England, and is extensively employed both




FIG. 275.—COMBINED SWEEPER AND SPRINKLER.




FIG. 276.—COMBINED SWEEPER AND SPRINKLER.

in that country and in America. It is manufactured in two sizes, viz., to sweep six feet and seven feet six inches, respectively. The smaller machine is made either with shafts for one horse or with a pole for two horses. The larger machine is made only with a pole for two horses.

COMBINED SWEEPER AND SPRINKLER, Figs. 275 and 276, is designed for cleansing either stone, wood, or asphalt pavements. The machine consists of a circular water-tank with a revolving brush beneath it. A water-pipe or spreader travels in advance of the brush and facilitates its operation.




FIG. 277.—SCRAPING MACHINE.

SCRAPING MACHINES.—For the removal of stiff mud and snow from pavements scraping machines are extensively employed. They generally consist of a number of steel or iron teeth, three to five inches wide, attached to a frame in such manner that they will rise and pass over any fixed obstacle without suffering injury.

Fig. 277 illustrates the Barnard Castle street-scrapers. It is drawn by either one or two horses, and delivers the mud or snow one side in ridges, similar to the sweeping machine. The extent of surface scraped per hour by one of these machines is about 8000 square yards.

Figs. 278 to 280 illustrate two forms of the hand-cart used in cleaning streets by the "patrol," or block system. Price \$25.




FIG. 278.—PATROL-CART.



FIG. 279.—PATROL-CART.



FIG. 280.—PATROL-CART.

Fig. 281 shows the hand scoop used by the street patrol in several cities.




FIG. 281.—HAND SCOOP.

Fig. 282 represents a hand sweeping machine which can be operated by one man. Price \$65.




FIG. 282.—HAND SWEEPER.

DUMP-CARTS.—The cart used to remove street-sweepings is shown in Fig. 283. The body is iron, and the usual dimensions are seven feet long, three feet eleven inches wide, and two feet six inches deep, and capacity one and one half tons.




FIG. 283.—DUMP-CART.

COMBINED SWEEPING AND COLLECTING MACHINE.—In consequence of the increasing use of improved pavements, and with the view of reducing the amount of manual labor required with the usual form of side-sweeping machines, inventors have sought to devise machines which will, instead of merely sweeping the dirt into windrows, collect and pick it up. Three types of "pick-up" machines are now on the market, viz., the "International," the "Universal," and the "Pneumatic."

The International machine (Figs. 284 and 285) consists of an iron collecting-box and a revolving broom. The box has hinged sides and bottom, and is open at the back to receive the dirt brushed up by the broom. The broom is entirely enclosed, and the




FIG. 284.—SWEEPING AND COLLECTING MACHINE.

back part of the casing forms a receptacle for dirt carried over by the broom, and which would otherwise be deposited upon the surface already swept. The operation resembles that of an ordinary carpet-sweeper.

The machine is made of iron and steel, is mounted on four wheels, and is drawn by two horses. The broom is 5 feet long, and revolves on a stationary spindle running through a tube in the

centre of the broom. Medium-coarse bass is used for the broom, and its life is from 18 to 25 days. The collecting-box has a capacity of one cubic yard, but it cannot be filled to its capacity, as the dirt would fall back upon the broom, and, in fact, the dirt has a tendency to form a ridge near the open end of the box, which prevents the entrance of fresh dirt carried up by the broom, so that the box has to be dumped frequently in order to prevent the dirt from dropping back on the street.




FIG. 285.—SWEEPING AND COLLECTING MACHINE.

The machine weighs about 2500 pounds, sweeps within one foot of the curb, and the driver can regulate the pressure of the broom on the pavement or throw it out of gear.

This machine has been successfully used for collecting and piling the dirt swept to the side of the street by an ordinary side-sweeping machine. When used in this way, it is said it saves the cost of three gutter-men, and half the teams for hauling off the sweepings, as the wagons can be loaded much more quickly on account of the piling of the dirt.

The Universal machine (Fig. 286) consists of an iron frame carrying a diagonal revolving broom, 26 inches in diameter, which sweeps the dirt into a windrow. Directly in line with this windrow, and behind the delivering-end of the long broom, is a short broom, 31 inches in diameter and 2 feet wide, which revolves at two and a half times the speed of the main broom, and drives the

material of the windrow into a chamber at the base of an endless-belt elevator, the buckets of which carry up the dirt and dump it into a chute, through which it falls into a covered bin mounted on the frame of the machine. This bin is carried by trunnion bearings at each end, and when full a dump cart is driven alongside the machine, and the bin is tilted by means of a crank-handle and gearing to discharge its load into the cart.



FIG. 286.—SWEEPING AND COLLECTING MACHINE.

The machine weighs about 4000 pounds, and is drawn by three horses; the capacity of the bin is about one cubic yard. If worked steadily without delays, the machine can sweep about a mile of street an hour.

This machine has been successfully tried in New York and Boston, and Mr. H. H. Carter, M. Am. Soc. C. E., Superintendent of Streets, Boston, states that it has demonstrated its ability to do the work at about 45 per cent of the cost under the former method, by which the dirt was swept into windrows by ordinary side-sweeping machines, then swept by hand into piles and shovelled into dump-carts.

The Pneumatic machine works by an air-blast. It consists of an iron box $6\frac{1}{2}$ feet wide, 16 feet long, and $7\frac{1}{2}$ feet from the ground to the top, mounted on four wheels, and equipped with an exhaust fan operated by a 5-horse-power engine, and rectangular brushes or scratchers. It is operated by two men and three horses, and in working order weighs about 6000 pounds.

In operation the scratchers drag on the street and loosen the

dirt, which is carried by the air-blast into the dirt-box. The exhaust steam is used to dampen the dirt, and any dust that may be picked up is carried to the furnace of the boiler. The dirt-box has a capacity of about half a cubic yard, and when full is dumped, leaving the material in convenient piles for shovelling into the dump-carts.

SPRINKLING-CARTS are made in various sizes, and of wood, iron, and steel, and with various devices for controlling and spreading the water.

The sprinkler shown in Fig. 287 is made in the following sizes:

	Price.
1000 gallons.....	\$550.00
750 "	475.00
550 "	425.00
350 "	400.00




FIG. 287.—STREET-SPRINKLER.

Fig. 288 shows a sprinkler made entirely of steel. Three sizes are on the market, viz., 600, 750, and 1000 gallons.

The sprinkler shown in Fig. 288a is styled the "Contractor's Sprinkler." The gear used is called "Contractor's Gear," and differs from an ordinary farm gear in that the reach is dovetailed




FIG. 288.—STREET-SPRINKLER.




FIG. 288a.—CONTRACTOR'S SPRINKLER.

into and firmly bolted and braced to both the front and hind bolsters, coupling the two gears together rigidly. The bolsters being thus kept in line and immovable as compared to each other, the tank rests firmly on them and the bolster-spring cases are not subject to any lateral strain. The front gear is so constructed that the front wheels cut under until they strike the reach, making it possible to turn very short. The tongue is stiff and is held up firmly by sway bars pressing against the under side of the reach and is heavily ironed its entire length with continuous iron. The axles are of



FIG. 288b.—STREET SPRINKLER.

solid steel, firmly clipped to the wood stocks. The tank is made of wood and rests on double coil-bolster springs in cast-iron cases; it can be lifted off the gear and set to one side, thus allowing the use of the gear in other hauling work. This combination is much in favor with contractors. The sizes and prices are as follows:

- No. 46. 750 gallons capacity, 2½" front and 2½" hind axles. . . . \$310.00
 No. 47. 600 gallons capacity, 2½" front and 2½" hind axles. . . . \$255.00

Fig. 288b shows the standard platform spring-gear sprinkling

wagon which has been adopted by the Street Sprinkling Association of New York City. It is made in various sizes as follows:

No. 28 $\frac{1}{2}$.	450 gallons capacity.....	\$315.00
No. 27.	600 gallons capacity.....	325.00
No. 26.	750 gallons capacity.....	365.00

SNOW-PLOUGHS.—The ploughs employed for the removal of snow on country highways are usually made of wood. The general form is shown in Figs. 289 and 290. They are loaded with stone. In light falls, say of 6 inches, one horse is sufficient, but in deeper falls two or more are necessary.

Side View.



Side View.





Plan.

FIG. 289.

SNOW-PLOUGHS.

Plan.

FIG. 290.



Snow-shovels.....	per dozen	\$4.50
Sidewalk-chisels.....	"	\$7.00 to \$17.00

MACHINES FOR MELTING SNOW have been experimented with in various cities—the results have not been entirely satisfactory—the capacity being low and the cost of operating high. A machine using naphtha as fuel was tried in New York City in 1897 for which is claimed a melting-capacity of 60 cubic yards per hour at a cost of \$8.

1041. Tools Employed for Artificial Stone Pavementa.—
TAMPERS (Fig. 291).—Cast iron, with hickory handle; range from
6 × 8 inches to 8 × 10 inches. Price from \$2 to \$2.50 each.



FIG. 291.



FIG. 292.



FIG. 293.




FIG. 295.




FIG. 294.



FIG. 296.



FIG. 297.

QUARTER-ROUND, Fig. 292, is used for rounding corners and sedge. Made of any desired radius. Price from \$1.75 to \$3 each.

JOINTER, Fig. 293, is used for trimming and finishing the joints. Price from \$2 to \$3 each.

CUTTER, Fig. 294, is used to cut the concrete into blocks. Price \$3 each.




FIG. 298.—CAST-IRON CATCH-BASIN.

GUTTER-TOOL, Fig. 295, is used for forming and finishing gutters. Price \$2.50 each.

IMPRINT-ROLLERS.—Figs. 296 and 297 show two designs of rollers for imprinting the surface of artificial stone pavements with grooves, etc. Price ranges from \$8 to \$15 each.

1042. Catch-basins, Sewer Inlets, and Gutter-crossings.—Fig. 298 illustrates a catch-basin made of cast iron, which is introduced as a substitute for the brick chambers now generally used. It is easily put together without skilled labor, and each piece or section is light enough to be handled readily. The front opening is 1 foot high and $4\frac{1}{2}$ feet wide, protected by a wrought-iron grating, so formed that floating refuse will not lodge and close the opening. Price, corner inlet \$125; side inlet \$115.

Fig. 299 shows a catch-basin cover and grating for use as a side



FIG. 299.—SIDE INLET.

inlet. The grate-opening is 12×24 inches. The lid or cover for removing sediment is 24 inches in diameter. Price \$16.



FIG. 300.—GUTTER-GRATING.

Fig. 300 shows a cast-iron gutter-box designed to fit into the hub of a 10-inch sewer-pipe, and is suitable for use on highways,

park walks and streets. Dimensions on top, 9 inches long, 6 inches wide, and 3 inches deep; total height, $4\frac{1}{2}$ inches; weight about 20 pounds. Price \$2.50.

Among the appliances invented for the purpose of closing the street inlets to sewers against the escape of gases, etc., may be mentioned the Hitchcock patent sewer inlet-trap (Fig. 301). The




FIG. 301.—THE HITCHCOCK SEWER INLET-TRAP.




FIG. 302.




FIG. 303.

device explains itself; the purpose is to prevent the escape of gases from the sewer during the cooler seasons, when the air in the sewer is usually warmer than the air in the streets. The lid *A* opens and permits the discharge of water entering the inlet; but at

other times it remains tightly closed by its own weight against the fixed spout *D*. The trap is made of cast iron, and has been successfully used in Springfield, Mass., for about fifteen years. The price is about \$4.50; including the grate and rim, which is 18 inches in diameter and weighs about 175 pounds, the price is \$9.

Figs. 302 and 303 show a cast-iron inlet and manner of setting designed for conducting storm-water from the side ditches of improved suburban or country roads into the under-drains.




FIG. 304.—GUTTER-CROSSING.




FIG. 305.—GUTTER-CROSSING PLATE.

The inlet-head is of cast iron, with a removable grate of wrought iron, which is placed at an angle of 60 degrees, to correspond with the slope of the bank. It is provided with flanges to rest upon a brick or stone foundation, is circular in form and 18 inches in diameter, and can be reduced to fit any desired size of pipe. Price, without reducer, \$6; with reducer, \$7.

Figs. 304 and 305 show two forms of gutter-crossings. Fig. 302

is made in widths from 4 to 26 inches, and from 4 to 10 inches in depth, and in lengths from 3 to 6 feet. Price per foot ranges from \$1.30 for the smaller sizes to \$7.60 for the larger. Fig. 303 is made in sections 30 inches wide and 5 feet long. Price \$12 each.




FIG. 306.—GUTTER-BOXES AND GRATINGS.

Fig. 306 shows cast-iron gutter-boxes and gratings for use with catch-basins. They are made in sizes from 4 feet long, 1 foot wide, and 9 inches deep to 15 inches long, 9 inches wide, and 9 inches deep. Prices range from \$25 for the largest size to \$3.75 for the smallest.

1042a. Street Name-plates.—The custom of using tablets of pottery and stone built into buildings was resorted to by the Romans, both to name streets in large towns, and to direct wayfarers from one place to another. Until the early part of the present century the names of streets and roads were usually painted or carved on boards, and sometimes the names were inscribed on stone, and in one instance on slate. Regarding the durability of the latter, Mr. Francis Smythe, C.E., states that he saw in Wales a direction notice written in slate which was stated to have been in

existence for over a century, and it showed but little ill effect from the action of the weather.

It was not until about the third or fourth decade of the present century that cast iron was known to be used for this purpose, having been previously introduced as mile-posts. At the present time in Europe probably more name-plates of this metal are used than any other kind, although many devices have been introduced. Among these may be mentioned enamelled iron plates; plates made of an alloy containing a large proportion of zinc; embossed or raised letters on sheet-iron and zinc plates, or letters cut out of the same metals; china or glass letters fastened on to wood or metal plates; plates made entirely of glass, glazed terra-cotta, or china; metal plates let into the surface of foot-paths; glass slips fastened into the lanterns of public lamps; and metal plates fastened to the lamp-columns or to independent columns.

Cast-iron name-plates have hitherto been most in use on account of their cheapness and durability, the objections to them being their brittleness and consequent liability to fracture, scaling of the paint, and corrosion.

Enamelled-iron name plates are extensively used. They are neat in appearance, and can be read from quite a distance. The colors generally employed are white for the letters and dark blue for the background. The letters are usually $2\frac{1}{4}$ inches in height. Enamelled signs deteriorate when subjected to frequent changes of temperature. The difference in expansion between the enamel and the backing causes the former to crack and scale, and when the backing commences to oxidize the lettering is quickly obliterated. Many manufacturers claim that their plates are proof against this defect, but experience shows that all are liable to this fault.

Wood is extensively used for name-plates. Oak is preferred. It should be well braced across the grain to prevent warping. With gilt letters on a sanded black surface, wood makes a sign satisfactory in appearance and durability, and not very expensive.

As a rule street name-plates are made too small and not sufficiently prominent. An extra-sized letter ($2\frac{1}{2}$ to 4 inches) does not add a very large proportion to the cost, as the time of fixing, which is a considerable portion of the expense, would not take any

longer. A bold moulding round the plate increases its prominence.

Various methods have been suggested for placing the names in the sidewalk. Among those tried may be mentioned the cutting of the name in the top of the curbstone and coloring the letters black. Where concrete is used for the sidewalk, wooden pattern letters 1 inch deep are bedded in the concrete, which, when the concrete is sufficiently set, are removed and the space filled with colored cement mortar or letters made of brass or composition metal.

The streets of St. Louis are posted with enamelled signs having clear white letters on a dark blue ground. The plates for these signs are $4\frac{1}{2}$ inches wide, from 16 to 26 inches long, and are made of No. 18 wrought iron, United States standard gauge. At the middle of the sides and ends and three-eighths of an inch from the edge of the plate are the four screw-holes, No. 9 brass screws being used. Where posts are used they are of cypress or cedar, 4×4 inches in section and 12 feet long. The signs are screwed on seven-eighths-inch clear pine kiln-dried lumber, painted with one coat of asphaltic paint. The letters on the signs are half block and three inches high. Numbered streets from First Street to Ninth Street, inclusive, are spelled out in full, but from 10th Street up figures are used, followed by "nd," "rd," or "th," as may be called for. The word "Street" is spelled out in full on the numbered streets. On named streets the abbreviation "St." is used after the name. Avenue is abbreviated to "Av."; Boulevard to "Bl."; Place to "Pl."; and "Road" to "Rd." No periods are used except after abbreviations. The enamel of the ground color on the plates is a dark, glossy blue, free from lumps and blisters, and guaranteed not to exude white powder when exposed to the atmosphere. The lettering is a clear white, free from dark spots. The back of the plate is thoroughly coated with enamel, and before acceptance the plates are subjected to an impact and bending test, any sign of flaking or scaling being rejected. The cost was $36\frac{1}{2}$ cents each, delivered.

1042b. Direction Indicators should be placed at junctions and crossing of roads for the convenience of travellers. They should be substantially made of an imperishable material, bold and neat in

design, with strong self-bracing bases. The lettering should be bold and legible, the direction arms easily fixed at any angle without the necessity for special castings or complicated fastenings.

1042c. The Viagraph (Fig. 307), invented by Mr. I. Brown, is an instrument for ascertaining and registering the inequalities in road-surfaces, so that any given road may be compared with another, or with itself at different times. In principle the viagraph is a straight-edge applied continuously to the road-surface along which it may be drawn, and conveying an apparatus for, first, recording on paper a profile of the road-surface; and, secondly, indicating a numerical index of the unevenness of the surface.

Fig. 307 gives a view of the instrument with the cover removed. The frame is in form like a sled, with straight runners on which are




Fig. 307.

mounted the working parts. The lever *T*, pivoted to the main frame at *H*, carries on its free end a toothed wheel, the upper part of which is seen at *V*. While the main frame in being drawn along the road preserves a sufficiently even line, the road-wheel *V* rises and falls over all the unevennesses of the surface, carrying with it the lever *T*, and thereby transmitting its movements by means of the link and lever *S* to the pencil *P* (raised abnormally in the figure) and recording them on the roll of paper drawn from the stock roll *C* and wound upon the receiving-drum *B*. The profile thus made is of full size, vertically, and $\frac{1}{8}$ inch in to 1 foot horizontally. The second pencil seen below *P* draws a datum line with which that drawn by pencil *P* would coincide if the road were perfectly even. The sum of the vertical registration of the pencil *P* is called "the numerical index of unevenness," and is recorded automatically by the decimal counter *W* operated by a cord attached to the free end of the lever *T* and passing once around a double-grooved pulley *X*.

CHAPTER XXIV.

MISCELLANEOUS NOTES.

1043. Comparison of European and American Methods and Prices.—Comparison is frequently made between the methods and cost of constructing and maintaining roads and pavements in the United States and Europe. In making such comparisons it must be remembered (1) that comparisons are of little value unless based upon similar conditions; (2) that the cost of materials and labor in Europe is generally much less than in America; (3) that the methods and cost will vary very much in different parts of the same country; (4) that the cost of constructing and maintaining roads and pavements depends upon many diverse elements, due to local conditions, customs, and habits, as well as upon the quality of the materials, distance of transport, skill of the workmen, character of the traffic, climatic conditions, etc.

Although it is evident that comparisons based upon such variable elements as are enumerated above must be imperfect, nevertheless intelligent observation and comparison of the methods and cost of construction and maintenance, both at home and abroad, will materially aid in avoiding unnecessary expenditure in experiments, and will promote economy and efficiency.

Table No. LXXXVIII shows the wages paid in several European localities.

TABLE LXXXVIII.

Kind of Labor.	London.	Berlin.	Paris.	England.	Belgium.	France.
Unskilled.....	\$0.60	\$0.48 to \$0.70	\$0.80	\$1.55 to \$1.75	\$0.06 to	\$0.58
Foreman.....	\$1.00 to \$2.00	\$0.83	\$0.90 to \$1.20	\$1.00	\$0.07*	\$20.00†
Favers.....	\$1.75	\$1.50	\$1.30			
Sweepers.....	\$0.80	\$0.71	\$0.80	\$0.80 to \$0.90		
Steam-roller drivers.	\$1.50		\$0.90 to \$1.10	\$0.80 to \$1.44		
Horse and cart....	\$2.00 to \$2.50	\$1.60 to \$1.80		\$1.75 to \$2.50		\$1.55
Masons.....	\$1.75	\$1.50	\$1.60	\$1.25		

* Per hour.

† Per month.

In European cities 10 hours constitute a day's labor.

Wages in the United States range between the following limits, and a day's work varies from 8 to 10 hours:

Foremen, \$3 to \$5.

Sub-foremen, \$1.75 to \$2.50.

Unskilled, \$1.25 to \$1.75.

Pavers, \$2.50 to \$4.50.

Masons, \$3 to \$4.50.

Steam-roller drivers, \$3 to \$4.50.

Single horse, cart, and driver, \$2.50 to \$3.50.

Double horse, wagon, and driver, \$3 to \$6.

Drillers, \$2 to \$3.

Sweepers, \$1.25 to \$2.

1043a. Statistics of Roads in the United States.—The following statistics concerning the weight of load for horses, cost of haulage, and length of haul from farms to markets are deduced from the investigation conducted by the office of Road Inquiry of the Department of Agriculture.

AVERAGE WEIGHT OF LOAD FOR TWO HORSES.

Eastern states.....	2216 pounds
Northern states.....	2186 "
Middle Southern states.....	1869 "
Cotton states.....	1897 "
Prairie states.....	2409 "
Pacific coast states.....	2197 "
Average for the United States.....	2002 "

AVERAGE COST OF HAULAGE PER TON PER MILE.

Eastern states.....	32 cents
Northern states.....	27 "
Middle Southern states.....	31 "
Cotton states.....	25 "
Prairie states.....	23 "
Pacific coast states.....	22 "
Average for the United States.....	25 "

**AVERAGE LENGTH OF HAUL IN MILES FROM FARMS TO
MARKET OR SHIPPING POINTS.**

Eastern states.....	5.9 miles
Northern states.....	6.9 "
Middle states.....	8.8 "
Cotton states.....	12.6 "
Prairie states....	8.8 "
Pacific coast states.....	23.3 "
Average for United States.....	12.1 "

**AVERAGE TOTAL COST PER TON FOR THE WHOLE LENGTH OF
HAUL.**

Eastern states.....	\$1.89
Northern states.....	1.86
Middle Southern states	2.72
Cotton states.....	3.05
Prairie states.....	1.94
Pacific coast states	5.12
Average for the United States.....	3.02

In consequence of the great attention which highway improvement is now receiving and the agitation for the construction of light railways connecting the markets and shipping points with the farms, accurate and reliable information as to the cost of haulage over country roads is in demand, and the above figures, if trustworthy, will be received with much satisfaction.

The accuracy of the figures cannot, however, be tested without a knowledge of the condition of the roads at the time the observations were made. If they were earth in a dry and hard condition, the cost seems high; but if they were earth covered with mud and ruts or dry sand they are not excessive. See also Table I, page 3.

1043b. Sprinkling Oil on Roads.—Crude petroleum has recently been used on country and park roads for the purpose of (1) reducing or abating the dust, (2) securing a non-absorbent surface, which will turn off rain-water, and (3) a dark-colored road-surface, which will be more pleasing to the eye than the ordinary light color.

The Department of Parks of the city of Boston has experimented with sprinkling the driveways with crude oil to lay the dust. The amount of oil used was 0.6 gallon per lineal foot of roadway 40 feet wide. The roadway was hard and smooth, and the effect of the oil seemed to be a slight disintegration of the surface or loosening

of the bond of the macadam. The small stones thus loosened were soon crushed into powder, and formed a layer on the surface at least $\frac{1}{4}$ inch thick, sufficiently permeated with oil to prevent it from being blown by any but strong winds.

During a period of two months on that part of the roadway subjected to dust the treatment resulted in the abatement of the dust. One disadvantage of the use of oil for park work is its disagreeable odor. The experiment was not considered so fruitful of good results as to induce the department to continue it. There is no question, however, but that it will effectually lay the dust. Superintendent Pettigrew suggests that on a hard macadam road it would be a good plan to spread a layer of loamy sand to receive the oil in order to prevent the disintegration of the surface of the macadam.

The experiment of sprinkling with oil the roads in Los Angeles Co., Cal., and in Jacksonville Fla., is considered a success.

In applying the oil it must be thoroughly mixed with the dust. If it is merely sprinkled on the surface, only the top layer of dust will be impregnated; the wheels of vehicles will break up the cake thus formed, exposing the dust below, and the road will be more disagreeable than before. Oil applied to a hard road to prevent the formation of dust will remain on the surface and be very disagreeable.

A process for applying the oil has been patented by F. W. Matern of Los Angeles, Cal., in which there is mixed a high-test, heavy oil with maltha. This compound is spread upon the road in parallel lines about six inches apart, in sufficient quantity to saturate the dry dust, and is then thoroughly incorporated by the use of rakes. Seven and a half gallons are applied to a square rod if the dust is half an inch thick. Water is then sprinkled upon the surface and the road rolled; it is then ready for travel.

The machine for distributing the oil consists of a tank six feet long, mounted on two wheels, and in use is attached to the rear of an oil-tank wagon. The oil is discharged through tubes, six inches apart, controlled by valves which are operated by a lever. The machine is furnished with hoes, one set of which form the furrows in which the oil flows, and the other set cover it with the dust. A set of teeth are also attached which incorporate the earth and oil.

NOTE.—For other experiments see Report Massachusetts Highway Commission, 1898, and Sixth Annual Report of the Commissioner of Public Roads of New Jersey.

1044. Pavements and Horseshoes.—A horse's hoof shod with a heavy iron shoe strikes a blow resembling that struck by a hammer in the hand of man, but with considerably more energy. When the shoes are furnished with sharp toe-pieces and heel-calks, as in the prevailing form, the combined effect of a cutting chisel and hammer is produced. This form of shoe is rendered necessary to obtain foothold on the rough and ill-conditioned pavements generally found in use, but on smooth improved pavements it is not required. Indeed, its use produces exceedingly destructive effects. Broken-stone pavements suffer the most; the surface is excavated and the stones displaced. Block pavements also suffer considerably; the blocks are chipped and rounded until they assume the form of boulders. Wood and asphalt probably suffer the least, unless the blows fall successively in the same place.

The European pavements are not subjected to the destroying effect of this form of shoe. There smooth, flat shoes of light weight are used, and in many localities the form of the shoe is regulated by law.

Flat shoes and wide tires have a large effect in the conservation of pavements, and where improved pavements have been introduced the imposition of a tax would be warranted to hasten their use.

1045. Annual Cost of Structures.—The annual cost of any structure, or the annual payments required to maintain the structure in perpetuity, is composed of three elements:

(1) *Interest on First Cost.*—If the structure is built with borrowed money, interest must be paid as a matter of course and charged against the structure. If it be not borrowed, but furnished by the owner, the case is not essentially different. He takes it from some other investment which would pay interest, and is a loser if the new structure does not make him the same return. Any structure which cannot bear this charge of interest, is a bad investment. But if the structure be neither built nor bought, but inherited by its present owner, its first cost to him is what he could sell it for; if it have no market value, its cost to him is nothing, and he may omit the interest charge entirely.

The general principle is that the cost of any structure is the amount of capital which its owner voluntarily keeps in it, and that on this amount the interest must be charged against the structure.

(2) *Annual Repairs*.—Under this head is included every expense of preserving the property, such as ordinary repairs, watchmen, insurance, etc. If by these means the property is maintained in its original condition, "as good as new," these two elements embrace the whole annual cost. But there are many cases in which this is not true. In spite of the annual repairs, the structure after a time wears out and must be replaced either in whole or in part by a new one. If it be a bridge, it has to be rebuilt; if it be a pavement or a set of rails, they have to be taken up and replaced by new ones. This makes a further payment necessary, viz.:

(3) *Annual Payments to the Renewal Fund*.—By this is meant the proportion of the sum finally needed to renew the structure chargeable to each year. If this fund be raised all at once when it is actually needed, the amount chargeable to each year is the total sum divided by the number of years in the life of the structure. But the amount of each contribution will be made very much smaller if it is actually paid each year and each payment improved at compound interest after the manner of an ordinary sinking fund for the extinction of bonds. This method distributes the burden equally over the whole term and makes it much lighter than is possible in any other way. Taking it for granted that this is the plan adopted, the formula to ascertain the value of these elements will be as follows:

Let x = total annual cost, or the annual payments needed to maintain the structure in perpetuity;

a = first cost:

b = value of old materials when no longer fit for use in the structure, and also the value of so much of the structure as needs no renewal;

c = cost of annual repairs;

n = number of years the structure lasts before renewal;

r = rate of interest on money;

m = amount or final value of an annuity of \$1.00 com-

$$\text{pounded each year for } n \text{ years,} = \frac{(1+r)^n - 1}{r};$$

The final cost of renewal = $a - b$. If the renewals should exceed first cost, b will equal the excess, and the total cost of renewal will = $a + b$.

To find the annual payment to the renewal fund, call it p .
Then will $1 : m :: p : a - b$.

$$\text{Whence } p = \frac{a - b}{m} = (a - b) \cdot \frac{r}{(1 + r)^n - 1}.$$

The annual interest charge will be $= ar$.

The total annual cost of the structure will therefore be

$$x = ar + c + (a - b) \cdot \frac{r}{(1 + r)^n - 1}.$$

The factor $(1 + r)^n$ is the amount of one dollar at compound interest for n years and is given in Table LXXXIX.

The value of the whole expression $\frac{r}{(1 + r)^n - 1}$ is given in Table XC.

As an example of the application of the formula, let the problem be to determine the relative economy of a wooden and an iron bridge for a given place. Let the length of the bridge be 500 feet, or 4 spans of 125 feet each, and let the other data be as follows:

For the wooden bridge

a = first cost = \$25 per foot. = \$12,500;

b = value of iron when the bridge is worn out; = say \$2 per foot. = \$1,000;

c = cost of annual repairs = \$1200;

n = life of the bridge = 10 years;

r = 6 per cent = $\frac{6}{100}$.

Then will $x = \$750 + \$1200 + (\$12,500 \times .0759) = \2822.85 .

For the iron bridge

a = first cost = \$50 per foot. = \$25,000.;

b = value of old materials = say \$10 per foot. = \$5000;

c = annual repairs = say \$500;

n = life of bridge = say 60 years;

r = 6 per cent = $\frac{6}{100}$.

Then will $x = \$1500 + \$500 + (\$20,000 \times .0019) = \2038 .

Showing a saving of \$784 per annum by using the iron bridge.

TABLE LXXXIX.

VALUE OF $(1 + r)^n$, OR THE AMOUNT OF \$1 AT COMPOUND INTEREST FOR A TERM OF YEARS.

Interest 2 per cent.

Years.	Value.	Years.	Value.	Years.	Value.
1	\$1.020	21	\$1.516	41	\$2.252
2	1.040	22	1.546	42	2.297
3	1.061	23	1.577	43	2.343
4	1.082	24	1.608	44	2.390
5	1.104	25	1.641	45	2.438
6	1.126	26	1.673	46	2.487
7	1.149	27	1.707	47	2.536
8	1.172	28	1.741	48	2.587
9	1.195	29	1.776	49	2.639
10	1.219	30	1.811	50	2.692
11	1.243	31	1.848	55	2.973
12	1.268	32	1.885	60	3.281
13	1.294	33	1.923	65	3.623
14	1.319	34	1.961	70	4.000
15	1.346	35	2.000	75	4.416
16	1.373	36	2.040	80	4.875
17	1.400	37	2.081	85	5.383
18	1.428	38	2.122	90	5.943
19	1.457	39	2.165	95	6.562
20	1.486	40	2.208	100	7.245

Interest 3 per cent.

1	\$1.030	21	\$1.860	41	\$3.860
2	1.061	22	1.916	42	3.461
3	1.093	23	1.974	43	3.565
4	1.126	24	2.033	44	3.671
5	1.159	25	2.094	45	3.782
6	1.194	26	2.157	46	3.895
7	1.230	27	2.221	47	4.012
8	1.267	28	2.288	48	4.132
9	1.305	29	2.357	49	4.256
10	1.344	30	2.427	50	4.384
11	1.384	31	2.500	55	5.062
12	1.426	32	2.575	60	5.892
13	1.469	33	2.652	65	6.830
14	1.513	34	2.732	70	7.918
15	1.558	35	2.814	75	9.179
16	1.605	36	2.898	80	10.641
17	1.653	37	2.985	85	12.326
18	1.702	38	3.075	90	14.300
19	1.754	39	3.167	95	16.578
20	1.806	40	3.262	100	19.319

VALUE OF $(1+r)^n$. (Continued.)Interest $3\frac{1}{2}$ per cent.

Years.	Value.	Years.	Value.	Years.	Value.
1	\$1.085	21	\$2.059	41	\$4.098
2	1.071	22	2.132	42	4.241
3	1.109	23	2.206	43	4.390
4	1.148	24	2.288	44	4.543
5	1.188	25	2.368	45	4.702
6	1.229	26	2.446	46	4.867
7	1.272	27	2.532	47	5.037
8	1.317	28	2.620	48	5.214
9	1.363	29	2.712	49	5.396
10	1.411	30	2.807	50	5.585
11	1.460	31	2.905	55	6.633
12	1.511	32	3.007	60	7.878
13	1.564	33	3.112	65	9.357
14	1.619	34	3.221	70	11.118
15	1.675	35	3.334	75	13.199
16	1.734	36	3.450	80	15.676
17	1.795	37	3.571	85	18.618
18	1.857	38	3.696	90	22.112
19	1.923	39	3.825	95	26.262
20	1.990	40	3.959	100	31.191

Interest 4 per cent.

Years.	Value.	Years.	Value.	Years.	Value.
1	\$1.040	21	\$2.279	41	\$4.993
2	1.082	22	2.370	42	5.193
3	1.125	23	2.465	43	5.400
4	1.170	24	2.563	44	5.617
5	1.217	25	2.666	45	5.841
6	1.265	26	2.772	46	6.075
7	1.316	27	2.888	47	6.318
8	1.369	28	2.999	48	6.571
9	1.423	29	3.119	49	6.833
10	1.480	30	3.243	50	7.107
11	1.539	31	3.378	55	8.646
12	1.601	32	3.508	60	10.520
13	1.665	33	3.643	65	12.799
14	1.732	34	3.794	70	15.572
15	1.801	35	3.946	75	18.945
16	1.873	36	4.104	80	23.050
17	1.948	37	4.268	85	28.044
18	2.026	38	4.439	90	34.119
19	2.107	39	4.616	95	41.511
20	2.191	40	4.801	100	50.505

VALUE OF $(1+r)^n$. (Continued.)*Interest 4½ per cent.*

Years.	Value.	Years.	Value.	Years.	Value.
1	\$1.045	21	\$2.520	41	\$6.073
2	1.092	22	2.634	42	6.352
3	1.141	23	2.752	43	6.637
4	1.193	24	2.876	44	6.926
5	1.246	25	3.005	45	7.218
6	1.302	26	3.141	46	7.574
7	1.361	27	3.282	47	7.915
8	1.422	28	3.430	48	8.271
9	1.486	29	3.584	49	8.644
10	1.553	30	3.745	50	9.033
11	1.623	31	3.914	55	11.256
12	1.696	32	4.090	60	14.027
13	1.772	33	4.274	65	17.481
14	1.852	34	4.466	70	21.784
15	1.935	35	4.667	75	27.147
16	2.022	36	4.877	80	33.880
17	2.112	37	5.097	85	42.158
18	2.208	38	5.326	90	52.537
19	2.308	39	5.566	95	65.471
20	2.412	40	5.816	100	81.589

Interest 5 per cent.

1	\$1.050	21	\$2.786	41	\$7.392
2	1.103	22	2.925	42	7.762
3	1.158	23	3.072	43	8.150
4	1.216	24	3.225	44	8.557
5	1.276	25	3.386	45	8.985
6	1.340	26	3.556	46	9.434
7	1.407	27	3.733	47	9.906
8	1.477	28	3.920	48	10.401
9	1.551	29	4.116	49	10.921
10	1.629	30	4.322	50	11.467
11	1.710	31	4.538	55	14.636
12	1.796	32	4.765	60	18.679
13	1.886	33	5.003	65	23.840
14	1.980	34	5.253	70	30.426
15	2.079	35	5.516	75	38.833
16	2.183	36	5.792	80	49.661
17	2.292	37	6.081	85	63.254
18	2.407	38	6.385	90	80.780
19	2.527	39	6.705	95	103.035
20	2.653	40	7.040	100	131.501

VALUE OF $(1 + r)^n$. (Continued.)

Interest 6 per cent.

Years.	Value.	Years.	Value.	Years.	Value.
1	\$1.060	21	\$3.400	41	\$10.908
2	1.124	22	3.604	42	11.557
3	1.191	23	3.820	43	12.250
4	1.262	24	4.049	44	12.985
5	1.338	25	4.292	45	13.765
6	1.419	26	4.549	46	14.590
7	1.504	27	4.822	47	15.466
8	1.594	28	5.112	48	16.394
9	1.689	29	5.418	49	17.378
10	1.791	30	5.743	50	18.420
11	1.898	31	6.088	55	24.650
12	2.012	32	6.458	60	32.988
13	2.133	33	6.841	65	44.145
14	2.261	34	7.251	70	59.076
15	2.397	35	7.686	75	79.057
16	2.540	36	8.147	80	105.796
17	2.698	37	8.636	85	141.579
18	2.854	38	9.154	90	189.465
19	3.026	39	9.704	95	253.546
20	3.207	40	10.286	100	339.303

TABLE XC.

VALUE OF $\frac{r}{(1 + r)^n - 1}$, OR THE SINKING FUND THAT WITH COMPOUND INTEREST WILL AMOUNT TO ONE DOLLAR AT THE END OF A TERM OF YEARS.

Interest 3 per cent.

Years.	Value.	Years.	Value.	Years.	Value.
1	\$1.0000	21	\$0.0349	41	\$0.0127
2	.4926	22	.0327	42	.0123
3	.8235	23	.0308	43	.0117
4	.2390	24	.0290	44	.0112
5	.1884	25	.0274	45	.0108
6	.1546	26	.0259	46	.0104
7	.1305	27	.0246	47	.0100
8	.1125	28	.0233	48	.0096
9	.0984	29	.0221	49	.0092
10	.0872	30	.0210	50	.0089
11	.0781	31	.0200	55	.0073
12	.0705	32	.0190	60	.0061
13	.0640	33	.0182	65	.0051
14	.0585	34	.0173	70	.0043
15	.0538	35	.0165	75	.0037
16	.0496	36	.0158	80	.0031
17	.0460	37	.0151	85	.0026
18	.0427	38	.0145	90	.0023
19	.0398	39	.0138	95	.0019
20	.0372	40	.0133	100	.0016

HIGHWAY CONSTRUCTION.

VALUE OF $\frac{r}{(1+r)^n - 1}$. (Continued.)

Interest $3\frac{1}{2}$ per cent.

Years.	Value.	Years.	Value.	Years.	Value.
1	\$1.0000	21	\$0.0880	41	\$0.0118
2	.4914	22	.0809	42	.0108
3	.3219	23	.0290	43	.0103
4	.2373	24	.0273	44	.0099
5	.1865	25	.0257	45	.0095
6	.1527	26	.0242	46	.0091
7	.1285	27	.0229	47	.0087
8	.1105	28	.0216	48	.0083
9	.0964	29	.0204	49	.0080
10	.0852	30	.0194	50	.0076
11	.0761	31	.0184	55	.0062
12	.0685	32	.0174	60	.0051
13	.0621	33	.0166	65	.0042
14	.0566	34	.0158	70	.0035
15	.0518	35	.0150	75	.0029
16	.0477	36	.0143	80	.0024
17	.0440	37	.0136	85	.0020
18	.0406	38	.0130	90	.0017
19	.0379	39	.0124	95	.0014
20	.0354	40	.0118	100	.0012

Interest 4 per cent.

1	\$1.0000	21	\$0.0813	41	\$0.0100
2	.4902	22	.0292	42	.0095
3	.3204	23	.0278	43	.0091
4	.2255	24	.0256	44	.0087
5	.1846	25	.0240	45	.0083
6	.1506	26	.0226	46	.0079
7	.1266	27	.0212	47	.0075
8	.1085	28	.0200	48	.0072
9	.0945	29	.0189	49	.0069
10	.0833	30	.0178	50	.0066
11	.0742	31	.0169	55	.0052
12	.0666	32	.0160	60	.0042
13	.0604	33	.0151	65	.0034
14	.0547	34	.0143	70	.0027
15	.0499	35	.0136	75	.0022
16	.0458	36	.0129	80	.0018
17	.0422	37	.0122	85	.0015
18	.0390	38	.0116	90	.0012
19	.0361	39	.0111	95	.0010
20	.0336	40	.0105	100	.0008

VALUE OF $\frac{r}{(1+r)^n - 1}$. (Continued.)

Interest 5 per cent.

Years.	Value.	Years.	Value.	Years.	Value.
1	\$1.0000	21	\$0.0280	41	\$0.0078
2	.4878	22	.0260	42	.0074
3	.3172	23	.0241	43	.0070
4	.2320	24	.0225	44	.0066
5	.1810	25	.0210	45	.0063
6	.1470	26	.0196	46	.0059
7	.1228	27	.0183	47	.0056
8	.1047	28	.0171	48	.0053
9	.0907	29	.0160	49	.0050
10	.0795	30	.0151	50	.0048
11	.0704	31	.0141	55	.0037
12	.0628	32	.0133	60	.0028
13	.0565	33	.0125	65	.0022
14	.0510	34	.0118	70	.0017
15	.0463	35	.0111	75	.0013
16	.0423	36	.0104	80	.0010
17	.0387	37	.0098	85	.0008
18	.0355	38	.0093	90	.0006
19	.0327	39	.0088	95	.0005
20	.0302	40	.0083	100	.0004

Interest 6 per cent.

1	\$1.0000	21	\$0.0250	41	\$0.0061
2	.4854	22	.0230	42	.0057
3	.3141	23	.0213	43	.0053
4	.2286	24	.0197	44	.0050
5	.1774	25	.0182	45	.0047
6	.1434	26	.0169	46	.0044
7	.1191	27	.0157	47	.0041
8	.1010	28	.0146	48	.0039
9	.0870	29	.0136	49	.0037
10	.0759	30	.0126	50	.0034
11	.0668	31	.0118	55	.0025
12	.0598	32	.0110	60	.0019
13	.0530	33	.0103	65	.0014
14	.0476	34	.0096	70	.0010
15	.0430	35	.0090	75	.0008
16	.0390	36	.0084	80	.0006
17	.0354	37	.0079	85	.0004
18	.0324	38	.0074	90	.0003
19	.0296	39	.0069	95	.0002
20	.0272	40	.0065	100	.0002

1046. Sinking Funds.—Table XC may also be used for ascertaining the annual payment required to be made to a sinking fund which invested at compound interest will yield at the end of a given period a sum of money sufficient to pay off a bond issue or other debt.

1047. Annual Cost of Pavements.—The annual cost of pavements may be ascertained by the same formula as given in Art. 1045, viz.,

$$x = ar + c + (a - b) \cdot \frac{r}{(1+r)^n - 1},$$

in which a = first cost;

r = rate of annual interest;

c = cost of annual repairs;

b = value of old material;

n = estimated life;

x = total annual cost.

The value of the expression $\frac{r}{(1+r)^n - 1}$ is given in Table XC.

As an example of the application of the formula let

$$a = \$2.00;$$

$$r = 3\%;$$

$$c = \$0.03;$$

$$b = \$0.50;$$

$$n = 15 \text{ years.}$$

$$\begin{aligned} \text{Then will } x &= (\$2.00 \times .03) = .0600 + .03 + (\$1.50 \times .0538) \\ &= .0807 = \$0.1707 \text{ cents per annum.} \end{aligned}$$

The economic limit of repairs may also be ascertained by the application of the above formula.

1048. Relative Economy of Materials.—The material which has cost the most is not always the best, nor is that which has cost the least the cheapest; the one which is truly the cheapest is the one which makes the most profitable returns in proportion to the amount which has been expended upon it. To make the most

economical selection from several samples of the same material the relative cheapness and quality of each must be ascertained.

The relative cheapness is found by dividing the lowest price by each of the others in succession and subtracting the quotient from 100 per cent taken as the standard.

The quality must first be determined by the special tests adapted to the material under consideration. The relative quality of each sample is then ascertained by dividing the quality of each by the maximum quality so found and subtracting the quotient from 100 per cent taken as the standard; then the relative value is found by multiplying the two ratios, price and quality, and the highest product will indicate the most economical. For example, three prices are submitted for a certain material which, examined in the manner described, shows the following results:

Price.	Relative Cheapness 100.00. Ratio.	Relative Quality 100.00. Ratio.	Relative Economy = quality \times cheapness.
\$2.00	100.00	65.41	65.41
2.40	99.18	100.00	99.18
2.80	99.29	86.25	85.60

APPENDIX.

I.

NAMING AND NUMBERING COUNTRY ROADS AND HOUSES.

1. THE naming of country roads and the numbering of country houses has not generally received that recognition which its importance demands; consequently commercial and social intercourse in rural sections is rendered extremely inconvenient. The indifference of rural communities on this subject has been due to several causes, but mainly to the want of a system which was applicable to all localities, and which should, without serious complication, be sufficiently elastic to cover the changes wrought by improvement. Such a system is now available. It is known as the "*Ten-block Method*," devised by Mr. A. L. Bancroft, and now in successful use in Contra Costa County, Cal.

2. *The Ten-block System.*—In this system the roads are first named in as long lengths as possible (names of towns or living residents are not used,—some landscape feature or historical association suggesting the name) and then carefully measured. The point from which the measurements of all roads within the county are commenced is the centre of the roadway directly in front of the main entrance to the county court-house; each mile is divided into 10 blocks of 528 feet, and each block is numbered, the even numbers being placed on the right-hand side and the odd ones on the left-hand side going from the court-house; the block numbers are conspicuously marked on the fences or on posts specially placed for the purpose; a line indicating the division of the block is placed between the numbers thus, 52 | 50; the end of each mile is indicated by an X painted inside a circle, the half-mile is marked by a V in a semicircle; the houses in each block have the same numbers as the block on which they stand, but are distinguished by a letter of the alphabet affixed thereto, as 3A, 3B, to 3Z; thus when new

houses are built in the block they can have numbers assigned to them without interfering with those already numbered; the number of roads entering or intersecting a given road makes no difference with the length or number of the block; in passing through villages or towns the names and numbers already in use are left unchanged, but outside the town limits the ten-block system is resumed, the first house having a number depending upon its distance from the court-house. In this way, although a road passes through a dozen towns, the numbers on each side of the town indicate the true position of the house and its distance from the commencement of the road. The distance from the court-house or between any two given houses is quickly ascertained by dividing half the even numbers by 10; for instances, if a house is numbered 506, its distance from the county court-house is $\frac{506}{2} = \frac{253}{10} = 25\frac{3}{10}$ miles, or the distance of the same house beyond another house numbered 315 is equal to $\frac{506}{2} - \frac{315}{2} = \frac{253 - 157}{10} = 9\frac{7}{10}$ miles, and on the opposite side of the road.

3. The data necessary to put this system in operation are contained in the following ordinance of the Board of Supervisors of the county of Contra Costa, Cal.:

An ordinance of the Board of Supervisors of the county of Contra Costa, State of California, naming the several public highways of the county and authorizing the use of certain other names and designations for private or local roads in use in said county; also providing for the erection and due preservation of suitable guide-boards at all road crossings and intersections, and at other necessary or suitable points upon such roads as have been properly measured or divided into blocks, according to the "Ten-block System," also providing for the affixing and maintaining by residents of house or farm-entrance numbers, based thereon, for all country residences upon such measured roads; also providing for an official road map of the county, and other records.

The Board of Supervisors of the County of Contra Costa do ordain as follows:

SECTION 1. All public highways which have been duly accepted

by the county shall hereafter be known and designated by the names prescribed in this ordinance, according to the designation and descriptions laid down in Section 29.

SEC. 2. All private or local roads designated in Sec. 29 of this ordinance shall in all official reference thereto be hereafter known by the names herein prescribed, and the public use and recognition of such designation is hereby recommended.

SEC. 3. Whenever the owner or owners of any strip or strips of land within the county shall represent to the Board of Supervisors their purpose and wish to devote the same to use as a public or private road, or as a right of way for access to any dwelling, and shall offer or accept a name for the same, approved by the road committee, to be appointed or confirmed by the Board of Supervisors, and shall comply with the provisions of the law respecting roads, such road name shall, when approved by the Board of Supervisors, be thereafter used in all official reference to the same, and its public use shall be recommended. Such road shall then be listed in the road list and given a designating number and letter immediately following the number of the road to which it is adjacent or tributary, until such time as the Board of Supervisors shall revise the list and renumber the roads. And such road shall thereafter come under the provisions of this ordinance the same as the roads enumerated.

SEC. 4. The streets of all unincorporated towns or villages in the county may come within the provisions of this ordinance and be named. When numbered, the numbers to be according to the town method of 100 numbers to the actual block or square.

SEC. 5. The authorities of the village, town, or city incorporations in the county are recommended and urged to name the streets within their corporate limits, and to cause the houses thereon to be numbered; also, to make use of one of the following designations only for the roadways within such incorporation, viz.: Alley, Avenue, Boulevard, Court, Park, Place, Plaza, Promenade, Row, Square, Street, Terrace.

SEC. 6. Road measuring and numbering, as contemplated by this ordinance, are hereby defined and described as follows: All roads shall be measured along the surface line of the same, as near to the middle of the roadway as practicable, and laid off in imaginary blocks one tenth of a mile, or 528 feet frontage each, according to

the "Ten-block System of Numbering Country Houses." A line to indicate the division between these blocks, with the block number on either side of the same, shall be marked or painted upon the fence where practicable, and where it exists in a fair state of preservation, or upon any other permanent object on one or both sides of the road. The odd numbers shall be applied to the blocks on the left-hand side of the road, and the even numbers to the right-hand side. The block numbers shall be in figures not less than two inches nor more than two and one half inches in height where the fence board or other object will admit of this size, and so plainly painted as to be easily read from the centre of the road. The mile distances shall be distinguished in some suitable manner, as by a full circle, and the half-mile by a half circle or other suitable device.

SEC. 7. The initial point of measuring for roads leading from the county seat shall be the centre of the street immediately in front of the main entrance to the court-house at Martinez. Other roads shall be measured at the end nearest the county seat, and branch roads the same, or from the main road to which they are tributary.

SEC. 8. Note shall also be taken and a record kept of the block within which is located, and the number of feet in or within the block (i. e., the distance from the commencement of the block), of all bridges, large culverts, important permanent springs, drinking troughs, public monuments, summits, road crossings and intersections and objects of special prominence, and the correct block number be marked thereon, or near thereto, where practicable.

SEC. 9. Note shall also be made and a record be kept of the number of the block within which is located, and the number of feet in or within the block, of each and every house entrance or gateway, lane, or road leading from the highway to any residence upon the roads, or to which access is had by way of the road, with the name or names of the owner or occupant, when practicable to procure them; also, to the entrance to all school-houses, churches, and public buildings.

SEC. 10. The measurement of all roads which pass through or enter the corporate limits of cities or towns shall be continuous, regardless of such boundaries; but the block and country-house numbers may be omitted within such corporations.

SEC. 11. In the measurement of the roads of the county re-

quired by this ordinance a record shall be made and preserved of the general course of bearings by the compass of all roads at road crossings or intersections; also, the general course of all private or local roads at their point of departure from the main road; and it shall be the duty of the county surveyor to prepare and place on file, in the office of the clerk of the county, a complete road map of the county, with the names of all roads, and, whenever the same are measured, the block numbers at their commencement at all roads, crossings, and at all crossings and connections of all roads, and at their endings, together with the boundaries of the several road districts in the county.

SEC. 12. The measurement of the roads of the county may include the record of the accurate reading by barometer of the altitudes or elevations above the sea-level of the commencement and ending of all roads, all plains, valleys, the foot and summit of hills and the slopes of mountains, at suitable distances. The records of such altitudes, if taken, to be placed over the block number nearest the point of observation, or otherwise suitably posted, to show the range of important elevations traversed.


SEC. 13. Whenever one or more residents or owners, upon any road enumerated in section 29, or hereafter designated and described, as required by this ordinance, or other person, shall furnish the Board of Supervisors satisfactory evidence that the provisions of this ordinance, respecting road measuring and numbering, have been faithfully complied with upon any road touching the county seat, or upon any road connecting with any other road which has been previously measured and blocked off; and whenever such residents shall file with the county clerk the record required in sections 8, 9, and 11; and whenever such resident, residents, or other persons shall have affixed block numbers at the beginning and ending of such roads, and at each mile and half-mile division thereof, where practicable or oftener,—then, and in that case, it shall be the duty of the Board of Supervisors to erect upon such road, or roads, guide-boards, as hereinafter prescribed.

SEC. 14. Whenever any such road is so measured and block numbers designated thereon, thenceforth and thereafter the several requirements of this ordinance as to the maintenance of house numbers, the protection and preservation of guide-boards, etc.,

shall become applicable and in force along and upon such road, or roads, and the penalties herein prescribed shall be duly enforced.

SEC. 15. The guide-boards, when ordered upon any road, shall be erected and permanently maintained at the following-named points, and at such places as the Board of Supervisors may hereafter prescribe: At or near the commencement of all roads or branch roads, at all road crossings or intersections, at all ferry landings, at all railroad stations, and at all crossings of the county boundary. They shall be so placed on the principal roads as to face the traveller when moving from the county seat.

SEC. 16. Such guide-boards shall be of iron, not less than No. 16 in thickness, galvanized and painted. They shall be at right angles to fit the post, and with two arms or boards for the lettering. The outer edges shall be bent back from the face one half inch in width, the lower portion being cut away the width of the post, and the upper lip to rest on top of the post, to which the board must be securely attached by a sufficient number of screws. The posts



NO. 1. ARRANGEMENT OF WORDING ON GUIDE BOARDS

shall be of sound redwood, 6×6 inches, and twelve feet long, to be set three feet in the ground, with cross-pieces nailed to the post, in light soils. The top and the portion below the ground to be in or painted with coal-tar, or some other wood preservative, the portion above the ground to be painted with two coats of good metallic or other suitable paint. The exposed surface of the boards

shall be 15×24 inches in size, each, except at the entrance to local roads, which may have but a single projecting arm 6×15 inches in size and affixed to a 4×4 inch post; in all other particulars to be of similar construction to the larger size; the wording and lettering to conform to the general plan indicated by the design accompanying this ordinance, and made a part thereof. All of the lettering upon the guide-boards, except the second line, which is in letters smaller than the others, and a section of eighteen inches of the two faces of the guide-post directly under the guide-board, shall be painted with luminous paint.

SEC. 17. Upon all guide-posts the following notice shall be conspicuously painted or stencilled:

A PENALTY FOR DEFACING OR POSTING.

SEC. 18. Whenever the provisions of section 13 have been complied with as to road or roads, and guide-boards have been erected, the supervisors shall also cause a printed notice to be served upon the occupants of every residence upon such road or roads outside the limits of incorporated towns, left at such residence, or, where the residence is distant a mile or more from the public or named roads, mailed to their address, accompanied by a copy of this ordinance or abstract thereof. Such notice shall also be delivered or mailed to one of the officers of each school district and church of which the building is located upon said measured road. These notices shall have a blank form, to be properly filled with the exact location and correct number of the entrance to the house, with instructions as to the house number to be posted and maintained.

SEC. 19. Every householder upon such measured road, residing outside the limits of incorporated towns, shall, within thirty days after the service of the notice required in section 18, post, and thereafter permanently maintain in legible condition, upon the road or at the entrance or right of way from the road, the correct house number of his residence as given in said notice. It shall be placed in such a conspicuous position as to be easily seen and read from the centre or opposite side of the road. The figures shall be well proportioned, and of a size not less than three inches in height, nor more than four inches, except in town or village settlements, where the numbers may be one inch less in height, and may be maintained upon the doorway or at the gate. The numbers must

be neatly made, and in the style and manner that a professional sign-writer would use.

SEC. 20. Any owner or occupant of any dwelling in the county which is reached by a private road or right of way is hereby permitted to post and maintain his house number upon the public highway at the entrance to such private road or right of way, or upon such private road or right of way, and he or she may place therewith his or her own name and business, provided such sign is made in a neat and tasteful manner, and conforms to the provisions of this ordinance.

SEC. 21. Whenever the occupant of any dwelling upon a measured and numbered road shall fail for the term of thirty days to maintain the proper house number at the entrance thereto, and having been notified by the road officer to comply with the law shall fail to do so, he shall be deemed guilty of a misdemeanor.

SEC. 22. Whenever any house upon a measured and numbered road now vacant shall be occupied, or any new dwelling-house shall be erected upon such road, it shall be the duty of the occupant within thirty days to properly post and thereafter permanently maintain, at the entrance thereto, the correct house number of the same as provided in this ordinance, and such residence shall thereafter come under the provisions of this ordinance the same as dwelling now occupied.


SEC. 23. There shall be prepared for county use a book of records for the roads of the county, in which shall appear, arranged in proper order, under the name of each road, an index of all ordinances or other official action relating to that road, making such road record an official history of all the roads of the county.

SEC. 24. A copy of all the field notes of the survey measurements, elevations, and other records, with the block and house numbers as provided for, shall be carefully preserved in the office of the county clerk, and open to the inspection of citizens as are other county records.

SEC. 25. The execution of the work required by this ordinance shall be subject to the inspection and be made to conform to the requirements of a road committee to serve without pay, and to consist of three members, one to be appointed by the Board of Supervisors, one to be named by the road-naming committee who have prepared this plan, and the third to be chosen by the two thus

appointed, and all to be confirmed by the Board of Supervisors; and any work of measurement, erecting guide-boards, or affixing numbers, shall not be held to be complete until approved by a majority of this committee.

SEC. 26. It shall be the duty of the road officials to thoroughly inspect the roads within their respective districts and to make reports to the Board of Supervisors at least as often as at the close of each six months of their terms of office, as to the condition of such roads, and any failure to comply with the provision of this ordinance. They shall also see that guide-boards are preserved in a legible condition and house numbers properly maintained, notifying residents of any neglect in this respect. It shall be their duty to report any person charged with violating the provisions of this ordi-



NO. 2. GUIDE BOARD AT RIGHT ANGLES TO NO. 1.

nance, and to enter complaint against them in such case; they shall also have full authority to arrest any person or persons found defacing or removing block or house numbers, or mutilating any guide-board, or posting any notice upon the post or boards, or in any way violating the provisions of this ordinance.

SEC. 27. If any person or persons shall mutilate, deface, destroy, or remove any guide-board or guide-post, any block or house number, any name, sign, or advertisement which may be lawfully posted at or upon the entrance to the residence or dwelling of any person to whom such notice belongs, whether such entrance be public or private or through right of way, or shall mar, deface, or injure, by shooting, stoning, or otherwise, any guide post or board, or shall

fasten, or paint, or stencil any notice or advertisement to such posts or boards, save such as are required by this ordinance, the person or persons so offending shall be deemed guilty of misdemeanor, punishable, upon due conviction, by a fine of \$50, one half of which shall go to the informer, or by imprisonment, or both.

SEC. 28. The roads of the county, as enumerated in section 29, are listed according to the following rule: Commence on the east side of a line extending due north from the county seat and work around in a circle to the east, southwest, and back again to the north, always facing outward and working from the county seat outward, and always from the left to the right. List first those roads touching the county seat; next the first left-hand branch roads, and any left-hand branches of these. Continue with the right-hand branches, follow with the remaining trunk roads and their branches, left-hand branches first, right-hand branches next; omitting nothing on the left until the entire circuit has been made and the roads of the county are all listed. Under this rule the roads leading from Martinez, five of them are first listed; then the first of the five which have branches, No. 2, and then continued in the order explained above.

SEC. 29. The following are the names of several public highways and private or local roads of the county, respectively hereby authorized and established. [List of 130 roads, among which are:

Alpha Way, from Martinez to Bull's Head; Contra Costa Highway, from Martinez to County line *via* Pacheco, Walnut Creek, and San Ramon Valley; Alhambra Way, from Martinez to Pinole; Granville Way, from Contra Costa Highway, near Walnut Creek, to Vista Ignacio, Franklin Road; Teal Local; Tule Road, Pecheco Exit, Vine Hill Way; Locust Way, Plover Connex; Willow Pass Road; Flunaveg (River Road), Black Diamond Way; Empire Road; Paso Corto; Camino Diablo, Carbon Way; Arbor Connex; Lone Tree Road, Almond Way; Summer Road, Dry Creek Local; Zigzag Way, Sunol Local; Concord Lateral; Pomona Road; Ferndale Local; Golden Gate Way; Vaca Crescent; Verdel Circuit; Acorn Local, Highland Drive; and Forest Road.]

SEC. 30. This ordinance shall take effect and be in force on the 16th day after its passage.

Passed March 8, 1892.

II.

METHODS OF ASSESSING THE COST OF STREET-PAVING.

THE following summary shows the different methods employed for assessing the cost of street-paving:

I. THE WHOLE COST BORNE BY THE ABUTTING PROPERTY; e.g., Albany, Brooklyn, Buffalo, New York, Rochester, Syracuse, Troy, N. Y.; Boston, Mass.; Newark, Paterson, N. J.; Philadelphia, Harrisburg, Scranton, Pa.; Baltimore, Md.; Dayton, Ohio; Indianapolis, Ind.; Peoria, Ill.; Milwaukee, Wis.; St. Paul, Minn.; San Francisco, Cal.; Kansas City, Mo.

II. THE WHOLE COST BORNE BY THE CITY AT LARGE; e.g., Portland, Me.; Manchester, N. H.; Springfield, Mass.; Wilmington, Del.; Richmond, Va.; Charleston, S. C.; Nashville, Tenn.

III. THE COST DIVIDED EQUALLY BETWEEN THE ABUTTING PROPERTY AND THE CITY; e.g., Washington, D. C.; Augusta, Ga.; Montgomery, Ala.

IV. THE COST DIVIDED IN PROPORTION OF TWO-THIRDS ON THE ABUTTING PROPERTY AND ONE-THIRD ON THE CITY; e.g., Oswego, N. Y.; Hartford, Conn.; Atlanta, Ga.; Jacksonville, Fla.

V. THE ABUTTING PROPERTY PAYS FOR ITS FRONTAGE, AND THE CITY PAYS FOR INTERSECTIONS; e.g., Allegheny, Pa.; Sioux Falls, S. Dak.

VI. THE ABUTTING PROPERTY PAYS FOR THE GRADING, THE CITY PAYS FOR THE PAVING; e.g., Lowell, Worcester, Mass.; Providence, R. I.

VII. THE CITY PAYS FOR THE GRADING AND ONE-THIRD OF THE PAVING, THE PROPERTY PAYS THE REMAINING TWO-THIRDS; e.g., Hartford, New Haven, Conn.; Atlanta, Ga.

VIII. THE CITY PAYS ONE-HALF COST OF GRADING AND ALL COST OF INTERSECTIONS, THE PROPERTY PAYS THE REMAINDER; e.g., Salt Lake City, Utah.

IX. THE CITY PAYS FOR ONE-HALF THE GRADING, THE ABUT-

TING PROPERTY THE OTHER HALF AND THE WHOLE COST OF THE PAVING; e.g., Omaha, Neb.

X. THE CITY PAYS ONE-FOURTH OF THE WHOLE COST, AND THE PROPERTY THREE-FOURTHS; e.g., New Orleans, La.

XI. CITY PAYS FOR GRADING AND FOR THE PAVING OF STREET AND ALLEY INTERSECTIONS; e.g., Detroit, Mich.

XII. THE COST DIVIDED BETWEEN THE CITY AND THE PROPERTY IN DIFFERENT PROPORTION; e.g., Cincinnati, Ohio, city pays 2%, property 98%; Cleveland, O., city pays $\frac{1}{10}$ and intersections, property $\frac{9}{10}$.

XIII. THE CITY PAYS FOR GRADING; COST OF PAVING ASSESSED UPON ABUTTING PROPERTY IN PROPORTION TO BENEFIT, DETERMINED BY APPRAISERS SPECIALLY APPOINTED; e.g., Topeka, Kan.

XIV. THE WHOLE COST PAID BY THE ABUTTING PROPERTY IN PROPORTION TO ITS VALUE; e.g., Little Rock, Ark.

When the assessment is by improvement districts, all land, including street areas, between termini of the improvements and within a fixed distance (usually one-half the depth of the block) of the street line on each side of the street improved constitutes an improvement district, except that when a cross-street has already been improved its area is excluded. The area on each side of the street-lines is divided into zones by lines drawn parallel to the street-line. The number of the zones may be three, four, or more. When four are used the total cost is levied on the area within the zones in the proportion of 40 per cent on the one immediately adjoining the street, and on the other at the rate of 25, 20, and 15 on the most remote. In some cases the centre line of the street to be improved is taken as the base for the zones; in this case the city at large pays the assessment charged to the street area.

In all cases where the assessment is made by frontage, the location or value of the property is not taken into account.

In cases where the cost is borne by the city at large it is paid either from the general tax or by the emission of bonds or improvement certificates.

The practice of assessing *corner lots* varies. In Louisville, Ky., they pay 25 per cent more than inside lots. In Portland, Ore., the corner lot is assessed $\frac{1}{2}$ and the one adjoining $\frac{1}{4}$.

The street-railway companies are assessed in various ways:

1. Directly for the area occupied by them.
2. Are required to do the paving and maintain the space between their rails and from $1\frac{1}{2}$ to 2 feet outside the rails.
3. They are required to maintain the pavement from curb to curb, as in Philadelphia.
4. A certain proportion of the cost is assessed against them, as $\frac{1}{4}$ in Brooklyn.

Renewals and Repaving are paid for either by the property or the city. The following are examples:

City pays: Albany, N. Y., $\frac{1}{4}$; Brooklyn, N. Y., $\frac{1}{4}$ in special cases; New York; Paterson, N. J.; Scranton, Pa., $\frac{1}{4}$; Dayton, O.; Detroit, Mich.

Property pays: Albany, N. Y., $\frac{1}{4}$; Syracuse, N. Y.; Newark, N. J.; Scranton, Pa., $\frac{1}{4}$.

III.

ORDINANCE REGULATING THE WIDTH OF WAGON-TIRES.

1. The owner, driver, or person for the time being employing or having the care or control of any wagon, truck, cart, or carriage drawn by animal power shall not cause or suffer such vehicle to be used on any road or highway in contravention of any such of the following regulations as may be applicable to such vehicle, that is to say:

2. No wagon, truck, cart, or carriage shall be used on any road of which the felloes or tires at the bottom or soles of the wheels are not of the width in proportion to the gross weight as hereinafter mentioned, such gross weight including not only the persons, load, or things carried by such vehicle, but also the weight of the vehicle itself. The tires must be neither concave nor convex.

Gross Weight, Pounds.	Description of Vehicle.			
	Two Wheels.		Four Wheels.	
	Without Springs.	With Springs.	Without Springs.	With Springs.
	Width of Tire.		Width of Tire.	
	Inches.	Inches.	Inches.	Inches.
Less than 2,000...				
2,000 and less than 3,000...				
3,000 " " " 4,000...				
4,000 " " " 6,000...				
6,000 " " " 8,000...				
8,000 " " " 10,000...				
10,000 " " " 12,000...				

For the transportation of loads exceeding 6 tons special permits must be obtained.

3. The owner, driver, or person for the time being employing or having the care or control of any wagon, truck, cart, or carriage

drawn by animal power on any road or highway shall not cause or suffer the wheel of such vehicle to be locked when descending a hill, except the hill be in a slippery condition from ice or snow, unless there be placed at the bottom of such wheel, during the whole time of its being locked, a skid-pan, slipper, or shoe, in such manner as to prevent the road from being destroyed or injured from the locking of such wheel. No vehicle shall, when descending a hill, have both hind wheels locked.

4. No vehicle shall have any nail or bolt on the tire of any wheel which shall not be countersunk so as not to project beyond one-quarter of an inch above any part of the surface of the tire of such wheel.

5. The driver or other person having for the time being the care or control of any wagon, truck, cart, or carriage shall, upon demand made to him by the county engineer, or any of his assistants, or by any officer duly appointed, empowered, or instructed in that behalf by the county authority of the county of _____ or by any police officer, stop such vehicle, and permit the person so demanding to examine for a reasonable time the wheels thereof, or the nature and amount of the loading thereof, with the view of ascertaining whether all or any of the regulations aforesaid are then being contravened.

6. The driver or other person having for the time being the control or care of any wagon, truck, cart, or carriage shall, upon demand made to him by any such person as aforesaid, cause such vehicle, together with the loading thereof, to be driven to any weighing-machine for the purpose of being, and shall cause or suffer the same to be, weighed thereby or thereon, provided that such driver or person shall not be required to drive or cause to be driven such vehicle, together with the loading thereof, to such weighing-machine if at the time when such demand as aforesaid shall be made such vehicle shall be at a greater distance than half a mile from such weighing-machine.

7. Every person who shall break any of the regulations of this ordinance shall be deemed guilty of a misdemeanor, punishable, upon due conviction, by a fine of \$10, or by imprisonment, or both.

8. This ordinance shall take effect and be in force on the day of _____, 18 .

IV.

CYCLE-PATHS.

Cycle-paths through the country may be constructed according to the most elaborate specifications for broken-stone road construction, or consist simply of a bed of gravel or cinders slightly raised above the adjoining surface. In city streets strips of asphalt or brick pavement are the most suitable.

Location.—In the country the paths should be placed at one side of the roadway and so protected that wagons cannot use them. In city streets the best location seems to be adjoining the curb, and there should be a path on each side of the street so the cyclists can move in the same direction as the traffic.

Width.—Six feet is the minimum width to allow wheelmen to meet and pass without danger of accident. Single paths at the side of streets should be 3 feet wide.

Crown.—

Paths 3 feet wide should have a crown of $1\frac{1}{4}$ inches.

" 6 " " " " " " " 3 "

" 10 " " " " " " " " 4 "


" 18 " " " " " " " " 6 "

Grades should be as flat as possible.

Drainage.—In paths through the country attention must be paid to the drainage.

Construction.—*Gravel* or *cinders* should have a thickness of 3 inches and should be well rolled. The gravel should pass through a $\frac{1}{2}$ -inch screen. If a foundation is required, it may consist of cinders 4 inches thick, thoroughly rolled and covered with a layer of loamy clay $\frac{1}{2}$ inch thick, moistened and rolled. A mixture of sand and loamy clay in sufficient quantity to bind the sand has given good results.

Broken Stone (Brooklyn, N. Y.).—Foundation consists of gravel covered with a layer of broken stone 3 inches thick, rolled with a steam-roller and covered with stone screenings from $\frac{1}{4}$ to $\frac{1}{2}$ inch in size.



INDEX

A

ARTICLE	PAGE
63. Abrasion of granite.....	26
63. limestone.....	26
63. paving-brick.....	26
63. wood.....	26
61, 855. tests of	25, 259
64. Absorptive power of bricks (Table V).....	27
cement (Table XLIV).....	336
granite (Table V).	27
limestones (Table V)	27
marbles (Table V).....	27
64. materials, effect of.....	26
64. mortar (Table V).....	27
64, 119. paving-bricks (Table V and Table XXI)....	27, 87
sandstones (Table V).....	27
64. stones, etc. (Table V).....	27
64, 131. wood (Table V and Table XXIII).....	27, 98
706. Abutments for pipe-culverts.....	468
714. thickness of (Table LXXVI)	478
22. Accidents to horses....	10
753. Accommodation summits.....	510
862. Accounts.....	599
617. Acres, number of, required per mile, for different widths of roads (Table LXIII).....	417
59, 410. Action of the weather.....	24, 284
482. Activity of cement.....	384
486. tests for.....	336
9. Adaptability of pavements.....	4
641. Adhesion of earth.....	424
500. Adhesive strength of mortar (Table XLV).....	344, 345
751. Adjustment of grades at street-intersections.....	507

ARTICLE	PAGE
153. Advantage of sorting granite blocks at the quarry.....	107
188. creosoting wood.....	182
511. mixing mortar by machinery.....	358
221. asphalt pavements.	159
281. and coal-tar pavements.....	203
305. brick pavements.....	219
346. broken-stone pavements.....	250
281. coal-tar and asphalt pavements ...	203
140. granite-block pavements.....	102
511. mixing concrete by machinery.....	358
396. rolling broken-stone pavements.....	274
13. smooth pavements.....	6
398. steam-rollers.....	275
439. stone trackways.....	306
550. wheels.....	387
177. wood pavements.....	124
485. Age, effect of, on cement.....	336
505. strength of mortar.....	350
1030. Agreement, form of.....	694
584. Alignment of roads.....	401
1025. Alteration of manhole heads, etc.....	687
92a. American asphaltum	42
99a. bituminous rock	51
300. cost of construction.....	212
308. pavement, specifications for.....	212
297. pavements.....	211
478. natural cements, colors of.....	323
473. specific gravity of.....	323
103a. Ammonia, action on bitumen.....	65
256. Amount of asphaltic cement made by one ton of refined asphaltum..	184
388. binding material required for broken-stone pavements..	272
103a. bitumen in asphaltic paving-cement	73
bluestone used for street purposes in 1889 (Table XI)...	35
874. dirt produced by different pavements.....	624
25, 842. dirt removed from streets.....	10
70. granite used for street purposes in 1889 (Table VII).....	30
limestone used for street purposes in 1889 (Table XIII)..	37
412. material required to replace wear on broken-stone pavements.....	239
414. material used to replace wear on broken-stone pavements in England.....	239
\$1 at compound interest for a term of years (Table LXXXIX).....	300
414. material used to replace wear on broken-stone pavements in France.....	239

ARTICLE	PAGE
256. Amount of paving-cement manufactured from one ton of refined asphaltum.....	184
699. rainfall.....	463
refuse collected from city streets (Table LXXXVI).....	623
404. rolling.....	277
sandstone used for street purposes in 1889 (Table X)....	35
366. stone broken by hand.....	266
618. transverse rise required for different pavements (Table LXIV).....	418
859. water required for sprinkling broken-stone roads.....	590
913. water required for street sprinkling.....	648
101, 265a. Analysis of Bermudez asphaltum.....	59, 196
102. Analysis of California asphaltum.....	60
99f. bituminous limestones (Table XV).....	52
102. sandstones.....	61
116. clay (Table XX).....	82
345. macadam pavement.....	250
sandstone (Table VIII).....	38
100h. the residue of refined Trinidad asphaltum.....	57
131. Tompkins Cove gravel.....	95
100d. Trinidad asphaltum, crude.....	55
Alcatraz liquid asphalt.....	47
Utah liquid asphalt.....	47
Pittsburg asphaltic flux.....	47
Trinidad asphaltum, refined.....	58
108a. and tests of asphaltum.....	62
596. Angle of repose.....	406
645. of earths.....	425
Angles of slopes (Table LXVI).....	425
Annual cost per head of population for street maintenance in the United States (Table LXXXVII).....	627
43. Annual cost of pavements.....	16
1045. structures.....	797
wood pavements in London (Table XXXI).....	136
108a. Apparatus for penetration tests of bitumen.....	66
89a. Appearance of asphaltum.....	89
405. broken-stone pavements after being rolled.....	278
267. European bituminous limestone.....	197
100d. Trinidad asphaltum.....	55
712. Arch-culverts.....	474
960. specifications for.....	665
713. thickness of (Table LXXV).....	474, 476
878, 895. Area cleaned by machine brooms.....	628, 635
878. Area cleaned by one man.....	629
793. covered by a barrel of Portland cement.....	545

ARTICLE	PAGE
435. Asphalt old, mixed with broken stone.....	803
262. one-coat pavement.....	188
874. pavement, amount of dirt produced by.....	624
19. and rain.....	2
894. area cleaned by one man.....	685
load drawn on, by a horse (Table LVII)....	880
221. pavements, advantages of.....	159
225. and street-car rails.....	163
222, 261. and variations in temperature.....	159, 185
224. brick gutters for.....	161
303 <i>d</i> . condition at end of guarantee period.....	217
232. cost of construction (Table XXXV)....	163, 169
887-889. cleaning.....	627, 632, 633
233, 234. maintenance (Table XXXV <i>a</i>)..	163, 173
303 <i>b</i> . cracks in.....	213
223. defects of.....	159
218. difference between European and American	157
303 <i>b</i> . disintegration of.....	213
97 <i>a</i> , 227. durability of.....	47, 166
303 <i>b</i> . expansion joints in.....	214
303 <i>a</i> . expansion of.....	213
232. extent of, in 1890.....	168
252. failure of.....	173
14. foothold on.....	7
240. foundation for.....	174
50. guarantee-period.....	21
303 <i>d</i> . condition at end of.....	217
266. in Europe.....	197
226. injured by illuminating gas.....	164
224. injured by water.....	160
223. injurious effects of sand on.....	160
217. introduction of.....	157
27. life of.....	11
233. maintenance, cost of.....	163
265. by contract.....	194
222, 261. maximum grade for.....	160, 186
261. on grades.....	186
264 <i>a</i> . on surface of old pavements.....	193
303 <i>b</i> . repair of.....	213
303 <i>b</i> . rolls or waves in.....	213
303 <i>b</i> . skimming process of repair.....	215
19-21. slipperiness of.....	9, 10
303 <i>d</i> . specifications for condition at end of guar- antee period.....	217
263. specifications for, on bituminous base.....	191

ARTICLE		PAGE
264.	Asphalt pavements, specifications for, on hydraulic concrete	
	base.....	193
303c.	specifications for repair of.....	215
262.	specifications for, Trinidad.....	186
897.	squillees for.....	636
1039.	tools used in the construction of.....	762
228.	traffic sustained by.....	167
	transverse rise for (Table LXIV).....	418
253.	Trinidad composition of the wearing sur- face.....	183
303b.	waves in.....	214
231.	wear of.....	168
103a.	paving-cement, amount of bitumen in.....	63
256.	area covered by a cubic yard of.....	184
257.	temperatures for working.....	184
256.	weight of a cubic yard.....	184
253, 255.	paving, proportion of the materials used.....	183, 184
262.	two-coat pavement.....	167
210.	wood pavement.....	141
90, 90a, 95c.	Asphaltene.....	40, 45
470.	Asphaltic cement for concrete.....	827
96, 97, 100c, 102.	Asphaltic cement.....	45, 47, 58, 61
99a.	paving compounds.....	50
99.	materials.....	50
450q.	Asphaltina.....	318
88.	Asphaltum.....	39
103a.	analyses and tests of.....	63
92a, 102.	Asphaltum, American.....	42, 60
101, 265a.	Bermudez.....	59, 196
265a.	analysis of.....	196
265a.	composition of the wearing-surface with	197
89c.	characteristics of.....	39
90.	composition of.....	40, 43
94.	crude.....	44
104.	Cuban, price of (Table XVII).....	74
	composition of.....	43
220.	different varieties, cost of preparing the.....	158
92.	distribution of.....	41
96a.	flux for.....	46
104.	imports of, into the United States in 1890 (Table XIX).....	74, 75
93.	nomenclature.....	43
92.	occurrence of.....	41
104.	prices of, in New York in 1897-98 (Table XVII).. production in the United States (Table XVIII)....	74 74

ARTICLE	PAGE
95. Asphaltum, refining.....	44
89c. specific gravity of (Table XXIV).....	40, 97
100. Trinidad.....	54
	analyses of..... 55
100c. characteristics of refined.....	55, 58
100d. of crude.....	55
100e, 248. preparation of.....	56, 175
104. price of (Table XVII).....	74
100n. refined, specific gravity of.....	58
100n. composition of.....	58
257. number of cubic yards to one ton	184
100. source of	54
108a. tensile strength of.....	68
105. uses of.....	75
89. varieties of.....	89
	weight of (Table XXIV)..... 97
450f. Artificial stone.....	818
1012. Assignment of contract.....	679
158. Assorting granite blocks at the quarry, advantage of.....	107
410. Atmospheric changes, effect of, on pavements.....	284
418. Austria, amount of material used in, to replace wear on broken-stone pavements.....	291
1086. Aveling & Porter steam-roller.....	756-760
Average width of sidewalks in various cities (Table LXXXII).	508

B.

629. Balancing transverse of earthwork.....	421
881. Baltimore, street-cleaning in.....	680
86. Basalt, description of.....	88
	resistance to crushing of (Table XXIV)..... 97
	specific gravity of (Table XXIV)..... 97
	weight of (Table XXIV)..... 97
897. Bass brooms.....	636
186. Belgian block pavement.....	101
172. cost of construction (Table XXVIII)	119
187. defects of.....	101
188. specifications for.....	101
418. Belgium, cost of maintaining broken-stone pavements in.....	290
572, 940. Bench-marks.....	892, 658
82. Benefit, economic, of good pavements.....	18
162. Berea sandstone.....	111
265a. Bermudez asphalt	196
745. Best arrangement of city streets	500
449. road.....	811

ARTICLE	PAGE
459. Beton.....	321
1029. Bid, form of	693
1028. Bidders, instruction to.....	689
386. Binding	271
391. effect of	273
388. using large quantities.....	272
390. necessity of.....	272
430. power of clay.....	300
389. proportions adopted by the French engineers...	272
388. quantity of.....	272
397. Birch brooms.....	637
101, 265a. Bermudez asphaltum	59, 196
88, 94. Bitumen	39, 43
103a. action of water and ammonia on.....	63
103a. change of, due to age.....	63
89a. earthy	39
89b. elastic	39
103a. essential characteristics of.....	63
89c. hard	39
103a. amount in asphaltic paving-cement.....	73
93d. liquid.....	43, 47
89c. specific gravity of (Table XXIV).....	40, 97
weight of (Table XXIV).....	97
91. origin of.....	41
103a. penetration tests of.....	66
103a. softness of.	63
89c. specific gravity of	40
103a. stability at high temperatures	63
103a. susceptibility to change of temperature.....	63
103a. viscosity of.....	63
96, 160. Bituminous cement, composition of	45, 109
161. cost of	110
160. for filling joints.....	109
161. manner of using	110
242, 263. Bituminous concrete	175, 191
259. limestone pavements, experience with, in Wash- ington.....	185
277. limestone pavements in the United States.....	201
specific gravity of (Table XXIV).....	97
268. test for	197
94, 99b. limestones	44, 51
268. appearance of European.....	198
99f. how used	51
270. preparation of.....	199
434. macadam	301

ARTICLE	PAGE
297. Bituminous rock, American	211
308. pavements, specifications for	212
104. production of, in the United States (Table XVIII)	74
99f. rocks, analyses of European (Table XV).....	52
102. sandstones, analyses of	61
99g. in America	52
99g. in Europe	52
99g. preparation of	52
456. Blast-furnace slag for foundations of pavements	320
330. used for bricks	233
450a. paving	311
663. Blasting	441
292. Block pavement of asphalt	208
182. Blocks sapless cedar	129
81. Bluestone, amount used for street purposes in 1889 (Table XI)	35
831. bridge-stones, specifications for	575
818. curb	566
818. specifications for	566
78. description of	33
776, 1018. flagging, specifications for	529, 685
774. for footpaths	528
resistance to crushing (Table IX)	34
specific gravity of (Table IX)	34
77. uses of	33
value of, used for street purposes in 1889 (Table XI)	35
value per cubic foot (Table XI)	35
weight of (Table IX)	34
658. Bogs, embankments across	435
1007. Bond for faithful performance of work	678
1081. form of	703
1021. indemnity	686
866. Books kept by cantonniers	610
632. Borrow-pits	422
636. form of	422
637. staking out	423
133. Boston, cobblestone pavements in	99
382. street cleaning in	630
711. Box-culverts	472
711. dimensions of (Table LXXIV)	474
597. Brakes, effect of	406
866. Breaches of highway law	609
362. Breaking stone by hand	265
365. cost of	266
364. machinery	266
367. cost of	266

ARTICLE	PAGE
60. Breaking tests of materials	24
954. Breast-walls, specifications for.....	663
Brennan's stone-crusher.....	737
107. Brick.....	77
64. absorptive power of (Table V).....	27
380. blast-furnace slag.....	233
common hard, resistance to crushing of (Table XXIV).....	97
specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
450m. copper slag.....	316
688. drains.....	457
784. footpaths.....	540
785. specifications for.....	541
828. gutters, specifications for.....	572
224. for asphalt pavements.....	160
329. iron.....	233
masonry, specific gravity of (Table XXIV).....	97
968. specifications for.....	667
weight of (Table XXIV).....	97
324. McReynold's patent.....	232
877. pavement, cost of cleaning.....	626
transverse rise for (Table LXIV).....	418
323. variety of systems.....	230
334. variations in specifications for.....	240
304. pavements.....	219
305. advantages of.....	219
326. Charleston plan.....	326
320. cost of.....	227
306. defects of.....	219
307. durability of.....	221
318. expansion joints in.....	223
308. experience with.....	221
309. failures of.....	221
334d. for country roads.....	243
316. foundation for.....	233
319. joint-filling for.....	225
27. life of.....	11
318. manner of laying.....	223
601. maximum grade for.....	407
394c. number of brick per square yard.....	242
317a. sand cushion.....	223
331-334. specifications for.....	233-240
327. Wheeling plan.....	233
64, 119. paving, absorptive power of (Table V and Table XXI).....	27, 87
117. characteristics of good.....	83

ARTICLE	PAGE
838. Brick, paving, Halwood block.....	281
114. manufacture of.....	79
834c. price of, per thousand	245
314. quality of.....	222
111. quality of clay for.....	78
119. resistance to crushing of (Tables XXIa, XXIV)	86, 88-91, 97
313. shape of.....	222
313. size of.....	222
119. specific gravity of (Table XXI and Table XXIV)...	87, 97
822. the Hayden	230
117, 119. weight of (Table XXI and Table XXIV).....	87, 97
pressed, resistance to crushing of (Table XXIV).....	97
specific gravity of (Table XXIV).....	97
weight of (Table XXIV)	97
soft inferior, resistance to crushing of (Table XXIV).....	97
specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
standard tests for.....	86
Stourbridge fire, resistance to crushing of (Table XXIV)....	97
specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
118. tests of.....	82
Ohio paving (Table XXIa).....	88-91
Brickwork in cement-mortar, resistance to crushing (Table XXIV)....	97
575. Bridge sites, selection of.. ..	395
720. specifications for.....	486
720. substructure of.....	488
880. stones	578
831. specifications for.....	575
421. Bridgeport, Conn., broken-stone pavements in.....	292
715. Bridges.....	780
858. examination of.....	589
716. live loads.....	780
718. materials for.....	481
716. proportioning of.....	780
933. setting out.....	655
435. Broken stone, and old asphalt.....	302
375. area covered by a cubic yard.....	268
378. determination of the voids in	268
410. pavement, action of the weather on.....	284
874. amount of dirt produced by.....	624
859. water required for sprinkling.....	593
894. area cleaned by one man.....	635
360. breaking the stone.....	265

ARTICLE	PAGE
877. Broken-stone pavement, cost of cleaning	626
406. rolling	260
344. defects of Telford's system	249
408. difference in the cost of European and American	263
410. effect of horse's hoofs on	284
410. wheels on	284
412. mud on	269
load drawn by a horse on (Table LVII).....	330
405. manner of applying the roller	278
381. sand core for	270
transverse rise for (Table LXIV)	418
388. Tresaguet's method	246
385. pavements	246
346. advantages of	250
396. rolling	274
414. amount of material required to replace wear	289
404. amount of rolling required	277
405. appearance of, after being rolled	278
413. average annual loss of thickness	289
393. compacting the stone	273
393. by the traffic	273
397. horse-rollers	273
398. steam-rollers	275
381. core for	270
407. cost of (Tables XLI and XLII)	281, 282
418, 860. maintenance	290, 593
347. defects of	350
350. erroneous methods of construction	251
349. essentials necessary to successful construction	251
380. failure of	270
15. foothold on	7
421. in Bridgeport Conn.	292
420. Chicago	293
418. loss of thickness	289
340. MacAdam's method	248
350. maintenance of	583
415. manner of restoring thickness	289
601. maximum grade for	407
419. modern, in England	291
351. quality of stone for	253
417. recoating, when it should be done	290
361. repair of	596

ARTICLE	PAGE
359. Broken-stone pavements, shape of stones for.....	265
357. size of stone for.....	265
423. specifications for.....	297
388. spreading the stone.....	270
339. Telford's method.....	247
378. thickness of.....	269
384. layers.....	271
1036. tools employed in the construction.....	734
1037. maintenance.....	761
traction on (Table L).....	872
392. watering, use of.....	278
63, 409. wear of.....	25, 234
383. quantity required per mile for different widths (Table LX).....	884
1019. specifications for.....	685
387. screening of.....	272
372, 461. voids in.....	267, 322
374. weight of.....	268
888. Brooklyn, N. Y., street cleaning in.....	632
897. Brooms, bass.....	636
897. birch.....	636
1840. prices of.....	770
897. rattan.....	636
897. steel-wire.....	636
102a. Buena Vista asphalt.....	61
1017. Bulkhead, specifications for a.....	681

C

674. Calculating amount of earth-work	447
676. the half-widths and areas of earth-work.....	448
102. California asphaltum	60
104. bituminous rock, price of.....	74
102. analysis of.....	60
866. Cantonniers, absence, fines for.....	611
annual gratuities.....	611
appointment of.....	605
books.....	610
chief.....	605
classification of.....	610
compulsory attendance of.....	609
distinctive mark	610
duties of	604
fines on account of absence.....	611
gratuitous assistance to travellers by.....	609

ARTICLE	PAGE
866. Cantonniers, indemnity for removal of.....	611
leave of absence	610
means of verifying absence of.....	610
regulations for.....	604
salary of.....	610
surrender of books and distinctive marks on dismissal of a.....	610
surveillance over breaches of the highway law.....	609
tools furnished by the	609
to the.....	609
keeping in repair by.....	610
working hours of.....	608
Capacity of drill-holes (Table LXVIII).....	442
1088. scrapers.....	713
sprinkling-carts.....	634
1086. stone-crushers.....	786
39. Care of pavements.....	14
1088. Carts, capacity of.....	717
earth	717
896. for street dirt.....	636
sprinkling, capacity of.....	634
price of.....	634
1042. Cast-iron gutter-crossings.....	788
specific gravity of (Table XXIV).....	97
984. specifications for.....	672
1042. Catch-basin covers.....	786
761. Catch-basins.....	516
1018. specifications for.....	685
704. -pools, use of.....	466
696. -water ditches ..	461
951. specifications for.....	663
858, 869. Causes producing dirt.....	587, 620
206, 216. Cedar-block pavement.....	140, 154
208. pavements.....	140
216. specifications for.....	150
482. Cement, activity of.....	334
485. age, effect of.....	336
473. American natural, specification.....	328
requirement for.....	328
amount of water absorbed by (Table XLIV).....	336
475. artificial Portland.....	329
96, 100, 102. asphalt.....	45, 52, 60
160. bituminous, composition of.....	109
161. cost of.....	110
161. manner of using.....	110

ARTICLE	PAGE
478, 479. Cement, color of American natural.....	828, 833
510. data for estimates	858
483. effect of variations of temperature on.....	834
475. English Portland, specific gravity of (Table XXIV)....	97, 829
476. weight of (Table XXIV).....	97, 831
790. expansion of.....	543
French Portland, weight of (Table XXIV).....	97
478. hydraulic.....	328
490. measuring fineness of.....	839
494. -mortar, composition of.....	842
474. natural Portland.....	829
706. pipe for culverts.....	467
707. cost of.....	471
dimensions of.....	471
161. Portland and iron slag for filling joints.....	110
476. characteristics of.....	331
475. effect of sand on.....	331
509. English specifications for.....	357
476, 489. fineness of.....	331, 338
477. necessity of testing.....	332
476. specific gravity of.....	332
476. tensile strength of.....	332
973. test for.....	669
476. weight of.....	331
482. quick- and slow-setting, definition of.....	334
Roman, specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
973. Rosendale, test for.....	669
473. specific gravity of American natural.....	328
972. specifications for.....	669
473. strength of American natural.....	328
492. testing machine.....	340
477. necessity of.....	332
477. tests.....	332
973. specifications for.....	669
473. weight of American natural (Table XXIV).....	97, 328
356a. Cementation test, description of.....	280
45. Census, traffic.....	17
48. form of.....	19
962. Centring, specifications for.....	666
450i. Ceramocrystal pavement.....	315
1031e. Certificate of acceptance.....	709
1031f. Certificate of final acceptance	709
1031c. Certificates, form of monthly.....	707
Chalk, resistance to crushing of (Table XXIV).....	97

ARTICLE	PAGE
Chalk, specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
89a. Chapapota.....	39
457. Character of concrete for pavement foundations.....	321
453. natural soils.....	319
543. vehicles.....	383
473. Characteristics of American natural cements.....	328
89. asphaltum.....	39
268. European bituminous limestone.....	198
117. good paving-brick.....	82
499. mortar.....	344
476. Portland cement.....	331
100d. crude Trinidad asphaltum.....	55
100n. refined Trinidad asphaltum.....	58
448. Charcoal roads.....	310
326. Charleston plan of brick pavements.....	332
29. Cheapest pavement.....	11
100a. Cheese pitch.....	54
122, 188. Chemical treatment of wood.....	98, 131
132a, 450c. Chert.....	96, 312
420. Chicago, broken-stone pavements in.....	292
Chief cantonnier.....	605
862. foreman, duties of.....	597
819. Circular curb.....	567
pipes, discharging capacity of (Table LXXXVIII).....	479
81. City ownership of street-car tracks.....	13
744. streets.....	500
873. amount of refuse collected from (Table LXXXVI).....	623
746. best arrangement of.....	500
749. grade of.....	506
748. maximum grade of, in various cities.....	506
747. width of (Table LXXXII).....	506, 508
1105. Claims, payment of.....	677
949. Classification of earth-work.....	662
107. Clay.....	77
116. analyses of (Table XX).....	82
430. binding power of.....	300
113. color of.....	79
108. composition of.....	77
450d. Florida.....	312
111. for paving-bricks.....	78
426. proportion of, to gravel.....	299
835. roads, improving of.....	577
836. maintenance of.....	578
836. trees on.....	578

ARTICLE	PAGE
639. Clay, shrinkage of.....	423
686. soils, drainage of.....	455
specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
with gravel, specific gravity of....	97
weight of	97
127. sand.....	94
1011. Cleaning up, specifications for.....	679
40. of pavements.....	15
126. Cleanness of sand, to test.....	94
868. Cleansing of streets.....	619
877. cost of.....	626
875. methods employed.....	624
944. specifications for.....	660
1040. tools employed for.....	770
944. Clearing, specifications for.....	660
1032. Clearing, tools for ...	710
884. Cleveland, Ohio, street cleaning in.....	682
418. Climate, effect of, on roads.....	290
450 <i>h</i> . Clinkers.....	314
945. Close cutting, specifications for.....	660
279. Coal-tar and asphalt.....	202
281. pavements, advantages of	203
284. cost of maintaining.....	204
282. defects of.....	203
291. specification for.....	205
278. pavements.....	201
450 <i>p</i> . paving-blocks	317
106. paving-pitch....	75
827. Cobblestone gutters, specifications for laying.....	571
133. pavement.....	99
172. cost of (Table XXX).....	120
183. in Boston.....	99
133. Philadelphia.....	99
166. on steep grades.....	111
135. specifications for.....	99
Coefficients for retaining-walls (Table XXXI).....	492
852. of quality of stones for broken-stone pavements (Table XXXVIII)	260
982. Cofferdams, specifications for.....	671
687. Collars for tiles.....	456
89 <i>a</i> , 100 <i>d</i> . Color of asphaltum.....	39, 55
473, 479. cements.....	328, 333
113. clay	79
65. granite.....	27

ARTICLE	PAGE
74. Color of sandstone.....	32
86. trap.....	38
450. Combinations of wood and iron.....	311
Common hard brick, resistance to crushing of (Table XXIV).....	97
specific gravity of ..	97
weight of.....	97
472. lime.....	327
1001. Commencement of work.....	676
79. Commercial names of sandstones.....	34
398. Compacting the broken stone.....	273
104. Comparative prices of asphaltum in 1897-98 (Table XVII).....	74
rank of pavements (Table IV)	21
15. safety of pavements.....	7
1002. Completion, time of.....	676
90. Composition of asphaltum (Table XIVa).....	40, 43
160. bituminous cement.....	109
494. cement-mortar.....	342
108. clay.....	77
459. concrete.....	321
872. mud (Table LXXXV).....	622
872. street dust.....	621
782a. Compressed-asphalt-tile footway-pavement.....	539
468. Compressive strength of concrete.....	325
502. mortar.....	347
866. Compulsory attendance of the cantonniers.....	609
623. Concave cross-section.....	420
466. Concrete, amount of ramming required.....	324
470. and furnace-slag.....	327
792. area covered by a cubic yard.....	545
242. bituminous.....	175
460. character of, for pavement foundations.....	323
459. composition of.....	321
468. compressive strength of.....	325
469. cost of.....	326
459. definition of.....	321
459. essentials necessary to the manufacture of good.....	321
791. footpaths.....	543
795. specifications for.....	547
460. for pavement foundations.....	322
470. formed with asphaltic cement.....	327
154. foundations, thickness of.....	108
466. laying of.....	324
436. macadam.....	303
465. mixing of.....	324
machine, price of.....	768

ARTICLE	PAGE
471. Concrete, mortar for.....	827
461, 462. proportions of ingredients.....	823
459. quality of stone for.....	821
464. quantity of materials required for one cubic yard.....	823
468. water required for.....	823
466. ramming of.....	824
127. sand for.....	94
459. size of stone for.....	822
460. specific gravity of (Table XXIV).....	97, 822
512-516, 977. specifications for.....	859-862, 670
460, 466. strength of.....	822, 825
458. thickness of.....	821
467. transverse strength of.....	825
461. usual proportions of ingredients.....	822
457. weight of (Table XXIV).....	97, 821
791. rammers for.....	545
28. Considerations concerning cost of pavements.....	11
942. tests of materials.....	659
555. governing location of roads.....	889
42. Consequential damages.....	15
444. Construction of plank roads.....	808
739. roads along the seashore or margins of rivers.....	494
184. wood pavements, essentials necessary to the successful.....	180
598. profile.....	404
560. Contour lines.....	390
635. transverse on hillside roads.....	420
618. of roadway.....	418
756. streets.....	512
1008. Contract, forfeiture of.....	676
1030. form of.....	694
1014. prices in.....	679
1012. subletting of.....	679
943. Contracts.....	660
476. Contraction of Portland cement.....	831
988. Contractor defined.....	672
989. notice to.....	672
1012. personal attention of.....	679
1081d. Contractor's affidavit.....	708
621. Convexity, excessive, objections to.....	418
450m. Copper-slag brick.....	816
447. Corduroy roads.....	810
381. Core for broken-stone pavements.....	270
450l. Cork pavement.....	816
43. Cost, annual, of pavements.....	16

ARTICLE	PAGE
1045. Cost, annual, of structures.....	797
wood pavements in London (Table XXXI)	186
per head of population for street maintenance in the United States (Table LXXXVII).....	627
88. first, of pavements.....	13
44. gross, " "	16
161. of bituminous cement.....	110
363. breaking stone by hand.....	266
320. brick pavements (Table XXXVIII).....	230
469. concrete.....	826
300. construction of American bituminous-rock pavements.....	212
294. asphalt-block pavements (Table XXXVI)...	210
232. asphalt pavements (Table XXXV).....	169
172. Belgian block pavements (Table XXVIII) ..	119
407. broken-stone pavements (Table XLII).....	281
172. cobblestone pavements (Table XXX).....	120
172. granite-block pavements (Table XXVII)...	118
432. gravel pavements (Table XLIII).....	301
172. sandstone pavements (Table XXIX).....	119
205. wood pavements (Table XXXIII).....	139
899. crematories.....	636
188. creosoting wood.....	133
710. different forms of culverts.....	472
688. drains.....	457
drain-tiles (Table LXXVII).....	479
840. earth roads	579
672. -work.....	445
706. earthenware culvert-pipe.....	467
668. excavating rock.....	443
742. fencing.....	496
709. iron pipe-culverts (Table LXXIII).....	472
233. maintaining asphalt.....	168
418, 860. broken-stone pavements.....	290, 592
841. earth roads.....	580
169. granite-block pavements	114
403. steam rollers.....	276
198, 206. wood pavements (Tables XXXI and XXXIV)	186, 140
905. melting snow	638
886. operating machine brooms.....	632
1088. ploughs.....	711
368. stone-crushers.....	266
28. pavements, considerations concerning.....	11
446. plank roads	310
707. Portland-cement pipe (Table LXXII).....	471

ARTICLE	PAGE
220. Cost of preparing the different varieties of asphalt.....	158
371. quarrying stone (Table XXX).....	267
900. removing snow.....	637
406. rolling.....	280
164. sandstone pavements.....	111
41. service of pavements.....	15
369, 370, 1036. Cost of stone-crushers.....	267, 736
371. crushing (Table XXXIX).....	268
377, 893. Cost of street cleaning.....	626, 635
915. sprinkling.....	644
893. sweeping.....	635
439. Cost of trackways.....	306
707. vitrified pipe-culverts (Table LXXI).....	471
5. wagon transportation (Table I).....	2, 794
878. per capita for street maintenance (Table LXXXVII).....	627
216a. Cottonwood blocks.....	155
555. Country roads, location of.....	389
862. County engineer.....	599
650. Covering of slopes.....	428
1042. Covers for catch-basins.....	786
899. Crematories, cost of.....	636
122, 188. Creosoting wood.....	98, 132
588. Crookedness, objections to.....	408
573. Cross-levels.....	392
677. -section of earth-work.....	448
770. -slope of footpaths.....	527
1033. -ties, number per mile.....	720
830. Crossing-stones.....	573
830. dressing of.....	573
830. quality of.....	573
832. relaying.....	575
831. specifications for.....	575
755. Crowns in gutters.....	512
94. Crude asphaltum.....	44
1043b. petroleum for sprinkling roads.....	795
369, 370. Crushers, capacity of.....	266, 736
369, 370. stone, cost of.....	266, 736
367. operating.....	266
370. horse-power required for.....	267, 736
369. size of.....	267, 736
368. wear of.....	266
132a. Crushing, resistance to, of basalt (Table XXIV).....	97
brick (Table XXIV).....	97
cast iron (Table XXIV).....	97
chalk (Table XXIV).....	97

ARTICLE	PAGE
182a. Crushing, resistance to, of common hard brick (Table XXIV)	97
69. granite (Table VI)	28
182a. lead (Table XXIV)	97
85. ligonier	37
84. limestone (Table XII)	37
182a. materials (Table XXIV)	97
119. paving-brick (Table XXIV)	97
182a. pressed brick (Table XXIV)	97
81. sandstone (Table IX)	34
182a. soft brick (Table XXIV)	97
Stourbridge (Table XXIV)	97
86. trap-rocks (Table XIV)	38
182a. wrought-iron (Table XXIV)	97
120. wood (Table XXII)	92
371. stone, cost of (Table XXXIX)	268
60. tests	24
104. Cuban asphaltum, price of (Table XIVa and Table XVII)	43, 73
Cubic contents of embankments and excavations (Table LXX)	453
377. yard of broken stone, area covered by a	270
464. concrete, materials required for	323
153. Culling of stone paving-blocks	107
697. Culverts	462
712. arch	474
699. area of water-way	462
711. box	472
711. dimensions of	472
706. cement pipe for	467
707. cost of cement pipes for	471
707. vitrified pipe	471
970. dry box, specifications for	668
706. earthenware pipes for	467
702. formula for calculating the area of water-way	465
708. iron pipes for	471
932. length of	654
705. materials for	466
971. pipe, specifications for	668
955, 960. specifications for	664, 665
981. staking out	653
821. Curb, setting, specifications for	567
987. stakes for	657
1018. specifications for	682
813. Curbing	562
815. artificial stone	564
822. specifications for	568
817, 819. bluestone, specifications for	566

ARTICLE	PAGE
818. Curbing, circular.....	566
818. dimensions of.....	562
815. fire-clay.....	564
816. granite, specifications for	565
825. hollow, of artificial stone.....	570
815. iron.....	564
814. materials employed for.....	563
823. old, dressing of.....	570
824. resetting, specifications for.....	570
813. setting of.....	562
585. Curves.....	401
586. grade on.....	401
929. staking out of.....	652
610. vertical use of.....	415
587. width of roadway on.....	403
589, 590. Curving and straight roads, difference between.....	403
155. Cushion-coat for granite blocks.....	108
155. quality of sand for.....	108

D

1009. Damage and loss.....	678
42. Damages, consequential.....	15
1004. for non-completion.....	677
842. Data required to calculate the value of improvements.....	580
558. for the location of roads.....	389
181. Death-rate and wood pavements.. ..	127
849. Decreasing the length, profit of.....	582
42. Defective pavements, cost of.....	15
998. work	674
222. Defects of asphalt.....	159
137. Belgian-block pavements.....	101
306. brick pavements.	219
347. broken-stone pavements.....	250
283. coal-tar and asphalt pavements.....	208
398. compacting broken stone by the traffic.....	278
846. existing roads.....	581
143. granite-block pavement.....	102
345. Macadam's pavements.....	250
186. plank and sand foundation.....	180
454. sand foundations.....	320
344. Telford's pavements.....	249
178. wood pavements.....	124
627. Definition of earth-work.....	421
353. maintenance.....	585

ARTICLE	PAGE
899. Disposal of street dirt.....	687
924. Distance apart to plant trees.....	650
283. Distillate pavements in Washington, D. C.....	204
Distinctive marks of cantonniers.....	610
92. Distribution of asphaltum.....	41
692. Ditches, cleaning out.....	459
692. side.....	459
685. Division of natural soils with reference to draining.....	455
689. Drain-tiles, dimensions of.....	457
682. Drainage, kinds of.....	455
452. necessity of.....	319
655. of embankments.....	483
452. foundations.....	319
803. grade-walks.....	554
647. side-slopes.....	426
651. slopes.....	430
758. sub-foundation of streets.....	513
693. the surface of roads.....	459
759. streets.....	516
762. -surface at street-intersections.....	520
683. Draining, methods employed for.....	455
1034. tools for.....	727
668. Drains.....	456
688. cost of.....	457
691. fall of.....	457
form of.....	458
687. materials for.....	456
686. mitre.....	455
687. outlets, protection of.....	456
950. specifications for.....	668
934. staking out.....	655
689. tile.....	457
688. tiles, cost of.....	457
size of (Table LXXVII).....	479
weight of (Table LXXVII).....	479
532. Draught of horses.....	877
830. Dressing of crossing-stones.....	573
149. stone paving-blocks.....	105
773. stones for footpaths.....	528
Drill-holes, capacity of (Table LXVIII).....	442
663. depth of.....	442
663. diameter of.....	442
Drills, steam, price of.....	732
970. Dry box-culverts, specifications for.....	668
969. masonry, specifications for.....	667

ARTICLE	PAGE
721. Dry-stone retaining-walls	486
Dump-cars, capacity of.....	719
670. -wagons.....	444-721
25. Durability and dirt.....	10
61. methods of testing.....	25
779. of asphalt footpaths.....	530
27, 97a, 227. pavements.....	11, 47-166
27, 307. brick pavements.....	11, 221
27, 167. granite blocks.....	11, 143
23. pavements.....	10
27, 193. wood pavements.....	11, 135
Duration of a horse's daily labor and maximum velocity unloaded (Table LIV).....	878
872. Dust, street, composition of.....	621
899. removal of.....	636
866. Duties of the cantonniers.....	604
862. chief foreman....	597
862. foremen.....	597
518. Dynamometer experiments.....	366, 374, 385

E

641. Earth, adhesion of.....	424
645. angle of repose of.....	425
647. effect of moisture on.....	426
669. loosening of.....	444
645. natural slopes of.....	425
840. roads, cost of.....	579
841. maintaining.....	580
load drawn by a horse on (Table LVII).....	380
transverse rise for (Table LXIV).....	418
889. use of scraping-machine on.....	579
640. settlement of.....	423
specific gravity of (Table XXIV).....	97
642. stability of.....	424
670. transport of.....	444
weight of (Table XXIV).....	97
674. -work, calculating the amount of.....	447
949. classification of.....	662
673. cost of.....	445
677. cross-sections.....	448
627. definition of.....	421
634. equalizing of.....	423
641. failure of.....	424
679. formulas for calculation of sectional areas.....	450

ARTICLE	PAGE
676. Earth-work, half-widths and areas.....	448
949. measurement of.....	662
651. slips of.....	428
table of cubic contents.....	453
629. transverse balancing.....	421
706. Earthenware pipe for culverts.....	467
89a. Earthy bitumen.....	89
32. Economic benefit of good pavements.....	13
84. Economies of pavements, the relative.....	14
81. Economy and public bodies.....	12
557. of motive power.....	389
13. smoothness.....	6
1048. relative, of materials.....	806
410. Effect of atmospheric changes on pavements.....	284
888. binding.....	272
892. excessive watering.....	278
307. frost upon mortars.....	351
531. grades upon the load drawn by horses (Table LVIII).....	981
410, 1044. horses' feet on pavements.....	284, 797
647. moisture on earth.....	426
544. narrow tires.....	384
7. reducing the cost of wagon transportation.....	4
475. sand on strength of Portland cement.....	330
504. size of grain of sand on strength of mortar (Table XLVIII).....	350
886. using large quantities of binding.....	271
554. vehicle springs.....	388
410. wheels on pavements.....	284
615. width on cost of maintenance.....	416
89b. Elastic bitumen.....	89
847. Eliminating unnecessary grades, profit of.....	591
652. Embankments ...	430
658. across bogs.....	435
657. marshes.....	433
655. drainage of.....	433
658. formation of.....	430
659. on hillsides.....	436
656. over plains ...	433
654. side-slopes of.....	432
948. specifications for.....	661
987. Engineer defined.....	672
990. Engineer's marks, preservation of.....	673
414. Éngland, amount of material used in, to replace wear on broken-stone pavements.....	289
100c. Epurée.....	54
628. Equalizing earth-work.....	421

ARTICLE	PAGE
186. Failures of wood pavements.....	180
1007. Faithful performance of work, bond for.....	678
691. Fall of drains.....	457
22. Falls of horses, kinds and causes of.....	10
1086. Farrell stone-crusher.....	738
Feldspar, specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
65. Feldspathic rock.....	28
741. Fencing.....	496
743. cost of.....	499
741. specifications for.....	496
354. Fieldstone.....	258
280. Filbert vulcanite pavement.....	202
160, 192. Filling for joints in pavements.....	109, 134
592. Final location.....	404
576. selection of route.....	396
920. Financial value of trees.....	649
476, 489. Fineness of Portland cement.....	331, 338
504. sand for mortar.....	347
815. Fire-clay curb.....	564
956. First-class masonry.....	664
33. cost of pavements.....	18
1018. Flagging, specifications for.....	682
776. Flagstone, specifications for.....	529
Flint, specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
450 <i>d</i> . Florida clay.....	312
96 <i>a</i> . Flux for asphaltum.....	46
14, 524. Foothold, influence of.....	7, 374
786. artificial stone for.....	542
778. Footpaths, asphalt for.....	529
784. brick.....	540
785. specifications for.....	541
782. compressed asphalt-tile.....	539
791. concrete for.....	543
795. specifications for.....	547
770. cross-slope of.....	527
768. definition of.....	527
775. dressing of stones for.....	529
771. foundation of.....	528
774. granite for.....	528
779. life of asphalt.....	530
773. materials employed for.....	528
838. price of.....	576
787. of artificial stone.....	542

ARTICLE	PAGE
796. Footpaths of artificial stone, specifications for.....	548
800. gravel	552
797. tar concrete.....	551
797. specifications for.....	551
773. qualities required.....	528
909. removal of snow from.....	642
780, 781. Footpaths, specifications for asphalt.....	530, 532
769. width of (Table LXXXII).....	508, 527
777. wood for.....	529
527. Force required to sustain a vehicle upon an inclined road.....	377
1003. Forfeiture of contract.....	676
1030. Form of agreement.....	694
1039. bid or proposal.....	693
1081. bond.....	708
636. borrow-pits and spoil-banks.....	423
620. contour suitable for country roadways.....	418
620. street pavements.....	418
1027. contract	688
721. retaining-walls.....	496
649. side-slopes.....	427
687. tiles.....	456
48. traffic census.....	19
652. Formation of embankments.....	430
948. specifications for.....	661
771. footpaths.....	528
801. the Central Park, N. Y., walks.....	552
862. Foreman, duties of.....	597
701. Formula for calculating area of water-way of culverts.....	465
730. thickness of retaining-walls.....	451
1086. Forster's crusher.....	737
452. Foundation, drainage of.....	319
452. essentials necessary to the forming of good.....	319
978. excavation, specifications for.....	671
240. for asphalt pavements.....	174
316. brick pavements.....	223
771. footpaths.....	528
451. pavements.....	319
154. stone pavements.....	108
456. of blast-furnace slag.....	320
457. concrete.....	321
154. thickness of	108
726. retaining-walls.....	490
186. sand, and plank, defects of.....	180
455. manner of forming.....	320
185. used for wood pavements.....	180

ARTICLE	PAGE
959. Fourth-class masonry.....	665
414. France, amount of material used to replace wear of broken-stone pavements.....	289
contract work on roads.....	615
418, 865. cost of maintaining roads in.....	291, 602
355. methods of testing the qualities of broken stone.....	259
865. national roads of.....	602
road commissioners in.....	612, 617
road police in.....	617
taxes in.....	613
task-work on roads in.....	615
866. French system of highway maintenance, regulations for cantonniers (road laborers).....	604
914. Frequency of street sprinkling.....	643
521. Friction, resistance of.....	372
507. Frost, effect of, upon mortars.....	351
411. on roads.....	286
921. Fruit-trees and roads in Saxony.....	649
880. Furnace slag for bricks.....	233
470. concrete.....	327
450a. paving.....	311

G

226. Gas, injurious effects of, on asphalt.....	164
106. tar.....	74
1086. Gates crusher.....	737
158. Gauging of granite blocks.....	107
General stipulations applicable to all contracts.....	672
91a. Gilsonite.....	41, 43
104. price of.....	73
450i. Glass pavement.....	315
specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
65. Gneiss.....	27
specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
605. Grade on mountain roads.....	408
1083. Grader, New Era.....	724
671, 1083. Graders, mechanical.....	444, 723
222, 261. Grades, and asphalt pavements.....	160, 185
899. steam-rollers.....	275
595. tractive power of horses.....	406
596. angles of.....	406

ARTICLE	PAGE
751. Grades at street-intersections, adjustment of.....	507
594. definition of.....	404
595. determination of.....	406
531. effect of, upon the load drawn.....	377
609. establishing the.....	415
532. loads drawn by horses on.....	377
599. maximum.....	407
601. suitable for different paving materials.....	407
608. methods of designating (Table LXII).....	414
606. minimum.....	413
745. of city streets (Table LXXXII).....	500, 508
585. on curves.....	401
847. profit of eliminating.....	581
608. rise in feet per hundred.....	414
608. mile.....	414
540. steep, objections to.....	382
166. pavements on.....	111
752. transverse of street.....	509
607. undulating.....	413
947. Grading, definition of.....	660
947, 1018. specifications for.....	660, 682
1038. tools for.....	711
Grahamite (Table XIVa).....	43
63. Granite, abrasion of.....	26
64. absorptive power of (Table V).....	27
70. amount used for street purposes in 1889 (Table VII).....	80
443. block, artificial.....	308
140. pavement	102
142. advantages of.....	102
874. amount of dirt produced by... ..	624
894. area cleaned by one man.....	635
877. cost of cleaning.....	625
172. construction (Table XXVII).....	118
169. maintaining.....	114
143. defects of.....	102
170. manner of paying for.....	114
173. specifications for.....	120
171. blocks, area covered by one ton (Table XXVI).....	97
65. color of.....	27
816. curb, specifications for.....	565
65. description of.....	27
774. for footpaths.....	528
27. life of.....	11
masonry, weight of (Table XXIV).....	97
167. paving-blocks, durability of.....	113

ARTICLE	PAGE
153. Granite paving-blocks, gauging of.....	107
156. laying off	108
78. manufacture of.....	81
171. number of, to a square yard.....	117
157. ramming of.....	109
168. wear of.....	113
144. quality of.....	104
69. resistance to crushing of (Table VI).....	29
19. slipperiness of.....	9
69. specific gravity of (Table VI).....	29
72. uses of	81
70, 71. value of, used for street purposes in 1889 (Table VII).....	30
69. weight of (Table VI).....	29
650. Grass on slopes.....	428
1043. Gratings for catch-basins.....	786
Gratuitous assistance to travellers.....	600
131. Gravel.....	95
639. and sand, shrinkage of	423
425. character of, for pavements.....	299
381. core for broken-stone pavements.....	270
800. footpaths.....	552
428. laying of	800
424. pavements.....	299
432. cost of construction (Table XLIII).....	801
481. repair of.....	800
428. sprinkling of.....	800
transverse rise for (Table LXIV).....	418
427. preparation of, for paving purposes.....	299
688. shrinkage of.....	423
427. size of, for paving.....	299
181. Tomkins Cove.....	95
181. analyses of.....	96
372, 461. voids in.....	267, 322
812. walks, directions for their construction.....	560
801. in Central Park, New York.....	552
433. weight of.....	301
with clay, specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
525. Gravity, effect of (Table LII) ..	375
Greenstone, specific gravity of (Table XXIV).....	97
62. Grinding test.....	25
44. Gross cost of pavements.....	16
967. Grouting, specifications for.....	667
946. Grubbing, specifications for.....	660
1082. tools for.....	710

ARTICLE	PAGE
50. Guaranteeing pavements.....	21
788. Guard stones.....	494
216c. Gum wood blocks.....	155
Gunpowder, specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
760, 826. Gutters.....	516, 571
828. brick, specifications for.....	573
827. cobblestone, specifications for.....	571
1042 -crossings of cast-iron.....	788
in Central Park, N. Y.....	553
694. on inclines, protection of.....	461
1018. specifications for.....	684
151. stone block.....	105
829. -stones, specifications for.....	573

H

676. Half-widths, calculating the.....	448
325. Hale pavement	282
583. Halting-places.....	401
323. Halwood paving-block.....	231
362, 1036. Hammers for breaking stone.....	265, 734
361. Hand-broken stone.....	265
897, 1040. -brooms, kinds of.....	636, 770
1040. -cart used by street patrol.....	774
362, 1036. -hammers.....	265, 734
465. -made concrete.....	324
1038. -rammers, price of.....	761
892. sweeping.....	685
89c. Hard bitumen.....	39
59, 352. Hardness of stones.....	24, 252
1036. Harrisburg roller.....	755
673. Haul.....	445
822. Hayden paving-block.....	230
423. Heads of specifications for broken-stone pavements.....	297
173. granite-block pavements.....	120
1027. repairing.....	688
262. standard Trinidad asphalt pavement.....	186
213. wood pavement.....	144
Heater for asphalt.....	769
211. Henson wood pavement.....	141
1016. Highway, specifications for construction of a.....	680
625. Hillside roads, form of transverse contour.....	420
659. Hillsides, embankments on.....	436
659. retaining-walls on.....	436

ARTICLE	PAGE
825. Hollow curbs of artificial stone.....	570
370, 1086. Horse power required for stone-crushers.....	267, 787
397. rollers, defects of.....	274
1086. dimensions of.....	752
1086. price of.....	752
work of, at different rates of speed (Table LVI).....	379
532. Horses, draught of.....	377
22. falls of, kinds and causes	10
410, 1044. feet, effect of, on pavements.....	284, 797
536. loads drawn by, on grades (Table LVII).....	379, 794
maximum velocity unloaded (Table LIV).....	378
11, 12. number required to move one ton on different pavements (Table II).....	6
tractive power of, at different velocities (Table LIII).....	378
584. work done by.....	378
1044. Horseshoes and pavements.....	797
78. Hudson River bluestone.....	33
478. Hydraulic cement.....	328
472. lime.....	327

I

Ice, specific gravity of (Table XXIV).....	97
weight of (Table XXIV)	97
104. Imports of asphaltum into the United States in 1890.....	73
212. Improved wood pavements.....	142
834. Improvement of roads.....	577
842. Improvements, value of.....	580
835. Improving clay roads.....	577
837. sand roads.....	579
850. the surface, profit of.....	583
648. Inclinations given to side-slopes in different materials.....	427
699. of culverts.....	465
691. drains.....	457
527. Inclines, force required to sustain vehicles on.....	377
536. loss of tractive power on.....	379
power required to haul one ton up different (Table LIX) ..	383
pressure of vehicles on.....	377
694. protection of gutters on.....	461
597. tractive power required in descending.....	406
991. Incompetent workmen, dismissal of.....	678
790. Increase in bulk of cement.....	548
688. of excavated rock.....	428
766. Increasing width of carriageway at street-intersections.....	525
1020. Indemnification for patent claims	686

ARTICLE	PAGE
1021. Indemnity bond	686
450o. India-rubber pavement	317
461-464. Ingredients for concrete, proportions of	322
1042. Inlet-traps for sewers	786
997. Inspectors	674
765. Instructions regarding street profiles	523
1028. to bidders	689
864. roadmen	600
566. Instruments employed in reconnoitring	391
3. Interests affected in the selection of pavements	2
578. Intermediate towns	398
985. Interpretation of specifications	672
152. Intersection, paving at street	105
450. Iron and wood, combinations of	311
cast, crushing resistance of (Table XXIV)	97
specific gravity of (Table XXIV)	97
984. specifications for	672
weight of (Table XXIV)	97
780. Iron curb	582
450. pavements	311
329. paving-bricks	233
708. pipe-culverts	471
weight of (Table LXXIII)	472
100b. Iron pitch	54
161. Iron, slag, and Portland cement for joint-filling	110
wrought, crushing resistance of (Table XXIV)	97
specific gravity of (Table XXIV)	97
983. specifications for	671
weight of (Table XXIV)	97
438. Italian trackways	306

J

442. Jasperite	307
319. Joint-filling for brick pavements	225
159. stone blocks	109
192. wood pavements	134
161, 319. Murphy's grout	110, 225
161. of Portland cement and iron slag for pavements	110
131. Joints in wood paving, width of	134
706. of pipe-culverts	467
441. Junctions of trackways	307
152. paving at street	105

K

ARTICLE	PAGE
216c. Karri wood pavement.....	154
Keeping tools in repair.....	598-610
99g. Kentucky bituminous sandstone.....	53
682. Kinds of drainage.....	455
796a. Kosmocrete.....	551
188. Kyanizing.....	182

L

881. Laborers' wages in Baltimore.....	680
878. Berlin.....	628
879. Paris.....	629
100, 100p. Lake pitch.....	58-59
100, 100a, 100p. Land pitch.....	58, 54, 59
616. Land, width of, appropriated for road purposes.....	416
884. Layers of broken stone, thickness of.....	271
965. Laying masonry in freezing weather, specifications for.....	666
466. of concrete.....	324
156. granite blocks.....	108
428. the gravel.....	300
Lead, resistance to crushing of (Table XXIV).....	97
specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
887. Leaves on sandy roads.....	579
645. Length and angle of slopes (Table LXVI).....	425
849. decreasing the, profit of.....	582
982. of culverts, to ascertain.....	654
level road equivalent to an inclined road (Table LIX)....	388
148. paving-blocks.....	105
687. tiles.....	456
608. Level stretches.....	414
572. Levels.....	392
779. Life of asphalt footpaths.....	530
27. pavements.....	11
27. brick pavements.....	11
27, 167. granite-block pavements.....	11, 113
27. limestone-block pavements.....	11
444. plank roads.....	308
27. sandstone pavements.....	11
27, 193. wood pavements.....	11, 135
85. Ligonier.....	87
472. Lime, common.....	327
472. hydraulic.....	327
specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97

ARTICLE	PAGE
63. Limestone, abrasion of.....	26
64. absorptive power of (Table V).....	27
amount produced for street purposes in the United States in 1890 (Table XIII).....	37
99b. bituminous.....	44, 51
99d. analysis of.....	51
99f. how used.....	51
27. block pavements, life of	11
82. description of.....	35
84, 165. paving, experience with	86, 111
resistance to crushing of (Table XII).....	37
specific gravity of (Table XII).....	37
88. uses of.....	36
value of, used for street purposes in 1890 (Table XIII) ..	37
weight of (Table XII).....	37
Limestones, bituminous, specific gravity of (Table XXIV).....	97
Liquid bitumen.....	47
specific gravity of (Table XXIV)	97
weight of	97
992. Liquors, spirituous.....	678
99c, 99e. Lithocarbon.....	43, 51
715. Live loads and bridges.....	480
31. Liverpool pavements.....	12
400. Loaded vehicles, pressure of.....	275
536. Loads drawn by horses on grades (Table LVII).....	380, 794
439. moved on trackways.....	307
639. Loam, shrinkage of.....	423
592. Location final.....	404
555. of country roads	389
447. Log roads.....	310
880. London, pavements.....	630
880. street cleaning in.....	630
858. Lose stones on roads.....	588, 607
669. Loosening earth.....	444
671. by machinery.....	444
1009. Loss and damage.....	678
581. of height.....	400
536. tractive power on inclines.....	379

M

434. Macadam, bituminous	301
345. concrete.....	250
343. pavements.....	249
345. analyses of.....	250
1037. roads, tools employed for maintenance of	761

ARTICLE	PAGE
1018. Macadamizing, specifications for.....	682
1086. tools for.....	784
345. MacAdam's method, defects of.....	250
364. Machine-broken stones, objections to.....	266
356a. for cementation test of stone.....	260
492. for testing cement.....	340
511. -mixing of mortar and concretes <i>vs.</i> hand-mixing.....	358
Machines for mixing concrete, price of.....	768
418. Maintenance, broken-stone pavements, cost of.....	290
36. considerations concerning.....	14
860. cost of.....	592
285. asphalt and coal-tar pavements.....	204
852. definition of.....	585
853. necessity of.....	585
265. of asphalt pavements by contract.....	198
233. cost of.....	168
836. clay roads.....	578
857. country roads.....	586
841. earth roads, cost of.....	580
169. granite-block pavements, cost of.....	114
macadam roads, tools employed for.....	784
403. steam-rollers, cost of.....	276
865. the French roads.....	602
206. wood pavements, cost of.....	189
214. by contract.....	147
856. systems of.....	586
88a, 93d, 96d, 98a. Maltha.....	39, 43, 46, 49
1025. Manhole covers, etc., alteration of.....	687
405. Manner of applying the roller.....	280
318. laying brick pavements.....	228
170. paying for granite-block pavements.....	114
415. restoring the thickness of broken-stone pavements.....	289
78. Manufacture of granite paving-blocks.....	31
114. paving-brick.....	79
570. Map.....	392
657. Marshes, embankments across.....	433
956. Masonry, first-class.....	664
959. fourth-class.....	665
965. laying, in freezing weather, specifications for.....	666
957. second-class.....	664
956. specifications for.....	664
958. third-class.....	665
weight of (Table XXIV).....	97
405. Massachusetts Highway Commission, rules for rolling.....	278
356a. tests of stone by.....	260

ARTICLE	PAGE
773. Materials employed for footpaths.....	528
718. for bridges.....	481
705. culverts.....	466
652. embankments.....	430
1023. old, disposal of.....	686
58. paving, selection of.....	24
993. quality of, specifications for.....	673
1048. relative economy of.....	806
994. samples of.....	673
595. Maximum grade.....	406
602. adopted by Telford.....	407
602. the French engineers.....	407
749. of streets in various cities.....	506
605. on mountain roads.....	408
604. to determine.....	408
949. Measurement of earth-work.....	662
999. overhaul.....	674
999. pavements.....	675
999. work.....	675
671. Mechanical graders.....	445, 722
1083. price of.....	722
895. sweepers.....	635
896. cost of operating.....	636
896. price of.....	771
162. Medina sandstone.....	111
905. Melting snow, cost of.....	638
571. Memoir.....	392
209. Mesquite-block pavements.....	141
209. paving.....	141
362. Method of breaking stones by hand.....	265
875. cleaning streets.....	624
682. Methods employed for draining.....	455
61. testing durability.....	25
Mica, specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
896. Mineral caoutchouc.....	39
93. Mineral pitch.....	42
88a, 94. tar.....	39, 44
606. Minimum grade.....	413
722. thickness of retaining-walls.....	486
613. width of roads.....	416
1010. Miscellaneous work, specifications for.....	678
686. Mitre-drains.....	455
465. Mixing concrete.....	824
842. Modern macadam pavements.....	249

ARTICLE	PAGE
342. Modern Telford pavements.....	249
647. Moisture, effects of, on earth.....	426
56. Money wasted in opening pavements.....	23
763. Monuments.....	520
64. Mortar, absorptive power of (Table V).....	27
500. adhesive strength of (Table XLV).....	345
484. amount of water required for.....	335
495. characteristics of.....	342
494. composition of.....	343
502. compressive strength of.....	347
505. effect of age on strength of.....	350
507. frost upon.....	351
504. size of grain of sand on strength of (Table XLVIII).....	350
471. for concrete.....	327
506. permeability of.....	351
496. quality of sand for.....	342
497. water for.....	243
501. shearing strength of (Table XLVI).....	346
specific gravity of (Table XXIV).....	97
976. specifications for.....	670
499. strength of.....	344
503. tensile strength of (Table XLVII).....	347
weight of (Table XXIV).....	97
557. Motive power, economy of.....	339
579. Mountain roads.....	400
605. grade on.....	458
582. water on.....	401
617. width of.....	417
872. Mud, composition of (Table LXXXV).....	621
specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
161, 819. Murphy's grout for joint-filling.....	111, 225

N

1042a. Name-plates for streets.....	789
79. Names, commercial, of sandstone.....	84
88a, 91. Naphtha.....	89, 41
specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
544. Narrow tires.....	884
865. National roads of France.....	602
478. Natural Portland cement.....	328
645. slopes of earth (Table LXV).....	426
890. Necessity of binding.....	272
858. maintenance.....	585

ARTICLE	PAGE
886. New York, street-cleaning in.....	682
43. Noisy pavements, objections to.....	16
93. Nomenclature of asphaltum.....	42
866. Nomination of cantonniers.....	605
1004. Non-completion, damages for.....	677
989. Notice to contractors.....	672
450j. Novaculite.....	315
Number of cubic yards of broken stone required for different widths (Table XL).....	271
171. granite blocks to a square yard (Table XXVI).....	117
11. horses required to move one ton on different pavements.....	6
188. wood blocks to a square yard.....	129

O

1. Object of pavements.....	1
613. raising the centre of roads.....	418
222. Objections to asphalt pavements.....	159
137. Belgian block pavements.....	101
134. cobblestone pavements.....	99
588. crookedness.....	403
43. dusty pavements.....	16
148. granite-block pavements.....	102
397. horse rollers.....	274
347. Macadam pavements.....	250
364. machine-broken stones.....	266
43. noisy pavements.....	16
540. steep grades.....	382
344. Telford pavements.....	249
395. traffic consolidation.....	273
695. water-breaks.....	461
179. wood pavements.....	125
591. zigzags.....	403
17. Observations in London on slipperiness of pavements.....	8
16. United States on slipperiness of pavements.....	8
92. Occurrence of asphaltum.....	41
953. Off-take ditches, specifications for.....	668
1043b. Oil for sprinkling roads.....	795
435. Old asphalt and broken stone.....	302
1023. materials, disposal of.....	686
986. Omissions in specifications.....	672
368. Operating stone crushers, cost of.....	266
403. steam-rollers, cost of.....	276
38. Opinions, prevailing, concerning pavements.....	15
862. Organization of road force.....	596

ARTICLE	PAGE
862. Organization of road force accounts.....	599
862. county engineer.....	599
862. chief foreman.....	597
862. foremen.....	597
862. number of men required.....	596
862. roller.....	598
862. snow.....	599
862. storage and delivery of broken stone.....	599
862. team labor and materials.....	598
862. tools.....	598
91. Origin of bitumen.....	41
687. Outlets, drain, protection of.....	456
678, 999. Overhaul, how measured.....	445, 674

P

735. Parapets.....	493
735. height of.....	493
964. specifications for.....	666
735. thickness of.....	493
879. Paris, street-cleaning in.....	629
1000. Partial payments.....	675
1020. Patent claims, indemnification for.....	686
880. Patrol system in London.....	630
29. Pavement, the cheapest.....	11
9. Pavements, adaptability of.....	4
874. amount of dirt produced by different.....	624
1044. and horseshoes.....	797
10. and popular prejudice.....	5
1047. annual cost of.....	806
450/, 786. artificial stone.....	814, 542
136. Belgian block.....	101
304. brick.....	219
335. broken-stone.....	246
346. advantages of.....	250
396. rolling.....	274
393. compacting the stone.....	273
393. by rollers drawn by horses....	273
393. by steam-rollers.....	273
393. the traffic.....	273
347. defects of.....	250
380. failure of thin.....	270
421. in Bridgeport, Conn.....	292
420. Chicago.....	292
419. England.....	291
413. loss of thickness, average annual.....	289

ARTICLE	PAGE
417. Pavements, broken-stone, recoating, when it should be done.....	290
428. specifications for.....	297
388. spreading the stone.....	270
378. thickness of.....	269
384. the layers.....	271
409. wear of.....	284
39. care of.....	14
201, 208, 216. cedar-block.....	187, 140, 151
40. cleansing of.....	15
184. cobblestone.....	99
comparative merit of (Table IV).....	21
28. considerations concerning cost of.....	11
216a. cottonwood blocks.....	155
10. desirability of	5
55. destruction of.....	22
28. durability of.....	10
32. economic benefit of good.....	13
410. effect of atmospheric changes on.....	284
451. foundations.....	319
460. character of concrete for.....	322
457. concrete for.....	321
140. granite-block.....	102
44. gross cost of.....	16
50. guaranteeing.....	21
216a. gum blocks.....	155
325. Hale brick.....	232
325. Hale system.....	232
323. Halwood system.....	231
322. Hayden system.....	230
211. Henson's system.....	141
3. interests affected in the selection of.....	2
load drawn by a horse on different (Table LVII).....	380
216c. Karri wood.....	154
345. macadam, analyses of.....	250
999. measurement of.....	675
209. mesquite block.....	141
1. object of.....	1
292. of asphalt block.....	208
208. cedar blocks.....	140
281. coal-tar.....	208
281. and asphalt.....	208
424. gravel.....	299
432. cost of construction.....	301
450. iron.....	311
31. Liverpool.....	11

ARTICLE	PAGE
309. Pavements of mesquite-block.....	141
166. on steep grades.....	111
451. permanence of.....	319
216 <i>d</i> . pine block.....	155
2. qualities of good.....	1
216 <i>f</i> . redwood block.....	155
84. relative economies of.....	14
15. safety of.....	7
454. sand as a foundation for.....	820
14. serviceability of.....	7
451. stability of.....	319
280. vulcanite.....	202
56. waste of money in opening.....	28
152. Paving at street-junctions.....	105
148. blocks, length of.....	105
73. makers, wages of.....	82
73. manufacture of granite.....	81
71. price of.....	80
146. shape of.....	104
146. size of.....	104
147. width of.....	104
63. brick, abrasion of.....	26
64, 119. absorptive power of (Table V).....	27, 86
117. characteristics of good.....	82
111. clay for.....	78
114. manufacture of.....	79
prices of (Table XXI).....	86
119. resistance to crushing of (Table XXIV).....	86, 97
size of.....	86
119. specific gravity of (Table XXI).....	86, 97
119. weight of (Table XXI).....	86
58. material, selection of.....	24
106. pitch.....	74
1005. Payment of claims.....	677
1018. workmen.....	679
1000. Payments, partial.....	675
1015. when made.....	679
Peat, weight of (Table XXIV).....	679
108 <i>a</i> . Penetration tests of bitumen.....	62
421. Permanence of pavements.....	319
506. Permeability of mortars.....	851
Peruvian asphaltum (Table XIV <i>a</i>).....	851
519. Penetration, resistance of.....	267
88 <i>a</i> , 91. Petroleum.....	39, 41
97 <i>b</i> . residuum.....	47

ARTICLE	PAGE
97 <i>d</i> . Petroleum residuum, specification for.....	49
97 <i>b</i> . test for.....	47
specific gravity of (Table XXIV).....	97
weight of (Table XXIV)	97
90, 90 <i>a</i> . Petrolene.....	40
183. Philadelphia, cobblestone pavements in.....	99
887. street-cleaning in	632
415. Picks on steam-rollers, objectionable.....	289
981. Piles, specifications for	671
216 <i>d</i> . Pine wood paving blocks.....	155
706. Pipe-culverts	467
971. specifications for.....	668
iron, dimensions, weight, and price of (Table LXXIII).....	472
707. vitrified, dimensions, weight, and price of (Table LXXI)	471
Pipes, discharging capacity of (Table LXXVIII).....	479
483. Pit-gravel, weight of.....	301
88 <i>a</i> , 98. Pitch, mineral.....	39, 42
106. paving.....	74
specific gravity of (Table XXIV)	97
weight of	97
656. Plains, embankments over	433
186. Plank-and-sand foundation, defects of.....	130
444. roads.....	308
445. construction of.....	308
446. cost of.....	310
446. life of.....	310
995. Plans and specifications, deviations from.....	673
1083. Ploughs, cost of operating	711
1083. for grading, price of.....	711
1083. quantity of material loosened with.....	711
966. Pointing, specifications for.....	667
59. Porosity of paving materials.....	24
Porphyry, specific gravity of (Table XXIV).....	97
weight of (Table XXIV)	97
1085. Portable boilers, price of.....	733
1086. engines, price of.....	747, 748
475. Portland cement.....	329
476. characteristics of.....	331
476. contraction of.....	332
509. English, specifications for.....	357
476. expansion of.....	332
476. fineness of	331, 335
476. specific gravity of.....	332
972. specifications for	669
476. tensile strength of.....	332

ARTICLE	PAGE
477. Portland cement, tests for.....	333
478, 501. weight of.....	331, 346
10. Popular prejudice and pavements	5
518. Power required to draw wheels over obstacles.....	366
haul one ton up different inclines (Table LIX)...	338
1008. to suspend work.....	678
99f. Preparation of the bituminous limestone.....	51
99g. bituminous sandstones	52
424. gravel for paving.....	299
516. roadbed, specifications for.....	362
100e. Trinidad asphaltum.....	55
990. Preservation of engineer's marks.....	678
188. wood.....	181
Pressed brick, resistance to crushing of (Table XXIV).....	97
specific gravity of.....	97
weight of.....	97
400. Pressure of loaded vehicles.....	275
397. rollers.....	274
528. vehicles on inclines.....	877
38. Prevailing opinions concerning pavements.....	12
334e. Price of paving-brick.....	245
1014. Prices in contract.....	679
104. of asphaltum in New York in 1898.....	73
161. bituminous cement.....	110
104. California bituminous rock.....	78
883. footwalk materials.....	576
104. gilsonite.....	78
71. granite blocks.....	30
1038. mechanical graders.....	722
paving-brick (Table XXI)	87
129. sand.....	94
367, 368. stone-crushers.....	266
1040. tools for cleaning.....	770
1032. clearing.....	710
1038. grading.....	711
1032. grubbing.....	710
1036. macadamizing.....	784
1037. maintenance.....	761
675. Prismoidal formula.....	447
8. Problem involved in the selection of pavements	4
104. Production of bituminous rock in the United States in 1898 (Table XVIII).....	73
bluestone in the United States in 1889 (Table XI)...	85
granite in the United States in 1889 (Table VII).....	30
limestone in the United States (Table XIII).....	37

ARTICLE	PAGE
104. Production of sandstone for street purposes in 1889 (Table X),.....	35
574. Profile.....	395
593. construction.....	404
765. Profiles, street.....	523
849. Profit of decreasing the length.....	582
847. eliminating unnecessary grades.....	581
850. improving the surface.....	583
1008. Progress of work	676
389. Properties of binding adopted by the French engineers.....	272
100. Trinidad asphaltum.....	54
426. Proportion of clay to gravel.....	299
716. Proportioning of bridges.....	480
461, 462. Proportions of ingredients for concrete.....	322
464. usual for concrete.....	323
253. materials used in the manufacture of Trinidad asphalt pavements.....	182
724. retaining-walls.....	486
1029. Proposal, form of.....	693
689. Protection of drain-outlets.....	457
694. gutters on inclines.....	460
1006. persons and property.....	677
784. roads.....	492
927. trees.....	651
31. Public bodies and economy.....	12

Q

314. Quality of bricks	222
830. cross-stones	573
776. flagstones.....	529
144. granite	104
425. gravel for roads.....	299
993. materials	673
459. materials for concrete.....	322
495. mortar.....	342
126. sand.....	94
155. for cushion-coat.....	108
349, 351. stone for broken-stone pavements	251, 252
459. concrete.....	321
497. water for mortar	343
187. wood for paving.....	131
2. Qualities of good pavements.....	1
780. required in footpaths.....	530
382. Quantity of broken stone required per mile for different widths (Table LX).....	270

ARTICLE	PAGE
1088. Quantity of material loosened with ploughs.....	711
464. materials required for one cubic yard of concrete.....	823
128. sand required for bedding-blocks.....	94
336. stone broken by hand.	246
367, 1086. machines.....	266, 734
463. water required for concrete.....	823
498. mortar.....	348
913. street sprinkling.....	648
371. Quarrying stone, cost of (Table XXX).....	267
Quartz, weight of (Table XXIV).....	97
specific gravity of (Table XXIV).....	97
67. Quartzite.....	28
487. Quick- and slow-setting cements, definition of.....	387

R

1033. Rails, weight of.....	720
19. Rain and asphalt pavement.....	9
411. effect of, on roads.....	284
699. Rainfall, amount of.....	464
466. Rammers for concrete, dimensions of.....	324
1038. hand, price of.....	762
1088. weight of.....	762
466. Ramming, amount required for concrete.....	324
466. concrete.....	324
158. granite-blocks.....	109
897. Rattan brooms.....	686
61. Rattler tests.....	25
417. Recoating broken-stone pavements, when it should be done.....	290
558. Reconnaissance.....	389
834. Reconstruction of roads.....	577
863. Records.....	600
189. Rectangular wood blocks.....	138
2167. Redwood paving blocks.....	155
95. Refined asphaltum.....	44
100n. specific gravity of.....	58
751. Refuges at street-intersections.....	507
878. Refuse, amount collected from streets (Table LXXXVI).....	623
899. disposal of.....	636
866. Regulations for cantonniers.....	604
34. Relative economies of pavements.....	14
832. Relaying bridge-stones, specifications for.....	575
900. Removal of snow.....	637
907. from footpaths.....	639
902. in Milan.....	637

ARTICLE	PAGE
861. Repair of broken-stone pavements.....	596
431. gravel pavements.....	300
1024. Repairs, security retained for.....	687
1026. Repaving, specifications for.....	687
862. Requisitions for tools, etc.....	599
521. Resistance of friction.....	372
525. gravity (Table LII).....	375
519. penetration.....	367
to crushing of basalt (Table XXIV).....	97
bluestone (Table IX).....	85
bricks (Table XXIV).....	97
cast iron (Table XXIV).....	97
chalk (Table XXIV).....	97
common hard brick (Table XXIV).....	97
concrete (Table XXIV).....	97
69. granite (Table VI).....	29
lead (Table XXIV).....	97
85. Ligonier "granite".....	37
limestones (Table XII).....	37
119. paving-bricks.....	86, 88, 97
pressed bricks (Table XXIV).....	97
81. sandstones (Table IX).....	34
soft brick (Table XXIV).....	97
steel (Table XXIV).....	96
Stourbridge brick (Table XXIV).....	97
87. trap-rocks (Table XIV).....	38
wood (Table XXII).....	92
wrought-iron (Table XXIV).....	97
517. traction.....	366
on different road surfaces (Table L).....	372
721. Retaining-walls.....	486
728. and springs.....	491
726. dry-stone.....	490
727. failure of.....	491
725. form of.....	490
780. formula for thickness of.....	491
726. foundation of.....	491
780. minimum thickness of.....	491
659. on hillsides.....	486
724. proportions of.....	486
954. specifications for.....	663
733. where they should be built.....	492
90, 90a. Retine.....	40
1036. Revolving stone screens, price of.....	640
996. Right reserved to alter details.....	673

ARTICLE	PAGE
1036. Ring gauge.....	784
953. Rip-rap, specifications for.....	663
Rise, amount of transverse (Table LXIV).....	418
739. River-banks, roads along.....	494
862. Road force, organization of.....	592
1033. -leveller, price of.....	726
1033. use of.....	726
1033. machines, price of.....	622
-surface, resistance to traction on different (Table L).....	872
1036. Roadbed roller, form of.....	735
1036. price of.....	735
1036. weight of.....	735
516. specifications for preparation of.....	862
864. Roadmen, instructions to.....	600
862. number required.....	596
584. Roads, alignment of.....	491
739. along river-banks.....	494
739. the seashore.....	494
448. charcoal.....	810
835. clay.....	577
447. corduroy.....	810
555. country, location of.....	889
846. defects of existing.....	581
662. drainage of.....	455
865. French, maintenance of.....	602
424. gravel.....	299
447. log.....	810
865. national, of France.....	602
number of acres required per mile for different widths of (Table LXIII).....	417
444. plank.....	308
734. protection of.....	492
834. reconstruction of.....	577
837. sand.....	579
625. transverse contour.....	420
919. trees on.....	648
611. width of.....	416
660. Roadways on rock-slopes.....	488
618. transverse contour of.....	418
661. Rock-cliffs, manner of forming roads along.....	439
662. excavations.....	441
664. cost of.....	448
1035. tools for.....	622
639. increase in bulk of....	423
662. quantity of, loosened by blasting.....	441

ARTICLE	PAGE
660. Rock slopes, roadways on	488
86. Rock, trap	38
397. Rollers, horse, defects of	274
1036. dimensions of	752
1036. price of	752
397. pressure of	274
396. steam, advantages of	274
401. area rolled per day	276
1036. dimensions of	756
405. manner of applying	286
404. speed of	277
404. Rolling, amount required for broken-stone pavements	277
406. cost of	286
453. foundations	319
520. resistance of wheels	371
Roman cement, specific gravity of (Table XXIV)	97
weight of (Table XXIV)	97
478. Rosendale cement	328
973. specifications for	669
tests for	669
478. weight of	329
26. Roughness and durability	11
182. Round wood blocks	129
576. Route, principles to be observed in final selection of	396

S

15. Safety of pavements	7
907. Salt used for the removal of snow	639
994. Samples of materials	673
123. Sand	93
639. and gravel, shrinkage of	423
454. as a foundation for pavements	320
126. cleanness of	94
381. core for broken-stone pavements	270
317a. cushion	223
475. effect of, on Portland cement	329
504. size of grain on strength of mortar (Table XLVIII) ..	350
127. for concrete	94
155. cushion-coat of stone blocks	108
504. mortar, fineness of	347
453. foundations, defects of	319
454. manner of forming	320
496. in mortar	343
223. injurious effects of, on asphalt pavement	160

ARTICLE	PAGE
129. Sand, price of.....	94
126. quality of.....	94
128. quantity required for bedding block.....	94
..... road, load drawn by a horse on (Table LVII).....	880
887. roads, improving of.....	578
887. trees of.....	569
125. sharpness of.....	94
128. size of, for paving purposes.....	93
504. sieves for sifting (Table XLIX).....	850
..... specific gravity of (Table XXIV).....	98
974. specifications for.....	669
126. to test.....	94
124. use of.....	93
916a. to prevent slipping.....	646
127, 462. voids in.....	94, 322
130. weight of (Table XXIV).....	94, 98
127. with clay.....	94
64. Sandstone, absorptive power of (Table V).....	27
79. amount produced for street purposes in 1889.....	35
..... analysis of (Table VIII).....	33
99g. bituminous, in America.....	52
99g. Europe.....	52
102. analysis of.....	61
99g. preparation of.....	52
164, 172. block pavements, cost of construction.....	111, 117
79. commercial names of.....	34
74. description of.....	32
27. pavements, life of.....	11
81. resistance to crushing of (Table IX).....	34
81. specific gravity of (Table IX).....	34
79. value of, used for street purposes in 1889 (Table X)....	35
..... weight of (Table IX).....	34
182. Sapless cedar blocks.....	129
1086. Scarifiers.....	758
1040. Scoop used by street patrol.....	775
670, 1088. Scrapers.....	444, 713
1088. capacity of.....	713
1083. cost of.....	713
1040. Scraping-machines.....	778
839. improper use of.....	579
839. on earth roads.....	579
350, 387. Screening the broken stone.....	251, 272
739. Seashore, roads along.....	494
916. water for street sprinkling.....	645
957. Second-class masonry.....	664

ARTICLE	PAGE
1024. Security retained for repairs.....	687
575. Selection of bridge sites.....	895
8. pavements, interests affected in the.....	2
58. paving-material.....	24
922. trees.....	649
Serpentine, specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
41. Service of pavements, cost of.....	15
14. Serviceability of pavements.....	7
821. Setting curb, specifications for.....	567
476. of Portland cement.....	832
987. stakes for curb.....	657
640. Settlement of earth.....	423
1041. Sewer inlet-traps.....	787
1023. Sewers, right to construct.....	686
Shales, specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
313. Shape of bricks.....	222
357. stone for broken-stone pavements.....	265
146. paving-blocks.....	104
182. wood paving-blocks.....	129
125. Sharpness of sand.....	94
501. Shearing strength of mortar (Table XLVI).....	846
132. Shingle.....	98
specific gravity of (Table XXIV).....	98
weight of (Table XXIV).....	98
670, 1033. Shovels.....	444, 711
639. Shrinkage of clay.....	423
639. earth.....	423
639. gravel.....	423
639. and sand.....	423
639. loam.....	423
639. vegetable soil.....	423
692. Side ditches.....	459
649. Side slopes, form of.....	427
648, 650. inclination of.....	427
654. of embankments.....	432
930. staking out.....	652
Sidewalks, average width of, in various cities (Table LXXXII).....	508
504. Sieves, size of, for sifting sand (Table XLIX).....	350
686. Silicious soils, drainage of.....	455
687. Silt basins.....	456
Sinking fund that with compound interest will amount to \$1 at the end of a term of years (Table XC).....	803
1046. Sinking funds.....	806

ARTICLE	PAGE
67. Sioux Falls stone.....	28
313. Size of bricks.....	223
131. gravel for paving	95
123. sand for paving purposes.....	94
504. sieves for testing sand (Table XLIX).....	350
367, 368. stone-crushers.....	266, 740
357. for broken-stone pavements.....	265
459. concrete	322
146. paving-blocks.....	104
182. wood paving-blocks.....	129
549. wheels.....	386
450b. Slag-blocks.....	311
Slate, specific gravity of (Table XXIV).....	98
weight of (Table XXIV),.....	98
19. Slipperiness of asphalt.....	9
21. and wood, cure for.....	10
19. granite.....	9
19. wood.....	9
651. Slips	428
916a. Slipperiness, use of sand to prevent	646
645. Slope, angles and length of (Table LXVI).....	425
788. of footpaths	542
954. -walls, specifications for.....	668
650. Slopes, covering of	428
651. drainage of	480
natural, of earth (Table LXV).....	425
654. of embankments	432
946. Sloping ground, specifications for preparation of.....	661
487. Slow-setting cement.....	387
13. Smoothness, economy of.....	6
906. Snow, disposal of.....	689
-ploughs, form of	788
900. removal of.....	637
903. cost of.....	688
907. from footpaths.....	589
902. in Milan.....	637
908. weight of (Table XXIV).....	97, 640
Soapstone, specific gravity of (Table XXIV).....	98
weight of (Table XXIV).....	98
Soft interior brick, resistance to crushing of (Table XXIV).....	97
specific gravity of (Table XXIV).....	97
weight of (Table XXIV).....	97
453. Soils, natural character of.....	319
100. Source of Trinidad asphaltum	52
470. Specific gravity of American natural cements.	328

ARTICLE	PAGE
89a. Specific gravity of asphaltum.....	89, 97
basalt (Table XXIV).....	97
bluestone (Table XI).....	35
brick masonry (Table XXIV).....	97
cast iron (Table XXIV).....	97
chalk (Table XXIV).....	97
clay (Table XXIV).....	97
with gravel (Table XXIV).....	97
common hard brick (Table XXIV).....	97
460. concrete (Table XXIV).....	97, 822
crude asphaltum.....	55
earth (Table XXIV).....	97
English Portland cement (Table XXIV).....	97
feldspar (Table XXIV).....	97
flint (Table XXIV).....	97
glass (Table XXIV).....	97
gneiss (Table XXIV).....	97
69. granite (Table VI).....	29
gravel with clay (Table XXIV).....	97
greenstone (Table XXIV).....	97
gunpowder (Table XXIV).....	97
ice (Table XXIV).....	97
lead (Table XXIV).....	97
lime (Table XXIV).....	97
limestone (Table XXII).....	37
liquid bitumen (Table XXIV).....	97
mica (Table XXIV).....	97
mortar (Table XXIV).....	97
mud (Table XXIV).....	97
naphtha (Table XXIV).....	97
119. paving-brick (Table XXIV).....	86, 97
petroleum (Table XXIV).....	97
pitch (Table XXIV).....	98
porphyry (Table XXIV).....	98
476. Portland cement (Table XXIV).....	97, 832
pressed brick (Table XXIV).....	97
quartz (Table XXIV).....	98
89. refined asphaltum.....	40
refined Trinidad asphaltum.....	58
Roman cement (Table XXIV).....	97
sand (Table XXIV).....	98
81. sandstones (Table IX).....	34
serpentine (Table XXIV).....	98
shales (Table XXIV).....	98
shingle (Table XXIV).....	98

ARTICLE	PAGE
81. Specific gravity of slate (Table XXIV).....	98
soapstone (Table XXIV).....	98
soft inferior brick (Table XXIV).....	97
steel (Table XXIV)	98
Stourbridge fire-brick (Table XXIV).....	97
trap-rocks (Table XIV).	38
Trinidad asphaltum	40, 58
water (Table XXIV).....	98
wood (Table XXII).....	92
wrought-iron (Table XXIV).....	97
943. Specifications, definition of.....	660
995. deviation from.....	678
509. (English) for Portland cement	357
1017. for a bulkhead	681
960; 961. arch-culverts.....	665, 666
823. artificial curb and gutter.....	568
979. foundations	671
796. stone footpaths.....	548
pavements.....	314
296. asphalt-block pavements.....	210
780, 781. footpaths	530, 532
263. pavement on bituminous base.....	191
264. hydraulic concrete base....	193
136. Belgian-block pavements.....	101
303. bituminous-rock pavements.....	212
818. bluestone curb.....	566
954. breast-walls.....	663
828. brick gutters.....	572
331-334. pavements.....	238, 240
784. footpaths.....	541
968. masonry	667
830-831. bridge-stones.....	573, 575
715. bridges.....	480
423. broken-stone pavements.....	297
984. cast iron.....	673
291. coal-tar and asphalt pavements.....	205
1018. catch-basins.....	685
951. water-ditches.....	668
972. cement	669
962. centring.....	566
944. clearing.....	660
1011. cleaning up.....	679
945. close cutting.....	660
135. cobblestone pavements.....	98
982. cofferdams....	671

ARTICLE		PAGE
782.	Specifications for compressed-asphalt-tile footway-pavement.....	539
795.	concrete footpaths.....	547
512-516, 977.	concretes.....	359-362, 670
803 <i>d</i> .	condition of asphalt pavements at end of guaran- tee period.....	217
880.	crossing-stones.....	573
960.	culverts.....	665
1018.	curbing.....	682
950.	drains.....	663
823.	dressing old curb.....	570
970.	dry box-culverts.....	668
969.	walls.....	667
948.	embankments.....	661
1018.	flagging.....	682
776.	flagstones.....	529
741.	fencing.....	496
978.	foundation excavation.....	671
947.	grading.....	660
178.	granite-block pavements.....	120
816.	curb.....	585
967.	grouting.....	667
946.	grubbing.....	660
829.	gutter-stones.....	573
828.	gutters.....	572
450 <i>g</i> .	hydraulic-cement pavement.....	314
827.	laying cobblestone gutters.....	571
965.	masonry in freezing weather.....	666
1018.	macadamizing... ..	682
956.	masonry.....	664
1010.	miscellaneous work.....	678
976.	mortars... ..	670
952.	off-take ditches.....	668
964.	parapets... ..	666
97 <i>d</i> .	petroleum residuum.....	49
981.	piles.....	671
971.	pipe-culverts.....	668
966.	pointing.....	667
516.	preparation of roadbed.....	362
948.	sloping ground.....	661
927.	protection of trees.....	651
993.	quality of materials.....	673
882.	relaying crossing-stones.....	575
308 <i>e</i> .	repair of asphalt pavements.....	215
1026.	repaving.....	667
824.	resetting curb.....	570

ARTICLE	PAGE
954. Specifications for retaining-walls.....	668
958. rip-rap.....	668
974. sand.....	669
820. setting curb.....	567
954. slope walls.....	668
1081b. for sprinkling.....	706
262. Standard Trinidad asphalt pavements.....	186
1027. street cleaning.....	688
797. tar-concrete footpaths.....	551
1081a. team labor.....	705
389, 422. Telford's pavement.....	247, 298
960. timber.....	671
1016. the construction of a highway.....	680
1019. the supply of broken stone.....	685
338. Tresaguet's pavement.....	246
975. water.....	670
968. wing-walls.....	666
218, 216. wood block pavements.....	144, 151
968. wrought-iron.....	671
985. interpretation of.....	672
986. omissions in.....	672
473. requirements for American natural cements.....	828
996. right to alter details in.....	678
334. variations in, for brick pavements.....	240
895. Speed of machine-brooms.....	635
404. steam-rollers.....	277
401. Spikes in steam-rollers, defects of.....	276
1033. number of, per mile of track.....	720
1033. size of.....	720
992. Spirituous liquors.....	673
1033. Splice-joints, number of, per mile.....	720
683. Spoil-banks.....	422
636. form of.....	422
388. Spreading the broken stone.....	270
1036. Springfield steam-roller.....	755
554. Springs on vehicles, effect of.....	388
728. behind or below retaining-walls.....	491
859. Sprinkling, amount of water required.....	590
859. broken-stone pavements, amount of water required for.....	590
1081b. specifications for.....	706
911. Sprinkling of streets.....	642
1036-1040. carts, capacity of.....	735, 773
1036-1040. prices of.....	735, 773
897. Squilgees for asphalt.....	686
prices of.....	770

ARTICLE	PAGE
888. St. Louis, street-cleaning in.....	633
889. St. Paul, street-cleaning in.....	633
644-646. Stability of earth....	425
451. pavements.....	319
637. Staking out borrow-pits.....	423
938. bridges.....	655
931. culverts.....	652
929. curves.....	652
934. drains.....	655
930. side-slopes.....	652
936. street contours.....	656
938. structures.....	657
935. vertical curves.....	655
928. work.....	652
767. Statistics of streets for each of fifty of the largest cities in the United States (Table LXXXIII).....	526
Steam-drills, price of.....	732
402. -rollers, and grades.....	276
404. area rolled per day.....	277
403. cost of maintaining.....	276
dimensions of.....	765
405. manner of applying.....	278
415. picks on, objectionable.....	289
404. speed of.....	277
Steel, resistance to crushing of (Table XXIV).....	97
specific gravity of (Table XXIV).....	97
450n. trackways.....	316
weight of (Table XXIV).....	97
397. wire brooms.....	636
402. Steepest grade upon which a steam-roller can be operated.....	276
541. Steep grades, objections to.....	332
166. pavements on.....	111
64. Stone, absorptive power of.....	26
412. amount of, worn away annually from broken-stone pavements.....	289
877. -block pavement, cost of cleaning.....	626
load drawn by a horse on (Table LVII)....	380
1088. tools used in the construction of.....	761
transverse rise for (Table LXIV).....	418
601. pavements, maximum grade for.....	407
159. blocks, joint-filling for.....	109
392. broken, quantity required per mile of different widths.....	370
355. coefficients of quality for broken-stone pavements (Table XXXVIII).....	259
1086. crushers, capacity of.....	737
1086. cost of.....	737

ARTICLE	PAGE
867. Stone crushers, cost of operating.....	266
1036. horse-power required for.....	737
1036. price of.....	737
1036. size of.....	737
368. wear of.....	266
1036. weight of.....	737
871. crushing, cost of (Table XXX).....	267
1036. forks, price of.....	734
151. gutters.....	105
1036. hammers, price of.....	734
133. pavements.....	99
152. paving-blocks at street-junctions.....	105
153. culling of.....	107
149. dressing of.....	105
351. quality of, for broken-stone pavements.....	252
459. concrete.....	321
371. quarrying, cost of (Table XXXIX).....	268
1036. rakes, price of.....	734
359. shape of, for broken-stone pavements.....	265
357. size of, for broken-stone pavements.....	265
438. for trackways.....	306
437. trackways.....	308
365. Stones, breaking by hand.....	266
362. Storage and delivery of broken stone.....	599
Stourbridge fire-brick, specific gravity of (Table XXIV).....	97
resistance to (Table XXIV).....	97
crushing of (Table XXIV).....	97
weight of (Table XXIV).....	97
1036. Straight-edge, use of.....	734
225. Street-car rails and asphalt.....	163
31. tracks, city ownership of.....	13
368. -cleansing.....	619
398. carts and wagons.....	636
398. cost of.....	635
397. hand-brooms for.....	636
381. in Baltimore.....	630
378. Berlin.....	628
382. Boston.....	630
383. Brooklyn.....	632
384. Cleveland.....	632
385. Detroit.....	632
380. London.....	630
386. New York.....	632
379. Paris.....	629
387. Philadelphia.....	632

ARTICLE	PAGE
888. Street-cleansing in St. Louis.....	633
889. St. Paul.....	633
890. Washington, D. C.	633
1027. specifications for.....	688
876. systems of.....	624
899. dirt, disposal of.....	686
872. dust, composition of.....	621
749. grades.....	506
grades in various cities (Table LXXXII).....	508
751. intersections, arrangement of.....	507
766. carriageway at.....	525
766. increasing width of.....	525
925. trees at.....	650
152. junctions, paving with stone blocks.....	105
763. lines and monuments.....	520
maintenance, annual cost per head of population in several cities of the United States (Table LXXXVII).....	627
875. methods of cleansing.....	624
872. mud, composition of (Table LXXXV).....	622
1042a. name plates.....	789
891. orderly system.....	684
878. patrol in Berlin.....	629
765. profiles.....	523
911. sprinkling.....	643
911. cost of.....	643
914. frequency of.....	643
913. quantity of water required.....	643
916. sea-water for.....	645
912. systems of.....	643
767. Street statistics for each of fifty of the largest cities in the United States (Table LXXXIII).....	526
745. Streets, city.....	500
57. excavations in.....	23
758. subfoundation, drainage of.....	513
759. surface-drainage of.....	514
893. sweeping, cost of.....	685
756. transverse contour of.....	512
752. grade of.....	509
917. trees on.....	647
910. washing.....	642
747. width of.....	506
in various cities (Table LXXXII).....	508
468. Strength, compressive, of concrete.....	325
478. of cements.....	328
460-468. concrete.....	322-325

ARTICLE	PAGE
491, 499. Strength of mortar.....	889, 844
1045. Structures, annual cost of.....	797
938. setting stakes for	657
1012. Subletting contract.....	679
720. Substructure of bridges.....	483
723. Surcharged walls.....	486
731. formula for.....	491
693. Surface-drainage.....	459
759. of streets.....	513
1033. -grader, price of.....	722
1033. use of.....	722
850. profit of improving the.....	583
377. to find area of that which can be covered by a cubic yard of broken stone.....	269
1008. Suspend work, power to.....	678
1040. Sweepers, mechanical.....	771-777
858. Sweeping, time for.....	588
893. streets, cost of	625
66. Syenite.....	28
876. Systems of street cleaning.....	624
856. maintenance.....	586
911. sprinkling.....	643

T

797. Tar-concrete for footpaths.....	551
797. footpaths, specifications for.....	551
106. -gas.....	74
450c. -macadam.....	813
88a. -mineral.....	39
862. Team-labor and materials.....	598
1031a. specifications for.....	705
422. Telford pavements, specifications for.....	293
343. Telford's method of broken-stone pavements.....	249
844. defects of	249
483. Temperature, effect of variations on cement.....	334
257. for working asphalt paving cement....	184
261. variation in, and asphalt pavements.....	185
108a. Tensile strength of asphaltum.....	62
503. mortar (Table XLVII).....	347
476. Portland cement.....	331
268. Test for bituminous rock.....	197
126. of the cleanness of sand.....	94
476. Testing cement, necessity of.....	331
492. machine for cement.....	340

ARTICLE	PAGE
60. Tests, breaking.....	24
973. cement, specifications for.....	669
60. Tests, crushing.....	24
118. of brick.....	85-88
477. cement.....	332
942. materials.....	659
61. Rattler.....	25
413. Thickness, loss of, on broken-stone pavements.....	289
415. manner of restoring, on broken-stone pavements.....	289
722. minimum, of retaining-walls.....	486
714. of abutments.....	476
	for arches (Table LXXVI).....
713. arch.....	474
	arch (Table LXXV).....
758. concrete.....	321
154. foundation.....	108
429. gravel layer.....	300
378. the broken-stone pavement.....	269
384. layers of broken stone.....	271
958. Third-class masonry.....	665
689. Tile-drains.....	457
688. Tiles, diameter of.....	457
689. form of.....	457
689. length of.....	457
	Timber bridges, dimensions for (Tables LXXIX and LXXX).....
980. specifications for.....	671
858. Time for sweeping.....	587
1002. of completion.....	676
545. Tires, width of.....	384
527. To find the force required to sustain a vehicle upon an inclined road.....	377
528. pressure of a vehicle against the surface of an inclined road.....	377
131. Tonikins Cove gravel.....	95
131. analyses of.....	95
1039. Tools employed for asphalt pavements.....	762
1038. block pavements.....	761
73. in the manufacture of granite paving-blocks.....	31
1040. for cleaning, price of.....	770
1037. maintenance of broken-stone roads.....	598, 761
1033. grading.....	711
1032. grubbing, prices of.....	710
1036. macadamizing.....	734
1035. rock excavation.....	728
	furnished by the administration.....
569. Topography.....	391

ARTICLE	PAGE
489. Trackways, cost of.....	806
488. in Italy.....	806
884. size of stone for.....	806
450 <i>n</i> . steel.....	816
487. stone.....	808
597. Tractive force required in descending inclines.....	406
force required to move a load of one ton on different pavements in Europe (Table LI).....	875
force required to move a load of one ton on different road- surfaces (Table L).....	372
581. Tractive power and gradients.....	377
582, 588. of horses.....	377
at different velocities (Table LIII).....	378
517, 520. Traction, resistance to (Table L).....	366, 372
45. Traffic census.....	17
898. defects of compacting the broken stone by the.....	278
228. sustained by asphalt.....	167
629. Transverse balancing.....	421
757. contour of streets.....	518
936. staking out.....	656
618. roadways.....	418
625. on hillside roads.....	420
756. grade of streets.....	512
467. strength of concrete.....	825
670. Transport of earth.....	444
5. Transportation-wagon, cost of.....	2
86. Trnp-rocks.....	88
86. color of.....	88
87. resistance to crushing of (Table XIV).....	88
87. specific gravity of (Table XIV).....	88
87. weight of (Table XIV).....	88
925. Trees at street-intersections.....	650
924. distance apart to plant.....	650
920. financial value of.....	649
919. on Belgian road.....	648
886. clay roads.....	578
917. roads.....	647
887. sand roads.....	579
917. streets.....	647
918. the French roads.....	648
927. protection of.....	651
922. qualities of.....	649
922. selection of.....	649
927. specifications for protection of.....	651
917. use of.....	647

ARTICLE	PAGE
338. Tresaguet's system of broken-stone pavements.....	246
100. Trinidad asphaltum	53
100 <i>d</i> . analyses of (Tables XIV <i>a</i> and XVI <i>a</i>).....	48-55
100 <i>e</i> . preparation of.....	55
104. price of, in 1898.....	78
100. source of.....	53
740. Tunnels.....	495
Types of timber bridges.....	483

U

607. Undulating grades.....	413
91 <i>a</i> . Uintahite.....	41
847. Unnecessary grades, profit of eliminating.....	581
704. Use of catch-pools.....	466
124. sand.....	93
105. Uses of asphaltum ..	74
72. granite.....	81
9, 83. limestone.....	4, 86
464. Usual proportions for concrete.....	323

V

Value of bluestone used for street purposes in 1889 (Table XI)	85
70. granite used for street purposes in 1889 (Table VII).....	30
842. improvements.....	590
limestone used for street purposes in 1889 (Table XIII) ..	37
sandstone used for street purposes in 1889 (Table X).....	85
834. Variations in specifications for brick pavements.....	240
of temperature, effect of, on asphalt pavements.....	159
482. cement.....	334
483. mortar.....	334
89. of asphaltum.....	89
120. Varieties of wood used for paving.....	87
543. Vehicles, character of	305
400. loaded pressure of	275
638. Vegetable soil, shrinkage of.....	423
610. Vertical curves.....	415
935. staking out.....	655
Vitrified pipe, weight of (Table LXXI).....	471
cost of (Table LXXI).....	471
461. Voids, determination of	323
372, 461. in broken stone.....	267, 323
373. to determine.....	268
372, 461. gravel.....	267, 323
127, 462. sand... ..	94, 323

ARTICLE	PAGE
280. Vulcanite pavement.....	202
881. Wages, in Baltimore.....	630
882. Boston.....	680
1043. Europe.....	798
879. Paris ..	629
78. of paving-block makers.....	82

W

5. Wagon-transportation, cost of.....	2, 794
670. Wagons, dump.....	444
910. Washing, street.....	642
890. Washington, D. C., cleaning streets in.....	683
56. Waste of money in opening pavements.....	28
108a. Water, action of, on bitumen.....	62
484. amount of, absorbed by cements (Table XLIV).....	885
484. required for mortars.....	835
859. sprinkling, broken-stone pavements.....	589
695. breaks, objections to.....	461
497. for mortar, quality of.....	843
224. injurious to asphalt.....	160
582. on mountain roads.....	401
484. quantity of, for mortar.....	835
463. required for concrete.....	823
913. street-sprinkling.....	643
specific gravity of (Table XXIV).....	97
975. specifications for.....	670
weight of (Table XXIV).....	97
392. Watering broken-stone pavements.....	273
392. effect of excessive.....	273
794. Wear of artificial stones.....	546
63. asphalt blocks.....	26
281. pavements.....	168
63. brick.....	26
63, 409. broken-stone pavements.....	26, 238
63, 168. granite pavements.....	26, 143
63, 202. wood pavements.....	26, 118
368. stone-crushers.....	266
253. Wearing surface of Trinidad-asphalt pavements.....	182
729. Weep-holes.....	491
256. Weight of a cubic yard of asphalt paving-cement.....	184
470. American natural cement (Table XXIV).....	97
256. asphaltum (Table XXIV).....	97
basalt (Table XXIV).....	97
bitumen (Table XXIV).....	97

ARTICLE	PAGE
256. Weight of bituminous limestones (Table XXIV).....	97
bluestone (Table IX).....	35
brick (Table XXI).....	87
masonry (Table XXIV)	97
374. broken stone	268
480. cast iron (Table XXIV)	97
cement.....	333
English Portland (Table XXIV).....	97
707. cement pipe (Table LXXII)	471
Rosendale (Table XXIV).....	97
chalk (Table XXIV).....	97
clay (Table XXIV)	97
with gravel (Table XXIV).....	97
common hard brick (Table XXIV).....	97
457. concrete (Table XXIV).....	97, 321
971. culvert-pipe (Tables LXXI, LXXVII).....	471, 479, 668
drain-tiles (Table LXXVII)....	479
earths (Table XXIV).....	97
feldspar (Table XXIV).....	97
flint (Table XXIV).....	97
French Portland cement (Table XXIV)	97
glass (Table XXIV).....	97
gneiss (Table XXIV).....	97
69. granite (Table VI)	29
gravel with clay (Table XXIV).....	97, 801
gunpowder (Table XXIV).....	97
1088. hand rammers.....	761
ice (Table XXIV)	97
709. iron pipes (Table LXXIII)	473
lead (Table XXIV).....	97
lime.....	97
84. limestone (Table XII).....	97
liquid bitumen (Table XXIV).....	97
masonry (Table XXIV).....	97
mica (Table XXIV).....	97
mortar (Table XXIV).....	97
mud (Table XXIV).....	97
naphtha (Table XXIV).....	97
paving-bricks (Tables XXI, XXIa, XXIV)	87, 88, 97
peat (Table XXIV).....	98
petroleum (Table XXIV).....	98
1088. picks	711
pitch (Table XXIV).....	98
433. pit-gravel.....	301
porphyry (Table XXIV).....	98

ARTICLE	PAGE
478. Weight of Portland cement (Table XXIV).....	97, 328
pressed brick (Table XXIV).....	97
quartz (Table XXIV).....	98
rails.....	720
791. rammers for concrete.....	548
road rollers.....	752-756
Roman cement (Table XXIV).....	97
Rosendale cement (Table XXIV).....	97
180. sand (Table XXIV).....	94, 98
81. sandstones (Table IX).....	84
scrapers.....	713
serpentine (Table XXIV).....	98
shales (Table XXIV).....	98
shingle (Table XXIV).....	98
slate (Table XXIV).....	98
snow (Table XXIV).....	98, 640
soapstone (Table XXIV).....	98
soft inferior brick (Table XXIV).....	97
steel (Table XXIV).....	98
1086. stone crushers.....	740
Stourbridge fire-brick (Table XXIV).....	97
87. trap-rocks (Table XIV).....	88
water (Table XXIV).....	98
wood (Tables XXII, XXIV).....	92, 97
wrought-iron (Table XXIV).....	97
707. vitrified pipe (Table LXXI).....	471
550. Wheels, advantages of.....	387
410. effect on, on pavements.....	284, 388
518. power required to draw, over obstacles.....	366
520. rolling, resistance of.....	371
549. size of.....	387
1088. Wheelbarrows.....	716
327. Wheeling, plan of brick pavements.....	282
618. Wheelway, minimum width of.....	416
611. Wide roads.....	416
747. Width of carriageway, increasing of, at street-intersections.....	506
747. city streets.....	506
769. footpaths.....	527
191. joints in wood pavements.....	134
616. land appropriated in various localities for roads.....	416
617. mountain roads.....	417
147. paving-blocks.....	104
611. roads.....	416
587. roadways on curves.....	408
sidewalks in various cities (Table LXXXII).....	508

ARTICLE	PAGE
587. Width of streets in various cities (Table LXXXII).....	508
545. tires	384
548. tires in Austria.....	385
547. Bavaria	385
112. ordinance regulating.....	78
546. in France.....	385
411. Wind, effect of, on roads	286
968. Wing walls, specifications for.....	666
742. Wire fence, cost of.....	496
1088. Wire screens, price of.....	761
120. Wood.....	86
122. absorptive power of (Table XXIII).....	93
450. and iron, combination of	311
183. blocks, number per square yard.....	129
188. chemical treatment of.....	181
122. creosoting, advantage of.....	63
188. cost of.....	132
743. for footpaths.....	506
177. pavements, advantages of	124
874. amount of dirt produced by.....	624
181. and death rate.....	127
201, 208, 216b. cedar blocks.....	187, 140, 154
186. chief cause of the failure of.....	130
877. cost of cleaning.....	626
205. cost of construction (Table XXXIII).....	139
206. maintenance.....	139
216c. cottonwood blocks.....	155
27, 198. durability of.....	11, 135
184. essentials necessary to successful construction ..	130
185. foundations used for.....	130
216c. gum blocks.....	155
216c. Karri wood.....	154
27. life of.....	11
214. maintenance by contract.....	147
599. maximum grade for.....	407
209. mesquite block.....	141
216a. microbes in.....	153
179. objections to.....	125
216d. pine blocks.....	155
216f. redwood block ..	155
19. slipperiness of.....	9
213, 216. specifications for.....	144, 151
182. transverse rise for (Table LXIV).....	418
63, 202. variety of systems.....	129
wear of.....	26, 137


ARTICLE	PAGE
190. Wood paving blocks, expansion of	184
182. shape of.....	129
181. size of.....	127
189. dimensions of blocks for	183
192. filling for joints	185
187. quality of the wood.....	181
191. width of joints	185
188. preservation of.....	181
121. quality of, for paving.....	98
resistance to crushing of (Table XXII).....	92
specific gravity of (Table XXII).....	92
120. varieties used for paving.....	92
weight of (Table XXII).....	92
719. Wooden bridges.....	481
dimensions of (Tables LXXIX and LXXX).....	484
786. railings for road protection.....	493
188. Woods best adapted to chemical treatment.....	181
1001. Work, commencement of.....	676
998. defective.....	674
584. done by horses.....	878
1007. faithful performance of, bond for.....	678
999. how measured.....	674
1010. miscellaneous.....	678
1008. Work, power to suspend.....	676
1009. progress of	676
1013. Workmen, payment of.....	679
988. Wrought-iron, specifications for.....	671
91a. Wurtzillite	41

Z

680. Zero-point, to ascertain, by calculation	454
591. Zigzags, objections to.....	408

INDEX TO ADVERTISEMENTS.

	PAGE
Austin Manufacturing Company, The F. C.	2
Buffalo Pitts Steam Roller Works.....	4
Rand Drill Company.....	1
Rendrock Powder Company.....	1
Warren Brothers Company.....	4
Wilson & Baillie Manufacturing Company, The.....	3



CONTRACTORS

AVOID ACCIDENTS
PREVENT LAWSUITS !
SAVE MONEY

IF WORKING IN THE CITY LIMITS,
BY USING

RACKAROCK

THE ONLY SAFE HIGH EXPLOSIVE.

RACKAROCK is a blasting-powder of exceptional strength, and is formed by the union of two ingredients, both of which are absolutely non-explosive until combined by the user. **Rackarock** does not freeze in the coldest weather, equally effective in wet or dry holes, and packs closer than dynamite: furnished in two grades. By reason of its safety it is **especially well adapted to water-works and highway construction** in crowded sections of the city.

Shipped and stored like ordinary merchandise.

Rendrock Powder Co., 128 BROADWAY,
NEW YORK.

RAND IMPROVED

"LITTLE GIANT" and "SLUGGER"

ROCK-DRILLS

For Contractors for Sewers, Cellars,
Streets, Mines, Quarries, etc.

ALSO

AIR-COMPRESSORS,

PORTABLE BOILERS, HOSE, WIRE ROPE, STEEL, ETC.




Send for
Catalogues
and full
Information.

RAND DRILL CO.

128 BROADWAY, - NEW YORK.

AUSTIN CRUSHERS



**TECHNICALLY AND
MECHANICALLY
WITHOUT A FAULT**

**LEAST LIABLE TO GET
OUT OF REPAIR, AND
MOST ECONOMICAL IN
CONSUMPTION OF POWER**


**WRITE TO DEPARTMENT A
for special catalogue of Crushers,
Dump Cars and Contractors'
Machinery.**



**Contractor's
Dump Wagon**



**Austin Reversible
Road Roller**



**Austin
Street Sweeper**



**Austin
Contractor's Plow**



Austin Wheeler



**Austin
Drag Scraper**



Austin Reversible Road Machine



Austin Rock Crusher and Elevator

F. C. AUSTIN MFG. CO., Harvey, Ill.
NEW YORK OFFICE, PARK ROW BUILDING.

T. HENRY DUMARY, President.
S. OLIN JOHNSON, Vice-President.

H. E. BAILLIE, Secretary.
F. B. JOHNSON, Treasurer.

The Wilson & Baillie Manufacturing Co.

Main Office and Factory, 85-93 Ninth Street, Brooklyn, N. Y.




ARTIFICIAL STONE.

*For Sidewalks, Driveways, Copings, Steps, Railroad Depot Platforms,
 Flooring for Warehouses and Apartment Houses, Water-tight
 Cellar Floors, and Improved Stable Floors.*

KOSMOCRETE STEEL-BOUND CURB.

"WAINWRIGHT'S PATENTS."



The Steel-Bound Curb is superior to any natural stone.

Laid in ten-foot lengths, with invisible joints, with concrete foundations, is never out of line.

Galvanized steel edges cannot rust or break.

It is the most beautiful and durable curb laid, and with gutter combined is the ideal for asphalt, brick, or macadam streets.

HEAVY CONCRETE CONSTRUCTION A SPECIAL FEATURE OF OUR BUSINESS.

Steel-Bound Curb has been laid in the following cities:

NEW YORK,
 BROOKLYN,
 BOSTON,

PROVIDENCE,
 NEWPORT,
 HARTFORD,

NEW HAVEN,
 ALBANY,
 TROY,

UTICA,
 AND
 SCHENECTADY.

By permission we refer to the Engineers and Architects in charge of the following work:

Bowling Green Building, Kosmocrete walks laid on Broadway and Greenwich Street fronts.

Six miles of foundations for Union Elevated Railroad of Brooklyn.

Swimming Tank, Bergen Beach, Brooklyn. Sea Wall, Wallabout Market, Brooklyn.

Causeway, New York Navy Yard, Brooklyn. Sidewalks, Curbs, etc., Terminals, New York and Brooklyn Bridge.

Sidewalks, Curbs, etc., New York State

Armories: 93d Regiment, Brooklyn; 14th Regiment, Brooklyn; Cohoes, Utica, Hornellsville.

Sidewalk, five miles long, eight feet in width, Ocean Parkway, Brooklyn.

Capitol, Albany, N. Y.; Floor of Terrace, 10,000 sq. feet.

Sidewalk and Curb, Rensselaer County Court House, Troy, N. Y.

Fireproof Floors, Abraham & Straus's New Warehouse, Brooklyn.

WARREN'S BITUMINOUS MACADAM PAVEMENT

Is the Latest Improvement in Roadways.

ENDORSED BY EXPERTS.

The stone takes the wear of traffic. Horses do not slip on it in any weather. It is not affected by water, nor does it rot, crack or shave. Successfully laid in streets up to 12 per cent. grade.

WE INVITE INVESTIGATION.

WARREN BROTHERS COMPANY,

Postal Telegraph Bldg.,
New York City.

93 Federal Street,
Boston.

BUFFALO PITTS STEAM ROLLERS

10, 12 AND 15 TONS.



Awarded Gold Medal, Pan American Exposition, 1901.

—BUILT BY—

BUFFALO PITTS STEAM ROLLER WORKS,
BUFFALO, N. Y.

15 COURT SQUARE, BOSTON, MASS.

Bought by
United States Govern-
ment,
Mass. Highway
Commission,
New York City, etc.

SHORT-TITLE CATALOGUE

OF THE
PUBLICATIONS

OF
JOHN WILEY & SONS,

NEW YORK.

LONDON: CHAPMAN & HALL, LIMITED.

ARRANGED UNDER SUBJECTS.

Descriptive circulars sent on application. Books marked with an asterisk are sold at net prices only, a double asterisk (**) books sold under the rules of the American Publishers' Association at net prices subject to an extra charge for postage. All books are bound in cloth unless otherwise stated.

AGRICULTURE.

Armsby's Manual of Cattle-feeding.....	12mo, \$1 75
Principles of Animal Nutrition.....	8vo, 4 00
Budd and Hansen's American Horticultural Manual:	
Part I.—Propagation, Culture, and Improvement.....	12mo, 1 50
Part II.—Systematic Pomology.....	12mo, 1 50
Downing's Fruits and Fruit-trees of America.....	8vo, 5 00
Elliott's Engineering for Land Drainage.....	12mo, 1 50
Practical Farm Drainage.....	12mo, 1 00
Green's Principles of American Forestry. (<i>Shortly.</i>)	
Grotenfelt's Principles of Modern Dairy Practice. (Woll.).....	12mo, 2 00
Kemp's Landscape Gardening.....	12mo, 2 50
Maynard's Landscape Gardening as Applied to Home Decoration.....	12mo, 1 50
Sanderson's Insects Injurious to Staple Crops.....	12mo, 1 50
Insects Injurious to Garden Crops. (<i>In preparation.</i>)	
Insects Injuring Fruits. (<i>In preparation.</i>)	
Stockbridge's Rocks and Soils.....	8vo, 2 50
Woll's Handbook for Farmers and Dairymen.....	16mo, 1 50

ARCHITECTURE.

Baldwin's Steam Heating for Buildings.....	12mo, 2 50
Berg's Buildings and Structures of American Railroads.....	4to, 5 00
Birkmire's Planning and Construction of American Theatres.....	8vo, 3 00
Architectural Iron and Steel.....	8vo, 3 50
Compound Riveted Girders as Applied in Buildings.....	8vo, 2 00
Planning and Construction of High Office Buildings.....	8vo, 3 50
Skeleton Construction in Buildings.....	8vo, 3 00
Briggs's Modern American School Buildings.....	8vo, 4 00
Carpenter's Heating and Ventilating of Buildings.....	8vo, 4 00
Freitag's Architectural Engineering. 2d Edition, Rewritten.....	8vo, 3 50
Fireproofing of Steel Buildings.....	8vo, 2 50
French and Ives's Stereotomy.....	8vo, 2 50
Gerhard's Guide to Sanitary House-Inspection.....	16mo, 1 00
Theatre Fires and Panics.....	12mo, 1 50

Hatfield's American House Carpenter.....	8vo,	5 00
Holly's Carpenters' and Joiners' Handbook.....	18mo,	75
Johnson's Statics by Algebraic and Graphic Methods.....	8vo,	2 00
Kidder's Architect's and Builder's Pocket-book.....	16mo, morocco,	4 00
Merrill's Stones for Building and Decoration.....	8vo,	5 00
Monckton's Stair-building.....	4to,	4 00
Patton's Practical Treatise on Foundations.....	8vo,	5 00
Siebert and Biggin's Modern Stone-cutting and Masonry.....	8vo,	1 50
Snow's Principal Species of Wood.....	8vo,	3 50
Sondericker's Graphic Statics with Applications to Trusses, Beams, and Arches. (<i>Shortly.</i>)		
Wait's Engineering and Architectural Jurisprudence.....	8vo,	6 00
	Sheep,	6 50
Law of Operations Preliminary to Construction in Engineering and Archi- tecture.....	8vo,	5 00
	Sheep,	5 50
Law of Contracts.....	8vo,	3 00
Woodbury's Fire Protection of Mills.....	8vo,	2 50
Worcester and Atkinson's Small Hospitals, Establishment and Maintenance, Suggestions for Hospital Architecture, with Plans for a Small Hospital.		
	12mo,	1 25
The World's Columbian Exposition of 1893.....	Large 4to,	1 00

ARMY AND NAVY.

Bernadou's Smokeless Powder, Nitro-cellulose, and the Theory of the Cellulose Molecule.....	12mo,	2 50
* Bruff's Text-book Ordnance and Gunnery.....	8vo,	6 00
Chase's Screw Propellers and Marine Propulsion.....	8vo,	3 00
Craig's Azimuth.....	4to,	3 50
Crehore and Squire's Polarizing Photo-chronograph.....	8vo,	3 00
Cronkrite's Gunnery for Non-commissioned Officers.....	24mo, morocco,	2 00
* Davis's Elements of Law.....	8vo,	2 50
* Treatise on the Military Law of United States.....	8vo,	7 00
*	Sheep	7 50
De Brack's Cavalry Outpost Duties. (Carr.).....	24mo, morocco,	2 00
Dietz's Soldier's First Aid Handbook.....	16mo, morocco,	1 25
* Dredge's Modern French Artillery.....	4to, half morocco,	15 00
Durand's Resistance and Propulsion of Ships.....	8vo,	5 00
* Dyer's Handbook of Light Artillery.....	12mo,	3 00
Eisler's Modern High Explosives.....	8vo,	4 00
* Fiebeger's Text-book on Field Fortification.....	Small 8vo,	2 00
Hamilton's The Gunner's Catechism.....	18mo,	1 00
* Hoff's Elementary Naval Tactics.....	8vo,	1 50
Ingalls's Handbook of Problems in Direct Fire.....	8vo,	4 00
* Ballistic Tables.....	8vo,	1 50
* Lyons's Treatise on Electromagnetic Phenomena. Vols. I. and II. 8vo, each,		6 00
* Mahan's Permanent Fortifications. (Mercur.).....	8vo, half morocco,	7 50
Manual for Courts-martial.....	16mo morocco,	1 50
* Mercur's Attack of Fortified Places.....	12mo,	2 00
* Elements of the Art of War.....	8vo,	4 00
Metcalf's Cost of Manufactures—And the Administration of Workshops, Public and Private.....	8vo,	5 00
* Ordnance and Gunnery.....	12mo,	5 00
Murray's Infantry Drill Regulations.....	18mo, paper,	10
* Phelps's Practical Marine Surveying.....	8vo,	2 50
Powell's Army Officer's Examiner.....	12mo,	4 00
Sharpe's Art of Subsisting Armies in War.....	18mo, morocco,	1 50

* Walke's Lectures on Explosives.....	8vo,	4 60
* Wheeler's Siege Operations and Military Mining.....	8vo,	2 00
Winthrop's Abridgment of Military Law.....	12mo,	2 50
Woodhull's Notes on Military Hygiene.....	16mo,	1 50
Young's Simple Elements of Navigation.....	16mo, morocco,	1 00
Second Edition, Enlarged and Revised.....	16mo, morocco,	2 00

ASSAYING.

Fletcher's Practical Instructions in Quantitative Assaying with the Blowpipe.....	12mo, morocco,	1 50
Furman's Manual of Practical Assaying.....	8vo,	3 00
Miller's Manual of Assaying.....	12mo,	1 00
O'Driscoll's Notes on the Treatment of Gold Ores.....	8vo,	2 00
Ricketts and Miller's Notes on Assaying.....	8vo,	3 00
Ulke's Modern Electrolytic Copper Refining.....	8vo,	3 00
Wilson's Cyanide Processes.....	12mo,	1 50
Chlorination Process.....	12mo,	1 50

ASTRONOMY.

Comstock's Field Astronomy for Engineers.....	8vo,	2 50
Craig's Azimuth.....	4to,	3 50
Doolittle's Treatise on Practical Astronomy.....	8vo,	4 00
Gore's Elements of Geodesy.....	8vo,	2 50
Hayford's Text-book of Geodetic Astronomy.....	8vo,	3 00
Merriman's Elements of Precise Surveying and Geodesy.....	8vo,	2 50
* Michie and Harlow's Practical Astronomy.....	8vo,	3 00
* White's Elements of Theoretical and Descriptive Astronomy.....	12mo,	2 00

BOTANY.

Davenport's Statistical Methods, with Special Reference to Biological Variation.....	16mo, morocco,	1 25
Thomé and Bennett's Structural and Physiological Botany.....	16mo,	2 25
Westermaler's Compendium of General Botany. (Schneider.).....	8vo,	2 00

CHEMISTRY.

Adriance's Laboratory Calculations and Specific Gravity Tables.....	12mo,	1 25
Allen's Tables for Iron Analysis.....	8vo,	3 00
Arnold's Compendium of Chemistry. (Mandel.) (<i>In preparation.</i>).....		
Austen's Notes for Chemical Students.....	12mo,	1 50
Bernadou's Smokeless Powder.—Nitro-cellulose, and Theory of the Cellulose Molecule.....	12mo,	2 50
Bolton's Quantitative Analysis.....	8vo,	1 50
* Browning's Introduction to the Rarer Elements.....	8vo,	1 50
Brush and Penfield's Manual of Determinative Mineralogy.....	8vo,	4 00
Classen's Quantitative Chemical Analysis by Electrolysis. (Boltwood.).....	8vo,	3 00
Cohn's Indicators and Test-papers.....	12mo,	2 00
Tests and Reagents.....	8vo,	3 00
Copeland's Manual of Bacteriology. (<i>In preparation.</i>).....		
Craft's Short Course in Qualitative Chemical Analysis. (Schaeffer.).....	12mo,	2 00
Drechsel's Chemical Reactions. (Merrill.).....	12mo,	1 25
Duhem's Thermodynamics and Chemistry. (Burgess.) (<i>Shortly.</i>).....		
Eissler's Modern High Explosives.....	8vo,	4 00

Effront's Enzymes and their Applications. (Prescott.)	8vo,	3 00
Erdmann's Introduction to Chemical Preparations. (Dunlap.)	12mo,	1 25
Fletcher's Practical Instructions in Quantitative Assaying with the Blowpipe.	12mo, morocco,	1 50
Fowler's Sewage Works Analyses.	12mo,	2 00
Fresenius's Manual of Qualitative Chemical Analysis. (Wells.)	8vo,	5 00
Manual of Qualitative Chemical Analysis. Part I. Descriptive. (Wells.)	8vo,	3 00
System of Instruction in Quantitative Chemical Analysis. (Cohn.)	2 vols. (Shortly.)	
Fuertes's Water and Public Health.	12mo,	1 50
Furman's Manual of Practical Assaying.	8vo,	3 00
Gill's Gas and Fuel Analysis for Engineers.	12mo,	1 25
Grotenfelt's Principles of Modern Dairy Practice. (Woll.)	12mo,	2 00
Hammarsten's Text-book of Physiological Chemistry. (Mandel.)	8vo,	4 00
Helm's Principles of Mathematical Chemistry. (Morgan.)	12mo,	1 50
Hinds's Inorganic Chemistry.	8vo,	3 00
* Laboratory Manual for Students.	12mo,	75
Holleman's Text-book of Inorganic Chemistry. (Cooper.)	8vo,	2 50
Text-book of Organic Chemistry. (Walker and Mott.)	8vo,	2 50
Hopkins's Oil-chemists' Handbook.	8vo,	3 00
Keep's Cast Iron.	8vo,	2 50
Ladd's Manual of Quantitative Chemical Analysis.	12mo,	1 00
Landauer's Spectrum Analysis. (Tingle.)	8vo,	3 00
Laszar-Cohn's Practical Urinary Analysis. (Lorenz.)	12mo,	1 00
Leach's The Inspection and Analysis of Food with Special Reference to State Control. (In preparation.)		
Lüb's Electrolysis and Electro-synthesis of Organic Compounds. (Lorenz.)	12mo,	1 00
Mandel's Handbook for Bio-chemical Laboratory.	12mo,	1 50
Mason's Water-supply. (Considered Principally from a Sanitary Standpoint.)		
3d Edition, Rewritten.	8vo,	4 00
Examination of Water. (Chemical and Bacteriological.)	12mo,	1 25
Meyer's Determination of Radicles in Carbon Compounds. (Tingle.)	12mo,	1 00
Miller's Manual of Assaying.	12mo,	1 00
Mixter's Elementary Text-book of Chemistry.	12mo,	1 50
Morgan's Outline of Theory of Solution and its Results.	12mo,	1 00
Elements of Physical Chemistry.	12mo,	2 00
Nichols's Water-supply. (Considered mainly from a Chemical and Sanitary Standpoint, 1883.)	8vo,	2 50
O'Brine's Laboratory Guide in Chemical Analysis.	8vo,	2 00
O'Driscoll's Notes on the Treatment of Gold Ores.	8vo,	2 00
Ost and Kolbeck's Text-book of Chemical Technology. (Lorenz-Bozart.)		
(In preparation.)		
* Penfield's Notes on Determinative Mineralogy and Record of Mineral Tests.	8vo, paper,	50
Pictet's The Alkaloids and their Chemical Constitution. (Biddle.) (In preparation.)		
Pinner's Introduction to Organic Chemistry. (Austen.)	12mo,	1 50
Poole's Calorific Power of Fuels.	8vo,	3 00
* Reisig's Guide to Piece-dyeing.	8vo,	25 00
Richards and Woodman's Air, Water, and Food from a Sanitary Standpoint.	8vo,	2 00
Richards's Cost of Living as Modified by Sanitary Science.	12mo,	1 00
Cost of Food, a Study in Dietsaries.	12mo,	1 00
* Richards and Williams's The Dietary Computer.	8vo,	1 50
Ricketts and Russell's Skeleton Notes upon Inorganic Chemistry. (Part I.—Non-metallic Elements.)	8vo, morocco,	75
Ricketts and Miller's Notes on Assaying.	8vo,	3 00
Rideal's Sewage and the Bacterial Purification of Sewage.	8vo,	3 50

Ruddiman's Incompatibilities in Prescriptions.....	8vo,	2 00
Schimpf's Text-book of Volumetric Analysis.....	12mo,	2 50
Spencer's Handbook for Chemists of Beet-sugar Houses.....	16mo, morocco,	3 00
Handbook for Sugar Manufacturers and their Chemists.....	16mo, morocco,	2 00
Stockbridge's Rocks and Soils.....	8vo,	2 50
* Tillman's Elementary Lessons in Heat.....	8vo,	1 50
* Descriptive General Chemistry.....	8vo	3 00
Treadwell's Qualitative Analysis. (Hall).....	8vo,	3 00
Turneure and Russell's Public Water-supplies.....	8vo,	5 00
Van Deventer's Physical Chemistry for Beginners. (Boltwood).....	12mo,	1 50
* Walke's Lectures on Explosives.....	8vo,	4 00
Wells's Laboratory Guide in Qualitative Chemical Analysis.....	8vo,	1 50
Short Course in Inorganic Qualitative Chemical Analysis for Engineering Students.....	12mo,	1 50
Whipple's Microscopy of Drinking-water.....	8vo,	3 50
Wiechmann's Sugar Analysis.....	Small 8vo,	2 50
Wilson's Cyanide Processes.....	12mo,	1 50
Chlorination Process.....	12mo,	1 50
Walling's Elementary Course in Inorganic Pharmaceutical and Medical Chemistry.....	12mo,	2 00

CIVIL ENGINEERING.

BRIDGES AND ROOFS. HYDRAULICS. MATERIALS OF ENGINEERING. RAILWAY ENGINEERING.

Baker's Engineers' Surveying Instruments.....	12mo,	3 00
Bixby's Graphical Computing Table.....	Paper, 19½ X 24½ inches.	25
** Burr's Ancient and Modern Engineering and the Isthmian Canal. (Postage, 27 cents additional.).....	8vo, net,	3 50
Comstock's Field Astronomy for Engineers.....	8vo,	2 50
Davis's Elevation and Stadia Tables.....	8vo,	1 00
Elliot's Engineering for Land Drainage.....	12mo,	1 50
Practical Farm Drainage.....	12mo,	1 00
Folwell's Sewerage. (Designing and Maintenance).....	8vo,	3 00
Freitag's Architectural Engineering. 2d Edition, Rewritten.....	8vo,	3 50
French and Ives's Stereotomy.....	8vo,	2 50
Goodhue's Municipal Improvements.....	12mo,	1 75
Goodrich's Economic Disposal of Towns' Refuse.....	8vo,	3 50
Gore's Elements of Geodesy.....	8vo,	2 50
Hayford's Text-book of Geodetic Astronomy.....	8vo,	3 00
Howe's Retaining Walls for Earth.....	12mo,	1 25
Johnson's Theory and Practice of Surveying.....	Small 8vo,	4 00
Statics by Algebraic and Graphic Methods.....	8vo,	2 00
Kiersted's Sewage Disposal.....	12mo,	1 25
Laplace's Philosophical Essay on Probabilities. (Truscott and Emory).....	12mo,	2 00
Mahan's Treatise on Civil Engineering. (1873.) (Wood).....	8vo,	5 00
* Descriptive Geometry.....	8vo,	1 50
Merriman's Elements of Precise Surveying and Geodesy.....	8vo,	2 50
Elements of Sanitary Engineering.....	8vo,	2 00
Merriman and Brooks's Handbook for Surveyors.....	16mo, morocco,	2 00
Nugent's Plane Surveying.....	8vo,	3 50
Ogden's Sewer Design.....	12mo,	2 00
Patton's Treatise on Civil Engineering.....	8vo, half leather,	7 50
Reed's Topographical Drawing and Sketching.....	4to,	5 00
Rideal's Sewage and the Bacterial Purification of Sewage.....	8vo,	3 50
Siebert and Biggin's Modern Stone-cutting and Masonry.....	8vo,	1 50
Smith's Manual of Topographical Drawing. (McMillan).....	8vo,	2 50

Sondericker's Graphic Statics, with Applications to Trusses, Beams, and Arches. (<i>Shortly.</i>)		
* Trautwine's Civil Engineer's Pocket-book	16mo, morocco	5 00
Walt's Engineering and Architectural Jurisprudence	8vo	6 00
	Sheep	6 50
Law of Operations Preliminary to Construction in Engineering and Architecture	8vo	5 00
	Sheep	5 50
Law of Contracts	8vo	3 00
Warren's Stereotomy—Problems in Stone-cutting	8vo	2 50
Webb's Problems in the Use and Adjustment of Engineering Instruments	16mo, morocco	1 25
* Wheeler's Elementary Course of Civil Engineering	8vo	4 00
Wilson's Topographic Surveying	8vo	3 50

BRIDGES AND ROOFS.

Boller's Practical Treatise on the Construction of Iron Highway Bridges	8vo	2 00
* Thames River Bridge	4to, paper	5 00
Burr's Course on the Stresses in Bridges and Roof Trusses, Arched Ribs, and Suspension Bridges	8vo	3 50
Du Bois's Mechanics of Engineering. Vol. II	Small 4to	10 00
Foster's Treatise on Wooden Trestle Bridges	4to	5 00
Fowler's Coffor-dam Process for Piers	8vo	2 50
Greene's Roof Trusses	8vo	1 25
Bridge Trusses	8vo	2 50
Arches in Wood, Iron, and Stone	8vo	2 50
Howe's Treatise on Arches	8vo	4 00
Design of Simple Roof-trusses in Wood and Steel	8vo	2 00
Johnson, Bryan, and Turneure's Theory and Practice in the Designing of Modern Framed Structures	Small 4to	10 00
Merriman and Jacoby's Text-book on Roofs and Bridges:		
Part I.—Stresses in Simple Trusses	8vo	2 50
Part II.—Graphic Statics	8vo	2 50
Part III.—Bridge Design. 4th Edition, Rewritten	8vo	2 50
Part IV.—Higher Structures	8vo	2 50
Morison's Memphis Bridge	4to	10 00
Waddell's De Pontibus, a Pocket-book for Bridge Engineers	16mo, morocco	3 00
Specifications for Steel Bridges	12mo	1 25
Wood's Treatise on the Theory of the Construction of Bridges and Roofs	8vo	2 00
Wright's Designing of Draw-spans:		
Part I. —Plate-girder Draws	8vo	2 50
Part II.—Riveted-truss and Pin-connected Long-span Draws	8vo	2 50
Two parts in one volume	8vo	3 50

HYDRAULICS.

Bazin's Experiments upon the Contraction of the Liquid Vein Issuing from an Orifice. (Trautwine.)	8vo	2 00
Bovey's Treatise on Hydraulics	8vo	5 00
Church's Mechanics of Engineering	8vo	6 00
Diagrams of Mean Velocity of Water in Open Channels	paper	1 50
Coffin's Graphical Solution of Hydraulic Problems	16mo, morocco	2 50
Flather's Dynamometers, and the Measurement of Power	12mo	3 00
Folwell's Water-supply Engineering	8vo	4 00
Frizell's Water-power	8vo	5 00

Fuertes's Water and Public Health.....	12mo,	1 50
Water-filtration Works.....	12mo,	2 50
Ganguillet and Kutter's General Formula for the Uniform Flow of Water in Rivers and Other Channels. (Hering and Trautwine.).....	8vo,	4 00
Hazen's Filtration of Public Water-supply.....	8vo,	3 00
Hazlehurst's Towers and Tanks for Water-works.....	8vo,	2 50
Herschel's 115 Experiments on the Carrying Capacity of Large, Riveted, Metal Conduits.....	8vo,	2 00
Mason's Water-supply. (Considered Principally from a Sanitary Stand-point.) 3d Edition, Rewritten.....	8vo,	4 00
Merriman's Treatise on Hydraulics. 9th Edition, Rewritten.....	8vo,	5 00
* Michie's Elements of Analytical Mechanics.....	8vo,	4 00
Schuyler's Reservoirs for Irrigation, Water-power, and Domestic Water-supply.....	Large 8vo,	5 00
** Thomas and Watt's Improvement of Rivers. (Post., 44 c. additional), 4to, 6 00		
Turneure and Russell's Public Water-supplies.....	8vo,	5 00
Wegmann's Design and Construction of Dams.....	4to,	5 00
Water-supply of the City of New York from 1658 to 1895.....	4to,	10 00
Weisbach's Hydraulics and Hydraulic Motors. (Du Bois.).....	8vo,	5 00
Wilson's Manual of Irrigation Engineering.....	Small 8vo,	4 00
Wolff's Windmill as a Prime Mover.....	8vo,	3 00
Wood's Turbines.....	8vo,	2 50
Elements of Analytical Mechanics.....	8vo,	3 00

MATERIALS OF [ENGINEERING.

Baker's Treatise on Masonry Construction.....	8vo,	5 00
Roads and Pavements.....	8vo,	5 00
Black's United States Public Works.....	Oblong 4to,	5 00
Bovey's Strength of Materials and Theory of Structures.....	8vo,	7 50
Burr's Elasticity and Resistance of the Materials of Engineering. 6th Edition, Rewritten.....	8vo,	7 50
Byrne's Highway Construction.....	8vo,	5 00
Inspection of the Materials and Workmanship Employed in Construction.....	16mo,	3 00
Church's Mechanics of Engineering.....	8vo,	6 00
Du Bois's Mechanics of Engineering. Vol. I.....	Small 4to,	7 50
Johnson's Materials of Construction.....	Large 8vo,	6 00
Keep's Cast Iron.....	8vo,	2 50
Lanza's Applied Mechanics.....	8vo,	7 50
Martens's Handbook on Testing Materials. (Henning.) 2 vols.....	8vo,	7 50
Merrill's Stones for Building and Decoration.....	8vo,	5 00
Merriman's Text-book on the Mechanics of Materials.....	8vo,	4 00
Strength of Materials.....	12mo,	1 00
Metcalf's Steel. A Manual for Steel-users.....	12mo,	2 00
Patton's Practical Treatise on Foundations.....	8vo,	5 00
Rockwell's Roads and Pavements in France.....	12mo,	1 25
Smith's Wire: Its Use and Manufacture.....	Small 4to,	3 00
Materials of Machines.....	12mo,	1 00
Snow's Principal Species of Wood.....	8vo,	3 50
Spalding's Hydraulic Cement.....	12mo,	2 00
Text-book on Roads and Pavements.....	12mo,	2 00
Thurston's Materials of Engineering. 3 Parts.....	8vo,	8 00
Part I.—Non-metallic Materials of Engineering and Metallurgy.....	8vo,	2 00
Part II.—Iron and Steel.....	8vo,	3 50
Part III.—A Treatise on Brasses, Bronzes, and Other Alloys and their Constituents.....	8vo,	2 50

Thurston's Text-book of the Materials of Construction.....	8vo, 5 00
Tillson's Street Pavements and Paving Materials.....	8vo, 4 00
Waddell's De Pontibus. (A Pocket-book for Bridge Engineers.).....	16mo, mor., 3 00
Specifications for Steel Bridges.....	12mo, 1 25
Wood's Treatise on the Resistance of Materials, and an Appendix on the Preservation of Timber.....	8vo, 2 00
Elements of Analytical Mechanics.....	8vo, 3 00

RAILWAY ENGINEERING.

Andrews's Handbook for Street Railway Engineers. 3X5 inches. morocco.....	1 25
Berg's Buildings and Structures of American Railroads.....	4to, 5 00
Brooks's Handbook of Street Railroad Location.....	16mo, morocco, 1 50
Butts's Civil Engineer's Field-book.....	16mo, morocco, 2 50
Crandall's Transition Curve.....	16mo, morocco, 1 50
Railway and Other Earthwork Tables.....	8vo, 1 50
Dawson's "Engineering" and Electric Traction Pocket-book. 16mo, morocco.....	4 00
Dredge's History of the Pennsylvania Railroad: (1879).....	Paper, 5 00
* Drinker's Tunneling, Explosive Compounds, and Rock Drills, 4to, half mor.,.....	25 00
Fisher's Table of Cubic Yards.....	Cardboard, 25
Godwin's Railroad Engineers' Field-book and Explorers' Guide.....	16mo, mor., 2 50
Howard's Transition Curve Field-book.....	16mo, morocco, 1 50
Hudson's Tables for Calculating the Cubic Contents of Excavations and Embankments.....	8vo, 1 00
Molitor and Beard's Manual for Resident Engineers.....	16mo, 1 00
Nagle's Field Manual for Railroad Engineers.....	16mo, morocco, 3 00
Philbrick's Field Manual for Engineers.....	16mo, morocco, 3 00
Pratt and Alden's Street-railway Road-bed.....	8vo, 2 00
Searles's Field Engineering.....	16mo, morocco, 3 00
Railroad Spiral.....	16mo, morocco, 1 50
Taylor's Prismoidal Formulas and Earthwork.....	8vo, 1 50
* Trautwine's Method of Calculating the Cubic Contents of Excavations and Embankments by the Aid of Diagrams.....	8vo, 2 00
* The Field Practice of Laying Out Circular Curves for Railroads.....	12mo, morocco, 2 50
* Cross-section Sheet.....	Paper, 25
Webb's Railroad Construction. 2d Edition, Rewritten.....	16mo. morocco, 5 00
Wellington's Economic Theory of the Location of Railways.....	Small 8vo, 5 00

DRAWING.

Barr's Kinematics of Machinery.....	8vo, 2 50
* Bartlett's Mechanical Drawing.....	8vo, 3 00
Coolidge's Manual of Drawing.....	8vo, paper, 1 00
Durley's Kinematics of Machines.....	8vo, 4 00
Hill's Text-book on Shades and Shadows, and Perspective.....	8vo, 2 00
Jones's Machine Design:	
Part I.—Kinematics of Machinery.....	8vo, 1 50
Part II.—Form, Strength, and Proportions of Parts.....	8vo, 3 00
MacCord's Elements of Descriptive Geometry.....	8vo, 3 00
Kinematics; or, Practical Mechanism.....	8vo, 5 00
Mechanical Drawing.....	4to, 4 00
Velocity Diagrams.....	8vo, 1 50
* Mahan's Descriptive Geometry and Stone-cutting.....	8vo, 1 50
Industrial Drawing. (Thompson.).....	8vo, 3 50
Reed's Topographical Drawing and Sketching.....	4to, 5 00

Reid's Course in Mechanical Drawing.....	8vo,	2 00
Text-book of Mechanical Drawing and Elementary Machine Design.....	8vo,	3 00
Robinson's Principles of Mechanism.....	8vo,	3 00
Smith's Manual of Topographical Drawing. (McMillan.).....	8vo,	2 50
Warren's Elements of Plane and Solid Free-hand Geometrical Drawing.....	12mo,	1 00
Drafting Instruments and Operations.....	12mo,	1 25
Manual of Elementary Projection Drawing.....	12mo,	1 50
Manual of Elementary Problems in the Linear Perspective of Form and Shadow.....	12mo,	1 00
Plane Problems in Elementary Geometry.....	12mo,	1 25
Primary Geometry.....	12mo,	75
Elements of Descriptive Geometry, Shadows, and Perspective.....	8vo,	3 50
General Problems of Shades and Shadows.....	8vo,	3 00
Elements of Machine Construction and Drawing.....	8vo,	7 50
Problems, Theorems, and Examples in Descriptive Geometry.....	8vo,	2 50
Weisbach's Kinematics and the Power of Transmission. (Hermann and Klein.).....	8vo,	5 00
Whipple's Practical Instruction in the Art of Letter Engraving.....	12mo,	2 00
Wilson's Topographic Surveying.....	8vo,	3 50
Free-hand Perspective.....	8vo,	2 50
Free-hand Lettering. (<i>In preparation.</i>).....		
Woolf's Elementary Course in Descriptive Geometry.....	Large 8vo,	3 00

ELECTRICITY AND PHYSICS.

Anthony and Brackett's Text-book of Physics. (Magie.).....	Small 8vo,	3 00
Anthony's Lecture-notes on the Theory of Electrical Measurements.....	12mo,	1 00
Benjamin's History of Electricity.....	8vo,	3 00
Voltaic Cell.....	8vo,	3 00
Classen's Quantitative Chemical Analysis by Electrolysis. (Boltwood.).....	8vo,	3 00
Crehore and Squier's Polarizing Photo-chronograph.....	8vo,	3 00
Dawson's "Engineering" and Electric Traction Pocket-book.....	16mo, morocco,	4 00
Flather's Dynamometers, and the Measurement of Power.....	12mo,	3 00
Gilbert's De Magnete. (Mottelay.).....	8vo,	2 50
Holman's Precision of Measurements.....	8vo,	2 00
Telescopic Mirror-scale Method, Adjustments, and Tests.....	Large 8vo,	75
Landauer's Spectrum Analysis. (Tingle.).....	8vo,	3 00
Le Chatelier's High-temperature Measurements. (Boudouard—Burgess.).....	12mo,	3 00
Löb's Electrolysis and Electrosynthesis of Organic Compounds. (Lorenz.).....	12mo,	1 00
* Lyons's Treatise on Electromagnetic Phenomena. Vols. I. and II. 8vo, each.....		6 00
* Michie. Elements of Wave Motion Relating to Sound and Light.....	8vo,	4 00
Niaudet's Elementary Treatise on Electric Batteries. (Fishback.).....	12mo,	2 50
* Parshall and Hobart's Electric Generators.....	Small 4to, half morocco,	10 00
* Rosenberg's Electrical Engineering. (Haldane Gee—Kinzbrunner.).....	8vo,	1 50
Ryan, Norris, and Hoxie's Electrical Machinery. (<i>In preparation.</i>).....		
Thurston's Stationary Steam-engines.....	8vo,	2 50
* Tillman's Elementary Lessons in Heat.....	8vo,	1 50
Tory and Fitcher's Manual of Laboratory Physics.....	Small 8vo,	2 00

LAW.

* Davis's Elements of Law.....	8vo,	2 50
* Treatise on the Military Law of United States.....	8vo,	7 00
*	Sheep,	7 50
Manual for Courts-martial.....	16mo, morocco,	1 50

Wait's Engineering and Architectural Jurisprudence.....	8vo,	6 00
	Sheep,	6 50
Law of Operations Preliminary to Construction in Engineering and Architecture.....	8vo,	5 00
	Sheep,	5 50
Law of Contracts.....	8vo,	3 00
Winthrop's Abridgment of Military Law.....	12mo,	2 50

MANUFACTURES.

Bernadou's Smokeless Powder—Nitro-cellulose and Theory of the Cellulose Molecule.....	12mo,	2 50
Bolland's Iron Founder.....	12mo,	2 50
"The Iron Founder," Supplement.....	12mo,	2 50
Encyclopedia of Founding and Dictionary of Foundry Terms Used in the Practice of Moulding.....	12mo,	3 00
Eissler's Modern High Explosives.....	8vo,	4 00
Effront's Enzymes and their Applications. (Prescott.).....	8vo,	3 00
Fitzgerald's Boston Machinist.....	18mo,	1 00
Ford's Boiler Making for Boiler Makers.....	18mo,	1 00
Hopkins's Oil-chemists' Handbook.....	8vo,	3 00
Keep's Cast Iron.....	8vo,	2 50
Leach's The Inspection and Analysis of Food with Special Reference to State Control. (<i>In preparation.</i>).....		
Metcalf's Steel. A Manual for Steel-users.....	12mo,	2 00
Metcalf's Cost of Manufactures—And the Administration of Workshops, Public and Private.....	8vo,	5 00
Meyer's Modern Locomotive Construction.....	4to,	10 00
* Reaisig's Guide to Piece-dyeing.....	8vo,	25 00
Smith's Press-working of Metals.....	8vo,	3 00
Wire: Its Use and Manufacture.....	Small 4to,	3 00
Spalding's Hydraulic Cement.....	12mo,	2 00
Spencer's Handbook for Chemists of Beet-sugar Houses.....	16mo, morocco,	3 00
Handbook for Sugar Manufacturers and their Chemists.....	16mo, morocco,	2 00
Thurston's Manual of Steam-boilers, their Designs, Construction and Operation.....	8vo,	5 00
Ulke's Modern Electrolytic Copper Refining.....	8vo,	3 00
* Walke's Lectures on Explosives.....	8vo,	4 00
West's American Foundry Practice.....	12mo,	2 50
Moulder's Text-book.....	12mo,	2 50
Wiechmann's Sugar Analysis.....	Small 8vo,	2 50
Wolff's Windmill as a Prime Mover.....	8vo,	3 00
Woodbury's Fire Protection of Mills.....	8vo,	2 50

MATHEMATICS.

Baker's Elliptic Functions.....	8vo,	1 50
* Base's Elements of Differential Calculus.....	12mo,	4 00
Briggs's Elements of Plane Analytic Geometry.....	12mo,	1 00
Chapman's Elementary Course in Theory of Equations.....	12mo,	1 50
Compton's Manual of Logarithmic Computations.....	12mo,	1 50
Davis's Introduction to the Logic of Algebra.....	8vo,	1 50
* Dickson's College Algebra.....	Large 12mo,	1 50
* Introduction to the Theory of Algebraic Equations.....	Large 12mo,	1 25
Halsted's Elements of Geometry.....	8vo,	1 75
Elementary Synthetic Geometry.....	8vo,	1 50

* Johnson's Three-place Logarithmic Tables: Vest-pocket size.....	paper,	15
	100 copies for	5 00
* Mounted on heavy cardboard, 8×10 inches,		25
	10 copies for	2 00
Elementary Treatise on the Integral Calculus.....	Small 8vo,	1 50
Curve Tracing in Cartesian Co-ordinates.....	12mo,	1 00
Treatise on Ordinary and Partial Differential Equations.....	Small 8vo,	3 50
Theory of Errors and the Method of Least Squares.....	12mo,	1 50
* Theoretical Mechanics.....	12mo,	3 00
Laplace's Philosophical Essay on Probabilities. (Truscott and Emory.)	12mo,	2 00
* Ludlow and Bass. Elements of Trigonometry and Logarithmic and Other		
Tables.....	8vo,	3 00
Trigonometry and Tables published separately.....	Each,	2 00
Maurer's Technical Mechanics. (<i>In preparation.</i>)		
Merriman and Woodward's Higher Mathematics.....	8vo,	5 00
Merriman's Method of Least Squares.....	8vo,	2 00
Rice and Johnson's Elementary Treatise on the Differential Calculus. Sm.,	8vo,	3 00
Differential and Integral Calculus. 2 vols. in one.....	Small 8vo,	2 50
Wood's Elements of Co-ordinate Geometry.....	8vo,	2 00
Trigonometry: Analytical, Plane, and Spherical.....	12mo,	1 00

MECHANICAL ENGINEERING.

MATERIALS OF ENGINEERING, STEAM-ENGINES AND BOILERS.

Baldwin's Steam Heating for Buildings.....	12mo,	2 50
Barr's Kinematics of Machinery.....	8vo,	2 50
* Bartlett's Mechanical Drawing.....	8vo,	3 00
Benjamin's Wrinkles and Recipes.....	12mo,	2 00
Carpenter's Experimental Engineering.....	8vo,	6 00
Heating and Ventilating Buildings.....	8vo,	4 00
Clerk's Gas and Oil Engine.....	Small 8vo,	4 00
Coolidge's Manual of Drawing.....	8vo, paper,	1 00
Cromwell's Treatise on Toothed Gearing.....	12mo,	1 50
Treatise on Belts and Pulleys.....	12mo,	1 50
Durley's Kinematics of Machines.....	8vo,	4 00
Flather's Dynamometers and the Measurement of Power.....	12mo,	3 00
Rope Driving.....	12mo,	2 00
Gill's Gas and Fuel Analysis for Engineers.....	12mo,	1 25
Hall's Car Lubrication.....	12mo,	1 00
Hutton's The Gas Engine. (<i>In preparation.</i>)		
Jones's Machine Design:		
Part I.—Kinematics of Machinery.....	8vo,	1 50
Part II.—Form, Strength, and Proportions of Parts.....	8vo,	3 00
Kent's Mechanical Engineer's Pocket-book.....	16mo, morocco,	5 00
Kerr's Power and Power Transmission.....	8vo,	2 00
MacCord's Kinematics; or, Practical Mechanism.....	8vo,	5 00
Mechanical Drawing.....	4to,	4 00
Velocity Diagrams.....	8vo,	1 50
Mahan's Industrial Drawing. (Thompson.).....	8vo,	3 50
Poole's Calorific Power of Fuels.....	8vo,	3 00
Reid's Course in Mechanical Drawing.....	8vo,	2 00
Text-book of Mechanical Drawing and Elementary Machine Design.....	8vo,	3 00
Richards's Compressed Air.....	12mo,	1 50
Robinson's Principles of Mechanism.....	8vo,	3 00
Smith's Press-working of Metals.....	8vo,	3 00
Thurston's Treatise on Friction and Lost Work in Machinery and Mill		
Work.....	8vo,	3 00
Animal as a Machine and Prime Motor, and the Laws of Energetics.....	12mo,	1 00

Warren's Elements of Machine Construction and Drawing.....	8vo,	7 50
Weissbach's Kinematics and the Power of Transmission. Herrmann— Klein.).....	8vo,	5 00
Machinery of Transmission and Governors. (Herrmann—Klein.).....	8vo,	5 00
Hydraulics and Hydraulic Motors. (Du Bois.).....	8vo,	5 00
Wolff's Windmill as a Prime Mover.....	8vo,	3 00
Wood's Turbines.....	8vo,	2 50

MATERIALS OF ENGINEERING.

Bovey's Strength of Materials and Theory of Structures.....	8vo,	7 50
Burr's Elasticity and Resistance of the Materials of Engineering. 6th Edition, Reeset.....	8vo,	7 50
Church's Mechanics of Engineering.....	8vo,	6 00
Johnson's Materials of Construction.....	Large 8vo,	6 00
Keep's Cast Iron.....	8vo,	2 50
Lanza's Applied Mechanics.....	8vo,	7 50
Martens's Handbook on Testing Materials. (Henning.).....	8vo,	7 50
Merriman's Text-book on the Mechanics of Materials.....	8vo,	4 00
Strength of Materials.....	12mo,	1 00
Metcalf's Steel. A Manual for Steel-users.....	12mo,	2 00
Smith's Wire: Its Use and Manufacture.....	Small 4to,	3 00
Materials of Machines.....	12mo,	1 00
Thurston's Materials of Engineering.....	3 vols, 8vo,	8 00
Part II.—Iron and Steel.....	8vo,	3 50
Part III.—A Treatise on Brasses, Bronzes, and Other Alloys and their Constituents.....	8vo,	2 50
Text-book of the Materials of Construction.....	8vo,	5 00
Wood's Treatise on the Resistance of Materials and an Appendix on the Preservation of Timber.....	8vo,	2 00
Elements of Analytical Mechanics.....	8vo,	3 00

STEAM-ENGINES AND BOILERS.

Carnot's Reflections on the Motive Power of Heat. (Thurston.).....	12mo,	1 50
Dawson's "Engineering" and Electric Traction Pocket-book.....	16mo, mor.,	4 00
Ford's Boiler Making for Boiler Makers.....	18mo,	1 00
Goss's Locomotive Sparks.....	8vo,	2 00
Hemenway's Indicator Practice and Steam-engine Economy.....	12mo,	2 00
Hutton's Mechanical Engineering of Power Plants.....	8vo,	5 00
Heat and Heat-engines.....	8vo,	5 00
Kent's Steam-boiler Economy.....	8vo,	4 00
Kneass's Practice and Theory of the Injector.....	8vo,	1 50
MacCord's Slide-valves.....	8vo,	2 00
Meyer's Modern Locomotive Construction.....	4to,	10 00
Peabody's Manual of the Steam-engine Indicator.....	12mo,	1 50
Tables of the Properties of Saturated Steam and Other Vapors.....	8vo,	1 00
Thermodynamics of the Steam-engine and Other Heat-engines.....	8vo,	5 00
Valve-gears for Steam-engines.....	8vo,	2 50
Peabody and Miller's Steam-boilers.....	8vo,	4 00
Pray's Twenty Years with the Indicator.....	Large 8vo,	2 50
Puplin's Thermodynamics of Reversible Cycles in Gases and Saturated Vapors. (Osterberg.).....	12mo,	1 25
Reagan's Locomotives: Simple, Compound, and Electric.....	12mo,	2 50
Rontgen's Principles of Thermodynamics. (Du Bois.).....	8vo,	5 00
Sinclair's Locomotive Engine Running and Management.....	12mo,	2 00
Smart's Handbook of Engineering Laboratory Practice.....	12mo,	2 50
Snow's Steam-boiler Practice.....	8vo,	3 00

Spangler's Valve-gears	8vo, 27	50
Notes on Thermodynamics	12mo, 1	00
Spangler, Greene, and Marshall's Elements of Steam-engineing	8vo, 3	00
Thurston's Handy Tables	8vo, 1	50
Manual of the Steam-engine	2 vols. 8vo, 10	00
Part I.—History, Structure, and Theory	8vo, 6	00
Part II.—Design, Construction, and Operation	8vo, 6	00
Handbook of Engine and Boiler Trials, and the Use of the Indicator and the Prony Brake	8vo, 5	00
Stationary Steam-engines	8vo, 2	50
Steam-boiler Explosions in Theory and in Practice	12mo, 1	50
Manual of Steam-boilers, Their Designs, Construction, and Operation	8vo, 5	00
Weisbach's Heat, Steam, and Steam-engines. (Du Bois.)	8vo, 5	00
Whitham's Steam-engine Design	8vo, 5	00
Wilson's Treatise on Steam-boilers. (Fletcher.)	16mo, 2	50
Wood's Thermodynamics, Heat Motors, and Refrigerating Machines	8vo, 4	00

MECHANICS AND MACHINERY.

Barr's Kinematics of Machinery	8vo, 2	50
Bovey's Strength of Materials and Theory of Structures	8vo, 7	50
Chase's The Art of Pattern-making	12mo, 2	50
Chordal.—Extracts from Letters	12mo, 2	00
Church's Mechanics of Engineering	8vo, 6	00
Notes and Examples in Mechanics	8vo, 2	00
Compton's First Lessons in Metal-working	12mo, 1	50
Compton and De Groodt's The Speed Lathe	12mo, 1	50
Cromwell's Treatise on Toothed Gearing	12mo, 1	50
Treatise on Belts and Pulleys	12mo, 1	50
Dana's Text-book of Elementary Mechanics for the Use of Colleges and Schools	12mo, 1	50
Dingey's Machinery Pattern Making	12mo, 2	00
Dredge's Record of the Transportation Exhibits Building of the World's Columbian Exposition of 1893	4to, half morocco, 5	00
Du Bois's Elementary Principles of Mechanics:		
Vol. I.—Kinematics	8vo, 3	50
Vol. II.—Statics	8vo, 4	00
Vol. III.—Kinetics	8vo, 3	50
Mechanics of Engineering. Vol. I.	Small 4to, 7	50
Vol. II.	Small 4to, 10	00
Durley's Kinematics of Machines	8vo, 4	00
Fitzgerald's Boston Machinist	16mo, 1	00
Fletcher's Dynamometers, and the Measurement of Power	12mo, 3	00
Rope Driving	12mo, 2	00
Goss's Locomotive Sparks	8vo, 2	00
Hall's Car Lubrication	12mo, 1	00
Holly's Art of Saw Filing	18mo, 75	
* Johnson's Theoretical Mechanics	12mo, 3	00
Statics by Graphic and Algebraic Methods	8vo, 2	00
Jones's Machine Design:		
Part I.—Kinematics of Machinery	8vo, 1	50
Part II.—Form, Strength, and Proportions of Parts	8vo, 3	00
Kerr's Power and Power Transmission	8vo, 2	00
Lanza's Applied Mechanics	8vo, 7	50
MacCord's Kinematics; or, Practical Mechanism	8vo, 5	00
Velocity Diagrams	8vo, 1	50
Maurer's Technical Mechanics. (<i>In preparation.</i>)		

Merriman's Text-book on the Mechanics of Materials	8vo, 4	00
* Michie's Elements of Analytical Mechanics	8vo, 4	00
Reagan's Locomotives: Simple, Compound, and Electric	12mo, 2	50
Reid's Course in Mechanical Drawing	8vo, 2	00
Text-book of Mechanical Drawing and Elementary Machine Design	8vo, 3	00
Richards's Compressed Air	12mo, 1	50
Robinson's Principles of Mechanism	8vo, 3	00
Ryan, Norris, and Hoxie's Electrical Machinery. (<i>In preparation.</i>)		
Sinclair's Locomotive-engine Running and Management	12mo, 2	00
Smith's Press-working of Metals	8vo, 3	00
Materials of Machines	12mo, 1	00
Spangler, Greene, and Marshall's Elements of Steam-engineering	8vo, 3	00
Thurston's Treatise on Friction and Lost Work in Machinery and Mill Work	8vo, 3	00
Animal as a Machine and Prime Motor, and the Laws of Energetics	12mo, 1	00
Warren's Elements of Machine Construction and Drawing	8vo, 7	50
Weisbach's Kinematics and the Power of Transmission. (Herrmann— Klein.)	8vo, 5	00
Machinery of Transmission and Governors. (Herrmann—Klein.)	8vo, 5	00
Wood's Elements of Analytical Mechanics	8vo, 3	00
Principles of Elementary Mechanics	12mo, 1	25
Turbines	8vo, 2	50
The World's Columbian Exposition of 1893	4to, 1	00

METALLURGY.

Egleston's Metallurgy of Silver, Gold, and Mercury:		
Vol. I.—Silver	8vo, 7	50
Vol. II.—Gold and Mercury	8vo, 7	50
** Iles's Lead-smelting. (Postage 9 cents additional.)	12mo, 2	50
Keep's Cast Iron	8vo, 2	50
Kunhardt's Practice of Ore Dressing in Europe	8vo, 1	50
Le Chatelier's High-temperature Measurements. (Boudouard—Burgess.)	12mo, 3	00
Metcalf's Steel. A Manual for Steel-users	12mo, 2	00
Smith's Materials of Machines	12mo, 1	00
Thurston's Materials of Engineering. In Three Parts	8vo, 8	00
Part II.—Iron and Steel	8vo, 3	50
Part III.—A Treatise on Brasses, Bronzes, and Other Alloys and their Constituents	8vo, 2	50
Ulke's Modern Electrolytic Copper Refining	8vo, 1	30

MINERALOGY.

Barringer's Description of Minerals of Commercial Value. Oblong, morocco	2	50
Boyd's Resources of Southwest Virginia	8vo, 3	00
Map of Southwest Virginia	Pocket-book form, 2	00
Brush's Manual of Determinative Mineralogy. (Penfield.)	8vo, 4	00
Chester's Catalogue of Minerals	8vo, paper, 1	00
	Cloth, 1	25
Dictionary of the Names of Minerals	8vo, 3	50
Dana's System of Mineralogy	Large 8vo, half leather, 12	50
First Appendix to Dana's New "System of Mineralogy."	Large 8vo, 1	00
Text-book of Mineralogy	8vo, 4	00
Minerals and How to Study Them	12mo, 1	50
Catalogue of American Localities of Minerals	Large 8vo, 1	00
Manual of Mineralogy and Petrography	12mo, 2	00
Egleston's Catalogue of Minerals and Synonyms	8vo, 2	50
Hussak's The Determination of Rock-forming Minerals. (Smith.) Small 8vo,	2	00

* Penfield's Notes on Determinative Mineralogy and Record of Mineral Tests.	8vo, paper,	0 50
Rosenbusch's Microscopical Physiography of the Rock-making Minerals.		
(Iddings.)	8vo,	5 00
* Tillman's Text-book of Important Minerals and Rocks.	8vo,	2 00
Williams's Manual of Lithology	8vo,	3 00

MINING.

Beard's Ventilation of Mines	12mo,	2 50
Boyd's Resources of Southwest Virginia	8vo,	3 00
Map of Southwest Virginia	Pocket-book form,	2 00
* Drinker's Tunneling, Explosive Compounds, and Rock Drills.		
	4to, half morocco,	25 00
Eissler's Modern High Explosives	8vo,	4 00
Fowler's Sewage Works Analyses	12mo,	2 00
Goodyear's Coal-mines of the Western Coast of the United States	12mo,	2 50
Ihseng's Manual of Mining	8vo,	4 00
** Iles's Lead-smelting. (Postage 9c. additional.)	12mo,	2 50
Kunhardt's Practice of Ore Dressing in Europe	8vo,	1 50
O'Driscoll's Notes on the Treatment of Gold Ores	8vo,	2 00
* Walke's Lectures on Explosives	8vo,	4 00
Wilson's Cyanide Processes	12mo,	1 50
Chlorination Process	12mo,	1 50
Hydraulic and Placer Mining	12mo,	2 00
Treatise on Practical and Theoretical Mine Ventilation	12mo,	1 25

SANITARY SCIENCE.

Copeland's Manual of Bacteriology. (<i>In preparation.</i>)		
Folwell's Sewerage. (Designing, Construction, and Maintenance.)	8vo,	3 00
Water-supply Engineering	8vo,	4 00
Fuertes's Water and Public Health	12mo,	1 50
Water-filtration Works	12mo,	2 50
Gerhard's Guide to Sanitary House-inspection	16mo,	1 00
Goodrich's Economical Disposal of Town's Refuse	Demy 8vo,	3 50
Hazen's Filtration of Public Water-supplies	8vo,	3 00
Kiersted's Sewage Disposal	12mo,	1 25
Leach's The Inspection and Analysis of Food with Special Reference to State Control. (<i>In preparation.</i>)		
Mason's Water-supply. (Considered Principally from a Sanitary Stand-point.) 3d Edition, Rewritten	8vo,	4 00
Examination of Water. (Chemical and Bacteriological.)	12mo,	1 25
Merriman's Elements of Sanitary Engineering	8vo,	2 00
Nichols's Water-supply. (Considered Mainly from a Chemical and Sanitary Standpoint.) (1883.)	8vo,	2 50
Ogden's Sewer Design	12mo,	2 00
* Price's Handbook on Sanitation	12mo,	1 50
Richards's Cost of Food. A Study in Dietarics	12mo,	1 00
Cost of Living as Modified by Sanitary Science	12mo,	1 00
Richards and Woodman's Air, Water, and Food from a Sanitary Stand-point	8vo,	2 00
* Richards and Williams's The Dietary Computer	8vo,	1 50
Rideal's Sewage and Bacterial Purification of Sewage	8vo,	3 50
Turneaure and Russell's Public Water-supplies	8vo,	5 00
Whipple's Microscopy of Drinking-water	8vo,	3 50
Woodhull's Notes and Military Hygiene	16mo,	1 50


MISCELLANEOUS.

Barker's Deep-sea Soundings	8vo,	2 00
Emmons's Geological Guide-book of the Rocky Mountain Excursion of the International Congress of Geologists.....	Large 8vo,	1 50
Ferrel's Popular Treatise on the Winds.....	8vo,	4 00
Haines's American Railway Management	12mo,	2 50
Mott's Composition, Digestibility, and Nutritive Value of Food. Mounted chart.		1 25
Fallacy of the Present Theory of Sound	16mo,	1 00
Ricketts's History of Rensselaer Polytechnic Institute, 1824-1894. Small	8vo,	3 00
Rotherham's Emphasized New Testament.....	Large 8vo,	2 00
Steel's Treatise on the Diseases of the Dog.....	8vo,	3 50
Totten's Important Question in Metrology.....	8vo,	2 50
The World's Columbian Exposition of 1893.....	4to,	1 00
Worcester and Atkinson. Small Hospitals, Establishment and Maintenance, and Suggestions for Hospital Architecture, with Plans for a Small Hospital.....	12mo,	1 25

HEBREW AND CHALDEE TEXT-BOOKS.

Green's Grammar of the Hebrew Language.....	8vo,	3 00
Elementary Hebrew Grammar.....	12mo,	1 25
Hebrew Chrestomathy.....	8vo,	2 00
Gesenius's Hebrew and Chaldee Lexicon to the Old Testament Scriptures. (Tregelles.).....	Small 4to, half morocco,	5 00
Letteris's Hebrew Bible.....	8vo,	2 25










The borrower must return this item on or before the last date stamped below. If another user places a recall for this item, the borrower will be notified of the need for an earlier return.

Non-receipt of overdue notices does not exempt the borrower from overdue fines.

Harvard College Widener Library
Cambridge, MA 02138 617-495-2413



Please handle with care.
Thank you for helping to preserve
library collections at Harvard.

